

IBM Cognos Report Studio
Version 10.2.2

User Guide



Note

Before using this information and the product it supports, read the information in "Notices" on page 1013.

Product Information

This document applies to IBM Cognos Business Intelligence Version 10.2.2 and may also apply to subsequent releases.

Licensed Materials - Property of IBM

© **Copyright IBM Corporation 2005, 2015.**

US Government Users Restricted Rights – Use, duplication or disclosure restricted by GSA ADP Schedule Contract with IBM Corp.

Contents

Introduction	xlix
Chapter 1. What's New in Cognos Report Studio?	1
New features in version 10.2.2	1
IBM Cognos Active Report preview.	1
IBM Cognos Active Report output	1
IBM Cognos Active Report templates	1
Reusable report styles	2
Slider orientation in IBM Cognos Active Report	2
Tabbed reports in HTML output	2
Dynamically named worksheet tabs in Excel 2007 output	2
New maps in IBM Cognos BI.	2
Report run format restrictions	2
Support for IBM Cognos Theme Designer	3
Improvements to the current default chart technology	3
Enhancements to extensible visualizations	3
New features in version 10.2.1.1	4
Extensible visualizations in regular reports	4
Extensible visualization render method	4
Report booklets	4
New features in version 10.2.1	4
Improved IBM Cognos Active Report performance	5
Extensible visualizations in IBM Cognos Active Report	5
Option to group or ungroup repeating cells in Excel 2007 reports.	5
Crosstab values as percentages	5
Share sets between reports.	6
Improved text-based relational filters	6
Improved data container and query naming support	6
Search parameter Ends with any of these keywords	7
Removed Features in Version 10.2.1	7
IBM Cognos Statistics	7
New features in version 10.2.0	7
Updated world and Africa maps.	7
Interactive repeater tables	7
Improved IBM Cognos Active Report integration with IBM Cognos Workspace	8
Improved support for bidirectional languages	8
Macro tab in expression editor	8
Inherited table styles in lists and crosstabs	9
Enhanced crosstab headers	9
Prompt API.	9
Excel 2007 Data report output format	9
Global classes for accessible reports	10
Changed features in version 10.2.0.	10
Change in line break rules in PDFs	10
Support for inline prompts in reports viewed on mobile devices.	10
Cognos Business Insight and Cognos Business Insight Advanced are renamed	11
Removed Features in Version 10.2.0	11
Saving and opening reports on your computer	11
New features in version 10.1.1	11
New active report controls	11
Conversion of controls to other types of controls	11
Improved user experience when authoring active reports	11
Active report access code.	12
New startup options	12
Keyboard shortcuts for accessibility	12

Updated maps	12
Custom groups	13
Larger worksheet sizes for Microsoft Excel 2007 report outputs	13
Microsoft Excel 2007 supported as an external data source.	14
Changed features in version 10.1.1.	14
Specify how to show no data contents	14
What's new in version 10.1.0	14
New Features in Version 10.1.0	14
Changed features in Cognos Business Insight Advanced version 10.1.0	22
Removed Features in Version 10.1.0	23
Chapter 2. Getting started with Report Studio	25
Building IBM Cognos Business Intelligence Applications	25
Relational and dimensional reporting styles	26
The User Interface	29
Work in design, structure, or Active Report preview view	33
Report Layout and Queries	33
Layout	33
Queries.	35
Report Objects	35
Find Objects in a Report	36
Options.	37
Web Browser Settings	41
The IBM Cognos Software Development Kit	41
Chapter 3. Creating a report	43
Specifying the Data Package.	43
Refresh the package	44
Choosing a basic report layout	44
Inserting a data container from the toolbox tab	45
Add Data	46
Data source icons	46
Insert a Single Data Item	47
Validate a Report	48
Save a Report.	49
Running a report	50
Specify Not to Render a Page If It Does Not Contain Data.	52
Controlling the Rows Per Page for Multiple Containers in HTML and PDF	52
Producing a Report in CSV Format	53
Producing a Report in Microsoft Excel Format.	53
Producing a Report in XML Format	57
Set PDF Page Options	57
View Lineage Information for a Data Item	58
The IBM Cognos Business Intelligence lineage tool	59
Access the IBM WebSphere Business Glossary	60
Support for bidirectional languages	60
Reports for workspaces in Cognos Workspace	62
Prompts in workspaces in Cognos Workspace	63
Enable filters in workspaces in Cognos Workspace	63
Creating Reports for IBM Cognos for Microsoft Office	64
Creating Reports for Mobile Devices	65
Creating location-aware reports.	65
Chapter 4. Lists	67
Set List Properties	67
Hide Columns in List Reports	68
Using Repeaters	68
Convert a List into a Repeater	69
Example - Create Mailing Labels	69

Chapter 5. Crosstabs	71
Crosstab Nodes and Crosstab Node Members	71
Set Crosstab Properties	73
Create a Single-Edge Crosstab	74
Create a Nested Crosstab	75
Creating headers automatically for sets in crosstabs	76
Showing crosstab values as percentages	76
Specify the Default Measure	77
Swap Columns and Rows	78
Indent Data	78
Change a List into a Crosstab	79
Example - Add Aggregate Data to a Crosstab	79
Example - Create a Discontinuous Crosstab	80
Chapter 6. Charts	83
Current Default Charts and Legacy Charts	83
Creating Charts	83
Chart Objects	84
Chart Types	87
Choosing a Chart Type and Configuration	87
Column Charts	88
Line Charts	89
Pie Charts	90
Bar Charts	91
Area Charts	92
Point Charts	93
Combination Charts	94
Scatter Charts	94
Bubble Charts	95
Quadrant Charts	96
Bullet Charts	97
Gauge Charts	98
Pareto Charts	99
Progressive Column Charts	100
Microcharts	100
Marimekko Charts	101
Radar Charts	102
Polar Charts	102
Range Indicator Charts	103
Chart Configurations	104
Convert Charts From One Type to Another	107
Convert Legacy Charts to Current Default Charts	107
Limitations When Converting Legacy Charts	107
Customizing Chart Properties	108
Resize a Current Default Chart	111
Resize a Legacy Chart	112
Customizing the Color Palette of a Chart	112
Creating a Conditional Color Palette in a Chart	115
Change a Chart Background in a Current Default Chart	119
Change a Chart Background in a Legacy Chart	119
Add Background Effects to a Chart Object in a Legacy Chart	120
Add Colored Regions in a Current Default Chart	121
Specify Custom Label Text	122
Customizing the Axes of a Chart	123
Showing Gridlines in a Chart	126
Customize the Legend in a Current Default Chart	128
Customize the Items in the Legend of a Legacy Chart	129
Adding a Note to a Chart	130
Adding a Baseline to a Chart	132
Adding Markers to Charts	135
Display Trendlines in Current Default Charts	138

Display Regression Lines in Legacy Scatter or Bubble Charts	139
Showing data labels or values in current default charts	140
Showing data values in current default pie and donut charts	141
Define Query Context When Customizing Legend Entries, Legend Titles, or Axis Labels	142
Summarize Small Slices, Bars, or Columns in Current Default Charts.	142
Customizing Lines and Data Points in a Line Chart	143
Customize a Current Default Combination Chart	145
Create a Matrix of Current Default Charts	145
Customize a Current Default Gauge Chart	147
Customize a Legacy Gauge Chart	149
Defining color by value in current default scatter or bubble charts.	150
Specify the Bubble Size in a Current Default Bubble Chart	151
Set the Position of the First Slice in a Current Default Pie Chart	152
Creating a Donut Chart from a Current Default Pie Chart	152
Pull Out Pie Slices in a Current Default Pie Chart	153
Define the Cumulation Line in a Current Default Pareto Chart	154
Define the Cumulation Line in a Legacy Pareto Chart	155
Insert a Microchart into a Crosstab	155
Customize a Current Default Bullet Chart	156
Changing the number of hotspots in a chart	156
Create a Drill-up and Drill-down Chart	157
Example - Creating Drill-through Access in a Legacy Chart	158
Create the target report	158
Create the Source Report	159
Define the Drill Behavior	159
Example - Creating and Customizing a Metrics Range Legacy Chart	160
Create a Metrics Range Chart	160
Customize the Chart	160
Customize the Chart Legend Labels	161
Adding a Metric Studio Diagram to a Report.	162
Add a Static Metric Studio Diagram to a Report.	162
Add a Data-driven Metric Studio Diagram to a Report	163
Chapter 7. Extensible visualizations.	165
Adding a visualization to a report	165
Adding a treemap visualization	166
Adding a heatmap visualization	168
Adding a packed bubble visualization	169
Adding a network diagram.	171
Visualization properties	172
Choosing where visualizations are rendered	172
Resizing a visualization	173
Changing the nesting order.	173
Specifying the range values that are displayed	174
Summarizing data in a visualization.	176
Populating a visualization with data from the visualization definition	176
Updating visualizations	177
Converting visualizations from one type to another	177
Sorting a category field by a measure in visualizations	178
Chapter 8. Maps	181
The Report Studio Map Object	181
New maps in IBM Cognos BI 10.2.2	182
Example - Create a Map Report	183
Set Map Properties	184
Example - Define Data Values for the Region Layer	186
Match Data Values to Names in the Map File.	186
Define Data Values for the Point Layer	187
Add Colors to the Region or Point Layer	188
Add a Legend Title to a Map	188

Add a Note to a Map	189
Drill Through to Another Report From a Map	189
Edit a Map	190
Additional Maps	190
Location Intelligence	191
Chapter 9. Active Reports	193
Active Report Controls	193
Active Report Variables	194
Convert an Existing Report to an Active Report	194
Specify Active Report Properties	195
Adding Interactivity to a Report	196
Create and Manage Active Report Variables	196
Adding Controls to a Report	197
Add Data to a Control	202
Define a Connection Between Controls	204
Specify the Selection Behavior of a Control	205
Specify the Reaction Behavior of a Control	206
Set the No Value List Item	208
Show or Hide a Column or Row	209
Sort Data in a List.	210
Recommendation - use master detail relationships when authoring decks	210
Formatting an active report in the preview view.	210
Summarizing Data in the Active Report Output	211
Run or Save an Active Report	212
Example - Create an Active Report Showing Revenue Data for Core Products.	213
Create the active report	213
Add data to the data drop-down list controls.	213
Add data to the list	214
Add interactivity to the report.	215
Specifying default values for the data drop-down list controls	216
Revenue data for core products report output	216
Example - Sales analysis active report	216
Creating a new active report	217
Adding data to the check box group control	218
Adding a default card to the deck and data to the data discrete values slider	218
Defining a connection between the check box group and the deck.	218
Adding data to the list object	219
Defining a connection between the slider and the list object	219
Adding a title to the list	220
Adding data to the data deck and chart	220
Defining a connection between the chart and the data deck	221
Adding a title to the chart	221
Sales analysis report output	222
Example - Network diagram visualization.	222
Adding a new visualization in IBM Cognos Active Report	223
Adding data to the nodes data container	223
Adding data to the links data container	223
Defining a connection between the data drop-down list and the visualization object.	224
Network diagram visualization output	224
Chapter 10. Relational Reporting Style	227
Add Relational Data to a Report	227
Group Relational Data	227
Perform Advanced Grouping	228
Creating relational custom groups	229
Set the Group Span for a Column	230
Divide Data into Sections	232
Summarizing Data Relationally	233
Add a Simple Summary.	235

Set the Auto Group & Summarize Property	235
Specify Detail or Summary Aggregation in the Model	236
Specify Aggregation Properties for a Data Item	236
Use Summary Functions in Data Item Expressions	236
Summary Functions	238
Focusing Relational Data	242
Create a Detail or Summary Filter	243
Edit or remove a filter	247
Browse or Search the Values of a Data Item	247
Ignoring the Time Component in Date Columns.	248
Sorting Relational Data	249
Perform Advanced Layout Sorting	249
Working with Relational Queries	250
Specify a List of Data Items for an Object	251
Relate a Query to a Layout.	251
Connecting Queries Between Different Data Sources	251
Add a Query to a Relational Report	252
Create a Union Query	253
Create a Join Relationship	256
Reference a Package Item in a Child Query	257
Create a Master Detail Relationship	257
Working with Queries in SQL	259
Using Relational Calculations	262
Create a Simple Calculation	263
Insert a Query Calculation	264
Create a Layout Calculation	266
Chapter 11. Dimensional Reporting Style	267
Add Dimensional Data to a Report	267
Customize the Source Tree	269
Insert a Member	269
Search for a Member	270
Nest Members	271
Insert a Hierarchy	271
Insert a Member Property	272
Create a Set of Members.	272
Sharing sets between reports	273
Edit a Set.	275
Extended Data Items	277
Tips for Working with Ragged or Unbalanced Hierarchies	278
Creating dimensional custom groups	279
Summarizing Data Dimensionally	280
Add a Simple Summary	282
Summarizing Values in Crosstabs	283
Summarizing Member Sets	285
Rolling and Moving Averages	286
Show Data for Specific Time Periods	287
Summary Functions	287
Focusing Dimensional Data.	292
Create a Context Filter	293
Sorting Dimensional Data	295
Sort Sets by Label	295
Sort Sets in the Opposite Axis by Value	296
Perform Advanced Set Sorting.	297
Working with Dimensional Queries	297
Specify a List of Data Items for an Object	298
Relate a Query to a Layout.	298
Using Dimensional Data Sources with Queries	298
Connecting Queries Between Different Data Sources	299
Multiple-fact Queries	299
Add a Query to a Dimensional Report	303

Add Dimension Information to a Query	304
Create a Master Detail Relationship	307
Working with Queries in SQL or MDX	309
Example - Create a Dynamic Report That Shows Period-to-date Data.	314
Using Dimensional Calculations	316
Create a Simple Member Calculation	316
Insert a Query Calculation	317
Create a Layout Calculation	319
Create an Intersection (Tuple)	320
Assigning a Hierarchy or Dimension	320
Drilling Up and Drilling Down in Dimensional Reports	320
Member Sets	321
Create a Drill-up and Drill-down Report	322
Example - Create a Dashboard Report	324
Chapter 12. Adding Prompts to Filter Data	327
Use the Build Prompt Page Tool	328
Build Your Own Prompt and Prompt Page	329
Example - Create a Report Showing Products Shipped for a Specific Time Interval	332
Create a Parameter to Produce a Prompt	333
Create a Prompt Directly in a Report Page	334
Modifying Prompts	335
Change the Prompt Control Interface	335
Specify That a Prompt Requires User Input	336
Allow Users to Select Multiple Values in a Prompt	336
Show or Hide Prompt Status	337
Specify a Default Selection for a Prompt	337
Customize Prompt Text	337
Specify Prompt Values	338
Add a Prompt Button	338
Create a Cascading Prompt.	339
Control the Data That Appears in a Tree Prompt	339
Using in_range Filters with Character Data	340
Showing prompt values in generated SQL or MDX.	340
Chapter 13. Laying Out a Report	343
Report Layout Recommendations.	343
The Page Structure View	343
Copy Object Formatting.	344
Add a Header or Footer to a Report or List	345
Add Borders to an Object	346
Add a Text Item to a Report	346
Specify the Font for a Report	347
Insert an Image in a Report	347
Insert a Background Image in an Object	348
Add Background Effects.	348
Add background effects to a chart	349
Add a background gradient to a page	349
Add a drop shadow to a container	350
Insert a Formatting Object in a Report	350
Elements Supported in Rich Text Items.	352
Example - Add a Multimedia File to a Report	352
Align an Object in a Report	353
Using a table to control where objects appear	353
Apply a Table Style	354
Apply Padding to an Object	355
Set Margins for an Object	356
Add Multiple Items to a Single Column	356
Example - Create a Report with Multiple Items in One Column	356
Reuse a Layout Object	358

Change a Reused Object	359
Update Reused Objects	360
Specify text and container direction	360
Specify Line Spacing and Breaking	362
Specify the Height and Width of an Object	362
Control How Other Objects Flow Around an Object	363
Specify Report Properties	364
Create and Modify Report and Object Styles	365
Modify the report style	365
Modify object styles	366
Reusing styles from another report	366
(Don't Print) Class.	367
Modify Classes to Format Query Studio Reports	368
Modifying the Default Layout Style Sheet	368
Add Color to an Object	368
Chapter 14. Working with your external data	371
My Data Sets	371
Manage external data.	372
Preparing to Work with your External Data	373
Import Data	375
Map Data	376
Finish Importing Data	377
Publish the Package	378
Edit Your External Data	378
Delete Your External Data	379
Running a Report That Contains External Data	380
Making your Reports Public	380
Chapter 15. Using Conditions	381
Highlight Data Using a Conditional Style	381
Create a New Conditional Style	382
Reuse an Existing Conditional Style	383
Create an Advanced Conditional Style	384
Manage Conditional Styles	384
Example - Add a Conditional Style to an Existing Report.	384
Highlight Data Using a Style Variable	385
Adding Conditional Rendering to a Report	386
Add a Variable from the Condition Explorer	386
Add a Variable from the Properties Pane	387
Hide or Show an Object	388
Add Conditional Rendering	389
Example - Create a Conditional Report	389
Add Multiple Layouts	391
Setting up a Multilingual Reporting Environment	392
Create a Multilingual Report in Report Studio	393
Chapter 16. Bursting Reports	395
Defining Burst Recipients	395
Create a Calculated Field	395
Creating the Burst Table in the Source Database	396
Importing the Table into a Package	397
Specify a Burst Group	397
Set Burst Options	398
Enable Bursting	399
Creating Burst Reports Using Dimensional Data Sources	399
Example - Burst a Report	400
Chapter 17. Format Data.	403
Set the Default Data Formats	403

Specify the Data Format for an Object	404
Specifying the Number of Decimals in Numbers	404
Digit shaping in charts and maps.	405
Locale-sensitive Properties	406
Suppress Empty Cells	407
Suppress Null Cells Using Filters.	407
Example - Suppress Zeros in Rows and Columns in an Existing Report	408
Specify what appears for data containers that contain no data	409
Using Patterns to Format Data	409
Pattern Guidelines.	410
Date and Time Symbols	411
Decimal Format Symbols	417
Chapter 18. Using Query Macros	419
Syntax.	419
Add a Query Macro	421
Creating Prompts Using Query Macros.	422
Examples - selecting country or region prompts	424
Examples - creating prompts that use parameter maps	426
Examples - creating a multiple value prompt.	427
Chapter 19. Using Drill-through Access	431
Understanding Drill-through Concepts	432
Drill-through Paths	432
Selection Contexts	433
Drilling Through to Different Report Formats	433
Drilling Through Between Packages	434
Bookmark References.	434
Members and Values	434
Member Unique Names	435
Conformed Dimensions	436
Business Keys	437
Scope	438
Mapped Parameters	438
Drilling Through on Dates Between PowerCubes and Relational Packages	439
Set Up Drill-through Access in a Report	439
Create a parameter in the target	440
Create a drill-through definition	441
Defining independent drill-through definitions for crosstabs.	443
Specify the Drill-through Text	444
Example - Drill Through to a Hidden Report from a Report Studio Report	445
Check the Target Report.	445
Create and Test the Drill-Through Definition	445
Try it yourself - create a report with drill-through access to itself	447
Drilling Through from IBM Cognos Series 7 to IBM Cognos BI.	450
Setting Up Drill-through Access from IBM Cognos Series 7 Visualizer	450
Setting Up Drill-through Access from PowerPlay Web	450
Create and Test the Target for a Series 7 Report	450
Chapter 20. Working with Multiple Pages	453
Add a Page to a Report	453
Page breaks, page sets, and page layers	453
Create simple page breaks	454
Create advanced page sets	455
Join Nested Page Sets	456
Create Page Layers	456
Example - Preparing a Product List Report	457
Add a Bookmark	459
Create a Table of Contents	460
Example - Add a Table of Contents to a Report	462

Insert Page Numbers in a Report	464
Control Page Breaks and Page Numbering	464
Creating a report booklet	467
Producing tabbed reports	468
Chapter 21. Creating Report Templates	469
Converting a Report to a Template	469
Create a New Template	469
Chapter 22. Managing Existing Reports	471
Copy a Report to the Clipboard	471
Copy a Report to the Clipboard in Internet Explorer	471
Copy a Report to the Clipboard in Firefox	471
Open a Report from the Clipboard	471
Open a File from Another Studio	472
Analysis Studio Query Specification	472
Managing Changes in the Package	476
Update a Name Reference	477
Change the Package	477
Chapter 23. Upgrading Reports.	479
Upgrading Reports from IBM Cognos BI Version 8.4	479
Upgrading Report Styles	479
Upgrading Legacy Charts	480
New Default for Hidden or Deleted Axis Titles	480
Upgrading Reports with SAP BW Prompt Variables	480
Upgrading Reports from IBM Cognos BI Version 8.1 or 8.2	481
Members Containing No Data Are Not Suppressed for SAP BW	481
Thousands Separators Missing	481
RQP-DEF-0177 Error When Upgrading Reports	481
Upgrading Reports from IBM Cognos ReportNet	482
Undocumented and Unsupported Features	482
No Sort Order	482
Layout Errors	482
Report Format	482
Customized Style Sheets.	482
PDF Reports.	482
IF-THEN-ELSE Statements	482
Solve Order	483
Chart Behavior	483
Database Only Processing of Queries	483
Changes in the Behavior of Functions Between ReportNet 1.1 and IBM Cognos BI	483
Appendix A. Accessibility Features	485
Accessibility features in IBM Cognos Report Studio	485
Keyboard Shortcuts	485
Considerations to Improve Report Accessibility	486
Enable Accessible Report Outputs	487
Alternate text and summary text	487
Designate Cells as Headers in Tables	489
Headings and emphasis	489
Prompt control labels.	490
Example - Conditionally Show a List Below a Chart for an Accessible Report	491
IBM and accessibility	493
Appendix B. Troubleshooting	495
Problems Creating Reports	495
Division by Zero Operation Appears Differently in Lists and Crosstabs	495
Application Error Appears When Upgrading a Report.	495
Nested List Report Containing a Data Item That is Grouped More Than Once Does Not Run After Upgrade	495

Background Color in Template Does not Appear	496
Subtotals in Grouped Lists	496
Chart Labels Overwrite One Another	496
Chart Shows Only Every Second Label	496
Chart Gradient Backgrounds Appear Gray in Internet Explorer.	497
Metadata Change in Oracle Essbase Not Reflected in Reports and in the Studios	497
Relationships Not Maintained in a Report With Overlapping Set Levels	497
Summaries in Query Calculations Include Nulls with SAP BW Data Sources	498
Creating Sections on Reports That Access SAP BW Data Sources	498
Error Characters (--) Appear in Reports.	498
Columns, Rows, or Data Disappear With SSAS 2005 Cubes	499
Function Unreliable with Sets	500
Searching for values might return unexpected results	500
Report Differences Between TM1 Executive Viewer and IBM Cognos Business Intelligence with TM1 Data Sources	500
Order of Metadata Tree Differs for TM1 Data Sources	501
MSR-PD-0012 error when importing external data	501
MSR-PD-0013 error when importing external data	501
Problems Calculating Data	501
Unexpected Summary Values in Nested Sets	501
Null Results for Calculations Using SAP BW Data Sources	502
Incorrect Results with IBM Cognos PowerCubes and Time Measures	502
Incorrect Results in Summaries When Using OLAP Data Sources	503
Problems Filtering Data	504
Unexplained Discrepancies in Number Calculations	504
Error when filtering on a _make_timestamp column	506
Problems Running Reports	506
Report Runs Slowly	506
Summaries in a report do not correspond to the visible members	508
Cannot Find the Database in the Content Store (Error QE-DEF-0288)	511
Parse Errors When Opening or Running an Upgraded Report	511
Overflow Error Occurs When a Value in a Crosstab Is More Than 19 Characters	511
The ORA-00907 Error Appears When Running a Report	511
A Report or Analysis Does Not Run Because of Missing Items	512
Cannot View Burst Report	512
A report upgraded from ReportNet does not retain its original look	513
Measure Format Disappears in SSAS 2005	513
Drill-through Links are Not Active in the Safari Browser	513
Data Does Not Appear in a Target Report or the Wrong Data Appears	514
A Running Total in Grouped Reports Gives Unexpected Results	514
Recursive evaluation error	514
Arithmetic Overflow Error When Running a Report in PDF Format	515
RQP-DEF-0177 An error occurred while performing operation 'sqlPrepareWithOptions' status='-69'	
UDA-SQL-0043 Error	515
Unable to View Active Reports in Mozilla Firefox	515
Problems with viewing saved Active Report output in Mozilla Firefox 8 or later versions	516
Problems with large SAP BW queries	516
Master Detail or Burst Reports with Charts or Crosstabs May Result in Denial of Service	517
PCA-ERR-0087 error when you run a large report	517
Differences in the appearance of charts that are run in different formats or on different operating systems	517
Out-of-memory errors with reports that are run in interactive HTML format	518
Charts in PDF Output Show Unexpected Results	519
Result set of a multi-fact query contains blanks	519
Cognos Statistics object is not displayed in a report	519
Maps are missing when a report is run in IBM Cognos BI 10.2.2 or later	520
Problems When Drilling Through	520
Cannot Drill Through Between PowerCubes Because MUNs Do Not Match	520
Unexpected or Empty Results When Drilling Through.	521
Cannot Drill Through From a Relational Source to a Cube	522
Calculations Do Not Appear in the Target Report	523
Nested Crosstab Only Filters on Some Items	523

Data is Not Filtered in the Target Report After Drill-Through	524
Drill-through links in active reports do not work	524

Appendix C. Sample Reports and Packages 525

The Sample Outdoors Company	525
The Sample Outdoors Group of Companies	525
Employees	527
Sales and marketing	527
Sample Outdoors database, models, and packages	528
Samples in the Sample Outdoors Sales (cube) package.	530
Consecutive Periods Comparison.	530
Samples in the Sales and Marketing (Cube) Package	530
Actual vs. Planned Revenue	530
Historical Revenue	531
Revenue by Date Range	531
Revenue by Product Brand (2011)	531
Same Month Prior Year	531
Selected Retailer Country or Region	532
Top Retailers by Country or Region	532
Samples in the GO Data Warehouse (analysis) Package	532
Budget vs. Actual	532
Core products results.	532
Customer Returns and Satisfaction	533
Employee Satisfaction 2012.	533
Employee Training by Year	533
Eyewear Revenue by Brand and Size	534
Global Bonus Report	534
GO Balance Sheet as at Dec 31 2012.	534
Sample Outdoors Company Balance Sheet as at Dec 31 2012	535
Manager Profile	535
New order methods	535
Planned Headcount	535
Positions to Fill.	535
Promotion Plan Revenue	536
Promotion Success.	536
Quantity Sold vs. Shipped and Inventory	536
Recruitment Report	536
Return Quantity by Order Method	537
Returned Items.	537
Returns by Damage, Failed Orders and Complaints in 2012	537
Returns by Failed Orders in 2012.	537
Returns by Order Method	538
Returns by Order Method - Prompted Chart	538
Revenue by GO Subsidiary 2011	538
Sales Commissions for Central Europe	539
Sales Growth Year Over Year	539
Sales target by region.	539
Succession Report	539
Top 10 Retailers for 2011.	539
Samples in the GO Data Warehouse (query) Package	540
Advertising-cost vs revenue	540
Burst Sales Performance Report	540
Employee Expenses (report)	540
Health Insurance	540
Pension Plan	541
Regular Salary	541
TOC Report	541
Total Revenue by Country or Region	541
Samples in the GO Sales (analysis) Package	541
2011 Quarterly Sales Forecast	541
2011 Sales Summary	542

Samples in the GO Sales (query) Package	542
Active Report Techniques	542
Briefing Book	542
Film strip.	542
Horizontal Pagination	543
Matrix-chart and graph	543
Order Invoices - Donald Chow, Sales Person	543
No Data	543
PDF Page Properties	543
Product details	544
Sales analysis	544
Sales Dashboard	544
Singletons on Page Body	544
Table of Contents	544
Visualization sample reports	544
Employee Satisfaction - Accessible	544
Returns by Order Method - Accessible	545
Revenue by Order Method - Accessible.	545
Sales Growth Year Over Year - Accessible	545
Interactive Samples	545
Burst Sales Performance Report	545
Percentage Calculation (by year)	546
Recruitment Report	546
Revenue by GO Subsidiary 2011	546
Rolling and Moving Averages	547
Top 10 Retailers for 2011.	547
Prompt API samples	547
Clear prompt selections	547
Date prompt presets	547
Display all prompt values ignoring user selections	547
Display user selected prompt values.	547
Filter country by letter	548
Limit date prompt selection by database value	548
Limit numeric prompt selection by database value	548
Limit time between two dates	548
Limit user selection to two items	548
Pass parameter via hidden prompt	548
Personal default prompt selections - set selections	548
Personal default prompt selections - use selections	548
Validate prompt values when button pushed	548
Validate type-in postal code values	548
Validate type-in product line code	548

Appendix D. Limitations when using dimensional data sources. 549

Running a Report Against a Dimensional Data Source.	549
Limitations When Using Set Expressions in List Reports	550
Limitations When Using Clauses in Summary Functions	550
Limited Support for Relational Functions When Used with OLAP Data Sources	551
Limitations When Summarizing Measures in DMR Data Sources	552
Limitations When Filtering Dimensional Data Sources.	552
Error Characters (--) When Filtering	553
Limitations When Specifying the Scope of Summary Filters with Dimensional Data Sources	553
Limitations When Filtering Data Using an SAP BW Data Source	554
Considerations when Creating Calculations	555
Calculation Solve Order	555
Length of Expressions	555
Quality of Service Indicators	555
Using Quotation Marks in Literal Strings	556
Limitations of calculations in dimensional reporting	556
Creating Expressions Using SAP BW Data Sources	556
Using Microsoft Excel Functions with SSAS 2005 Data Sources	557

Concatenating Strings	557
Intersecting Calculations in Crosstabs and Charts	557
Null (Missing) Values in Calculations and Summaries	560
Dimensional Coercion Rules	562
Recommendation - Use Member Unique Name (MUN) Aliases	565
Limitations When Formatting Empty Cells in SAP BW Data Sources	566

Appendix E. Limitations When Producing Reports in Microsoft Excel Format. 567

Unable to Load Images from the IBM Cognos Business Intelligence Content Store in a Report	567
Blank Worksheet Appears	567
Warning Message Appears When Excel Opens an IBM Cognos Business Intelligence Report	567
Spreadsheet Content Not Saved for Reports Saved in XLS Format	567
Unable to Load Excel Report in Netscape 7.01	568
Unable to Nest Labels in Charts	568
Data Series Are Truncated	568
Colors Different From Those in HTML or PDF	568
Repeating Pie Charts	568
Unable to Skip Discrete Axis Labels	568
Unsupported IBM Cognos BI Formatting	568
Cells Contain Series of #.	569
Table and Column Widths	569
Secure Socket Layer (SSL) Is Not Supported in Some Excel Formats and Versions	569
Number Formats Become Currency Formats in Japanese Excel	570
Reports Show Data in Wrong Columns	570
Unable to Access Reports on Remote Servers	570
Drill-through Reports Are Not Supported in Excel	570
Map Reports Are Not Supported in Excel	570
Unsupported Excel Formatting	570
Hyperlink Buttons Are Not Supported in Excel	571
Unable to View Reports in Excel Format Sent as Email Attachments	571
Many items on axis produces empty chart in Excel	571
Chart legend titles are not supported in Excel	571
Unsupported Chart Properties in Excel	571
Unsupported Chart Types in Excel	572
Cell Height and Width Are Incorrect	573

Appendix F. Using the expression editor. 575

Operators	575
(.	575
).	575
*.	575
/.	575
/	575
.	575
+	576
-.	576
<	576
<=	576
<>	576
=	576
>	576
->	577
>=	577
and.	577
auto	577
between	577
case	577
contains	578
currentMeasure.	578
default	578

distinct	578
else.	578
end.	578
ends with	579
escape.	579
for	579
for all	579
for any	579
for report.	579
if	580
in	580
in_range	580
is missing	581
is null	581
is not missing	581
is not null	581
like.	581
lookup	582
not	582
or	582
prefilter	582
rows	582
rows	583
starts with	583
then	583
when	583
Summaries	583
Statistical functions	583
aggregate.	592
average	592
count	593
maximum	593
median	593
minimum.	593
moving-average	594
moving-total.	594
percentage	595
percentile.	595
quantile	596
quartile	597
rank	597
running-average	598
running-count	598
running-difference.	599
running-maximum	600
running-minimum.	600
running-total	601
total	601
Member Summaries	602
aggregate.	602
average	602
count	602
maximum	602
median	603
minimum.	603
percentage	603
percentile.	603
quantile	604
quartile	604
rank	604
standard-deviation	604

standard-deviation-pop	604
total	605
variance	605
variance-pop	605
Constants	605
date	605
date-time	605
time with time zone	605
timestamp with time zone	605
interval	605
interval year	605
interval month	605
interval year to month	606
interval day	606
interval hour	606
interval minute	606
interval second	606
interval day to hour	606
interval day to minute	606
interval day to second	606
interval hour to minute	606
interval hour to second	606
interval minute to second	606
null	606
number	606
string	606
time	606
Constructs	607
if then else	607
in_range	607
search case	608
simple case	608
Business Date/Time Functions.	608
_add_seconds	608
_add_minutes	609
_add_hours	609
_add_days	610
_add_months	610
_add_years	611
_age	612
_day_of_week	612
_day_of_year	612
_days_between	613
_days_to_end_of_month	613
_first_of_month	613
_last_of_month	614
_make_timestamp	614
_months_between	614
_shift_timezone	615
_week_of_year	616
_years_between	616
_ymdint_between	617
Block Functions	617
_firstFromSet	617
_remainderSet	618
Aster Data	618
Aster Data String	618
Aster Data Data Type Formatting.	620
Aster Data Math	620
Aster Data Trigonometry	621
ascii	622

chr	622
current_schema	622
translate	622
date_trunc	622
version	622
DB2	623
DB2 Math	623
DB2 Trigonometry	623
ascii	625
ceiling	625
char	625
chr	625
concat	626
date	626
day	626
dayname	626
dayofweek	627
dayofweek_iso	627
dayofyear	627
days	628
dec	628
decimal	628
difference	628
digits	629
double	629
event_mon_state	629
float	629
hex	629
hour	629
insert	630
integer	630
int	630
julian_day	630
lcase	631
left	631
length	631
locate	631
long_varchar	632
ltrim	632
microsecond	632
midnight_seconds	632
minute	633
month	633
monthname	633
quarter	634
radians	634
repeat	634
replace	634
right	634
round	635
rtrim	635
second	635
sign	636
smallint	636
soundex	636
space	636
substr	636
table_name	637
table_schema	637
time	637
timestamp	637

timestamp_iso	637
timestampdiff	638
to_char	638
to_date	638
translate	638
trunc	639
truncate	639
ucase	639
value	640
varchar	640
week	640
year	640
Greenplum	641
Greenplum String	641
Greenplum Data type formatting	642
Greenplum Math	643
Greenplum Trigonometry	643
ascii	645
chr	645
current_database	645
current_schema	645
{current_user}	645
{session_user}	645
translate	645
date_trunc	646
version	646
Informix	646
Informix Math	646
Informix Trigonometry	646
cardinality	647
char_length	647
concat	647
date	648
day	648
extend	648
hex	648
initcap	649
length	649
lpad	649
mdy	649
month	649
nvl	649
octet_length	650
replace	650
round	650
rpad	650
substr	650
to_char	651
to_date	651
trunc	651
weekday	651
year	651
MS Access	652
MS Access Cast	652
MS Access Math	653
MS Access Trigonometry	653
ascii	653
ceiling	653
chr	654
concat	654
curdate	654

curtime	654
dayname	654
dayofmonth	654
dayofweek	655
dayofyear	655
hour	655
instr	655
lcase	655
left	655
length	656
locate	656
ltrim	656
minute	656
month	656
monthname	656
now	657
position	657
quarter	657
right	657
round	657
rtrim	657
sign	658
space	658
substr	658
substring	658
truncate	659
ucase	659
week	659
year	659
MySQL	659
MySQL String	659
MySQL Math	660
MySQL Trigonometry	661
ascii	662
database	662
schema	662
session_user	663
system_user	663
version	663
Netezza	663
Netezza Math	663
Netezza Trigonometry	663
Netezza Fuzzy	664
Netezza Phonetic	665
ascii	665
chr	665
decode	666
initcap	666
instr	666
lpad	666
ltrim	666
months_between	666
next_day	667
nvl	667
round	667
rpad	667
rtrim	667
substr	668
{current_db}	668
{current_user}	668
{session_user}	668

to_char	668
to_date	668
to_number	668
translate	669
date_trunc	669
trunc	669
version	669
Oracle	669
Oracle Math	669
Oracle Trigonometry	669
add_months	671
ascii	671
ceil	671
char_length	671
chr	671
concat	672
decode	672
dump	672
greatest	672
initcap	672
instr	672
instrb	673
least	673
length	673
lengthb	673
lpad	673
ltrim	673
months_between	674
new_time	674
next_day	674
nls_initcap	674
nls_lower	674
nls_upper	675
nvl	675
replace	675
round	675
rpad	675
rtrim	676
sign	676
soundex	676
substr	676
substrb	676
{sysdate}	677
to_char	677
to_date	677
to_number	678
translate	678
trunc	678
trunc	678
{user}	678
vsize	678
Paracel	679
Paracel String	679
Paracel Data type formatting	679
Paracel Math	680
current_database	680
current_schema	680
{current_user}	680
{session_user}	680
translate	680
version	680

Postgres	681
Postgres String	681
Postgres Data type formatting	682
Postgres Math	683
Postgres Trigonometry	683
ascii	685
chr	685
{current_db}	685
{current_catalog}	685
{current_schema}	685
{current_user}	685
{session_user}	685
translate	685
date_trunc	686
version	686
Red Brick	686
ceil	686
concat	686
{current_user}	686
date	686
dateadd	687
datediff	687
datename	687
dec	687
decimal	687
decode	687
float	688
ifnull	688
int	688
integer	688
length	688
lengthb	688
ltrim	689
nullif	689
positionb	689
real	689
round	689
rtrim	689
sign	690
string	690
substr	690
substrb	690
time	690
timestamp	691
timestamp	691
to_char	691
SAP BW	691
SAP BW Trigonometry	691
SAP BW Math	692
Salesforce.com	692
Date Functions	692
convertCurrency	696
convertTimezone	696
SQL Server	696
SQL Server Math	696
SQL Server Trigonometry	697
ascii	698
char	698
charindex	698
{current_user}	699
datalength	699

dateadd	699
datediff	699
datetime	699
datepart	700
day	700
difference	700
getdate	700
isnull	701
left	701
ltrim	701
month	701
patindex	701
replace	702
replicate	702
reverse	702
right	702
round	702
rtrim	702
sign	703
soundex	703
space	703
str	703
stuff	703
year	703
Sybase	704
Sybase Math	704
Sybase Trigonometry	704
ascii	706
char	706
charindex	706
datalength	706
dateadd	706
datediff	707
datetime	707
datepart	707
day	707
difference	708
getdate	708
left	708
ltrim	708
month	708
patindex	709
rand	709
replicate	709
reverse	709
right	709
round	709
rtrim	710
soundex	710
space	710
str	710
stuff	710
substring	711
to_unichar	711
uhighsurr	711
ulowsurr	711
uscalar	711
year	712
Teradata	712
Teradata Trigonometry	712
account	714

add_months	714
bytes	714
case_n	714
char2hexint	714
characters	714
database	715
date	715
format	715
index	715
log	715
nullif	715
nullifzero	715
profile	715
random	716
role	716
session	716
soundex	716
substr	716
time	716
type	717
user	717
vargraphic	717
zeroifnull	717
Vectorwise	717
Vectorwise String	717
Vectorwise Math	718
Vectorwise Trigonometry	718
{initial_user}	719
{session_user}	719
numeric_trunc	719
Vertica	720
Vertica String	720
Vertica Data type formatting	721
Vertica Math	722
Vertica Trigonometry	722
ascii	723
chr	724
current_database	724
current_schema	724
{current_user}	724
{session_user}	724
translate	724
date_trunc	724
version	724
Macro Functions	725
+	725
_add_seconds	725
_add_minutes	726
_add_hours	726
_add_days	727
_add_months	727
_add_years	728
array	728
csv	729
dq	729
getConfigurationEntry	729
grep	730
_first_of_month	730
_last_of_month	730
join	731
lstrip	731

prompt	731
promptmany	732
rstrip	733
sb	734
sq	734
sort.	734
split	734
strip	735
substitute.	735
timestampMask	736
toLocal	737
tolower	737
toupper	738
toUTC.	738
unique	739
urlencode	739
CSVIdentityName	739
CSVIdentityNameList	739
CAMPassport	740
CAMIDList	740
CAMIDListForType	740
simple case	741
Common Functions	741
abs	741
cast.	741
ceil	742
ceiling.	742
char_length	743
character_length	743
coalesce	743
current_date.	743
current_time.	744
current_timestamp.	744
exp	744
extract.	744
floor	745
ln	745
localtime	745
localtimestamp	746
lower	746
mod	746
nullif	746
octet_length	747
position	747
power	747
_round	748
row	748
sqrt.	749
substring	749
trim	749
upper	750
width-bucket	750
Trigonometric functions	751
Dimensional Functions	753
ancestor	753
ancestors	754
bottomCount	754
bottomPercent	755
bottomSum	755
caption	755
children	756

closingPeriod	756
cousin	757
completeTuple	757
currentMember	758
defaultMember	758
descendants	759
except	761
filter	761
firstChild	761
firstSibling	762
_format	762
emptySet	762
generate	763
head	763
hierarchize	764
hierarchy	764
item	765
intersect	765
lag	765
lastChild	765
lastPeriods	766
lastSibling	766
lead	767
level	767
levels	768
linkMember	768
members	768
nextMember	769
openingPeriod	769
order	770
ordinal	771
parallelPeriod	771
parent	772
periodsToDate	772
prevMember	772
member	773
nestedSet	773
set	773
siblings	774
tail	774
topCount	774
topPercent	775
topSum	775
tuple	776
union	776
roleValue	776
rootMember	777
rootMembers	777
subset	778
unique	778
value	778
Report Functions	779
Today	779
Now	779
AsOfDate	779
AsOfTime	779
ReportDate	779
ReportName	780
ReportPath	780
ReportDescription	780
ReportLocale	780

GetLocale	780
Locale	780
ReportProductLocale	780
ReportAuthorLocale	780
ReportSaveDate	781
ReportCreateDate	781
ReportID	781
ReportOutput	781
ReportOption	781
ServerName	781
ServerLocale	781
ModelPath	782
BurstKey	782
BurstRecipients	782
IsBursting	782
ParamNames	782
ParamName	782
ParamDisplayValue	782
ParamValue	782
ParamCount	783
RowNumber	783
PageNumber	783
PageCount	783
IsPageCountAvailable	783
HorizontalPageNumber	783
HorizontalPageCount	783
PageName	783
URLEncode	784
TOCHeadingCount	784
IsAccessible	784
IsBooklet	784
ColumnNumber	784
IsCrosstabRowNodeMember	784
IsCrosstabColumnNodeMember	784
IsInnerMostCrosstabRowNodeMember	784
IsInnerMostCrosstabColumnNodeMember	785
IsOuterMostCrosstabRowNodeMember	785
IsOuterMostCrosstabColumnNodeMember	785
IsFirstColumn	785
IsLastColumn	785
IsLastInnerMostCrosstabColumnNodeMember	785
IsLastInnerMostCrosstabRowNodeMember	785
CubeName	786
CubeDescription	786
CubeCreatedOn	786
CubeDataUpdatedOn	786
CubeSchemaUpdatedOn	786
CubeIsOptimized	786
CubeDefaultMeasure	786
CubeCurrentPeriod	787
CellValue	787
InScope	787
Data Type Casting Functions	787
_add_days	787
_add_months	787
_add_years	787
_age	788
_day_of_week	788
_day_of_year	788
_days_between	788
_days_to_end_of_month	788

_first_of_month	789
_last_of_month	789
_make_timestamp	789
_months_between	789
_week_of_year	790
_years_between	790
_ymdint_between	790
abs	790
ceiling	790
character_length	790
date2string	791
date2timestamp	791
date2timestampTZ	791
DTinterval2string	791
DTinterval2stringAsTime	791
exp	791
extract	792
floor	792
int2DTinterval	792
int2YMinterval	792
ln	793
lower	793
mapNumberToLetter	793
mod	793
nullif	793
number2string	793
octet_length	794
position	794
power	794
round	794
sqrt	794
status	795
string2date	795
string2double	795
string2DTinterval	795
string2int32	795
string2int64	795
string2time	795
string2timestamp	795
string2timestampTZ	796
string2YMinterval	796
substring	796
time2string	796
timestamp2date	796
timestamp2string	796
timestamp2timestampTZ	797
timestampTZ2date	797
timestampTZ2string	797
timestampTZ2timestamp	797
timeTZ2string	797
trim	797
upper	797
YMinterval2string	798

Appendix G. Report Studio Object and Property Reference 799

Report Studio Objects	799
3-D Area	799
3-D Bar	799
3-D Combination Chart	800
3-D Line	800
3-D Scatter Chart	800

Angular Axis	801
Angular Measure	801
Area	801
Area	801
As of Time Expression	801
Axis Labels	802
Axis Title	802
Axis Title	802
Bar	802
Bar	802
Baseline	803
Baseline	803
Baseline	803
Baseline	803
Block	804
Bookmark	804
Bubble Chart	804
Bubble Chart	805
Bubble Measure	805
Bubble Measure	805
Bullet Chart	805
Bullet Measure	806
Button	806
Button	806
Button Bar	806
Button Label	807
Calculated Measure	807
Calculated Member	807
Calculated Member	807
Caption	807
Card	807
Category	808
Category Axis	808
Category axis	808
Category Baseline	808
Chart Body	808
Chart Body	809
Chart Footer	809
Chart Footer	809
Chart Measure	809
Chart Node Member	809
Chart Subtitle	810
Chart Subtitle	810
Chart Text Item	810
Chart Text Item	810
Chart Title	811
Chart Title	811
Check Box	811
Check Box Group	811
Check Box Label	811
Class	811
Color by Value Measure	812
Colored Region	812
Colored Region	812
Combination Chart	813
Combination Chart	813
Component Override	813
Conditional Block	814
Conditional Block	814
Context Item Text	814
Continuous Values Slider	814

Crosstab	815
Crosstab Columns	815
Crosstab Columns	815
Crosstab Corner	816
Crosstab Fact Cells	816
Crosstab Intersection	816
Crosstab Member Fact Cells	817
Crosstab Node Member	817
Crosstab Rows	817
Crosstab Rows	818
Crosstab Space	818
Crosstab Summary	818
Cumulation Label	819
Cumulation Line	819
Cumulation Line	819
Cumulation Line	819
Cumulation Line Axis	819
Cumulation Line Label	819
Custom Groups	820
Data Button Bar	820
Data Check Box Group	820
Data Container	820
Data Deck	821
Data Discrete Values Slider	821
Data Drop-Down List	821
Data Item	821
Data Iterator.	822
Data List Box	822
Data Radio Button Group	822
Data Tab Control	823
Data Toggle Button Bar	823
Date	823
Date & Time Prompt	823
Date Prompt.	824
Deck	824
Default Measure	824
Default Measure	824
Default Measure	824
Detail Filter	825
Dimension	825
Dimensional Edge Summary	825
Discrete Values Slider	825
Display Layer	825
Drop-Down List	826
Edge Summary.	826
Equation Label	826
Equation Label	826
Explicit Member Set	826
Extra Category	827
Extra Value	827
Fact	827
Field Set	827
Gauge Axis	827
Gauge Chart.	828
Gauge Chart.	828
Gauge Labels	829
Gauge Numerical Axis	829
Generated Prompt.	829
Hierarchy Set	829
HTML Item	829
Hyperlink	830

Hyperlink Button	830
Image	831
Intersection (Tuple)	831
Interval Prompt	831
Iterator	831
Iterator First	832
Iterator Label Area	832
Iterator Last	832
Iterator Next	832
Iterator Previous	832
Iterator Value Label	833
Join	833
Key	833
Label	833
Layout Component Reference	833
Legend	833
Legend	834
Legend Title	834
Legend Title	834
Level	834
Level Hierarchy	835
Level Set	835
Line	835
Line	835
List	835
List Box	836
List Cell	836
List Column	836
List Column Body	837
List Columns	837
List Columns	837
List Columns Body Style	838
List Columns Title Style	838
List Column Title	838
List Footer	839
List Header	839
List Item	839
List Item Label	839
List Page Footer	839
List Page Header	840
List Row	840
List Row Cells Style	840
List Summary	840
List Summary	840
Map	841
Map Location	841
Map Location	841
Map Refinement Location	841
Map Refinement Location	842
Marimekko Chart	842
Marker	842
Marker	843
Marker	843
MDX	843
Measure	843
Member	844
Member Children Set	844
Member Hierarchy	844
Member Property	844
Member Property	844
Member Set	844

Metrics Range Chart	845
Metric Studio Diagram	845
Named Set	845
Node	845
Note	846
Note	846
Note Content	846
No Value List Item	846
Numerical Axis.	846
Numerical Axis.	847
Numeric Axis	847
Numeric Baseline	847
Page	847
Page Body	847
Page Break Text	848
Page Footer	848
Page Header	848
Page Number	848
Page Set	848
Pareto Bars	848
Pareto Chart.	849
Pareto Chart.	849
Percentaged Measure.	850
Pie Chart	850
Pie Chart	850
Pie Labels	851
Point Color Legend Title	851
Point Layer	851
Point Measure	852
Point Size Legend Title	852
Point Size Measure	852
Polar Chart	852
Primary Axis	853
Primary Bottom Axis	853
Progressive Chart	853
Progressive Chart	854
Prompt Button	854
Queries	854
Query	854
Query Operation	855
Query Reference	855
Radar Chart	855
Radial Axis	855
Radial Measure.	856
Radio Button	856
Radio Button Group	856
Radio Button Label	856
Region Color Legend Title	856
Region Layer	857
Region Measure	857
Regression Line	857
Regression Line Label	857
Repeater	857
Repeater Table	857
Repeater Table Cell	858
Repeater Table Cell	858
Report Reference	858
Rich Text Item	859
Row Number	859
Row Number	859
Scatter Chart	859

Scatter Chart	860
Scatter Marker	860
Secondary Axis	861
Secondary Bottom Axis	861
Select & Search Prompt	861
Set Expression	861
Singleton	862
Slicer Member Set	862
Slider Value Label	862
SQL	862
Static Repeater Table	862
Summary Filter	863
Tab	863
Tab Control	863
Table	863
Table Cell	863
Table of Contents	864
Table of Contents Entry	864
Table Row	864
Target Measure	864
Target Measure	864
Text Box Prompt	865
Text Item	865
Time	865
Time Prompt	866
Toggle Button Bar	866
Tolerance Measure	866
Total Column	866
Total Column Label	867
Tree Prompt	867
Trendline	867
Trendline Label	867
Value	867
Value	867
Value	867
Value Prompt	868
Variable	868
Variable Text Item	868
Visualization	868
Win-Loss Chart	869
Win-Loss Measure	869
X Axis	869
X Axis	869
X Axis	870
X Axis Measure	870
Y1 Axis	870
Y2 Axis	870
Y Axis	871
Y Axis	871
Y Axis	871
Y Axis Measure	871
Z Axis	871
Z Axis	872
Z Axis Measure	872
Report Studio Properties	872
3-D Viewing Angle	872
Absolute Position	872
Across	872
Active Dot Color	873
Active Report Variable	873
Actual Measure	873

Aggregate Data Item	873
Aggregate Function	873
Aggregation Method	874
Aggregation Method	874
Allow 45° Rotation	874
Allow 90° Rotation	874
Allow Skip	874
Allow Sorting	874
Allow Stagger	874
Allow Ties	875
Alternate Text	875
Angular Axis	875
Animate	875
Application	875
Application Drill-Through	876
Apply Single Class	876
Area Shape	877
Auto Font Size	877
Auto Group & Summarize	877
Auto Select	877
Auto-Sort.	877
Auto-Submit	877
Auto Truncation	878
Avoid Division by Zero	878
Avoid Label Collision	878
Axis Angles	878
Axis Assignment	878
Axis Assignment	878
Axis Justification	878
Axis Labels	879
Axis Labels	879
Axis Line.	879
Axis Line.	879
Axis Line.	879
Axis Range	880
Axis Title.	880
Axis Title.	880
Axis Title.	880
Background Color	881
Background Effects	881
Background Image	882
Bar, Line, or Area Index	882
Bar Shape	883
Bar Width	883
Based on	883
Baselines	883
Bevel	883
Block Variable	883
Border.	884
Border Color	884
Border Color	884
Borders	885
Borders	885
Borders	885
Bottom Position	885
Bottom Position (px)	885
Bottom Position (px)	885
Box Type	886
Box Type	886
Bubble Size	887
Bubble Size	887

Bullet Indicators	887
Button Definition	887
Button Gap	887
Buttons Definition	887
Button Width	888
Button Width	888
Calculation Intersection	888
Calendar Type	888
Caption	888
Caption	888
Cardinality	889
Cascade Source	889
Case Insensitive	889
Catalog	889
Category Axis	889
Category Baselines	889
Category Range	890
Category Range	890
Chart Orientation	890
Chart Type	890
Chart Type	890
Chart Type	891
Check Boxes Definition	891
Choices Deselect All Text	891
Choices Select All Text	891
Choices Text	891
Classes	891
Clickable Region	892
Clickable Region	892
Clickable Regions	893
Clickable Regions	893
Clock Mode	893
Color by Value	893
Colored Regions	893
Color Legend Title	894
Color Legend Title	894
Column Coordinate	894
Column Titles	894
Column Visibility	894
Combinations	895
Component Reference	895
Component Reference	895
Conditional Palette	895
Conditional Palette	895
Conditional Styles	895
Connecting Lines	896
Connecting Lines	896
Contained Text Direction	897
Container Filter	897
Container Selection	897
Contents Height	898
Control Data Item Value	898
Control Data Item Value	898
Control Data Item Value	898
Control Enable	899
Cross Product Allowed	899
Cumulation Axis	899
Cumulation Label	899
Cumulation Label	899
Cumulative Line	899
Cumulative Line	900

Current Block	900
Current Card	900
Current Tab	900
Custom Label	900
Custom Label	900
Data Format.	900
Data Format.	901
Data Format.	901
Data Item	901
Data Item	902
Data Item Label	902
Data Item Label	902
Data Item Label	902
Data Item Label	902
Data Item Label	902
Data Item Value	902
Data Item Value	903
Data Item Value	903
Data Item Value	903
Data Item Value	903
Data Item Value	903
Data Item Value	903
Data Item Value	903
Data Item Value	903
Data Item Value	903
Data Item Value	903
Data Language	904
Data Points	904
Data Source	904
Days Text	904
Deck Cards Definition	904
Default Card	904
Default Card	904
Default Measure	905
Default Selections	905
Default Title.	905
Default Title.	905
Define Contents	905
Define Custom Grouping	905
Define Member Sets	905
Definition	906
Depth	906
Description	906
Deselect Text	906
Detail	906
Diagram Identifier.	907
Dial Face Fill	907
Dial Outline Color.	907
Dictionary	907
Dimension	907
Direction & Justification	907
Display After Overall Header	908
Display for Orientation	908
Display Frequency.	909
Display Milliseconds	909
Display Seconds	909
Display Value	909
Display Values	910
Dot Color	910
Down	910
Drill-Through Definitions	910
Drop-Down Width.	911
Drop Shadow	911
Drop Shadow	911
Duplicates	911

Embed	911
Empty Item Label	911
End Position.	912
Execution Method	912
Execution Optimization	912
Expand Features	912
Exploded Slices.	912
Expression	913
Expression	913
Expression	913
Expression	913
Extend Width	913
Face Color	914
Fact Cell Data Format	914
Fact Cells Precedence.	914
Fill Effects	914
Filter Type	914
First Column Color	914
First Date.	915
First Label Index	915
First Slice Angle	915
Floating	915
Font	916
Font Auto-Sizing	916
Footer	916
Footer	917
Foreground Color	917
From Text	917
Gauge Axes	917
Gauge Axis Colors	918
Gauge Axis Inner Radius	918
Gauge Axis Outer Radius	918
Gauge Border	918
Gauge Labels	918
Gauge Needle	918
Gauge Palette	918
Gauge Pivot.	919
Generated SQL	919
Gradient	919
Gridlines	919
Gridlines	919
Gridlines	919
Gridlines	919
Grouping & Sorting	919
Grouping Type	920
Group Span	920
Has Fact Cells	920
Header Text	920
Heading Level	920
Height (px)	920
Hide Adornments	921
Hide Text.	921
Hierarchy	921
Hierarchy Unique Name	921
Highest Value Text	922
Hole Size (%)	922
Horizontal Alignment	922
Hours Text	923
HTML.	923
HTML Source Variable	923
Icon	923
Ignore Data with No Features	923

Ignore Hover when No Data	923
Include Zero For Auto Scale	923
Inherited Style	924
Insert Text	924
Iterator First.	924
Iterator Label Area	924
Iterator Last	924
Iterator Next	924
Iterator Previous	925
Iterator Values Definition	925
Join Relationships	925
Keywords Text	925
Label	925
Label	925
Label	925
Label	926
Label	926
Label	926
Label	926
Label	926
Label	926
Label	926
Label	926
Label	926
Label	926
Label	926
Label Color	927
Label Control	927
Label Control	927
Label For.	927
Label Location	927
Labels	928
Last Date.	928
Layout Table	928
Left Position.	928
Left Position (px)	928
Left Position (px)	928
Legend	928
Legend	929
Legend Label	929
Legend Separator	929
Legend Title.	929
Legend Title.	929
Legend Title.	929
Level	930
Level Indentation	930
Level Unique Name	930
Line and Markers	930
Line Shape	931
Line Style	931
Line Style	931
Line Style	931
Line Styles	931
Line Type	931
Line Weight (pt)	931
List Items Definition	932
Loss Color	932
Lowest Value Text	932
Map & Layers	932
Map Drills	932
Margin	932
Marimekko Totals	933
Marker Color	933
Marker Color	933
Marker Label	933

Markers	933
Markers	934
Marker Shape	934
Marker Shape	934
Marker Size (pt)	934
Marker Size (pt)	934
Marker Style	934
Marker Text Location	935
Master Detail Relationships	935
Material Effects	935
Material Effects	935
Matrix Rows and Columns	936
Maximum Characters	936
Maximum Execution Time	936
Maximum Hotspots	936
Maximum Rows Retrieved	937
Maximum Size (pt)	937
Maximum Tables	937
Maximum Text Blob Characters	937
Maximum Truncation Characters	937
Maximum Value	938
Maximum Value	938
MDX	938
Member	938
Member Offset (%)	938
Members	939
Members	939
Member Unique Name	939
Milliseconds Text	939
Minimum Size (pt)	939
Minimum Value	940
Minimum Value	940
Minor Gridlines	940
Minor Gridlines	940
Minor Gridlines	940
Minor Gridlines	940
Minutes Text	941
Multi-Line	941
Multi-Select	941
Name	941
Name	941
Name	942
Name	942
Name	942
Name	942
Name	942
Name	942
Name	942
Name	943
Name	943
Name	943
Name	943
Name	943
Name	943
Name	943
Name	943
Name	943
Name	944
Name	944
Name	944
Negative Column Color	944
Nested Label Display	944
Nesting Order	944
No Data Contents	945
No Data Features Size (pt)	945
Node Coordinate	945
Note Border	945

Notes	945
Notes	946
Note Text.	946
No Value List Item	946
Number of Minor Intervals.	946
Number of Minor Intervals.	946
Number of Regression Lines	947
Number of Stagger Levels	947
Numbers Only	947
Number Style	947
Number Style	947
Numerical Axis.	947
Numerical Axis.	947
Numeric Baselines.	948
Numeric Value	948
Numeric Value	948
Numeric Value	948
Options Text.	948
Orientation	948
Outer Join Allowed	949
Output Aggregation Method	949
Output Aggregation Method	949
Override Dimension Info	949
Overrides	949
Padding	949
Pagination	950
Palette.	950
Palette.	951
Palette.	951
Parameter	951
Pareto Axis	951
PDF Page Setup	951
Percentage Based On	951
Percentile.	952
Percentile.	952
Percentile.	952
Percent of Axis	952
Percent of Axis	952
Percent of Axis	952
Performance Pattern	953
Pie Labels	953
Plot Area Fill	953
Point Shape	953
Polynomial Exponent.	953
Position	953
Position	953
Position in List	954
Position type	954
Position type	954
Position type	954
Position type	954
Positive Column Color	954
Pre-populate.	954
Pre-populate Levels	954
Pre-Sort	955
Processing	955
Progressive Axis	955
Progressive Palette	955
Projection List	956
Properties	956
Property	956
Property Unique Name	956

Push To Bottom	957
Query	957
Query	957
Radar Type	958
Radial Axis	958
Radio Buttons Definition	958
Range	958
Range Label	958
Range Type	959
Referenced Report	959
Regression Line	959
Regression Type	959
Relative Alignment	959
Remove Text	960
Render	960
Render Fact Cells	960
Render Method	960
Render Page when Empty	960
Render Variable	961
Repeater Direction	961
Repeater Table Values Definition	962
Report Expression	962
Report Expression	962
Report Expression	962
Report Expression	962
Report Expression	962
Report Expression	962
Report Expression	963
Report Expression	963
Report Expression	963
Report Expression	963
Report Expression	963
Report Expression	963
Report Expression	963
Report Expression	963
Required	963
Results Deselect All Text	964
Results Select All Text	964
Results Text	964
Reverse	964
Reverse Category Order	964
Right Position	964
Right Position (px)	965
Rollup Aggregate Function	965
Rollup Method	965
Rollup Processing	965
Roll Up Table of Contents	965
Root Members Only	966
Rotate Values	966
Rotation Angle	966
Row Coordinate	966
Rows Per Page	967
Saved Parameter Values	967
Scale	967
Scale Interval	967
Scope	967
Search Instructions Text	968
Search Text	968
Seconds Text	968
Select UI	968
Select UI	968
Select UI	968
Select UI	968
Select UI	969
Select UI	969

Separator	969
Series Color	969
Series Type	969
Set Operation	969
Set Sorting	970
Set Variable Values	970
Share Result Set	970
Show Caption	971
Show Data Points	971
Show Data Range in Legend	971
Show Features with No Data	971
Show Feelers	971
Show Hover.	971
Show Hover.	972
Show Icon	972
Show Icon	972
Show Labels.	972
Show Legend Values	972
Show line	972
Show Pointer Cursor	972
Show Prompt Pages	973
Show Tooltip	973
Show Values.	973
Show Values.	973
Show Values.	973
Show Values.	974
Show Values.	974
Show Values.	974
Show Values.	974
Show Values.	974
Size	974
Size & Overflow	974
Size & Overflow	975
Size Legend Title	975
Slice Direction	975
Slide Animation Direction	975
Slider Values Definition	976
Solve Order	976
Solve Order	976
Sorting	976
Source Type	976
Source Type	977
Source Type	977
Source Type	977
Spacing & Breaking	977
Spider Effects	977
SQL	977
SQL Join Syntax	978
SQL Syntax	978
Standard Deviations	978
Standard Deviations	978
Standard Deviations	978
Start Heading Level	979
Start Position	979
Static Choices	979
Step	979
Style Variable	979
Subtitle	980
Subtitle	980
Summarize Small Items	980
Summarize Small Slices	980
Summary Text	981

Suppress	981
Suppression	981
Table Header	981
Table of Contents	982
Table of Contents Entry	982
Table of Contents Name	982
Table Properties	982
Tab Orientation	982
Tabs Definition	982
Tab Width	982
Target Color	983
Target Marker	983
Target Marker Border Color	983
Target Marker Position	983
Target Range (%)	983
Text	983
Text Color	983
Text Color	984
Text Orientation	984
Text Source Variable	984
Text Truncation	984
Tick Interval	984
Tick Interval	984
Tick Label Skip Interval	985
Tick Type	985
Title	985
Title	985
Title	985
Tolerance Color	985
Tolerance Label	986
Tooltips	986
Tooltips	986
Tooltips	986
Tooltips	986
Tooltips	986
Top Position	987
Top Position (px)	987
Total Column	987
Total Column	987
Total Column Color	987
To Text	987
Track Length	988
Trendline Label	988
Trendlines	988
Truncation	988
Truncation Text	988
Type	988
Type	989
Type	989
Type	989
Type	989
Update Variables Live	989
Upper Range Skew (%)	989
URL	990
URL	990
URL Source Variable	990
Usage	990
Use 1.x Behavior	990
Use Aggregate Cache	990
Use Decimal	990
Use Detail Value on Page	991

Use Embedded Data	991
Use for Parameter Info	991
Use Local Cache	991
User SAP Member Cache	991
Use Same Range For All Instances	992
Use SAP MUN as Business Key	992
Use Set Aggregation	992
Use SQL Parameters	992
Use SQL With Clause.	993
Use Thousands Separator	993
Use Value	993
Use Value	993
Value Location:	993
Value Markers	993
Value Range.	994
Value Representation	994
Values.	994
Values.	994
Values.	994
Values.	994
Value Type	995
Variable	995
Variable for Maximum	995
Variable for Minimum	995
Vertical Alignment.	995
Visible.	995
Visible.	996
Visual Angle	996
White Space.	996
Width (px)	997
Win Color	997
Win-Loss Threshold	997
X Axis.	997
X Axis.	997
X-Axis Data Item Value	998
Y1 Axis	998
Y2 Axis	998
Y2 Axis Position	998
Y Axis.	998
Y Axis.	998
Y-Axis Data Item Value	999
Data Formatting Properties	999
"Not Applicable" Characters	999
Any Error Characters.	999
Calendar Type	999
Clock	999
Currency	999
Currency Display	999
Currency Symbol	999
Currency Symbol Position.	1000
Date Ordering.	1000
Date Separator	1000
Date Style	1000
Decimal Separator	1000
Digit Shaping	1000
Digit Shaping	1000
Display AM / PM Symbols	1000
Display As Exponent	1000
Display Days	1001
Display Eras	1001
Display Hours.	1001

Display Milliseconds	1001
Display Minutes	1001
Display Months	1001
Display Months	1001
Display Seconds	1001
Display Time Zone	1001
Display Weekdays	1002
Display Years	1002
Display Years	1002
Divide By Zero Characters	1002
Exponent Symbol	1002
Group Size (digits)	1002
International Currency Symbol	1002
Mantissa (digits)	1002
Maximum No. of Digits	1002
Minimum No. of Digits	1002
Missing Value Characters	1003
Negative Pattern	1003
Negative Sign Position	1003
Negative Sign Symbol	1003
No. of Decimal Places	1003
Numeric Overflow Characters	1003
Padding Character	1003
Pattern	1003
Percentage Symbol	1003
Percent Scale (integer)	1003
Scale	1004
Secondary Group Size (digits)	1004
Security Error Characters	1004
Thousands Separator	1004
Time Separator	1004
Time Style	1004
Time Unit	1004
Use Thousands Separator	1004
Zero Value Characters	1004

Appendix H. Prompt API for IBM Cognos BI. 1005

cognos.Prompt object	1005
cognos.Prompt.getControlByName method	1005
cognos.Prompt.getControls method	1006
cognos.Prompt.Control object	1006
cognos.Prompt.Control.addValues method	1006
cognos.Prompt.Control.clearValues method	1007
cognos.Prompt.Control.getName method	1007
cognos.Prompt.Control.getValues method	1008
cognos.Prompt.Control.setValidator method	1009
cognos.Prompt.Control.setValues method	1009
cognos.Report object	1010
cognos.Report.getReport method	1010
cognos.Report.sendRequest method	1011
cognos.Report.Action object	1011
cognos.Report.Action.BACK	1011
cognos.Report.Action.CANCEL	1011
cognos.Report.Action.FINISH	1011
cognos.Report.Action.NEXT	1011
cognos.Report.Action.REPROMPT	1012
cognos.Value class	1012

Notices	1013
Glossary	1017
A	1017
B	1018
C	1018
D	1019
E	1020
F	1020
G	1020
H	1020
I	1020
J	1021
L	1021
M	1021
N	1022
O	1022
P	1022
Q	1023
R	1023
S	1024
T	1024
U	1025
V	1025
W	1025
Index	1027

Introduction

This document is intended for use with IBM® Cognos® Report Studio. It provides step-by-step procedures and background information to help you create standard and complex reports. Report Studio is a Web product for creating reports that analyze corporate data according to specific information needs.

Finding information

To find product documentation on the web, including all translated documentation, access IBM Knowledge Center (<http://www.ibm.com/support/knowledgecenter>).

Accessibility features

Accessibility features help users who have a physical disability, such as restricted mobility or limited vision, to use information technology products. Report Studio has accessibility features. For more information, see Appendix A, “Accessibility Features,” on page 485.

IBM Cognos HTML documentation has accessibility features. PDF documents are supplemental and, as such, include no added accessibility features.

Forward-looking statements

This documentation describes the current functionality of the product. References to items that are not currently available may be included. No implication of any future availability should be inferred. Any such references are not a commitment, promise, or legal obligation to deliver any material, code, or functionality. The development, release, and timing of features or functionality remain at the sole discretion of IBM.

Samples disclaimer

The Sample Outdoors Company, Great Outdoors Company, GO Sales, any variation of the Sample Outdoors or Great Outdoors names, and Planning Sample depict fictitious business operations with sample data used to develop sample applications for IBM and IBM customers. These fictitious records include sample data for sales transactions, product distribution, finance, and human resources. Any resemblance to actual names, addresses, contact numbers, or transaction values is coincidental. Other sample files may contain fictional data manually or machine generated, factual data compiled from academic or public sources, or data used with permission of the copyright holder, for use as sample data to develop sample applications. Product names referenced may be the trademarks of their respective owners. Unauthorized duplication is prohibited.

Chapter 1. What's New in Cognos Report Studio?

This section contains a list of new, changed, and removed features for this release. It will help you plan your upgrade and application deployment strategies and the training requirements for your users.

For information about upgrading, see the *IBM Cognos Business Intelligence Installation and Configuration Guide* for your product.

For information about other new features for this release, see the *IBM Cognos Business Intelligence New Features Guide*.

To review an up-to-date list of the environments that are supported by IBM Cognos products, including information about operating systems, patches, browsers, web servers, directory servers, database servers, and application servers, visit the Software Environments site (<http://www.ibm.com/support/docview.wss?uid=swg27042164>).

New features in version 10.2.2

This release of IBM Cognos Report Studio contains new features.

IBM Cognos Active Report preview

IBM Cognos Active Report has a preview view that you can use to format an active report and immediately see the layout changes. You no longer have to run the report whenever you make a formatting change.

Related tasks:

“Formatting an active report in the preview view” on page 210

IBM Cognos Active Report has a preview view that you can use to format an active report and immediately see the layout changes. You no longer have to run the report whenever you make a formatting change.

IBM Cognos Active Report output

You can produce an IBM Cognos Active Report in HTML format.

Consequently, you can now view active reports in browsers that do not have MIME HTML (MHT) capabilities.

Related tasks:

“Run or Save an Active Report” on page 212

You can run an active report in HTML format or save it as a MIME HTML (MHT) file so that you can send the report to your consumers. MHT files are viewable in the Microsoft Internet Explorer or Mozilla Firefox browsers.

IBM Cognos Active Report templates

You can convert an active report to a template so that formatting and styles can be reused.

Related tasks:

“Converting a Report to a Template” on page 469

Convert a new or existing report to a template so it can be reused. You can use sample reports that are provided with IBM Cognos Report Studio.

Reusable report styles

In IBM Cognos Report Studio, you can apply styles that come from one report in another report.

Related tasks:

“Reusing styles from another report” on page 366

You can apply local and global styles from one report in another report.

Slider orientation in IBM Cognos Active Report

In IBM Cognos Active Report, you can show sliders horizontally or vertically.

The orientation of a slider is set by clicking the **Orientation** property.

Tabbed reports in HTML output

When an IBM Cognos Report Studio report is run in HTML format, you can show each report page in its own tab. Report page names are used to name each tab.

This option is set in the Report Properties window (**File > Report Properties**).

In Excel output, each tab becomes a single sheet within the same workbook.

Related tasks:

“Producing tabbed reports” on page 468

When you produce reports in HTML format, you can show each report page as a tab.

Dynamically named worksheet tabs in Excel 2007 output

When you produce reports in Excel 2007 format, you can configure IBM Cognos Business Intelligence to dynamically name the Excel worksheet tabs, based on the data items that are used to break pages.

For example, you specify page breaks by Product line. In Excel 2007 output, the five worksheet tabs that are generated are named Camping Equipment, Mountaineering Equipment, Personal Accessories, Outdoor Protection, and Golf Equipment.

Related concepts:

“Page breaks, page sets, and page layers” on page 453

You can create simple page breaks, advanced page sets, or page layers to associate pages with a query structure to force page breaks.

New maps in IBM Cognos BI

This version of IBM Cognos Business Intelligence contains new maps. The new maps replace the maps that are in previous IBM Cognos BI releases.

Related concepts:

“New maps in IBM Cognos BI 10.2.2” on page 182

IBM Cognos Business Intelligence 10.2.2 contains new maps that replace the maps that are in previous releases.

Report run format restrictions

To manage system resources, IBM Cognos Business Intelligence administrators can now restrict the ability of users to run reports in the CSV, PDF, Microsoft Excel, and XML report output formats.

If your Cognos BI administrator implements these restrictions, you might not be able to run reports in all output formats.

Related tasks:

“Running a report” on page 50

Run your report to see the data that is retrieved. Save time by validating it first to check for errors.

Support for IBM Cognos Theme Designer

IBM Cognos Theme Designer provides a graphical user interface that makes it easy to tailor IBM Cognos BI applications to your brand requirements. You can replace images, change colors, or edit html to get the look you want. You can produce multiple themes for users to choose from or different themes for each tenant or application in multiple tenant environments.

In addition to existing support for Cognos Theme Designer by IBM Cognos Connection, IBM Cognos Viewer, and IBM Cognos Workspace, this version adds support by IBM Cognos Report Studio and IBM Cognos Workspace Advanced.

To download Cognos Theme Designer and its documentation, go to IBM Cognos Theme Designer Tool (www.ibm.com/support/docview.wss?rs=0&uid=swg24035533).

Improvements to the current default chart technology

Improvements were made to the IBM Cognos Business Intelligence current default chart technology. For example, new chart properties are available that control how labels are rendered.

With these improvements, you might see minor pixel differences in chart output or minor layout changes in data and axis label placement when you upgrade a report to IBM Cognos BI 10.2.2.

Related information:

“Label Control” on page 927

Controls how the labels in a chart are rendered.

Enhancements to extensible visualizations

Enhancements were made to extensible visualizations that simplify the authoring experience.

The following list describes the enhancements that were made to extensible visualizations.

- Optional category fields

When you add an extensible visualization to a report, it is no longer necessary to insert data items in all category drop zones. For example, you can create a visualization that has only a measure and categories, and no data series.

In previous IBM Cognos BI releases, you cannot run a visualization until all required data drop zones contain data items.

- Conversion of visualizations from one type to another

You can convert an existing visualization to another visualization type. With this enhancement, you do not have to re-author the data items in the original visualization.

- Support for more properties

Visualizations support more properties, giving report authors greater control over the appearance and behavior of visualizations in reports.

Related concepts:

Chapter 7, “Extensible visualizations,” on page 165

You can use extensible visualizations in IBM Cognos reports to visualize data.

“Visualization properties” on page 172

The properties that you can set for each visualization affect how you work with visualizations that are inserted in a report.

Related tasks:

“Converting visualizations from one type to another” on page 177

You can convert a visualization from one type to another type.

New features in version 10.2.1.1

This release of IBM Cognos Report Studio contains new features.

Extensible visualizations in regular reports

In IBM Cognos Report Studio version 10.2.1.1, you can now create extensible visualizations in regular reports.

In the previous release, extensible visualizations were supported only in IBM Cognos Active Report.

Related concepts:

Chapter 7, “Extensible visualizations,” on page 165

You can use extensible visualizations in IBM Cognos reports to visualize data.

Extensible visualization render method

When you add a visualization to an IBM Cognos Active Report, you can choose how the visualization is rendered.

You can choose to render visualizations on the IBM Cognos server or on the client. When visualizations are rendered on the Cognos server, they are rendered as static images. Client-side visualizations are rendered as JavaScript code. The render method that you choose has an impact on report size and performance.

Related tasks:

“Choosing where visualizations are rendered” on page 172

When you add a visualization to an IBM Cognos Active Report, you can choose to render the visualization on the IBM Cognos server or on the client.

Report booklets

In IBM Cognos Report Studio version 10.2.1.1, you can now create report booklets. A report booklet is a report that references other reports.

Related tasks:

“Creating a report booklet” on page 467

In an IBM Cognos Report Studio report, you can add references to other reports to create a report booklet. Each report reference represents a booklet item.

New features in version 10.2.1

The following topics describe the new features in this release.

Improved IBM Cognos Active Report performance

Active Report performance is improved in this release.

You can now compress Active Report output. The compression feature compresses Active Report controls within the output and produces files that are smaller and open faster. The compression feature significantly improves the performance of Active Reports that include large amounts data versus graphical content. The option to compress Active Report output is set in the **Active Report Properties** window.

In addition, improvements to the Active Report engine streamline performance, and result in improved memory consumption characteristics. With these improvements, large active reports perform better, particularly when they are consumed within the IBM Cognos Business Intelligence Mobile application.

Related tasks:

“Specify Active Report Properties” on page 195

You can specify properties for active reports, such as the text that appears in the browser window title bar, the maximum number of rows that a report can contain, and an access code that users must enter to view a report.

Extensible visualizations in IBM Cognos Active Report

With extensible visualizations, you can use innovative new visualizations in active reports.

IBM Cognos Business Intelligence introduces new visualizations to Report Studio, such as treemaps and packed bubble visualizations. Your administrator can download sample visualizations to a gallery that is accessible from the Active Report authoring environment. Sample visualizations can be used or modified to meet your requirements.

Related concepts:

Chapter 7, “Extensible visualizations,” on page 165

You can use extensible visualizations in IBM Cognos reports to visualize data.

Option to group or ungroup repeating cells in Excel 2007 reports

When you produce reports in Excel 2007 format, you can choose to group repeating cells into a single merged cell.

Grouped or ungrouped cells are produced by various report objects, such as grouped data items, headers and footers, and nested objects. The option to group or ungroup repeating cells is controlled by the **Group repeating cells when exporting to Excel** report property.

Related concepts:

“Option to group repeating cells in reports produced in Excel 2007 format” on page 54

When you produce reports in Excel 2007 format, you can specify whether repeating cells are grouped, or merged, into a single cell.

Crosstab values as percentages

In crosstabs, you can now show values as a percentage of a summary instead of the actual values. For example, you can show the revenue that was generated by each product line as a percentage of the total revenue.

Related tasks:

“Showing crosstab values as percentages” on page 76

When you work with dimensional data sources, you can show crosstab values as a percentage of a summary instead of the actual values. When you show values as a percentage, you can compare the contribution of an item to the whole.

Share sets between reports

When you work with dimensional data, you can now share a set. Shared sets appear in the model tree for inclusion in other reports.

When you include a shared set, you can designate it to be either **Run Time** or **Design Time**. If a set is designated as **Run Time**, the report always uses whatever is in the shared set as it is defined. If a set is designated as **Design Time**, the report caches the contents of the shared set at the time when it is initially included. The report uses this definition until you explicitly refresh it.

Related tasks:

“Sharing sets between reports” on page 273

When you are working with dimensional data, you can share a set to make it available for inclusion in multiple reports.

Improved text-based relational filters

You can now define relational filters that are based on a text pattern.

In previous releases, text-based relational filters were defined by selecting actual values, such as Camping Equipment. Performance is impacted when the number of strings in a filter condition increases. This feature automatically generates filters that contain strings or members that match a text pattern. The following text matching options are available:

- Starts with
- Ends with
- Contains
- Matches SQL pattern

Related tasks:

“Create a Detail or Summary Filter” on page 243

Add a filter expression to focus a report and minimize processing time by excluding unwanted data. For example, you can filter data to show only customers who placed purchase orders that were valued at over one thousand dollars during the past year. When you run the report, you see only the filtered data.

Improved data container and query naming support

In IBM Cognos Report Studio, when you insert a data container from the toolbox tab into a report, you can immediately specify a name for the container and a name for the query that you want to link to the container. You can also link an existing query to the container.

In previous releases, Cognos Report Studio automatically generated the names for data containers that are inserted in a report and the names of the queries that are linked to the containers. For example, when you insert a list, the generated name of the list is List1, and the name of the query that is linked to the list is Query1. To change either name, you must modify the **Name** property of the object in the **Properties** pane.

Related tasks:

“Inserting a data container from the toolbox tab” on page 45
You can insert data containers from the toolbox tab into a report.

Search parameter Ends with any of these keywords

A search parameter, **Ends with any of these keywords**, is now available when you perform searches, such as when you search for members when you create a filter expression.

Removed Features in Version 10.2.1

The following features were removed since the last release.

IBM Cognos Statistics

IBM Cognos Statistics was removed from this version of IBM Cognos Business Intelligence.

To ensure that reports that were created in previous releases, and that contain statistical objects, will run in this and future releases, statistical objects are removed when the reports are upgraded. Each removed statistical object is replaced with the following image:



Figure 1. Image that replaces statistical objects in upgraded reports

A warning also appears in the Upgrade Information window for each statistical object that is replaced with the image.

Tip: Queries and their data items that are associated to statistical objects are not removed from upgraded reports.

You can use IBM SPSS® Statistics to perform statistical reporting and analysis.

New features in version 10.2.0

This section describes new features in this release.

Updated world and Africa maps

The world and Africa maps were updated to include the region of South Sudan in IBM Cognos Report Studio version 10.2.0.

Related tasks:

“Use maps from previous versions” on page 13

The old versions of the World, Europe, Africa, and India maps that were included with IBM Cognos Business Intelligence prior to version 10.1.1 are still available. To continue using the previous maps, your IBM Cognos BI administrator must enable them.

Interactive repeater tables

You can now add interactive behavior to repeater tables in IBM Cognos Active Report.

Adding interactive behavior to repeater tables is useful for creating button bars and grids of custom content. For example, you can insert a data item in a repeater table that shows a different chart for each data value. You can customize the repeater table so that the data values appear as buttons in a two-column grid.

Related concepts:

“Adding Controls to a Report” on page 197

IBM Cognos Active Report offers several active report controls. For many controls, two different versions are available, a static version and a data-driven version.

Improved IBM Cognos Active Report integration with IBM Cognos Workspace

Check boxes and sliders in workspaces in IBM Cognos Workspace can now drive IBM Cognos Active Report.

You can define public variables and range variables in Cognos Active Report that allow Cognos Workspace check boxes and sliders to drive active reports in a workspace.

Related tasks:

“Create and Manage Active Report Variables” on page 196

Create active report variables to allow controls in a report to interact with each other. Active report variables pass information from one control to another control.

Improved support for bidirectional languages

IBM Cognos Report Studio offers improved support for bidirectional languages.

The improved support for bidirectional languages includes the following capabilities:

- Base text direction for text in more report objects, such as charts, maps, and prompts
- Control of object direction for charts, maps, and prompts
- Digit shaping

In addition, the improved support for bidirectional languages includes the report formats PDF, Microsoft Excel, and IBM Cognos Active Report.

Related concepts:

“Support for bidirectional languages” on page 60

You can author reports that support bidirectional languages. You can specify base text direction, digit shaping, and container direction.

Macro tab in expression editor

A macro tab is now available in the IBM Cognos Report Studio expression editor. With the macro tab, you can add parameter maps, session parameters, and macro functions to expressions.

Related tasks:

“Insert a Query Calculation” on page 264

Insert a query calculation into your report to add a new row or column with values that are based on a calculation.

“Insert a Query Calculation” on page 317

When working with dimensional data, insert a query calculation into your report to add a new row or column with values that are based on a calculation. For example, you create a query calculation named Euros that converts dollars to euros by multiplying an existing dollar measure by a conversion rate. Euros can then be displayed to end users in a separate row or column.

Inherited table styles in lists and crosstabs

When an item is inserted in a list or crosstab, the item inherits the table style of one of the items in the data container.

By default, items inherit the style of an item of the same type. For example, if you insert a measure in a list, the measure inherits the style of a measure that is in the list, if one exists. Inheritance rules control which style is inherited.

Related tasks:

“Apply a Table Style” on page 354

Apply a table style to quickly format tables. You can also apply a table style to lists, crosstabs, and repeater tables.

Enhanced crosstab headers

In crosstabs, you can display headers that indicate the parent categories of the data items in the columns and rows. The headers help users to understand where the data is located in the hierarchy.

Related tasks:

“Creating headers automatically for sets in crosstabs” on page 76

You can automatically add header labels on columns and rows when working with sets in a crosstab that uses a dimensional data source. The headers help consumers of the report to understand where the data is in the hierarchy.

Prompt API

A JavaScript Prompt API is available to provide report authors with a method of customizing prompt interaction in the reports that they author.

With the prompt API, JavaScript applications can interact with IBM Cognos Business Intelligence report prompts for the purposes of validation or custom interaction. The prompt API can query and set user selections, validate typed-in values using patterns, set default values using expressions or query data, and more. Sample reports exist to demonstrate various usage scenarios of the prompt API.

Related reference:

Appendix H, “Prompt API for IBM Cognos BI,” on page 1005

The JavaScript Prompt API provides report authors with a method of customizing prompt interaction in the reports they author.

Excel 2007 Data report output format

A new Excel output format, Excel 2007 Data, is available in IBM Cognos Report Studio. The Excel 2007 Data report output format generates native Microsoft Excel 2007 spreadsheets containing list report data for further manipulation.

This format is similar to a comma-separated values file (.csv). It has no formatting such as headers, footers, styling, or data formatting.

Related concepts:

“Producing a Report in Microsoft Excel Format” on page 53

You can export your report output to several different Microsoft Excel spreadsheet software formats.

Global classes for accessible reports

New global classes that you can apply to text objects were added to IBM Cognos Report Studio. The new classes make text easier to read for visually impaired users.

The new global classes are as follows:

- Heading 1 to heading 6
- Emphasize text
- Strong text

Related concepts:

“Headings and emphasis” on page 489

You can apply certain global classes to text objects to make the text easier to read for visually impaired users.

Changed features in version 10.2.0

This section describes changed features since the last release.

Change in line break rules in PDFs

Line break rules for word wrapping in PDFs are slightly different than in IBM Cognos Business Intelligence 10.1.0 and 10.1.1. Brackets and parenthesis such as { } and () are no longer valid line delimiters.

For example, in Cognos BI 10.1.0 and 10.1.1, in the string *Boilers(Steam)*, "Boilers" and "(Steam)" are treated as separate strings. When the string occurs at the end of a line, the following result occurs.

Boilers

(Steam)

In Cognos BI 10.2.0, *Boilers(Steam)* is treated as a single non-breaking string.

Support for inline prompts in reports viewed on mobile devices

IBM Cognos Mobile now supports several inline prompt types. Previously, all inline prompts in reports viewed on a mobile device appeared in a prompt page.

The prompt types that Cognos Mobile supports as inline prompts are as follows:

- Text Box
- Value
- Date
- Time
- Date & Time
- Interval

Cognos Business Insight and Cognos Business Insight Advanced are renamed

Two product components are renamed in this release to avoid confusion with the names of other components. IBM Cognos Business Insight is now IBM Cognos Workspace. IBM Cognos Business Insight Advanced is now IBM Cognos Workspace Advanced.

Removed Features in Version 10.2.0

This section describes features that were removed since the last release.

Saving and opening reports on your computer

The ability to save and open reports locally on your computer by enabling the **Allow local file access** option was removed in this release.

To save and open reports on your computer, use the **Copy Report to Clipboard** and **Open Report from Clipboard** commands in the **Tools** menu instead.

Related concepts:

“Copy a Report to the Clipboard” on page 471

You can copy a report specification to the clipboard so you can open it from the clipboard later.

Related tasks:

“Open a Report from the Clipboard” on page 471

You can open a report specification that was previously copied to the clipboard.

New features in version 10.1.1

This section describes new features in this release.

New active report controls

IBM Cognos Active Report offers new controls, including iterators, sliders, and row numbers.

Related concepts:

“Adding Controls to a Report” on page 197

IBM Cognos Active Report offers several active report controls. For many controls, two different versions are available, a static version and a data-driven version.

Conversion of controls to other types of controls

You can now convert a control in an active report to another type of control that is compatible to the original control. For example, you can convert a radio button group control to a check box group control.

Related concepts:

“Adding Controls to a Report” on page 197

IBM Cognos Active Report offers several active report controls. For many controls, two different versions are available, a static version and a data-driven version.

Improved user experience when authoring active reports

Improvements were made to the IBM Cognos Report Studio user interface for authoring active reports. For example, there are two new tabs that respectively show the controls and variables defined in a report.

Controls are shown in a hierarchical structure, allowing you to see their relationships to one another as well as the variables that drive them. For each variable in a report, you can see the default values defined for each one, as well as the controls to which they are linked.

Related tasks:

“Create and Manage Active Report Variables” on page 196
Create active report variables to allow controls in a report to interact with each other. Active report variables pass information from one control to another control.

“Define a Connection Between Controls” on page 204
Define a connection between controls to link them together. When you link controls, an action performed on one control affects the behavior of the other control.

Active report access code

You can now specify an access code that users will have to enter before they can view an active report.

Related tasks:

“Specify Active Report Properties” on page 195
You can specify properties for active reports, such as the text that appears in the browser window title bar, the maximum number of rows that a report can contain, and an access code that users must enter to view a report.

New startup options

A new **Start page view** option allows you to specify whether IBM Cognos Report Studio opens in **Page Design** or **Page Structure** view (**Tools > Options > View**). By default, Report Studio opens in **Page Design** view.

Related concepts:

“Options” on page 37
You can set various options that control the appearance and behavior of IBM Cognos Report Studio (**Tools, Options**).

Keyboard shortcuts for accessibility

To make the report authoring experience more accessible to people who have a physical disability, such as restricted mobility or limited vision, IBM Cognos Report Studio now includes new keyboard shortcuts to allow navigating the user interface with a keyboard.

Related concepts:

“Keyboard Shortcuts” on page 485
This product uses some standard Microsoft Windows and accessibility shortcut keys.

Updated maps

Some maps included with IBM Cognos Report Studio version 10.1.1 were updated.

- The World and Europe maps were updated to include the countries and regions of Montenegro and Kosovo.
- The India map was updated to include the northern region of Kashmir.

Related concepts:

Chapter 8, “Maps,” on page 181
IBM Cognos Report Studio provides a set of maps that you can use to represent tabular data in a spatial context. For example, on a map of the world, countries

and regions can be colored to represent the level of revenue.

Use maps from previous versions

The old versions of the World, Europe, Africa, and India maps that were included with IBM Cognos Business Intelligence prior to version 10.1.1 are still available. To continue using the previous maps, your IBM Cognos BI administrator must enable them.

Procedure

1. Go to the *c10_location/maps* directory.
2. Rename the files **world.cmf**, **europa.cmf**, **africa.cmf**, and **india.cmf** to remove the .cmf extension, as follows: **world_default_cmf**, **europa_default_cmf**, **africa_default_cmf**, and **india_default_cmf**.
3. Rename the files **world8_4_cmf**, **europa8_4_cmf**, **africa8_4_cmf**, and **indiaUN_cmf** to remove 8_4 and add the .cmf extension, as follows: **world.cmf**, **europa.cmf**, **africa.cmf**, and **india.cmf**.

Custom groups

You can create custom groups of existing data items based on elements that you define and that are meaningful to you.

For example, you can create custom groups for product names based on their alphabetical order. You might create groups for products that start with the letters A to C, D to F, G to H, and so on.

Related tasks:

“Creating relational custom groups” on page 229

Create custom groups to classify existing data items into groups that are meaningful to you.

“Creating dimensional custom groups” on page 279

Create custom groups to classify existing data items into groups that are meaningful to you.

Larger worksheet sizes for Microsoft Excel 2007 report outputs

IBM Cognos Business Intelligence now supports a larger worksheet size for report outputs exported in Microsoft Excel 2007 format.

In previous versions of IBM Cognos Business Intelligence, report output in Microsoft Excel format was limited to a maximum of 256 columns by 65,000 rows. Although this remains as the default worksheet size, administrators can now enable larger worksheets and change the maximum number of rows in a worksheet - up to a maximum of 16,384 columns by 1,048,576 rows - by using advanced server properties. This number matches the Microsoft Excel 2007 worksheet size limitations.

For more information, see the *IBM Cognos Business Intelligence Administration and Security Guide*.

For an up-to-date list of environments supported by IBM Cognos products, such as operating systems, patches, browsers, Web servers, directory servers, database servers, and application servers, visit <http://www.ibm.com/>.

Related concepts:

“Producing a Report in Microsoft Excel Format” on page 53
You can export your report output to several different Microsoft Excel spreadsheet software formats.

Microsoft Excel 2007 supported as an external data source

IBM Cognos Business Intelligence now supports external data sources from Microsoft Excel up to version Microsoft Excel 2007.

For an up-to-date list of environments supported by IBM Cognos products, such as operating systems, patches, browsers, Web servers, directory servers, database servers, and application servers, visit <http://www.ibm.com/>.

Related concepts:

“Use Your Own External Data” on page 15
You can now supplement your enterprise data with your own external data file.

Changed features in version 10.1.1

This section describes changed features in this release.

Specify how to show no data contents

The user interface for specifying what appears for data containers that contain no data was modified.

You can now select between showing an empty data container, alternate content that you specify, or text that you specify.

The new default for data containers that have no data available is to show the text **No Data Available** instead of showing an empty data container.

Related tasks:

“Specify what appears for data containers that contain no data” on page 409
You can specify what appears in a data container when no data is available from the database.

What's new in version 10.1.0

This section contains a list of new, changed, and removed features for past releases.

Knowing this information will help you plan your upgrade and application deployment strategies and the training requirements for your users.

To review an up-to-date list of environments supported by IBM Cognos products, such as operating systems, patches, browsers, Web servers, directory servers, database servers, and application servers, visit www.ibm.com.

For information about upgrading, see the IBM Cognos Business Intelligence *Installation and Configuration Guide* for your product.

For an overview of new features for this release, see the IBM Cognos Business Intelligence *New Features Guide*.

New Features in Version 10.1.0

This section describes new features in this release.

Use Your Own External Data

You can now supplement your enterprise data with your own external data file.

You can import an .xls, .txt, .csv, or .xml file into IBM Cognos and create reports that contain your own data. This allows you to leverage the IBM Cognos platform, including the security, data integrity, and full range of reporting functionality.

You can perform self-service reporting without the need to ask your IT department or administrator to set up a data source connection to your file. You import your own data file and start reporting on it right away.

After importing, your external data file is protected by the same IBM Cognos security as your enterprise data, thus allowing you to report on your data in a secure environment.

Active Reports

You can now use IBM Cognos Report Studio to create active reports.

IBM Cognos Active Report is a report output type that provides a highly interactive and easy-to-use managed report. Active reports are built for business users, allowing them to explore their data and derive additional insight.

Active reports make business intelligence easier for the casual user. Report authors build reports targeted at their users' needs, keeping the user experience simple and engaging. Active reports can be consumed by users who are offline, making them an ideal solution for remote users such as the sales force.

Related concepts:

Chapter 9, "Active Reports," on page 193

You can use IBM Cognos Report Studio to create active reports. IBM Cognos Active Report is a report output type that provides a highly interactive and easy-to-use managed report. Active reports are built for business users, allowing them to explore their data and derive additional insight.

Statistical Analysis

IBM Cognos Report Studio now offers statistical functionality in an add-on package called IBM Cognos Statistics.

Report Studio integrates statistical analysis and reporting, providing you with the capability to distribute reports that now can include statistical information. Unlike specialized statistical tools, this functionality is easy to use within the IBM Cognos Business Intelligence authoring environment.

This functionality covers three main areas in statistical analysis:

- the distribution of data
- data analysis and testing
- statistical process control

Mozilla Firefox Support

Versions 3.5 and 3.6 of the Mozilla Firefox Web browser are now supported for IBM Cognos Report Studio.

For a full list of supported software environments, see <http://www.ibm.com/>.

Enhanced charts

Chart enhancements concentrate on improved effectiveness of communication. The new bullet chart and extensions to pie and gauge charts are especially beneficial in dashboard reports. Additional enhancements provide superior presentation through conditional notes and markers and improved legends.

Current Default Charts and Legacy Charts:

IBM Cognos Report Studio has a new default chart technology. Any new charts added to a report use the current default charts.

The current default charts use more properties that allow you to customize more aspects of the chart. In addition, the current default charts offer you a preview of the style changes that you make to your chart.

If you prefer to continue working with the legacy charts, you can select the **Use legacy chart authoring** option.

You can also convert legacy charts to the current default charts. When you convert a chart to a different chart type, Report Studio maps the chart properties that exist in the new chart type. For more information, see “Upgrading Legacy Charts” on page 480 and “Convert Charts From One Type to Another” on page 107.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Bullet Charts:

You can now create bullet charts to complement your dashboard reports and as an alternative to gauge charts.

A bullet chart features a single primary measure, such as current revenue, compares that measure to one or more other measures to enrich its meaning, such as the target or planned revenue, and displays it in the context of a qualitative range of performance, such as poor, satisfactory, or good.

Related concepts:

“Bullet Charts” on page 97

Bullet charts are a variation of bar charts. They compare a featured measure (the bullet) to a targeted measure (the target). They also relate the compared measures against colored regions in the background that provide additional qualitative measurements, such as good, satisfactory, and poor.

Chart Matrix:

You can now convert a complex nested chart into a matrix configuration that shows multiple small charts arranged in rows and columns.

The numeric scale of all the charts is the same so that you can easily compare and analyze values from each chart.

Related tasks:

“Create a Matrix of Current Default Charts” on page 145

You can view a complex chart that includes nested series or categories into a matrix, or crosstab, that shows multiple small charts arranged in rows and columns.

Customize the Legend:

You can hide or show the legend and change its position relative to the chart object, chart area, or using a specific report expression.

For more information, see “Customize the Legend in a Current Default Chart” on page 128.

If your legend includes items that are too long, you can truncate long legend items at a specific number of characters. You can also show the values of the data items in your legend. For more information, see “Customize the Items in the Legend of a Current Default Chart” on page 128.

Legends can display trend lines and conditional item entries.

Colored Regions:

You can now define colored regions in the body of a chart to make your chart more informative.

For example, you can divide the background of a scatter chart into quadrants and color each quadrant. For more information, see “Add Colored Regions in a Current Default Chart” on page 121.

Enhanced Pie Charts:

You can customize how data labels appear in a pie chart, including their format and placement.

For more information, see “Showing data values in current default pie and donut charts” on page 141.

To make your pie charts easier to read and analyze, you can now:

- pull out pie slices from the rest of the pie to highlight them. For more information, see “Pull Out Pie Slices in a Current Default Pie Chart” on page 153.
- set the position at which the first slice in a pie chart appears. For more information, see “Set the Position of the First Slice in a Current Default Pie Chart” on page 152.
- summarize the smaller slices in a pie chart to avoid having many tiny slices in your pie. For more information, see “Summarize Small Slices, Bars, or Columns in Current Default Charts” on page 142.

Enhanced Chart Styles:

You can customize the palette, drop shadows, gridlines, backgrounds, and bar shapes in charts.

You can create a new chart palette or edit an existing chart palette, including specifying colors, fill types, and patterns. For more information, see “Customizing the Color Palette of a Chart” on page 112.

You can add drop shadows to chart elements, such as lines in line charts. For more information, please see “Add Background Effects to a Chart Object in a Legacy Chart” on page 120.

You can customize the color, style, and weight of chart gridlines or set the background of your chart to display bands of color. For more information, see “Show Gridlines in a Current Default Chart” on page 127.

You can change the bar shape in a bar or column chart to one of the following two dimensional and three dimensional shapes: box, cylinder, cone, pyramid, rectangle, and triangle. You can also change the width of the bars or columns in a bar or column chart to a percentage of the chart body, such as 80% or 25%.

Chart Axes:

To make your charts easier to read, you can now customize the color, style, weight, and transparency of chart axis lines and specify where to display major and minor gridlines on the chart.

For more information, see “Customize the Axes of a Current Default Chart” on page 123.

Color by Value in Scatter and Bubble Charts:

In scatter and bubble charts, you can now specify data to appear in different colors based on the data values.

The color of the points or bubbles adds an additional aspect to the chart to assist you in finding relationships in large amounts of data. An entry appears in the legend to identify the color and its value. For more information, see “Defining color by value in current default scatter or bubble charts” on page 150.

Bubble Size:

In a bubble chart, you can now set the maximum and minimum bubble size and specify the smallest bubble to show in the chart.

For more information, see “Specify the Bubble Size in a Current Default Bubble Chart” on page 151.


Positioning and Formatting Notes:

When you add a note to a chart, you can now set the note's position relative to the sides of the chart area or chart body. You can also use a report expression to position the note next to a data item within the chart.

For example, in a bar chart showing revenue for each product line by country or region, you could type [Country or Region]='Canada' to position the note relative to the Canada bar. You can also customize the background of the note with color and background images. For more information, see “Add a Note to a Current Default Chart” on page 131.

Insert Charts With the Toolbar Button:






You can now insert a specific chart type from any report with the insert chart

button  on the toolbar. When you insert a chart into a report that already contains a list, the list data is added to the chart automatically.


Enhancements to the User Interface

IBM Cognos Report Studio includes enhancements to the user interface layout, buttons, tooltips, and visual aids.

These enhancements include the following:

- You can now position the content and **Properties** panes to the right of the work area, to match the user interface of IBM Cognos Business Insight and IBM Cognos Business Insight Advanced. For more information, see “Options” on page 37.
- When working with dimensional data sources, the insert individual members button  and the insert member with children button  have moved to the **Source** tab . These buttons have the same function as they did in the previous release. For more information, see “Insert a Member” on page 269.
- When working with dimensional and mixed model data sources, you can now switch between viewing the full data tree and the dimensional-only data tree by clicking the view package tree button  and the view members tree button . For more information, see “Add Dimensional Data to a Report” on page 267.

These same buttons are available in the expression editor.

- You can now remove all of the filters at once from your report with new options in the filters button . For more information, see “Focusing Dimensional Data” on page 292 and “Focusing Relational Data” on page 242.
- Expanded tooltips for toolbar buttons now include a description of what the button does. To see a tooltip, pause the pointer over a button in the toolbar. You can turn off the expanded tooltips (**Tools, Options**).
- A new **Show Container Selectors** visual aid allows you to select list, crosstab, repeater table, table of contents, active report application objects, and table container objects with one click. When enabled, a small clickable region (three orange dots) appears in the top left corner of these report objects. This selector provides easier access to the container objects' properties and allows you to easily move containers with one mouse gesture. For more information, see “Visual Aids Button” on page 31.

Improved Set Operations

You can now perform more operations on a set of members when working with dimensional data sources.

You can do the following by right-clicking a set, and clicking **Edit Set**:

- Exclude members from the initial set or from the set as it is currently shown. For more information, see “Exclude Members from a Set” on page 275.
- Move members to the top or bottom of the set. For more information, see “Move Members Within a Set” on page 275.
- Show only the members with the top or bottom values. For more information, see “Limit Data to Top or Bottom Values” on page 276.
- Filter the members in a set. For more information, see “Filter the Members Within a Set” on page 276.
- Expand and collapse members to add its child members below it as new rows.

For more information, see “Expand and Collapse a Member Within a Set” on page 277.

Preview Reports when Opening and Saving

You can now see a preview of the report when you open or save it (**Tools, Options, Display report preview**).

For more information, see “Options” on page 37.

Report Name Used for the Exported Output File Name

When you run a report in an export format such as PDF, delimited text (CSV), Microsoft Excel (XLS), the IBM Cognos report name is now used as the exported file name.

This allows you to save the report output using the same name as the original report. For more information, see “Running a report” on page 50.

Enhancements for SAP BW Data Sources

IBM Cognos Business Intelligence includes prompting for SAP BW variables and time-dependent hierarchies when creating reports with SAP BW data sources.

Prompting for SAP BW Variables

SAP BW variables are parameters in a SAP BW query that your business warehouse administrator sets up. When the queries run, the SAP BW variables are filled with values. SAP BW variables are automatically exposed as prompts when you run a report or when you add data to a report.

Prompting for SAP BW variables in IBM Cognos BI has improved. You are prompted for optional variables when you initially drag and drop data items.

Time-dependent Hierarchies

Time-dependant hierarchies now automatically reflect hierarchy or structure changes. When a structure is imported into IBM Cognos Framework Manager, each SAP BW time hierarchy is depicted as an individual level. IBM Cognos Report Studio users can use these structures to report on and compare levels that are valid for a specific time period.

Column Titles When Drilling up or Down

When you drill down or up, you can now specify whether the column title shows the member caption value or the level label value.

For more information, see “Create a Drill-up and Drill-down Report” on page 322.

Custom Properties for Prompts

You can now customize the text that instructs your report users how to use report prompts.

For example, you can now change the default text that appears above a search text box from **Keywords** to the text of your choice. For more information, see “Customize Prompt Text” on page 337.

Simplified Calculations

To add a calculation, you now choose to add either a **Query Calculation** or **Layout Calculation** object from the toolbox tab.

For more information, see “Using Relational Calculations” on page 262 and “Using Dimensional Calculations” on page 316.

Function Description Improvements:

The functions that you can use to create calculations now include improved descriptions and more examples.

The descriptions and examples appear in the Report Studio user interface and in this user guide. For more information about functions, see Appendix F, “Using the expression editor,” on page 575.

New Vendor-specific Functions:

Functions that are specific to Postgres, Vertica, Netezza, Paracel, MySQL, and Greenplum now appear in the expression editor in the **Vendor Specific Functions** folder.

For more information, see Appendix F, “Using the expression editor,” on page 575.

New Report Style

IBM Cognos Business Intelligence includes a new default report style with updated colors and gradients.

If your report uses a custom report template, your report will appear the same in this version of IBM Cognos Report Studio as it did in previous versions. By default, new reports appear in the new report style. For more information, see “Create and Modify Report and Object Styles” on page 365.

If you want to create new reports with the custom template style, you can edit the default template for new reports to match your custom template. For more information about custom templates, see Chapter 21, “Creating Report Templates,” on page 469.

List Enhancements

Report Studio includes enhancements to aggregate summaries, grouping, and hiding columns in lists.

You can now specify whether to automatically include an overall aggregate summary in the list footer. For more information, see Chapter 4, “Lists,” on page 67.

You can also specify whether grouping a column automatically makes it the first column in the list. For more information, see “Group Relational Data” on page 227.

You enable these behaviors in the IBM Cognos Report Studio options, by selecting the **Group and automatic summary behavior for lists** check box.

A new **Render** property allows you to hide columns from the output of list reports. For more information, see “Hide Columns in List Reports” on page 68.

Accessible Report Output

IBM Cognos Report Studio now includes features that allow you to create reports that are more accessible to people who have a physical disability, such as restricted mobility or limited vision.

Accessible reports contain features that allow users with disabilities to access report content using assistive technologies, such as screen readers. You can

- add alternative text for non-text objects, such as images, charts, and maps.
- add summary text for crosstabs, lists, repeater tables, and tables.
- specify whether table cells are table headers.
- use command keys, or shortcut keys, to navigate through IBM Cognos Business Insight Advanced.
- use a screen-reader software with a digital speech synthesizer to listen to what is displayed on the screen.
- set your system's display settings for high-contrast displays.

In addition, the documentation now includes alternate text for all graphics so that screen readers can interpret graphics.

Braces and Parentheses are Breakable

When you run a report in PDF format, braces {} and parentheses () no longer stay on the same line as the text before them.

For example, **Products(2012)** may now break to a new line between **Products** and **(2012)**.

Changed features in Cognos Business Insight Advanced version 10.1.0

In this release, some features have been changed.

Report Studio Express Authoring Mode Replaced by Business Insight Advanced

The two authoring modes in IBM Cognos Report Studio, Professional and Express, no longer exist.

Report Studio is still the tool that professional report authors use to create advanced and managed reports. The Express authoring mode is now replaced by IBM Cognos Business Insight Advanced. Business Insight Advanced is part of a new report consumption experience that provides an integrated business intelligence experience for business users. It offers much greater capability, such as full support for list reports, charts, and relational data sources. It offers an entirely different user experience that is designed for data exploration.

For more information, see the Business Insight Advanced *User Guide*.

Order of Drawing Bars in Bar Charts

In a horizontal bar chart, the new default chart type draws bars from bottom to top. Legacy charts draw the bars or columns in the reverse order.

To control the order of the bars, use the property for the category axis.

Line break rules in PDFs have changed

Line break rules for word wrapping in PDFs have changed slightly from the last release. Brackets and parenthesis such as {} and () are now treated as breakable. For example, in past releases, the following string would be treated as a single non-breaking string.

Boilers(Steam)

In this release, "Boilers" and "(Steam)" are treated as separate strings which might result in the following when the string occurs at the end of a line.

Boilers

(Steam)

Removed Features in Version 10.1.0

This section describes features that were removed since the last release.

Analyze with Analysis Studio

The ability to open a report with IBM Cognos Analysis Studio from within IBM Cognos Report Studio (**Tools** or right-click, **Analyze**) was removed in this release.

Conformed Dimensions on SAP BW Data Sources

Support for conformed dimensions generated by IBM Cognos Framework Manager for SAP BW data sources was removed in this release.

Excel 2000 and Excel 2000 Single Sheet Report Outputs

The Microsoft Excel 2000 spreadsheet software and Excel 2000 Single Sheet spreadsheet software report outputs are no longer supported in this release.

Chapter 2. Getting started with Report Studio

IBM Cognos Report Studio is a Web-based report authoring tool that professional report authors and developers use to build sophisticated, multiple-page, multiple-query reports against multiple databases. With Report Studio, you can create any reports that your organization requires, such as invoices, statements, and weekly sales and inventory reports.

Use Report Studio for reports that

- are intended for a wide audience
- exist long enough to require maintenance for changing requirements and data
- require detailed control over the appearance

Your reports can contain any number of report objects, such as charts, crosstabs, and lists, as well as non-BI components such as images, logos, and live embedded applications that you can link to other information.


Building IBM Cognos Business Intelligence Applications

You use the IBM Cognos Business Intelligence components to build reporting and analysis applications.

The lifetime of an IBM Cognos Business Intelligence application can be months, or even years. During that time, data may change and new requirements appear. As the underlying data changes, authors must modify existing content and develop new content. Administrators must also update models and data sources over time. For more information about using data sources, see the *IBM Cognos Business Intelligence Administration and Security Guide* and the *IBM Cognos Framework Manager User Guide*.

In a working application, the technical and security infrastructure and the portal are in place, as well as processes for change management, data control, and so on. For information about the workflow associated with creating IBM Cognos BI content, see the *IBM Cognos Architecture and Deployment Guide*. For additional information, see the IBM Cognos Solutions Implementation Methodology toolkit, which includes implementation roadmaps and supporting documents. Information about the toolkit is available on the IBM Support Portal (<http://www.ibm.com/support/>).

The following graphic provides an overview for how to use IBM Cognos BI to build applications across all of your IBM Cognos BI components.



1. Locate and prepare data sources and models

IBM Cognos BI can report from a wide variety of data sources, both relational and dimensional. Database connections are created in the Web administration interface, and are used for modeling, for authoring, and for running the application.

To use data for authoring and viewing, the business intelligence studios need a subset of a model of the metadata (called a package). The metadata may need extensive modeling in Framework Manager.

2. Build and publish the content

Reports, scorecards, analyses, workspaces, and more are created in the business intelligence studios of IBM Cognos BI. Which studio you use depends on the content, lifespan, and audience of the report, and whether the data is modeled dimensionally or relationally. For example, self-service reporting and analysis are done through IBM Cognos Workspace Advanced, IBM Cognos Query Studio, and IBM Cognos Analysis Studio, and scheduled reports are created in IBM Cognos Report Studio. Report Studio reports and scorecards are usually prepared for a wider audience, published to IBM Cognos Connection or another portal, and scheduled there for bursting, distribution, and so on. You can also use Report Studio to prepare templates for self-service reporting.

3. Deliver and view the information

You deliver content from the IBM Cognos portal or other supported portals, and view information that has been saved to portals, or delivered by other mechanisms. You can also run reports, analyses, scorecards, and more from within the business intelligence studio in which they were created.

For information about tuning and performance, see the *IBM Cognos Business Intelligence Administration and Security Guide* and <http://www.ibm.com>.

Relational and dimensional reporting styles

You can create reports in IBM Cognos Report Studio using either a relational reporting style or a dimensional reporting style.

The Report Studio tools and query language are the same for both styles. However, it is important to choose a reporting style to ensure that you are making the most of your data and to avoid mixing dimensional and relational concepts.


How to choose a reporting style


When authoring a report, first choose your preferred reporting style for working with data: relational or dimensional. You can choose a reporting style from your viewpoint:

- If you think about your data as tables and columns, you have a relational viewpoint and should use a relational reporting style.
- If you think about your data as a number of dimensions intersecting at cells, you have a dimensional viewpoint and should use a dimensional reporting style.

Relational reporting style

The relational reporting style consists of lists. You focus the data with filters and summarize with header and footer summaries.

- If your data is purely relational, then only query subjects and query items appear in the **Source** tab , and you must use the relational reporting style.

- If your data is dimensional, then dimensions appear in the **Source** tab , and you can still use a relational reporting style, but instead of query items (columns) and query subjects (tables), you use measures, levels, and level properties.

To see an example of relational style reporting with dimensional data, see the Manager Profile sample report in the GO Data Warehouse (analysis) package.

The relational reporting style is similar to report authoring in IBM Cognos Query Studio.

Dimensional reporting style

The dimensional reporting style consists of measures and members from different hierarchies arranged in a crosstab with cell values at the intersections. You focus the data with set expressions that navigate from specific members in the hierarchy and summarize with set summaries.


To see an example of dimensional style reporting with dimensional data, see the GO Balance Sheet as at Dec 31, 2012 sample report in the GO Data Warehouse (analysis) package.

The dimensional reporting style is similar to report authoring in IBM Cognos Analysis Studio.

Guidelines for each reporting style

This user guide is divided into relational and dimensional reporting sections so that you can follow the best practices for using this product with the reporting style that you have chosen. The following table outlines the best practices for both reporting styles.


Item	Relational reporting	Dimensional reporting
Report type	<ul style="list-style-type: none"> Lists Crosstabs pivoted from lists Charts created from lists Maps created from scratch or from lists 	<ul style="list-style-type: none"> Crosstabs Charts created from scratch or from crosstabs Maps created from scratch or from crosstabs

Item	Relational reporting	Dimensional reporting
Package tree	<p>In the Source tab , click the view members tree button.</p> <p>If you are using dimensional data, hide members in the source tree by right-clicking the tree, clicking Package Tree Settings, and clearing the check boxes for Members and Members for each level.</p> <p>The view will include the following:</p> <ul style="list-style-type: none"> package folder namespace query subject query item measure level 	<p>In the Source tab, click the view members tree button.</p> <p>Ensure that the source tree tool bar is set to Create sets for members:</p> <p>The view will include the following:</p> <ul style="list-style-type: none"> package folder measure member named set
Inserting data	<p>From the package tree, add query items or levels to the report.</p> <p>Avoid using hierarchies directly in the report.</p> <p>Avoid using named sets.</p>	<p>From the package tree, add sets of members to the report.</p> <p>You can also choose to insert just the member, just the children of the member, or the member and its children.</p>
Calculating data	<p>Add query calculations using only relational and common constructs.</p> <p>Choose only Other expression.</p>	<p>Add query calculations using only dimensional and common constructs.</p> <p>Use Other expression only for value calculations.</p> <p>Avoid Common functions that are marked with an exclamation mark (!) because they have limited support.</p>
Summarizing data	<p>Headers and footers in lists</p> <p>Crosstab member summaries; for example, aggregate within detail</p>	<p>Member set summaries; for example, aggregate within set</p>
Focusing data	<p>Add detail or summary filters to view only the data you want to see. For example, add the Quarter query item to a list and filter by Q3.</p>	<p>Add only the relevant members to an edge of the crosstab or to the context filter. For example, only add the Q3 member to your report.</p> <p>Use a set expression such as Topcount or Filter.</p>

Item	Relational reporting	Dimensional reporting
Drilling	Drilling through by value	Drilling through by member Drilling up and down
Page and section breaks	Simple page breaks Page sets Sections Master detail relationships using parameterized filters	Simple page breaks Page sets Page layers Master detail relationships using parameterized edge or slicer expressions

The User Interface




The IBM Cognos Report Studio user interface has two panes, an explorer bar, and a work area to help you create reports.






We recommend that you use a screen resolution of at least 1024 by 768 pixels.

Content Pane

The content pane contains objects that you can add to a report. You add objects to a report by dragging them to the work area. The content pane contains these tabs:

- The **Source** tab  contains items from the package selected for the report, such as data items and calculations.
- The **Data Items** tab  describes the queries created in the report.
- The **Toolbox** tab  contains a variety of objects that you can add to the report, such as text and graphics.

Tip: Click the icons below the **Toolbox** title bar to view toolbox items as icons or as a list, to sort items, and to filter items by different groups. To add a toolbox item to the favorite toolbox items group, right-click the item and click **Add to Favorite Toolbox Items**.

- The **Search** tab  contains the results when you perform a search for members. You can insert the members found in a search directly into a report.
- If you are authoring an active report, the **Active Report Controls** tab  shows the controls and active report variables inserted in a report and their relationships to one another. You can click a control in this tab to quickly locate the control in the report as well as set default values for variables.
- If you are authoring an active report, the **Active Report Variables** tab  shows the active report variables defined in a report. Use this tab to create new variables and set default values.

Properties Pane

The **Properties** pane lists the properties that you can set for an object in a report.



You can obtain additional information about a property by selecting it and pressing F1. For example, you can view the list of objects that use each property.

When you specify a value for a property, press Enter, click another property, or save the report to ensure that the value is saved.

Tip: To view a description of the currently selected property at the bottom of the pane, from the **View** menu, click **Property Descriptions**.

Explorer Bar

Pause the pointer over the following buttons on the Explorer bar to work with different parts of a report:

- the page explorer button 
You use Page Explorer to view or create new report pages and prompt pages or to create and modify classes.
- the query explorer button 

You use Query Explorer to create or modify queries in relational reporting or dimensional reporting and to perform complex tasks, such as defining union joins and writing SQL statements.

- the condition explorer button 

You use Condition Explorer to work with variables to define conditions in a report.

The Explorer bar also contains icons for the different views in which you can author reports.

- page design view 

The page design view shows you what the report will look like after you run it.

- page structure view 


The page structure view shows you an overview of all objects in the report in a tree structure.

- Active Report preview 

When you are authoring an IBM Cognos Active Report, the Active Report Preview view shows you live data as you format the report.

Page Layers Area


Use the **Page layers** area to create sections, or page breaks, in a report to show values for each member on a separate page. For example, you can drag **Northern**

Europe sales territory from the **Source** tab  to the **Page layers** area. The report is broken into a separate page for each territory within northern Europe. Each page's context appears in the report header.

For more information, see “Create Page Layers” on page 456.

Context Filter Area

When working with dimensional data, use the **Context filter** area to filter your report to show values, or context, for only a specific data item. This technique is also known as a slicer filter. For example, you can drag **Sales Territory** from the

Source tab  to the **Context filter** area. When you click a specific territory from the list, the values in the crosstab change to represent data for that territory.

For more information, see “Create a Context Filter” on page 293.

Visual Aids Button

The visual aids button  provides the following options to help you when you are designing reports in the layout.

Option	Description
Show Boundary Lines	Shows all boundary lines around objects.
Force Boundary Lines	Overrides boundary lines around objects.

Option	Description
Show Repeating	Repeats objects when you insert them. For example, when you insert a data item in a crosstab, the data item appears in each row or in each column of the crosstab.
Show Page Header & Footer	Shows the page header and page footer.
Show Drag & Drop Padding	Shows drag-and-drop zone when the Padding property for an object is set to 0. If the Padding property is set to a value that is greater than the minimum padding that IBM Cognos Report Studio uses to show drag-and-drop zones, only the minimum padding is shown.
Show Hidden Objects	Shows objects for which the Box Type property was set to None or for which the Visible property was set to No .
Show Sorting	Shows the sorting icon for data items for which a sort order was specified. For more information about sorting data, see "Sorting Relational Data" on page 249 or "Sorting Dimensional Data" on page 295.
Show Grouping	Shows the grouping icon for grouped data items.
Show Source Type	Shows the icon for the source type of objects, such as layout calculation.
Show Data Item Type	Shows the icon for the type of data item, such as query item, member, or measure.
Show Drill-through Definitions	Shows data items for which the drill-through definition was defined as a hyperlink.
Show Table of Contents Entries	Shows table of contents entries inserted in the report.
Show Bookmarks	Shows bookmarks inserted in the report.
Show Master Detail Relationships	Shows master detail relationships defined in the report. Tip: Pausing the pointer over the master detail relationship icon shows the relationship.
Show No Data Contents Tab Control	Shows tabs if the data container's No Data Contents property is set to Yes .
Show Repeater and Singleton Containers	Shows repeater and singleton containers inserted in the report.
Show Interactive Object Controls	Shows controls in the top right corner of active report application objects. For more information about active reports, see Chapter 9, "Active Reports," on page 193.
Show Flyout Drop Zones	When in Page Design view, shows drop zones as flyouts that appear only when you hover your mouse over the data container. When this visual aid is not enabled, the drop zones are always displayed.
Show Container Selectors	Shows a small selector (three orange dots) in the top left corner of the following container objects and allows you to select all the objects within them: list, crosstab, repeater table, table of contents, table, and active report application objects.
Show Empty Extra Item Drop Zones	When you are creating a visualization, this visual aid shows empty drop zones for extra items that you can insert. The extra drop zones are displayed only when data items are inserted in all required drop zones.

Work in design, structure, or Active Report preview view

IBM Cognos Report Studio has three views in which you can author reports: Page Design view, Page Structure view, and Active Report Preview view. Active Report Preview view is available only when you are authoring an IBM Cognos Active Report. You can choose a report authoring view on the **View** menu or by clicking the view icons in the Explorer bar.

Different options are available in each view, so you often need to use all views. For example, you must use the Page Design and Page Structure views to remove sections in relational reporting.

Page design view

The page design view is the default view in IBM Cognos Report Studio. In this view, you can see what your report will look like after you run it.

Page structure view

The page structure view displays an overview of all of the report objects in your report in a tree structure, which is organized by page.

Active Report preview view

When you are authoring an IBM Cognos Active Report, the Active Report Preview view shows you live data as you format the report.

Related concepts:

“The Page Structure View” on page 343

When you add objects to a report, you usually work in the layout. An alternative view of the report is available.

Report Layout and Queries

All reports have two components: a layout component that defines the report appearance and a query component that defines report data. Understanding these components will help you design effective reports.

Layout

A layout is a set of pages that defines the appearance and formatting of a report.

When you design the layout of a report, you


- present the data in a meaningful way by using lists, crosstabs, charts, and maps
- add formatting, such as borders, color, images, and page numbers
- specify how the data flows from one page to the next

Pages

Pages are containers for the layout objects that you use to build a report. A page is made up of the following mandatory and optional components:

- page header (optional)
- page body (mandatory)
- page footer (optional)

When you run a report, the amount of data queried often exceeds one page. As a result, a page will repeat until all the data is shown. You have control over how data flows from one page to the next. For example, here are alternative representations of a report that contains a chart and a lengthy list.



1 The chart appears on its own page. The list begins on the next page and fills subsequent pages until all rows appear.

2 The chart and the first few rows of the list appear on the first page. The rest of the data in the list appears on the subsequent pages.

Objects

You add layout objects to a page when you create a report. Below are objects that you will use often when building reports in IBM Cognos Report Studio:

- list
Add a list to show data in rows and columns.
- crosstab
Add a crosstab to show data in a grid with dimensions along the rows and columns and measures in the cells or intersection points.
- chart
- map
- repeater
Add a repeater to show each instance of a certain column or data item in a separate frame.
- text
- block
Add a block to hold text or other information. Blocks are often used to lay out horizontal bands of information.
- table

Related tasks:

“Insert a Formatting Object in a Report” on page 350

In addition to text and images, the **Toolbox** tab  contains other objects that you can add to the report layout.

Queries

Queries determine what data items appear in the report. Sometimes you want detailed rows of data, which you obtain by using a simple SELECT statement. Other times you must calculate totals or averages using summary functions and grouped columns or must apply filters to show only the data you want.

IBM Cognos Report Studio automatically creates the queries you need as you build reports. However, you can modify these queries or create your own custom queries to get the results you want.

Related concepts:

“Working with Relational Queries” on page 250

Queries specify what data appears in the report. In IBM Cognos Report Studio, you create and modify queries using **Query Explorer**.

“Working with Dimensional Queries” on page 297

Queries specify what data appears in the report. In IBM Cognos Report Studio, you create and modify queries using Query Explorer.

Report Objects

You build reports by adding objects and manipulating them to obtain the results you want. To understand how to work with objects in IBM Cognos Report Studio, you must be familiar with the following concepts:

- object types
- objects as containers
- locking and unlocking objects
- hierarchy of objects

Object Types

In IBM Cognos Report Studio, layout objects are either inline or block. You can insert other objects on the same line as an inline object, but not on the same line as a block object. When you insert an object to the left or to the right of a block object, the object appears on the line above or below the block object, respectively. Examples of inline objects include graphics and text items. Examples of block objects include any report type (list, crosstab, chart, map, or repeater) and tables.

You can also use an object's floating property to define how other objects flow around the object. For example, you can specify how text flows around an image.

Objects as Containers

Objects, such as tables, blocks, and any report frame, are containers in which you can insert other objects. For example, you can insert a list in one cell of a table and a chart in another.

You can also nest objects to create a sophisticated layout. For example, you can insert a table in a cell of another table.

Locking and Unlocking Objects

To manipulate the contents of some objects, you must first unlock the object. For example, you have a list that contains the column Product Name. You want to

insert a graphic inside the Product Name column to show an image of each product. Unlocking the list allows you to insert the image object inside a list column.

Tip: From the **Structure** menu, click **Lock Page Objects**. Toggling this menu item locks and unlocks all layout objects in a report. However, this setting is not saved with the report.

Hierarchy of Objects

In IBM Cognos Report Studio, objects are organized hierarchically. For example, a list contains list columns, and each list column contains a text item, which is the name of the inserted data item.

The hierarchy of objects is useful to remember when you apply formatting because formatting is applied to the child objects of the object. For example, you can specify that all list column titles in a list have red as the background color. The formatting is automatically applied to any new columns you add to the list because the formatting is applied to the list and is therefore applied to the objects in the list. If you apply formatting to a specific object, it will override the same formatting specified for the parent object.

Related concepts:

Appendix G, “Report Studio Object and Property Reference,” on page 799
This appendix contains definitions of the objects and properties found in IBM Cognos Report Studio. They are available contextually, by pressing F1 when an object or property is active in the Report Studio authoring environment.

Find Objects in a Report

You can quickly locate specific objects in a report by using **Find**.

Procedure

1. From the **Edit** menu, click **Find**.
2. Click **Find what** and choose the type of object to find.
3. In the **Options** box, specify the search criteria.
For example, if you want to find the objects that reference a specific data item, you must specify the query that contains the data item and the data item name.
4. To search for objects that are hidden in the report, in the **View** box, select the **Show Hidden Objects** check box.
5. In the **View** box, under **Page view**, select whether you want to do the search in the Page Design or Page Structure view.
6. Click **Find Next**.

Results

The first object that meets the search criteria is selected in the report. Continue clicking **Find Next** to show all other objects that meet the search criteria.

Note: In some cases, such as searching for a data item that is used to define a conditional style, IBM Cognos Report Studio cannot directly select the object in the report. Instead, Report Studio selects the object that uses the object for which you are searching.

Related concepts:

“Work in design, structure, or Active Report preview view” on page 33
 IBM Cognos Report Studio has three views in which you can author reports: Page Design view, Page Structure view, and Active Report Preview view. Active Report Preview view is available only when you are authoring an IBM Cognos Active Report. You can choose a report authoring view on the **View** menu or by clicking the view icons in the Explorer bar.

Options

You can set various options that control the appearance and behavior of IBM Cognos Report Studio (**Tools, Options**).

View Options

Table 1. Descriptions of the options on the **View** tab of the Options window

Option	Description
Show all hidden dialogs	Shows all dialog boxes where the Show this dialog in the future check box was cleared, such as the Welcome dialog box at startup.
Reuse IBM Cognos Viewer window	Reuses the same IBM Cognos Viewer window when you rerun a report without first closing the window.
Resize IBM Cognos Viewer window	Maximizes the IBM Cognos Viewer window when you run a report.
Enable animation	Animates the appearance of dialog boxes, menus, and panes.
Window startup size	Specifies the size of the Report Studio window at startup.
Position pane on the right (requires restart)	Moves the content and Properties panes to the right of the work area. This check box is cleared by default. For the change to take effect, you must close and then restart Report Studio.
Show rich tooltips (requires restart)	Specifies whether to show descriptive tooltips when you hover over a button in the toolbar. This check box is selected by default. For the change to take effect, you must close and then restart Report Studio.
Display report preview	Shows a preview of the report when you open or save a report, within the Open , Save , and Save As dialog boxes.
Start page view	Enables you to start Report Studio in Page Design or Page Structure view. For the change to take effect, you must close and then restart Report Studio.

Edit Options

Table 2. Descriptions of the options on the **Edit** tab of the Options window

Option	Description
Wrap text in editors	Automatically wraps text in all editors where you can define expressions.

Table 2. Descriptions of the options on the **Edit** tab of the Options window (continued)

Option	Description
Automatically populate values list	When building expressions in the expression editor, automatically shows values when you browse the data of a data item.
Automatically validate expressions	Automatically validates calculations, such as filters, created in the expression editor. For more information, see “Using Relational Calculations” on page 262 or “Using Dimensional Calculations” on page 316.
In-place edit	Enables the editing of text in place when double-clicking.
Drop replace on crosstab and chart nodes	Specifies what the existing members are replaced with when you drag a new member onto a report.
Double-click on member action	When working with dimensional data, specifies what happens when you double-click a member data item. By default, you drill down or up on the item that you double-click.
Layout dimensions	Specifies the width and height of the area where you will create reports.

Report Options

Table 3. Descriptions of the options on the **Report** tab of the Options window


Option	Description
Alias member unique names	When working with a dimensional data source, creates an alias when you add a member to the report or to an expression.
Delete unreferenced query objects	Automatically deletes query objects linked to another object. For example, if you delete a list, the query linked to the list is deleted as well.
Delete unreferenced conditional styles and palettes	Automatically deletes conditional styles or palettes when the last data item that refers to the conditional style or palette is also deleted.

Table 3. Descriptions of the options on the **Report** tab of the Options window (continued)

Option	Description
<p>Always create extended data items for new reports</p>	<p>When working with dimensional data sources, determines whether Report Studio creates extended data items or expression-based data items for new reports.</p> <p>Expression-based data items allow you to view or edit the expression by double-clicking the Expression property for the item.</p> <p>If you are working with a dimensional data source and this option is not selected, the appropriate dimensional data item is added when you insert items such as members, levels, or calculated members. For example, if you insert a level, a level set is created. This makes it easier to work with dimensional data items because Report Studio knows the data item type of the items that are in the report.</p>
<p>Table Style inheritance</p>	<p>When a table style is applied to a list or crosstab, specifies whether new objects inserted in the list or crosstab should inherit the style. For more information, see “Apply a Table Style” on page 354.</p>
<p>Automatic group and summary behavior for lists</p>	<p>When working with lists, automatically adds an overall aggregate summary in the list footer and a summary for any groups in the list. When grouping a column, automatically makes it the first column in the list.</p>
<p>Automatically create crosstab headers for sets</p>	<p>When adding sets in a crosstab that uses a dimensional data source, automatically adds header labels on new columns and rows. The headers help consumers of the report to understand where the data is in the hierarchy.</p>
<p>Limit on inserted individual members</p>	<p>When working with a dimensional data source, limits the number of child members that are inserted. For example, you specify 3 for this option and, in the toolbar, you specify the option to insert children when you drag a member to a data container. You then drag the Camping Equipment member to the rows of a crosstab. What you see as rows are the child members Cooking Gear, Tents, and Sleeping Bags and a row named Others (Camping Equipment) for the remaining child members of Camping Equipment.</p>

Advanced Options

Table 4. Descriptions of the options on the **Advanced** tab of the Options window

Option	Description
Use operating system clipboard	Uses the Microsoft Windows (or other operating system) clipboard instead of the internal Report Studio clipboard.
Use legacy chart authoring	Enables you to create new reports using the legacy charts instead of the default charts and disables the automatic upgrade of charts in existing reports to the current default charts. Select this check box if you do not want to upgrade the charts in your existing reports.
Disable previews	When editing properties such as date and number formatting, does not display a sample of the formatting that is applied to data. When this option is not enabled, either sample data or data from your data source is displayed with formatting options applied. Additionally, when in Page Design view, displays a static image for a chart instead of updating the chart with a preview of your chart, using simulated data.
Override 10.x styles with 8.x styles on new reports	Specifies whether to use the Version 8.x report styles by default when creating new reports. For more information about report styles, see “Create and Modify Report and Object Styles” on page 365.
Active Report validation of visualization	Specifies whether to validate visualizations in an active report when the report is run from Report Studio.
Enable accessibility (requires restart)	Specifies whether to enable accessibility features in Cognos Report Studio. For the change to take effect, you must close and then restart Cognos Report Studio. For more information about accessibility features, see “Accessibility features in IBM Cognos Report Studio” on page 485.
Map feature display limit	When working with maps, specifies the maximum number of features that can appear in a map.
Member display count limit (in source tree)	When working with dimensional data, specifies the maximum number of members that can appear in the Source tab  before you must perform a search.

Related concepts:

“Recommendation - Use Member Unique Name (MUN) Aliases” on page 565
If you are working with a dimensional data source, use MUN aliases to simplify building reports and expressions. In addition, you can tie the MUN back to the

member in the package.

Web Browser Settings

IBM Cognos Report Studio can be used in the Microsoft Internet Explorer and Mozilla Firefox Web browsers.

To review an up-to-date list of the environments that are supported by IBM Cognos products, including information about operating systems, patches, browsers, web servers, directory servers, database servers, and application servers, visit the Software Environments site (<http://www.ibm.com/support/docview.wss?uid=swg27042164>).

IBM Cognos Business Intelligence uses the default browser configurations provided by Internet Explorer and Firefox. Additional required settings are specific to the browser.

For Internet Explorer, the following settings are required:

- Allow Cookies
- Active Scripting
- Allow META REFRESH
- Run ActiveX controls and plug-ins
- Script ActiveX controls marked safe for scripting
- Binary and script behaviors
- Allow programmatic clipboard access
- Userdata persistence
- Enable pop-ups for the IBM Cognos BI server

For Firefox, the following settings are required:


- Allow Cookies
- Enable Java™
- Enable JavaScript
- Load Images
- Enable pop-ups for the IBM Cognos BI server

Report Studio uses the native Microsoft Internet Explorer XML support, which is a component of the browser. ActiveX support must be enabled because Microsoft implements XML using ActiveX. IBM Cognos BI does not provide or download ActiveX controls. Only the ActiveX controls that are installed as part of Internet Explorer are enabled through this configuration.

For more information about the Web browser configuration and cookies used by IBM Cognos BI, see the IBM Cognos Business Intelligence *Installation and Configuration Guide*.

The IBM Cognos Software Development Kit

When you create a report, you are creating a report specification.

A report specification is an XML file that you can view (**Tools, Show Specification** ). In addition, you can view the specification for a selected object with the **Show Specification (Selection)** menu option.

You can also programmatically create or modify reports by using an editing tool to work with report specifications. You then use the IBM Cognos Software Development Kit to implement the reports in your IBM Cognos Business Intelligence environment. This is useful if, for example, you must make the same modification in many reports. Rather than opening each report and making the change, you can automate the process using the Software Development Kit, thereby saving you time. For more information about the Software Development Kit, contact your local sales office.

Tips

- When you are viewing the report specification, you cannot modify or copy parts of it.
- You can also modify the XML code in a report specification by saving the report specification on your computer.

Chapter 3. Creating a report

When you create a report, you are actually creating a report specification. The report specification defines the queries and prompts that are used to retrieve data and the layouts and styles used to present the data. For simplicity, the report specification is named by the same name as the report.

Specifying the Data Package

Specify the package that provides items for the report.

The packages that you use to generate reports are based on models that are created in the modeling tool, IBM Cognos Framework Manager. A model is a set of related objects, such as query subjects, dimensions, filters, and calculations. When you open a package in IBM Cognos Business Intelligence, these model objects are visible in the left frame.

Before you begin

The package must be previously created and published to the IBM Cognos Connection portal. For more information, see the *IBM Cognos Framework Manager User Guide*.

Important: If the package version changed since you opened IBM Cognos Report Studio, close and restart Report Studio to ensure that you are working with the latest version of the package.

Procedure

1. Open IBM Cognos Report Studio with the package you want to use.
2. In the **Welcome** dialog box, choose whether to create a new report or template, open an existing report or template, or create a new report from an existing template.
 - To create a new report or template, click **Create New** and choose a basic report layout.

Tip: You can specify a language other than the default language for your package by clicking the ellipsis button to the right of the **Package** field, clicking the **Language** ellipsis button in the **Report Package** dialog box, highlighting the desired language, and then clicking **OK**. As stated on the language selection dialog box, items such as separators and decimals might need to be manually updated for language-specific syntax rules as a result of your selection.

- To open an existing report or template, click **Open Existing** and select a report or template.

Tip: You can also open a Cognos Query Studio query or a Cognos Analysis Studio analysis.

- To create a new report from an existing template, click **New from Template** and select a template.

Tip: You can also create a new report from an existing Report Studio report, Cognos Query Studio query, or a Cognos Analysis Studio analysis.

Results

Objects from the selected package, such as query items, appear on the **Source** tab



Tip: You can later change packages.

Refresh the package



If the package that a report is using changed, refresh it to ensure that you are working with the latest content.

About this task

The contents of a package can change without the package version changing. For example, your modeler makes changes to a model and republishes the package with model versioning disabled.

Procedure

Refresh the package.

- To get the latest contents of the current package version being used, in the **Source** tab , click the refresh icon .
- To get the latest package version, close and restart your component.

Choosing a basic report layout


IBM Cognos Report Studio includes several basic report layouts that include report objects, such as lists, crosstabs, maps, repeaters, and headers and footers.

About this task

You can also choose to start with a blank report or create a new report from an existing report or template.

Tip: The Budget vs. Actual sample report in the GO Data Warehouse (analysis) package is based on a basic report layout. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure

1. From the **File** menu, click **New** .
2. If you want to change the package, click the ellipsis button and click a different package.
3. Choose a basic report layout:
 - To create a report from a blank layout, double-click **Blank**.
 - To create a report that uses one of Report Studio's predefined report layouts, double-click the layout.

- To create a new report template that can be applied to reports created in Report Studio, IBM Cognos Workspace Advanced, IBM Cognos Query Studio, or IBM Cognos Analysis Studio, double-click **Report Template**.
- To create a financial report that uses the basic financial report layout, double-click **Financial**.
- To create an IBM Cognos Active Report, double-click **Blank Active Report**.
- To create a new report from an existing report or template, double-click **From Template**, locate the report or template, and click **Open**.

Tip: Click the **Type** box and then click **Report templates** to see only existing templates.

Results

The basic report layout appears in the report page.

Related concepts:

Chapter 21, “Creating Report Templates,” on page 469

A report template is a pattern you use to build reports. Create your own report templates when you frequently produce the same type of report.

Chapter 9, “Active Reports,” on page 193

You can use IBM Cognos Report Studio to create active reports. IBM Cognos Active Report is a report output type that provides a highly interactive and easy-to-use managed report. Active reports are built for business users, allowing them to explore their data and derive additional insight.

Inserting a data container from the toolbox tab

You can insert data containers from the toolbox tab into a report.


About this task

When you insert a data container from the **Toolbox** tab, you can specify a name for the data container and the query that you want to create for the container instead of accepting the default names that are generated.

Extensible visualizations can contain one or more data containers. When you insert an extensible visualization, you can specify the visualization name, the names of its data containers, and the query that you want to create for the data containers.

Tip: By default, a single query is created for a visualization so that any filters that you add are shared across all data containers in the visualization. You can specify a different query for each data container.

Procedure

1. From the **Toolbox** tab , drag the data container that you want to insert in the report.
2. In the window that appears, type a name for the data container and a name for the query to be created for the container.



Tip: You can link a container to an existing query by clicking the query menu and choosing from the list of available queries.

Add Data

Select the data items you want to appear in your report.

For more information about adding data to a relational style report, see “Add Relational Data to a Report” on page 227. For more information about adding data to a dimensional style report, see “Add Dimensional Data to a Report” on page 267.

Procedure

From the **Source** tab , drag data items to the report object. A flashing black bar indicates where you can drop a data item. Data items in the report appear on the **Data Items** tab .

Data source icons

Each object in the data source has a representative icon. You can insert all of the following objects in a report, except for packages and dimensions.

Table 5. Objects represented by data source icons















Icon	Object
	Package, which contains the objects you can insert in a report.
	Namespace, used to organize objects.
	Query subject, which represents a table in the database.
	In relational data sources, query item, which represents a column of qualitative data in the database, such as product name or country or region. In dimensional data sources, level attribute, which represents a property of a level.
	A member is a unique item within a hierarchy. For example, Camping Equipment and 4 Man tent are members of the Products Hierarchy.
	Dimension, which represents a broad grouping of descriptive data about a major aspect of a business, such as products, dates, or markets.
	Hierarchy, which represents a collection of dimensional members organized into a tree structure.

Table 5. Objects represented by data source icons (continued)

Icon	Object
	<p>Level, which is a set of members that have common attributes. For example, a geographical dimension might contain levels for country or region or city.</p> <p>Multiple levels can exist within a level hierarchy, beginning with the root level. The root level is the parent and rollup of all members in the first level. It is used to obtain a rollup of all values across the hierarchy and to provide a convenient point to start drilling.</p> <p>For example, a Years level hierarchy may contain the following levels:</p> <ul style="list-style-type: none"> • Root level Years • First level Year • Second level Quarter • Third level Month
	Measure or fact, a query item that represents a column of quantitative data in the database, such as revenue or quantity, in a relational model.
	Measure or fact, a query item that represents a column of quantitative data in the database, such as revenue or quantity, in a dimensional model.
	Measures folder, which contains hierarchical measures, in a dimensional model.
	Model filter.
	Model calculation.
	Folder, used to organize data items. You cannot import a folder into your report.

Insert a Single Data Item

You can insert a single data item anywhere in your report using the singleton object. The singleton object retrieves only the first row value for that query. Inserting a single data item is useful when you want to show a value that is independent from the rest of the values in the report or when you want to insert some boilerplate text, such as a company name and address. For example, you can add the total revenue value in the header of each page in a report.

You can associate multiple singleton objects with a single query in relational reporting and dimensional reporting to optimize performance, such as when all the data items in the singleton are from the same database table. In addition, two or more singletons can reference data items from the same query. This is useful when using a single query is more efficient to display a set of single values than using multiple queries.



You can also filter the data item in the singleton. For example, you can show the total revenue for only the year 2012.

Queries that are associated to a singleton object are not supported when producing report output in delimited text (CSV) format.

Tip: The Returns by Damage, Failed Orders and Complaints in 2012 sample report in the GO Data Warehouse (analysis) package includes a singleton. For more

information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure

1. From the **Toolbox** tab , drag **Singleton** to the report.
An empty data container is created.
2. From the **Source** tab , drag a data item into the **Singleton** container.

Tip: To create a singleton, you can also drag a data item anywhere in your report layout.
3. To change the query associated to the singleton object, in the **Properties** pane, double-click the **Query** property and make changes.

Results


When the report is run, the first row value for the data item is retrieved.

Validate a Report

Validate your report to ensure that it contains no errors.

When you open a report created in a previous version of IBM Cognos Business Intelligence, it is automatically upgraded and validated. For more information, see Chapter 23, “Upgrading Reports,” on page 479.

Procedure

1. From the **Tools** menu, click **Validate Report** .
A message box appears indicating whether any errors were found in the report.
2. If you require more detail from the validation process, from the **Tools** menu, click **Validate Options** and do the following:
 - Click one of the following validation levels.

Validation level	Description
Error	Retrieves all errors returned from the query.
Warning	Retrieves all errors and warnings returned from the query. This is the default validation level.
Key Transformation	In addition to errors and warnings, retrieves informational messages describing important transformation steps from the report specification to the native query sent to the data source. These messages can show the cause of errors and warnings returned from the query.
Information	Retrieves errors, warnings, key transformations, and other information related to query planning and execution.

Tip: Your administrator can change the default validation level. For more information, see the *IBM Cognos Business Intelligence Administration and Security Guide*.

- Select the **Interactive data** check box to specify that no query optimization is to be used.

The **Interactive data** check box controls how queries will be processed during validation.

Clear the **Interactive data** check box to set the **Execution Optimization** property to **All Rows**.

Tip: For more information about the **Execution Optimization** property, see Execution Optimization in Appendix G, “Report Studio Object and Property Reference,” on page 799.

A message box appears indicating whether any errors were found in the report.

- To view messages that result from the conversion of your report to use the dynamic query mode instead of the compatible query mode, select the **Dynamic Query Migration** check box.

For more information about using the dynamic query mode, see the *IBM Cognos Business Intelligence Dynamic Query Guide*. For more information about managing the migration from the compatible query mode to the dynamic query mode, see the *IBM Cognos Lifecycle Manager Installation and User Guide*.

- Revalidate your report.
3. If you encounter validation errors and want IBM Cognos Report Studio to identify incorrect objects in your report, from the **Tools** menu, click **Auto Correct**.

Report Studio provides a list of such objects that you can remove individually to successfully run your report.


In some cases, the information or error message is linked to the location of the issue in your report. To go to the location of the issue, click the message, and then click **Select**. If only warnings and information appear in the dialog box, these will disappear when you click **OK**.

Save a Report

Save your report to preserve the modifications you made.

Reports are saved to the IBM Cognos Business Intelligence server. You can also save your report on your computer.

Procedure

1. From the **File** menu, click **Save**  or click **Save As** to save a copy of the report under a different name.
2. If you are saving the report for the first time, specify where to save the report and type a file name.

For information about setting up folders in IBM Cognos Connection for your reports, see the *IBM Cognos Connection User Guide*.

3. Click **Save**.

Running a report

Run your report to see the data that is retrieved. Save time by validating it first to check for errors.

You can also run a report or a group of reports in IBM Cognos Connection. Furthermore, you can save report outputs to a file system. For more information, see the *IBM Cognos Business Intelligence Administration and Security Guide*.

You can specify not to render a report page if it does not contain any data.

When you run a report in an export format such as PDF, delimited text (CSV), Microsoft Excel spreadsheet software (XLS), the IBM Cognos report name is used as the exported file name.

If you run a report that uses functions or features not supported by the data source, an error message appears. We recommend that you periodically test your reports while you author them in IBM Cognos Report Studio to ensure that you do not encounter multiple error messages when you run the report.

Procedure

1. Open a report.
2. If you want to clear parameter values stored on the IBM Cognos Business Intelligence server, from the **File** menu, click **Clear Parameter Values**.
Parameter values stored by the IBM Cognos BI server include signon, validation, and prompt information. For example, if you define two data source connections in IBM Cognos Connection that point to the same data source, you are prompted to choose one when you run a report. This information is stored so that you are not prompted each time you run the report.
3. If you want to view only the tabular data, click **Run > View Tabular Data**.
If the report contains multiple queries, you must first click an object, such as a list or crosstab, that uses the query for which you want to view the tabular data.
Use this command to ensure that the right results appear. For example, you create a calculation and you want to ensure it is giving you the results you want.
Tip: You can also view tabular data in Query Explorer, which is useful when you are building queries.
4. If you want to set run options, from the **Run** menu, click **Run Options**.
The default value is the value of the selected corresponding run option in IBM Cognos Connection.
Note: The run options that you set apply only to the current session. When you close Report Studio, the options return to the default settings.
5. Change any values for the current session.

Option	Description
Format	Specify to change the default format from HTML.
Paper size	Specify only if the output format is PDF.
Paper orientation	Specify only if the output format is PDF.

Option	Description
Data mode	<p>Specify how much data is returned:</p> <ul style="list-style-type: none"> • All Data returns all data. • Limited Data limits the amount of data returned based on design mode filters defined in the package. • No Data returns artificial data instead of actual data from the data source. <p>For more information about design mode filters, see the <i>IBM Cognos Framework Manager User Guide</i>.</p>
Language	The content language sets the preferred language for the data, IBM Cognos Viewer, dates, and so on.
Rows per page	<p>Specifies the number of rows to appear on each page.</p> <p>A Rows Per Page property exists in the Properties pane for lists and crosstabs. If you set this property, the setting overrides the same-named run option. This property applies to both HTML and PDF outputs. For more information about this property, see “Controlling the Rows Per Page for Multiple Containers in HTML and PDF” on page 52.</p>
Prompt	<p>Select to be prompted for each prompt defined unless the prompt is defined in a report page.</p> <p>If you clear the Prompt check box, you are prompted only if the report cannot run without user intervention. For example, if a report has a single parameterized filter that is optional, you are not prompted when you run the report.</p>
Include accessibility features	<p>Specifies whether accessibility features, such as alternate text on images and charts and summary text in tables, are included in the report output.</p> <p>This option is also used for conditional layouts in Report Studio. When the option is selected, you can specify that a crosstab is rendered as an accessible alternate to a chart.</p> <p>For more information about how to create accessible reports, see “Considerations to Improve Report Accessibility” on page 486.</p>
Enable bidirectional support	<p>Specifies whether to enable bidirectional support in the report output.</p> <p>Tip: You can also enable bidirectional support in Cognos Connection by modifying your user preferences (My Preferences link). If you enable bidirectional support in Cognos Connection, this run option will be automatically selected.</p>

6. From the **Run** menu, click one of the options to produce the report in the format you want.

You can produce a report in HTML, PDF, CSV, various Microsoft Excel formats, and XML. You cannot produce a report in CSV format if you have more than one query defined in the report unless the additional queries are used for prompts.

Restriction: The formats that are available depend on the capabilities set by the administrator for each user. You may not be able to run reports in all formats. For more information, see the *IBM Cognos Business Intelligence Administration and Security Guide* or contact your administrator.

Results

The report runs in IBM Cognos Viewer. Once the report has finished running, you can run the report again in the same format or in a different format. If you run the report again in CSV or XLS format, the report will appear in a new browser window.

Related concepts:


“Running a Report Against a Dimensional Data Source” on page 549

You can cancel a report that is running against Microsoft SQL Server Analysis Services only during the initial portion of its execution. After this time, the report runs to completion.

Specify Not to Render a Page If It Does Not Contain Data

You can specify not to render a report page if the page does not contain any data when the report is run.

Procedure

1. In the report page, click a data container.
2. In the **Properties** pane, click the select ancestor button  and click the data container type.

For example, if the data container is a list, click **List**.

Tip: You can also click the container selector (three orange dots) of the container to select it.

3. Set the **Render Page when Empty** property to **No**.
4. Repeat steps 1 to 3 for all other data containers in the page and any table of contents objects.

Results

When you run the report, if no data is produced in all data containers and table of contents objects in a page, the page is not rendered. The page is not rendered even if the page contains other objects, such as text items or images.

Controlling the Rows Per Page for Multiple Containers in HTML and PDF

If you have more than one data container in a report, such as a list and a crosstab, you can control how the report is rendered in HTML and PDF by setting the **Rows Per Page** property for each container.

For HTML output, the report property option **Page break by data container for interactive HTML** controls whether the default number of rows is rendered for each data container on each page.

IBM Cognos Business Intelligence uses the following rules when rendering reports in HTML and PDF:

- If the **Rows Per Page** property is not set for any of the data containers, 20 rows per page are rendered in HTML and each page is completely filled in PDF. The first data container is rendered until there is no more data, followed by the next container, and so on.

Tip: The number of rows that appear on a PDF page depends on the font size set in the report.

- If the **Rows Per Page** property is set for each data container, the specified numbers of rows are rendered in HTML and PDF on each page until there is no more data.
- If the property is set for only some of the containers, the specified numbers of rows are rendered in HTML and PDF on each page until there is no more data. For the remaining containers, 20 rows per page are rendered on each page in HTML and each page is completely filled in PDF.

For example, you have two lists, List1 and List2. You set the **Rows Per Page** property to 5 for List1. When you run the report in HTML, the first page contains the first 5 rows from List1 followed by the first 15 rows of List2.

- If no data is returned for a data container, an empty container is rendered.

Producing a Report in CSV Format

IBM Cognos Business Intelligence can produce reports in CSV format so you can open them in other applications, such as Microsoft Excel spreadsheet software.

Reports saved in CSV format

- support Unicode data across many client operating systems
- are UTF-16 Little Endian data encoded
- include a BOM (Byte Order Mark) at the beginning of the file
- are tab-delimited
- do not enclose strings in quotation marks
- use a new line character to delimit rows

You can open reports saved in CSV format using a variety of spreadsheet software applications. By default, reports produced in CSV format will appear in the application associated with the .csv file type.

You cannot produce the following in CSV format:

- maps
- charts that do not have at least one category or series
- reports that have more than one query defined in the report, unless the additional queries are used for prompts

In IBM Cognos Connection, you can configure the CSV output to suit your environment. For example, you can specify the character used to delimit fields. For more information, see the IBM Cognos Business Intelligence *Administration and Security Guide*.

Producing a Report in Microsoft Excel Format

You can export your report output to several different Microsoft Excel spreadsheet software formats.

Excel 2007 and **Excel 2007 Data** formats render report output in native Excel XML format, also known as XLSX. This format provides a fast way to deliver native Excel spreadsheets to Microsoft Excel 2002, Microsoft Excel 2003, and Microsoft Excel 2007. Users of Microsoft Excel 2002 and Microsoft Excel 2003 must install the Microsoft Office Compatibility Pack, which provides file open and save capabilities for the new format.

Excel 2007 provides fully formatted reports for use in Microsoft Excel version 2007.

The output is similar to other Excel formats, with the following exceptions:

- Charts are rendered as static images.
- Row height can change in the rendered report to achieve greater fidelity.
- Column widths that are explicitly specified in reports are ignored in Microsoft Excel 2007.
- Merged cells are used to improve the appearance of reports.
- The default size of worksheets is 65 536 rows by 256 columns.

Your IBM Cognos administrator can enable larger worksheets and change the maximum number of rows in a worksheet, up to a maximum of 16,384 columns by 1,048,576 rows, by using advanced server properties. For more information, see the *IBM Cognos Business Intelligence Administration and Security Guide*.

Excel 2007 Data provides data for use in Microsoft Excel version 2007. These reports only contain minimal formatting. Default data formatting is applied to the data based on data type and assumes that each column has a single data type.

The output is similar to other Excel formats, with the following exceptions:

- The generated output includes only the first list query in the report. If a report contains multiple queries and the first query is a multi-dimensional query for a crosstab or for a chart, an error message is displayed when the report runs.
- Nested frames and master-detail links are not supported.
- Cells in the Microsoft Excel file have a default width and height. You must adjust the column width and height if the data is larger than the default size.
- Style specifications are not rendered, including color, background color, and fonts.
- Borders are not rendered.
- User-specified data formatting in the report specification are not applied, including exception highlighting and color rules for negative numbers.

Excel 2002 provides fully formatted reports for use in Microsoft Excel versions earlier than 2007. Excel 2002 format also offers the following benefits:

- Spreadsheets are contained in a single file for reliable spreadsheet navigation.
- The maximum size of worksheets is 65,536 rows by 256 columns.

Related concepts:

Appendix E, "Limitations When Producing Reports in Microsoft Excel Format," on page 567

There are limitations when producing reports in Microsoft Excel format.

Option to group repeating cells in reports produced in Excel 2007 format

When you produce reports in Excel 2007 format, you can specify whether repeating cells are grouped, or merged, into a single cell.

Report outputs to Excel 2007 format are easier to read and look more like other output formats when repeating values are grouped. If further analysis of the data is required within Excel or if the outputs are used to provide data to another tool, it is often preferable for repeating values to be populated in each row or column to which they apply.

By default, repeating cells are merged in Excel 2007 output. For example, Product line is a grouped column in a list. The values for Product line, such as Camping Equipment and Golf Equipment, appear once in a merged cell in Excel output. When repeating cells are not grouped, the values for Product line appear in each repeating cell. The option to merge repeating cells in Excel output is controlled by selecting or clearing the **Group repeating cells when exporting to Excel** check box in the **Report Properties** dialog box.

Crosstabs

In general, grouped data item values appear in each repeating cell. For example, a crosstab contains Product line and Product type as rows. When repeating cells are ungrouped, the label for each product line value is rendered in each repeating row cell.

If a cell on a column edge spans multiple worksheet rows, the cell label is not repeated in all rows. If a cell on a row edge spans multiple columns, the cell label value is not repeated in multiple worksheet columns. For example, a crosstab contains Product line, Product type, and Product as rows. A summary is added for Product line. The product line summary cell spans Product line, Product type, and Product. In Excel, repeating cells are produced for the summary row, but the label for the summary appears only in the first cell.

Repeating cells that are produced from crosstab headers follow this behavior. For example, Product line and Product type are inserted as rows in a crosstab. Headers named Product line and Product type are created, and each header spans two columns. In Excel, the header labels appear only in the first cell. The repeating cells are empty.

If a layout object, such as a table or image, is inserted in the crosstab corner, the size of the object might cause the crosstab corner column edge to span multiple rows and row edges to span multiple columns. When this situation occurs, column labels repeat only in the column span and row labels repeat only in the row span.

The following figure shows a crosstab that contains Year as columns and Order method type as rows. A three by three table is inserted in the crosstab corner. In Excel output, the size of the table produces repeating cells in the columns and in the rows. Year labels, such as 2010, repeat only in the columns and not in the rows. Order method labels, such as E-mail, repeat only in the rows.

Year	Product	Quantity
2010	Camping Equipment	16,840
2010	Personal Accessories	7,121
2010	Outdoor Protection	20,166
2010	Golf Equipment	9,203
2010	United States	214,504
2010	Canada	137,774
2010	Japan	21,936
2010	Singapore	88,931
2010	Korea	44,691
2010	Netherlands	1,159
2010	Sweden	25,565
2010	Denmark	9,625
2010	France	19,919
2010	Germany	8,875
2010	Italy	10,672
2010	Spain	23,700
2010		36,471
2010		3,311
2010		30,551
2010		9,451
2010		36,231
2010		19,114
2010		143
2010		255
2010		608
2010		204,002
2010		101,389
2010		158,959
2010		52,189
2010		67,801
2010		19,476
2010		66,848
2010		24,921
2010		25,347
2010		1,100
2010		7,475
2010		3,668

Figure 2. Excel 2007 output of a crosstab with a table inserted in the crosstab corner

Lists

In lists, grouped data values are repeated in ungrouped cells. For example, a list contains Product line and Product type, and Product line is grouped. When repeating cells are ungrouped in Excel, the label for each product line value is rendered in the repeating cells.

Group header and list page header labels are not repeated. These labels appear only in the first cell, and repeating cells are empty.

Nested data containers, images, and charts

Nested data containers, images, and charts in a report can produce merged cells. For example, when a crosstab is inserted in a list, other columns in the list appear as merged cells in Excel 2007 output. The following rules are applied when merged cells are split.

1. If a cell is merged as a result of a data item grouping, then data values are repeated in the split cells.
2. If a cell is merged as a result of a nested data container, image, or chart, then data values are not repeated in split cells.

For example, a list contains Product line, Product type, Quantity, and an image as columns. The Product line column is grouped. The image produces merged cells in Excel output because its size spans more than one row. When the report is run with the option to ungroup repeating cells, Product line values are repeated, but Product type and Quantity values are not.

Bookmarks

When you produce Excel 2007 output with ungrouped repeating cells, clicking an entry in a table of contents brings you to the first row that contains that entry. For

example, a report contains a list with a table of contents. Product line values are repeated in the list in Excel output. When you click Camping Equipment in the table of contents, you are brought to the first cell in the list that contains Camping Equipment.

Related tasks:

“Specify Report Properties” on page 364

You can change the default report property settings.

Producing a Report in XML Format

XML report outputs save the report data in a format that conforms to an internal schema, `xmldata.xsd`.

You can find this schema file in `c10_location/bin`.

This format consists of a dataset element, which contains a metadata element and a data element. The metadata element contains the data item information in item elements. The data element contains all the row and value elements.

You can create models from reports and other data that conform to the `xmldata.xsd` schema. This is useful if you want to use a report as a data source for another report, or if you use a database that cannot be read by IBM Cognos Framework Manager. In this case, export the data from the data source to an XML file, in conformance with the `xmldata` schema, and then open the XML file in Framework Manager.

For more information, see the Framework Manager *User Guide*.

You cannot produce the following in XML format:

- maps
- charts that do not have at least one category or series
- reports that have more than one query defined in the report, unless the additional queries are used for prompts

If a report contains more than one data container, such as a crosstab and a list, and both containers use the same query, only the output for the list is produced. If a report contains multiple lists, only the output for the first list is produced. If a report contains multiple crosstabs and multiple lists, only the output for the first list is produced.

Set PDF Page Options



Set PDF page options, such as page orientation and paper size, to control how report pages appear in PDF. You can set PDF page options for individual report pages or for all report pages in a layout.

Tip: The PDF Page Properties sample report in the GO Sales (analysis) package includes PDF page options. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

You can also set PDF page options in IBM Cognos Connection. For more information, see the IBM Cognos Connection *User Guide*.

The paper size for PDF output can be a maximum of 200 x 200 inches or 500 x 500 centimeters. A larger paper size produces a blank page.

Procedure

1. To set PDF page options for all report pages in a layout, do the following:
 - From the **File** menu, click **PDF Page Setup** and set the page options.
2. To set PDF page options for an individual page, do the following:
 - Pause the pointer over the page explorer button  and click the page.
 - In the work area, click anywhere on the page.
 - In the **Properties** pane, click the select ancestor button  and click **Page**.
 - Double-click the **PDF Page Setup** property, select the **Override the page setup for this page** check box, and set the page options.

View Lineage Information for a Data Item

View lineage information of a data item to see what the item represents before you add it to a report.

Lineage information traces the metadata of an item back through the package and the data sources used by the package. Lineage also displays any data item filters that were added by the report author or that were defined in the data model. Viewing lineage information ensures that you add the correct data items to a report. For example, you can view the lineage information of a model calculation to see how it was created.

Note: Lineage is available only after your administrator has configured it. For more information, see the *IBM Cognos Business Intelligence Administration and Security Guide*. In addition, lineage is not supported in reports that are not linked to packages.

You can use the lineage tool that comes with IBM Cognos Business Intelligence, or you can use another lineage tool by specifying the URL to the tool in IBM Cognos Administration. Note that if the URL source is secured, the source must be able to prompt users for a password because IBM Cognos BI does not pass security information. IBM Cognos BI also supports the IBM Metadata Workbench as a lineage tool. For more information about configuring other lineage tools, see the *IBM Cognos Business Intelligence Administration and Security Guide*.

Tip: The Customer Returns and Satisfaction sample report “Customer Returns and Satisfaction” on page 533 in the GO Data Warehouse (analysis) package includes lineage information. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

You cannot use lineage information to troubleshoot queries. For example, lineage information will not explain why a data item is double counted. Also, you cannot view lineage information when running a report from a mobile device.

Before you begin

Before you can access lineage information for a report, your administrator must configure lineage in IBM Cognos Administration. Also, the administrator must enable the lineage capability and grant read permission for you on the report.

Note: The IBM Cognos BI lineage tool shows lineage on a report at its highest level. The lineage does not change after you drill down on a report. Because the selection context used to launch lineage can be affected by drill-down operations,

we recommend that you always launch lineage at the highest report level before drilling down on the report. Otherwise, the lineage may not start properly.

Procedure

From the **Source** tab , right-click the data item and click **Lineage**.

Tip: You can view lineage information for multiple data items at the same time by first Ctrl+clicking the items. The IBM Metadata Workbench does not support viewing lineage for multiple data items at once.

Results

The lineage tool opens showing the lineage information of the selected data item.

The IBM Cognos Business Intelligence lineage tool

The IBM Cognos Business Intelligence lineage tool includes two views: the business view and the technical view.

The business view displays high-level textual information that describes the data item and the package from which it comes. This information is taken from IBM Cognos Connection and the IBM Cognos Framework Manager model.

The technical view is a graphical representation of the lineage of the selected data item. The lineage traces the data item from the package to the data sources used by the package.

When you click an item, its properties appear below it. If you click an item in the **Package** area, you see the model properties of the item. If you click an item in the **Data Sources** area, you see the data source properties of the item.




Figure 3. The technical view in the IBM Cognos Business Intelligence lineage tool

You can also view lineage information in IBM Cognos Viewer after you run a report. For example, you can click a cell in a crosstab to see how the cell value was calculated. To view lineage information in IBM Cognos Viewer, right-click an item

in the report and then click **Lineage**. If you or an administrator runs a saved report with the IBM Cognos BI lineage tool, both the business view and the technical view are visible. Report consumers can see only the business view. In addition to the **Package** and **Data Sources** areas, a **Report** area exists when looking at the technical view.

Access the IBM WebSphere Business Glossary

Business glossaries help you manage and share an enterprise vocabulary and classification system.

If you use the IBM WebSphere® Business Glossary, you can access the glossary from any of the following data objects:

- Query subject
- Query item
- Measure
- Dimension
- Hierarchy
- Level
- Property or attribute
- Top node member
- Member
- Level item

Procedure

Right-click the data item and click **Glossary**.
The IBM WebSphere Business Glossary appears.

Support for bidirectional languages

You can author reports that support bidirectional languages. You can specify base text direction, digit shaping, and container direction.

Arabic, Hebrew, Urdu, and Farsi are languages written from right to left, using the Arabic or Hebrew scripts. However, numbers in those languages, as well as embedded segments of Latin, Cyrillic, or Greek text, are written from left to right. Using the bidirectional settings in IBM Cognos Report Studio, you can control the direction in this type of text in reports.

Report formats

Bidirectional languages are supported for reports produced in HTML, PDF, and Microsoft Excel. IBM Cognos Active Report also supports bidirectional languages.

Enabling bidirectional support

To enable support for bidirectional languages when a report is run, in IBM Cognos Connection, users must open their **My Preferences** page and select the **Enable bidirectional support** check box.

To enable support for bidirectional languages when a report is run from Report Studio, select the **Enable bidirectional support** check box in the **Run Options** window.

Tip: If you enable bidirectional support in Cognos Connection and you then start Report Studio, the bidirectional support run option in Report Studio is selected. If you disable bidirectional support in Cognos Connection and you then start Report Studio, the run option in Report Studio is cleared.

Base text direction

Base text direction sets the text direction as left-to-right or right-to-left. You can specify the base text direction for any text object in a report. You specify the base text direction for text by clicking the **Direction & Justification** property for the text or for the object that contains the text, such as a list column.

A contextual option also exists in the **Direction & Justification** property that sets the text direction based on the first letter in the text.

For compound objects that contain text, you specify the base text direction of the text contained in the object by clicking the **Contained Text Direction** property for the object. Examples of compound objects are charts, prompts, and active reports.

Digit shaping

Digit shaping allows users to consume reports with numbers that they can read after they select the content language in IBM Cognos Connection. You can specify digit shaping at the following levels:

- Report
- Container (except for charts and maps)
- Text
- Number

You specify digit shaping for an object by clicking the **Data Format** property for the object. To specify digit shaping at the report level, click the **Default Data Formats** option in the **Data** menu.

Tip: Digit shaping has no impact on reports produced in Excel format, since the shaping of digits in Excel depends on Windows regional settings.

Container direction

Container direction sets the direction of container objects in a report as left to right or right to left. You specify container direction for an object by clicking the **Direction & Justification** property for the object.

Tip: Container direction is not supported in reports produced in Excel format. Excel spreadsheets do not natively support mirroring at the container level.

Related concepts:

“Digit shaping in charts and maps” on page 405

When working with bidirectional content, you cannot specify digit shaping at the chart or map level. You can specify digit shaping for the objects in charts and maps.

Related tasks:

“Running a report” on page 50

Run your report to see the data that is retrieved. Save time by validating it first to check for errors.

“Specify text and container direction” on page 360

You can specify text and container direction by choosing any of these options.

“Set the Default Data Formats” on page 403

Set the default data properties for each type of data, including text, number, currency, percent, date, time, date/time, and time interval.

“Specify the Data Format for an Object” on page 404

Specify the format for a particular object if you are not getting the results you want.

Reports for workspaces in Cognos Workspace

When building a workspace in IBM Cognos Workspace, business users can insert an entire IBM Cognos Report Studio report or insert only individual objects from within a report.

To create effective reports for use in workspaces in Cognos Workspace:

- Ensure that all the objects and pages within the report have meaningful names. For some objects, such as data containers, Report Studio gives the object in a report a default name such as List 1, List2, and so on. In Cognos Workspace, these names appear in the **Content** tree. To help business users recognize the report objects, rename them to something more meaningful (**Properties** pane, **Name** property).

If you do not want an object to be added in a workspace, clear the **Name** property for that object. The object will not appear in the **Content** tree. However, you cannot clear the name of data containers. Report Studio requires that data containers have names.

Note: Cognos Workspace does not support tables and blocks. Unsupported objects do not appear in the **Content** tree in Cognos Workspace, even if you specify a name for the object.

- Create a container report that includes all the report objects that workspace users might want to add in a report. Such a report is not meant to be run and does not need to show report objects in a proper layout. It is only used as a container for the various report parts. Each page of a report appears as a folder within the Cognos Workspace **Content** pane.

For example, on one page named Prompts you can insert all the possible prompts that users might want to add to a workspace, and give each prompt a useful business name, such as Value Prompt for Region. On a second page named Charts, you can insert a number of charts useful for workspaces.

- Ensure that the titles and labels used in your report are understandable by business users.
- Ensure that you use report objects that are well suited for dashboards. They convey the most information in as little space as possible. For example, if you include a chart, use bullet charts, microcharts, line charts, or column and bar charts. Use conditional blocks to show business indicators.
- If your report includes charts, customize the font sizes so that the charts appear correctly in a dashboard. You may need to reduce the font sizes.
- If your report includes embedded objects, such as a list with an embedded chart and crosstab, the embedded objects do not appear in the Cognos Workspace

Content pane, unless the embedded objects are in a table object. When you insert an object that contains embedded objects, the embedded objects will be inserted in the workspace.

When embedded objects are in a table object, the embedded objects appear in the **Content** pane. Table objects do not appear in the **Content** pane because Cognos Workspace does not support Report Studio table objects. Consequently, you can insert the embedded objects in a workspace, but not the table.

- If your report includes a map, customize the colors of the map in Report Studio so that they match the color palette of the dashboard. You cannot edit the color palette of a map from within a workspace in Cognos Workspace.
- If your report is using a dimensional data source and you enable drill-up and drill-down, in the Drill Behavior window, specify that the column title uses member caption values.

Cognos Workspace does not support drill up and drill down with level label values as the column titles. Cognos Workspace always uses member captions.

Related tasks:

“Create a Drill-up and Drill-down Report” on page 322

You can link groups of data items from different queries so that when you drill up or drill down in one query, the data item also drills up or drills down in the linked queries.

Prompts in workspaces in Cognos Workspace

A prompt control, when assigned a **Name** property in IBM Cognos Report Studio, appears as an object that you can insert from the **Content** pane in a workspace in IBM Cognos Workspace.

If a workspace includes reports and report parts from the same model, prompts automatically filter the appropriate data item in all the widgets in the dashboard. For example, a prompt filters on Product Line. Any widget in the dashboard that includes the Product Line data item is filtered when you select a value from this prompt control. If you do not want a prompt to control a widget in the dashboard, you can disable communication between the two widgets.



If a dashboard includes prompted reports or report parts from different models, ensure that the prompts use the same parameter names. For example, a year prompt should use the same parameter **p_Years** in reports from both models. Otherwise, the prompt control is unable to control reports from another package.

Enable filters in workspaces in Cognos Workspace

You can include a data item in the query of the report, but not show that data item in the actual report. This is useful for creating calculations and filters. If you want IBM Cognos Workspace users to filter content in a workspace based on a data item that is not visible in the report, you must include this data item in its own query and name it **_BusinessInsight_** within the IBM Cognos Report Studio report. Therefore, the data item must exist in both the query used for the data container (such as the list, crosstab, or chart) and in this separate query.

For example, a chart shows the revenue for the product lines for each region. You want to filter the chart to show only data for the year 2012. When you author the report, in addition to including Year in the Query1 used for the chart data container, you create a new query named **_BusinessInsight_** that includes Year.

Procedure

1. Pause your pointer over the **Query Explorer** and click **Queries**.
2. From the **Toolbox** tab , drag a **Query** object to the work area.
3. Click the **Query** object, and in the **Properties** pane, in the **Name** box, type **_BusinessInsight_**.
4. Double-click the **Query** object, and from the **Source** tab , add the data item to use as a filter.
Ensure that the same data item also exists in the query used for the data container.

Creating Reports for IBM Cognos for Microsoft Office

IBM Cognos for Microsoft Office provides an integrated environment for IBM Cognos products and Microsoft Office. You can use IBM Cognos for Microsoft Office to select pieces of reports to embed in Microsoft Excel workbooks, Microsoft Word documents, or Microsoft PowerPoint presentations, including data, metadata, headers, footers, and charts. You can use predefined reports or you can create new content using IBM Cognos PowerPlay® Web, IBM Cognos Query Studio, IBM Cognos Workspace Advanced, or IBM Cognos Report Studio.

Note: Note that to access PowerPlay content, your administrator must configure PowerPlay to work with IBM Cognos Business Intelligence. PowerPlay content that is published only to Upfront is not available to IBM Cognos for Microsoft Office.

Because IBM Cognos for Microsoft Office cannot fully convert highly formatted reports into Excel or other Microsoft document output types, you may not get the results that you want.

To create effective reports for IBM Cognos for Microsoft Office, follow these recommendations:

- Create content to meet specific Microsoft Office integration needs.
For example, in IBM Cognos BI, many options are available to format data. Use less formatting to make data more accessible to Office applications.
- Organize reports.
You can publish workbooks to IBM Cognos Connection and organize them with your reports in **Public Folders** or **My Folders**. For more information, see the IBM Cognos Connection *User Guide*. By organizing your content, you can quickly retrieve the information that you want.

Tip: Workbooks, documents, and presentations that are enabled for IBM Cognos for Microsoft Office are identified by their own unique icons, helping you to distinguish them from other types of files.

- Optimize report templates for Microsoft Office.
If you rely on IT personnel or other report authors to create content, request report templates that are optimized for your Microsoft Office integration needs. You may want to request only the data elements or queries that you need and request minimal formatting so that you can more easily use Microsoft Office formatting capabilities with the IBM Cognos content. For example, reports authored in Report Studio can contain list objects embedded within list objects

with specific formatting applied. When converted to the tabular representation available in Excel, these reports may not be rendered in the same way in which they appear in IBM Cognos BI.

- Format elements in the Office application.

Instead of formatting objects in IBM Cognos BI, add the formatting in the Office application. By applying less formatting in IBM Cognos BI, you can import more data into the desired locations.

- Label report elements using descriptive names.

This practice makes them more easier to find after you import them. Examples of report elements include lists, crosstabs, and charts.

- Do not nest report objects.

If you nested report objects, some objects may not appear in the correct location, or they may not appear at all. In addition, nesting report objects may cause the following error message to appear:

RDS-ERR-1000 Report Data Service could not process from the content provider.

For example, this error occurs if a repeater or repeater table is inside a block or table. It also appears when layout objects, such as lists, crosstabs, and charts, are in a conditional block that is inside another block or table.

- Keep table sizes small.

For example, because of the size of slides, the maximum number of rows and columns that you can have in Microsoft PowerPoint tables is 25. Although Word and Excel permit larger tables, it takes more time to download and render them.

- Use images with transparent backgrounds.

The background will show through the image in the Office application, making the image look like part of the presentation. If you want, you can then supply your own background color.

- Specify the height and width of images in a list.

This practice ensures that the image appears in the correct size in the Office application.

- Remember that graphs and charts are imported as images.

Images in IBM Cognos BI have image maps associated with them to enable tooltips and hotspots. IBM Cognos BI for Microsoft Office cannot import tooltips and hotspots into Office applications.

- Consider the additional limitations that exist when producing reports in Excel format.

Creating Reports for Mobile Devices

You can send IBM Cognos Report Studio reports to mobile devices that have IBM Cognos Mobile installed, or that are using the IBM Cognos Mobile Web portal.

Creating location-aware reports

A location-aware report filters report data based on the user's current location as determined by the GPS coordinates of the mobile device. For example, a Vice President of Sales travels frequently to visit his Regional Sales Managers. When he arrives at an airport, he wants to filter his sales report to show information about the region that he is visiting.

You can create location-aware reports in IBM Cognos Report Studio if your IBM Cognos Mobile administrator has set up location-aware parameters. For more information, check with your IBM Cognos Mobile administrator or see the *IBM Cognos Administration and Security Guide*.

Location-aware reports must include at least one prompt that requests the location information. This location information, as defined by your IBM Cognos Mobile administrator, could use either coordinates or defined regions, such as states, provinces, cities, or voter regions. Your administrator also defines the parameter names for the prompts, which you must provide when adding the location prompt.

Chapter 4. Lists

Use lists to show detailed information from your database, such as product lists and customer lists.

A list shows data in rows and columns. Each column shows all the values for a data item in the database or a calculation based on data items in the database.

Product line	Quantity
Camping Equipment	27,301,149
Golf Equipment	5,113,701
Mountaineering Equipment	9,900,091
Outdoor Protection	12,014,445
Personal Accessories	34,907,705
Overall - Summary	89,237,091

You can specify whether to automatically add an overall aggregate summary in the list footer and a summary for any groups in the list by selecting **Automatic group and summary behavior for lists** in the IBM Cognos Report Studio options. The default aggregation as specified in your enterprise data source is used.

Tip: The Order Invoices - Donald Chow, Sales Person sample report in the GO Sales (query) package includes a list. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Related concepts:

“Limitations When Using Set Expressions in List Reports” on page 550

In list reports, we recommend that you avoid using set expressions. When in a list, set expressions, such as TopCount, may produce fewer rows than in the corresponding crosstab.

Related tasks:

“Change a List into a Crosstab” on page 79

Change a list into a crosstab to view your data from a different perspective.



Set List Properties

Format lists to give them the appearance you want. You can specify formatting for individual column titles or bodies or for all columns in a list. When you specify formatting for all columns in a list, the formatting is automatically applied to new columns you subsequently add.

You can also quickly format lists by applying table styles.

Formatting for specific columns overrides formatting for entire columns. For example, you specify red as the background color for a specific column body and green as the background color for all columns. When you run the report, the specific column body is red and the remaining columns in the list are green. New columns added to the list will be green.

Procedure

1. To format an individual column, do the following:
 - a. Click the column title or column body.
 - b. To format the text in the column title or the data in the column body, click the unlock button  in the toolbar and then click the title or body.
 - c. To format the whole column, click the select ancestor button  in the title bar of the **Properties** pane and click **List Column**.
 - d. In the **Properties** pane, set the property value.
For example, to specify a background color, click **Background Color** and choose the color.
2. To format all columns, do the following:
 - a. Click a column in the list.
 - b. To format list column bodies, click the select ancestor button in the title bar of the **Properties** pane and click **List Columns Body Style**.
 - c. To format list column titles, click the select ancestor button in the title bar of the **Properties** pane and click **List Columns Title Style**.
 - d. To format entire columns, click the select ancestor button in the title bar of the **Properties** pane and click **List Columns**.
 - e. To format the entire list, click the select ancestor button in the title bar of the **Properties** pane and click **List**.

Tip: You can also click the container selector (three orange dots) of the list to select it.
 - f. In the **Properties** pane, set the property value.
For example, to specify a background color, click **Background Color** and choose the color.

Related concepts:


Chapter 13, “Laying Out a Report,” on page 343

When creating a report, a good layout is essential to ensure that the information in the report is presented in a clear and effective manner.

Hide Columns in List Reports

You can hide columns from the output of list reports. If you select to hide a column, the query for that column is still executed.

Procedure

1. Select the column that you want to hide.
2. Click the select ancestor button  in the title bar of the **Properties** pane and click **List Column**.
3. Set the **Render** property to **No**.

Results

When you run your report, the column is hidden in the report output.

Using Repeaters

Use repeaters to repeat items when you run the report. For example, you can use repeaters to create mailing labels, including customer names and addresses.

To build a repeater, drag the **Repeater** or **Repeater Table** object from the **Toolbox** tab to the work area. Use repeaters to repeat items across a single row without a particular structure. For example, you want to create a list that contains Year, and Product line. For each year, you want all product lines to appear in a single row. To do this, create a list with Year as a column and with a repeater as a second column. Then insert Product line into the repeater. Use repeater tables to repeat items in a table structure. Drop the items in the repeater, and modify the properties of the repeater to obtain the results you want. For example, you can specify how many frames appear per page in a repeater table by typing values in the **Across** and **Down** properties.

Horizontal pagination is not supported for data containers, such as lists or crosstabs, that are nested in repeater tables.

Convert a List into a Repeater

You can convert a list into a repeater table to take advantage of an existing list.


Procedure

1. Click any part of the list.
2. From the **Structure** menu, click **Convert List to Repeater**.


Example - Create Mailing Labels





You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create mailing labels for all of the company's retailers.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **Repeater Table** and click **OK**.
4. Click the repeater, click the select ancestor button  in the **Properties** pane title bar, and click **Repeater Table**.

Tip: You can also click the container selector (three orange dots) of the repeater table to select it.

5. In the **Properties** pane, set the following properties:
 - Set the **Across** property to 2.
 - Set the **Down** property to 5.
 - Double-click the **Table Properties** property, select the **Fixed size** check box, and click **OK**.
6. From the **Toolbox** tab , drag the **Table** object to the repeater. The **Insert Table** dialog box appears.
7. In the **Number of columns** box, type 1 and click **OK**.
8. Click the table, ensure that you see **Table Cell** in the **Properties** pane title bar, and modify the following properties:
 - Double-click **Background Image**, click **Specified** and click **Browse**.
 - Click **logo.jpg** and click **OK**.
 - In the **Background Image** dialog box, in the **Position** box, click the align top right button.

- Under **Tiling**, click **Do not tile** and click **OK**.
 - Double-click **Size & Overflow**, and in the **Height** box, type **175**, and click **OK**.
9. Click the table, click the select ancestor button in the **Properties** pane title bar, and click **Table**.
- Tip:** You can also click the container selector (three orange dots) of the table to select it.
10. In the **Properties** pane, specify properties for the table:
- Double-click **Border**.
 - In the **Style** box, click **Solid line**.
 - In the **Width** box, click **1 pt**.
 - In the **Color** box, click **Black**.
 - Under **Preview**, click the apply all borders button  and click **OK**.
 - Double-click **Font**, and under the **Size** box, click **8pt**, and click **OK**.
11. From the **Toolbox** tab , drag the **Block** object to the repeater 8 times to create 8 blocks.
12. Drag the **Text Item** object  to the first block:
- In the **Text** dialog box, type **To:** and click **OK**.
 - Select the text item.
 - Double-click the **Font** property, set the weight to **Bold**, and click **OK**.
13. Click the first block, and, in the **Properties** pane, specify properties for the first block:
- Double-click the **Padding** property, type **35** in the box on the right, click **mm** as the unit, and click **OK**.
 - Set the **Horizontal Alignment** property to **Center**.
14. From the **Source** tab , expand **Sales and Marketing (query)**, **Sales (query)**, and **Retailer site** and drag seven data items to the remaining seven blocks.
15. Ctrl+click the seven blocks to select them, and in the **Properties** pane, specify properties for the seven blocks:
- Double-click the **Padding** property, type **25** in the box on the left, click **mm** as the unit, and click **OK**.
 - Set the **Horizontal Alignment** property to **Left**.

Results

When you run the report, each page contains 10 mailing labels in two columns.

Chapter 5. Crosstabs

Use crosstab reports, also known as matrix reports, to show the relationships between three or more query items. Crosstab reports show data in rows and columns with information summarized at the intersection points.

For example, the following crosstab shows the gross profit and revenue by product line for each year.

		2013			2012
		Gross profit	Revenue	Cost of Goods Sold	Gross profit
Mountaineering Equipment	Climbing Accessories	\$15,110,667.58	\$29,483,205.87	\$14,372,538.29	\$15,286,177.75
	Tools	\$18,683,965.74	\$44,578,458.74	\$25,894,493.00	\$21,981,831.82
	Rope	\$12,487,333.44	\$39,444,903.89	\$26,957,570.45	\$14,677,667.24
	Safety	\$10,436,847.43	\$28,014,081.20	\$17,577,233.77	\$12,287,850.59
Outdoor Protection	First Aid	\$450,357.59	\$846,984.93	\$396,627.34	\$923,995.66
	Sunscreen	\$930,913.91	\$1,561,978.22	\$631,064.31	\$2,006,172.66

Tip: The Same Month Prior Year sample report in the Sales and Marketing (cube) package includes a crosstab. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Related tasks:

“Insert a Microchart into a Crosstab” on page 155

You can use microcharts to improve the visualization of data in crosstabs.

Crosstab Nodes and Crosstab Node Members

When you add data items to crosstabs, you create crosstab nodes and crosstab node members. These objects allow you to easily create crosstabs, by dragging data items to crosstabs.

Crosstabs are dimensional objects that have row edges and column edges. Each edge is composed of a set of crosstab nodes. Each crosstab node contains the following:

- One or more crosstab node members.
- Zero or one nested crosstab node, which contains one or more crosstab node members or nested crosstab nodes.

Each crosstab node member refers to a data item that contains an expression to define the members in the crosstab.

The following crosstab contains four crosstab nodes.

(4)

Revenue		<#Year#>	<#Year#>
		<#Month#> Total	<#Month#> Total
(1) Total		<#1234#>	<#1234#>
(2) <#Product line#>	<#Product type#>	<#1234#>	<#1234#>
	<#Product type#>	<#1234#>	<#1234#>
(3) Average		<#1234#>	<#1234#>

1 Crosstab node 1 contains a single node member for the total. This node refers to the data item Total(Product line).

2 Crosstab node 2 contains a crosstab node member that refers to the data item Product line. This member has a nested crosstab node containing a crosstab node member that refers to the data item Product type.


3 Crosstab node 3 contains a single node member for the average. This node refers to the data item Average(Product line).

4 Crosstab node 4 contains a crosstab node member that refers to the data item Order year. This member has two nested crosstab nodes. The first node contains a crosstab node member that refers to the data item Order month. The second node contains a crosstab node member for the total. This node refers to the data item Total(Order month).

Tip: Nodes are also created when you add data items to charts.

Moving Crosstab Nodes


Crosstab nodes can be placed anywhere in the crosstab. For example, in the previous diagram, you can drag **Order month** under **Average** to create a row edge.

To move nested items from one edge to another, ensure that you select the crosstab node and not the crosstab node member. For example, in the previous diagram, you want to move **Product line** and **Product type** to the column edge. To do this, click **Product line** and, in the **Properties** pane, click the select ancestor button  and click **Crosstab Node**. Both **Product line** and **Product type** are selected.

Crosstab Node Creation Option

In the **Structure** menu, the **Create Crosstab Nodes** option affects the drag-and-drop behavior in crosstabs. When the option is turned on and you add a data item to a crosstab, the item is created as a crosstab node. If the option is turned off, the item is created as a crosstab node member to an existing crosstab node.

For example, in the previous diagram, if the option is turned on and you drag

Country or Region from the **Source** tab  to beneath **Product line**, **Country or Region** becomes a new peer node to **Product line**. If the option is turned off, **Country or Region** becomes a new peer node to **Product line** and has **Product type** as a nested crosstab node. This happens because instead of adding a new node, you are adding a new member to the existing node that already contains **Product line**.

Tip: To create discontinuous crosstabs, turn the **Create Crosstab Nodes** option on. If you want the items on the edges of crosstabs to be related (contain the same nested items), turn the **Create Crosstab Nodes** option off.

Set Crosstab Properties

Format crosstabs to give them the appearance you want. You can specify formatting for rows, columns, and fact cells in a crosstab or for the entire crosstab. When you specify formatting for all rows, columns, fact cells, or the crosstab, the formatting is automatically applied to any new items you add.

If you apply the same styles, such as font color, to crosstab rows, columns, and crosstab intersections, the styles are applied in the following order:


1. crosstab fact cells
2. fact cells in the outermost rows
3. fact cells in the innermost rows
4. fact cells in the outermost columns
5. fact cells in the innermost columns
6. crosstab intersections

The style applied to the last object in the list overrides styles applied to previous objects. In addition, class styles are applied before styles that you apply manually.

You can also quickly format crosstabs by applying table styles and add white space to a crosstab by inserting crosstab space objects.

Tip: In cases where fact cell formatting applied to rows conflicts with fact cell formatting applied to columns, you can set the **Fact Cells Precedence** property in the **Properties** pane to determine whether the row formatting or the column formatting has precedence. To set this property, click anywhere in the crosstab, click the select ancestor button in the title bar of the **Properties** pane, and click **Crosstab**. Or you can click the container selector (three orange dots) of the crosstab to select it.


Procedure

1. To format the entire crosstab, do the following:
 - a. Click anywhere in the crosstab.
 - b. Click the select ancestor button  in the title bar of the **Properties** pane and click **Crosstab**.
 - c. In the **Properties** pane, set the property value. For example, to specify a background color, click **Background Color** and choose a color.
2. To format all rows, columns, or fact cells, click a row, column, or fact cell in the crosstab and then do the following:
 - a. If you clicked a row, click the select ancestor button in the title bar of the **Properties** pane and click **Crosstab Rows**.
 - b. If you clicked a column, click the select ancestor button in the title bar of the **Properties** pane and click **Crosstab Columns**.
 - c. If you clicked a fact cell, click the select ancestor button in the title bar of the **Properties** pane and click **Crosstab Fact Cells**.
 - d. In the **Properties** pane, set the property value. For example, to specify a background color, click **Background Color** and choose the color.

- Tip:** You can also right-click the row or column and click **Select Fact Cells**.
3. To format all crosstab cells for a specific row or column, do the following:
 - a. Click the row or column.
 - b. Click the select ancestor button in the title bar of the **Properties** pane and click **Crosstab Member Fact Cells**.

Tip: You can also right-click the row or column and click **Select Member Fact Cells**.

- c. In the **Properties** pane, set the property value. For example, to specify a background color, click **Background Color** and choose the color.
 4. To format all row or column titles, do the following:
 - a. Click a row or column title.
 - b. Click the select ancestor button in the title bar of the **Properties** pane and click **Crosstab Rows** or **Crosstab Columns**.
 - c. In the **Properties** pane, set the property value. For example, to specify a background color, click **Background Color** and choose the color.
 5. To format an individual row, column, or intersection, do the following:
 - a. Click the row, column, or intersection.

Tip: To format the data in a row, column, or intersection, click the unlock button  in the toolbar and then click the text item to format.

- b. In the **Properties** pane, set the property value. For example, to specify a background color, click **Background Color** and choose the color.

Related concepts:



Chapter 13, “Laying Out a Report,” on page 343

When creating a report, a good layout is essential to ensure that the information in the report is presented in a clear and effective manner.

Create a Single-Edge Crosstab

Create a single-edge crosstab report to show data in a list-like form. For example, to show the quantity of products sold for each year and for each order method, you could create a crosstab with **Order Year** and **Order Method** as rows and **Quantity** as the measure.

Procedure

1. From the **Toolbox** tab , insert a crosstab object to the work area.
2. From the **Source** tab , drag data items to the **Rows** or **Columns** drop zone. A black bar indicates where you can drop the data item.
3. Repeat step 2 to insert additional data items:
 - If you dragged the data item in step 2 to the **Rows** drop zone, drag the additional items above or below the first item.
 - If you dragged the data item in step 2 to the **Columns** drop zone, drag the additional items to the left or right of the first item.
4. To add measures to the crosstab, drag the measures to the **Measures** drop zone.

Results

When you run the report, a crosstab is produced that has only one edge.

Create a Nested Crosstab

Nest data in a crosstab report to compare information by using more than one data item in a column or row. For example, a report shows the number of sales by product line for the past fiscal year. You decide to add a data item to further break down the number of sales by quarter.

When nesting columns in a crosstab report, there are four distinct drop zones where you can insert a new data item. The drop zone you choose will define the relationship between the data item and the column.

The following relationships are created when you insert a data item as a row:

- Inserting a data item to the left or right of a column creates a parent-child relationship between them.

When you insert a data item to the left of a column, the data item becomes a parent to the column. When you insert a data item to the right of a column, the data item becomes a child of the column.

- Inserting a data item above or below a column creates a union relationship between them.

The following relationships are created when you insert a data item as a column:


- Inserting a data item to the left or right of a column creates a union relationship between them.
- Inserting a data item above or below a column creates a parent-child relationship between them.

When you insert a data item above a column, the data item becomes a parent to the column. When you insert a data item below a column, the data item becomes a child of the column.

For example, you have a crosstab with Product line as rows and Quantity and Revenue as nested rows. For columns, you have Order method with Country or Region as a nested column. In this crosstab,

- Product line is a parent to Quantity and Revenue.
- Quantity and Revenue are peers.
- Order method is a parent to Country or Region.

Procedure

1. From the **Source** tab , click the data item to add.
2. Drag the data item to the report as a nested column or nested row.
A black bar indicates where you can drop the data item.
3. Repeat steps 1 to 2 to add other nested columns or rows.

Tip: If you add more than one measure to a crosstab, all measures appear as columns. You cannot have one measure appear as a row and another as a column. To make all measures appear as rows, swap columns and rows.

Creating headers automatically for sets in crosstabs

You can automatically add header labels on columns and rows when working with sets in a crosstab that uses a dimensional data source. The headers help consumers of the report to understand where the data is in the hierarchy.

Header labels are added only when you add new sets to your crosstab. The labels are not added to existing sets. After you enable this option, it remains on until you disable it, and applies to any new crosstabs that you create.

Procedure

1. From the **Tools** menu, click **Options**, then click the **Report** tab.
2. Select **Automatically create crosstab headers for sets**.
3. Click **OK**.

Results

Header labels are created in the rows and columns in a crosstab.

Showing crosstab values as percentages

When you work with dimensional data sources, you can show crosstab values as a percentage of a summary instead of the actual values. When you show values as a percentage, you can compare the contribution of an item to the whole.

About this task

You can show crosstab values as a percentage of a summary on the rows, the columns, or the rows and columns. For example, a crosstab has Product line as rows, Year as columns, and Revenue as the measure. You can show the following crosstab values:

- The actual values of Revenue
- A percentage of a summary on Product line
- A percentage of a summary on Year
- A percentage of a summary on Product line, Year

By default, the summary type that is used to calculate the percentages is Automatic summary.

When you show values as a percentage, a percentage measure data item is created.

You can also create a custom percentage calculation. For example, you can show values as a percentage of an intersection (tuple). Or you can show values as a percentage of a different summary type, such as Maximum.

When you show values as a percentage, the fact cells are formatted with the percent data format. When you show the actual values, the fact cells are formatted with the number format. If you modify the data format of the actual values, the change is lost when you switch between showing the actual values and percentage values.

You can show values as a percentage only in crosstabs. If you insert a chart, you cannot fill the chart with data from a crosstab that shows values as a percentage. If

you create a chart from a crosstab that shows values as percentages, an empty chart is created in the report.

Procedure

1. Select the measure for which you want to show values as a percentage.
If there is only one measure in the crosstab, click the crosstab corner.
2. From the **Data** menu, click **Show Value As**, and click the percentage values that you want to show.
3. If you click **Custom**, provide the information that is required to calculate the percentage values.
 - a. To change the default name of the percentage data item that you are creating, type the new name in the **Name** field.
 - b. In the **Percentage based on** box, choose to build the percentage data item based on a summary of sets in the crosstab or based on an intersection (tuple).
 - c. If you choose to build the percentage data item based on a summary of sets, in the **Choose sets** box, click the sets that you want to use. Then, click the **Summary type** menu and select the summary that you want to use to calculate the percentage values.
If there is more than one data item on the crosstab edge that you chose for the sets, select which data item that you want to use.
 - d. If you choose to build the percentage data item based on an intersection (tuple), click the ellipsis and select the items that you want to use to create the intersection.
 - e. Click **OK**.
4. To edit a measure percentage data item, follow these steps.
 - a. Select the measure.
 - b. From the **Data** menu, click **Show Value As > Edit**.
 - c. Modify the information for the data item as described in step 3.
 - d. If you replaced a set in the crosstab with a different set, in the **Choose sets** box, click **Existing sets** when you want to base the percentage values on the set that you replaced.

Related tasks:

“Create an Intersection (Tuple)” on page 320


When working with dimensional data, an intersection, also known as a tuple, is useful for obtaining a value from the combination of two or more members that you specify. Each member must be from a different hierarchy. The intersection can include only one measure.

Specify the Default Measure

You can specify the default measure for crosstabs and certain chart types. Specify the default measure to be used when the measures cannot be determined by what is on the edges. For example, you create a crosstab with Order method as rows and Product line as columns. You add Quantity and Revenue as nested rows, making Order method their parent. You then add Country or Region under Order method. Since there is no measure specified for Country or Region, you specify the default measure so that data is returned for each country or region.

Note: In crosstabs, IBM Cognos Report Studio automatically sets the default measure when you insert a measure into the crosstab cells.

Procedure

1. To specify the default measure for a crosstab, do the following:
 - Click any part of the crosstab, and then click the select ancestor button  in the title bar of the **Properties** pane.
 - Click **Crosstab**.


Tip: You can also click the container selector (three orange dots) of the crosstab to select it.
 - Set the **Default Measure** property to the default measure.
2. To specify the default measure for a chart, drag the measure to the **Default measure** box in the chart.

Swap Columns and Rows

Swap columns and rows to look at information from a different perspective. This may help you discover high and low points in the data that you hadn't previously noted.

You can only swap columns and rows in a crosstab or chart. In a chart, you swap the x- and y-axes.

Procedure

From the toolbar, click the swap rows and columns button .

Results

In the report, the rows become the columns and the columns become the rows.

Indent Data

You can indent crosstab node members to set them apart from surrounding data.

When you insert a hierarchy in rows, all members are automatically indented according to their level. By default, the first member in a set is not indented. If you insert a hierarchy in columns, the members are not automatically indented. You can change the indentation properties of members in the report.

Relative indentation means that the member will shift by one tab when the member's level increases relative to the previous member in the hierarchy.

Indenting based on the level in the hierarchy means that the member will shift the number of tabs equivalent to the level in the hierarchy.

You can also indent objects by applying padding.

Procedure

1. Click the crosstab node member to indent.
2. In the **Properties** pane, set the **Level Indentation** property to your indentation type, length, and direction.

Change a List into a Crosstab

Change a list into a crosstab to view your data from a different perspective.

Procedure

1. Click the columns to appear as columns or nested columns in the crosstab.
2. From the **Structure** menu, click **Pivot List to Crosstab**.

Results


The list becomes a crosstab with the columns you selected in step 2 appearing as columns and nested columns. The unselected columns, except for measures, appear as rows and nested rows. If you have one measure, it becomes the cells of the crosstab. If you have more than one measure, they appear as columns.

Tip: To make all measures appear as rows, swap columns and rows.


Example - Add Aggregate Data to a Crosstab

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a report showing sales by order method to determine which methods are generating the most revenue and the highest sales volume.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **Crosstab** and click **OK**.
4. From the **Source** tab :
 - Expand **Sales and Marketing (query)** and **Sales (query)**.
 - Expand **Product** and double-click **Product line** to add it as rows.
 - Expand **Order method** and double-click **Order method** to add it as columns.
 - Click **Product type** and drag it just to the right of **Product line**.
Product type is now nested in **Product line**.
 - Expand **Sales fact** and drag **Quantity** to the **Measures** drop zone to add it as a measure.
 - Drag **Revenue** to the right of **Quantity** to add it as a second measure.

Tip: Drop **Revenue** into the crosstab when you see a vertical bar between the **Product type** column and the **Order method** column.

5. Click any part of the crosstab, and then click the select ancestor button  in the title bar of the **Properties** pane.
6. Click **Crosstab**.

Tip: You can also click the container selector (three orange dots) of the crosstab to select it.

7. In the **Properties** pane, double-click the **Font** property.
8. In the **Size** box, click **8pt** and click **OK**.

9. Click one of the measures.

10. Click the summarize button  and click **Maximum**.

Results

When you run the report, you can see that for camping equipment, **Cooking Gear** generated the highest sales volume for the **Special** order method and **Tents** generated the most revenue. Tents ordered by the **Web** order method generated the largest revenue.

		E-mail		Fax		Mail		Sales visit		Special	
		Quantity	Revenue	Quantity	Revenue	Quantity	Revenue	Quantity	Revenue	Quantity	Revenue
Personal Accessories	Binoculars	37,637	4,284,108.12	15,530	1,826,685.29	10,281	1,098,108.29	76,412	8,285,309.35	4,499	501,383.29
	Eyewear	350,203	14,640,359.21	142,334	5,625,130.49	14,189	1,263,524.31	80,122	6,941,087.7	18,492	830,547.24
	Knives	217,439	4,930,481.24	127,848	2,943,473.65	60,329	1,376,954.66	630,593	14,138,765.34	70,325	1,525,039.64
	Navigation	91,639	7,978,990.89	36,726	3,434,569.89	16,901	1,734,352.52	159,215	13,914,997.1	16,964	1,591,269.23
	Watches	94,987	10,817,147.08	36,976	4,133,126.14	13,508	946,417.25	60,765	4,415,282.96	7,478	738,389.1
	Maximum	350,203	14,640,359.21	142,334	5,625,130.49	60,329	1,734,352.52	630,593	14,138,765.34	70,325	1,591,269.23
Mountaineering Equipment	Climbing Accessories	138,242	2,038,855.77	172,803	2,390,328.78	46,488	679,297.57	598,362	8,432,511.02	63,772	802,217.59
	Rope	8,118	2,237,177.54	10,804	3,006,587.53	4,209	1,133,910	45,383	12,623,472.19	5,350	1,395,807.43
	Safety	17,881	1,283,131.17	36,195	2,658,809.76	8,065	592,500.66	125,179	9,265,767.61	8,386	625,119.3
	Tools	34,973	1,917,287.48	72,606	3,792,644.01	22,497	1,125,950.43	272,313	14,294,875.82	16,348	850,863.79
	Maximum	138,242	2,237,177.54	172,803	3,792,644.01	46,488	1,133,910	598,362	14,294,875.82	63,772	1,395,807.43
Camping Equipment	Cooking Gear	667,254	12,660,160.31	222,711	4,375,855.61	171,358	3,349,528.79	1,435,032	29,955,819.16	115,031	2,344,882
	Lanterns	263,370	6,786,981.1	61,991	1,724,287.33	56,107	1,486,107.02	535,633	14,243,626.26	30,150	835,346.38
	Packs	151,719	18,578,756.65	38,840	5,737,253.88	34,452	4,260,591.65	276,738	35,504,440.57	14,940	2,659,194.73
	Sleeping Bags	174,310	14,711,086.99	48,580	5,894,604.37	39,916	3,997,819.92	325,265	35,363,204.56	20,638	2,806,666.82
	Tents	156,431	23,162,109.58	41,836	5,322,397.49	46,225	8,254,596.71	327,086	53,544,871.32	22,769	3,742,899.51
	Maximum	667,254	23,162,109.58	222,711	5,894,604.37	171,358	8,254,596.71	1,435,032	53,544,871.32	115,031	3,742,899.51
Outdoor Protection	First Aid	69,710	1,172,104.41	20,051	290,765.82	19,719	321,745.23	108,442	1,512,056.66	12,455	172,402.16
	Insect Repellents	394,117	2,517,273.14	169,275	1,072,328.08	172,800	1,097,464.84	836,274	5,266,401.35	101,333	627,243.75
	Sunscreen	441,329	2,193,100.32	122,257	603,390.82	135,579	679,181.64	656,810	3,251,426.3	69,287	337,285.32

Figure 4. Crosstab showing quantity and revenue by order method by product line and product type


Example - Create a Discontinuous Crosstab

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a report showing sales for each product line by quarter and by order method. Since the report will have columns with data from different dimensions, you create a discontinuous crosstab report.

Discontinuous crosstabs are also known as disconnected or disjoint crosstabs or crosstabs with unrelated columns.


Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **Crosstab** and click **OK**.

4. From the **Source** tab  :
 - Expand **Sales and Marketing (query)** and **Sales (query)**.
 - Expand **Product** and drag **Product line** to the **Rows** area.
 - Expand **Order method** and drag **Order method** to the **Columns** area.
 - Expand **Sales fact** and drag **Revenue** to the **Measures** area.

- On the **Source** tab, expand **Retailer site** and drag **Region** to the left of **Order method**.

Tip: Drop **Region** into the crosstab when a flashing vertical bar appears between the **Product line** column and the **Order method** column. Otherwise, **Region** may appear as a nested row instead of a column.

- Click **Region**.
- In the **Properties** pane, double-click the **Sorting** property.
- From the **Data Items** pane, drag **Region** to the **Sort List** pane.
- Click the sort order button  to sort in ascending order and click **OK**.
- Run the report.

Results

Revenue	Americas	Asia Pacific	Central Europe	Northern Europe	Southern Europe	E-mail	Fax	Mail
Camping Equipment	481,445,781.04	421,639,391.62	343,645,848.36	180,851,396.88	161,454,246.13	75,899,094.63	23,054,398.48	21,348,644.09
Golf Equipment	217,262,995.22	193,677,873.68	153,632,833.39	84,424,300.9	77,413,364.7	47,933,933.16	15,241,303.27	12,693,287.48
Mountaineering Equipment	123,127,397.88	107,505,775.01	88,051,532.89	46,091,108.04	44,884,319.08	7,476,451.96	11,848,370.08	3,531,658.68
Personal Accessories	593,696,783.38	439,800,120.35	437,336,485.23	210,608,208.82	204,231,710	42,651,086.54	17,962,985.46	6,419,357.03
Outdoor Protection	23,002,647.68	19,716,018.32	17,488,870.77	8,346,431.17	7,440,328.31	5,882,477.87	1,966,484.72	2,098,391.71

Figure 5. Crosstab showing revenue by product line by region

Chapter 6. Charts

You can use IBM Cognos Report Studio to create many chart types, such as column, bar, area, and line charts.

Current Default Charts and Legacy Charts

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

You will find procedures in this chapter for using both the legacy charts and the current default charts. To use the legacy chart type, set the **Use legacy chart authoring** option (**Tools > Options > Advanced** tab).

Related concepts:

“Limitations When Converting Legacy Charts” on page 107

When you convert a legacy chart to the current default chart, some chart types or chart properties might not be migrated properly. For example, clustered area charts and 100% stacked line charts are not available in the current default charts. If your exact chart configuration is not available, select the closest matching template.


Related tasks:

“Convert Legacy Charts to Current Default Charts” on page 107

You can convert charts from the legacy charts to the current default charts. When you convert a legacy chart, select the template that most closely matches your legacy chart in order to preserve as many settings as possible.

Creating Charts

Before creating charts, review the available chart types to select the best chart for your needs. Also review the chart objects that make up charts.

Tip: To view the available chart types, from the **File** menu, click **New**, and then double-click the chart icon . You can also view the available chart types by adding a **Chart** object from the **Toolbox** tab in the **Insertable Objects** pane to an existing report.

To create charts, drag data items from the **Source** tab  to the measures, data series and categories drop zones.

Note: When you are working with dimensional data sources, do not insert member properties in the series or categories of a chart. By default, IBM Cognos Report Studio groups items that are inserted in these areas. Grouping member properties produces a warning when you validate the report.

To help you when creating charts, you can do the following:

- Preview your chart style changes.


As you author your chart and edit the chart properties, IBM Cognos Report Studio provides you with a preview of your chart, using simulated data. This allows you to view your style changes without running your report. You need to run your report to see the chart with your actual data. You can disable the chart preview in the options.

- Resize your charts.
- Move the chart drop zones into flyouts so that they appear only when you pause your pointer over the chart.


After you create a basic chart, modify the various chart objects to customize your chart.

Chart Objects

The following shows the most common chart objects as they appear in your report output in IBM Cognos Viewer.




The following shows the same chart as it appears in the IBM Cognos Report Studio user interface. The Y-axis is selected, and the axis titles are displayed.



Click chart objects to specify properties

The default charts have more properties that allow you to customize more aspects of the chart than in earlier versions. You can click in different areas of the chart to get access to different properties.

For example, by clicking the axis, you can customize the color, style, weight, and transparency of chart axis lines and specify where to display major and minor gridlines on the chart.



Data Series

A data series is a group of related data points that are plotted in a chart. Each series has a unique color or pattern and is described in the legend. You can plot one or more data series in a chart; pie charts have only one data series.

In the example chart, the data series are order years 2010, 2011, 2012, and 2013.

Categories

Categories are groups of related data from the data series that are plotted on the X-axis. Categories of multiple data series are shown together using clustered and stacked data markers.

In the example chart, the categories are the product lines of The Sample Outdoors Company in clustered columns.

Axes

Axes are lines that provide references for measurement or comparison.

The primary axis (or Y-axis) refers to measures of quantitative data, such as sales figures or quantities. Charts can have more than one primary axis.

The category axis (X-axis or ordinal axis) plots qualitative data, such as products or regions. It runs horizontally, except in bar charts.

The z-axis is the vertical axis in a 3-D chart.

Major gridlines extend from the tick marks on an axis and run behind the data markers.

Related concepts:

“Customizing the Axes of a Chart” on page 123

Chart axes are lines that border the chart area and provide a reference for measurements. They act as a vehicle for tick marks and scales and form a frame around the chart. The Y-axis is usually the vertical axis and contains data. The X-axis is usually the horizontal axis and contains categories.

Legend

A legend is a key to the patterns or colors assigned to the data series or categories in a chart.

Columns, Lines, and Areas

Charts use graphical elements such as columns, horizontal bars, points, bubbles, lines, and areas as visual representations of data points.

Chart Types

IBM Cognos Report Studio provides many types of charts for presenting your data in a way that is meaningful for your users.

You can select from a variety of chart types (such as pie, bar, line, gauge, scatter, and so on) and you can select from a variety of chart configurations (such as stacked columns, 3-D pies). Combination charts allow you to use more than one chart type within your chart.

Some chart types are not supported for Microsoft Excel output or appear differently in Excel. For more information, see Appendix E, “Limitations When Producing Reports in Microsoft Excel Format,” on page 567.

Choosing a Chart Type and Configuration

To choose a chart type, consider what you want the chart to illustrate. Different chart types and configurations emphasize different things.

Purpose	Chart type or configuration
Show contributions of parts to a whole	Bar Charts Pie Charts Stacked Charts, when you want to display measures of the whole, as well as the parts 100 Percent Stacked Charts

Purpose	Chart type or configuration
Show trends in time or contrast values across different categories	Line Charts Area Charts Bar Charts Column Charts Always place time in the horizontal axis.
Compare groups of related information against actual values	Bar Charts Radar Charts
Compare different kinds of quantitative information	Combination Charts
Rank values in descending or ascending order	Bar Charts Column Charts
Show correlation between two sets of measures	Point Charts
Show key performance indicators in an executive dashboard report	Gauge Charts Bullet Charts


Column Charts

Column charts are useful for comparing discrete data or showing trends over time.

Column charts use vertical data markers to compare individual values.

Note: The Sales Growth Year Over Year sample report “Sales Growth Year Over Year” on page 539 in the GO Data Warehouse (analysis) package includes a column chart. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

The following example shows the revenue for each product line.



Column charts can plot data using standard, stacked, 100 percent stacked, and three-dimensional configurations.


Line Charts

Line charts are useful for showing trends over time and comparing many data series.

Line charts plot data at regular points connected by lines.

Line charts can plot data using standard, stacked, 100 percent stacked, and three-dimensional configurations. It is best not to use stacked line charts because they are difficult to distinguish from unstacked line charts with multiple data series.

The following example shows a revenue trend that peaked in 2012 in every territory.



Note: The Top Retailers by Country or Region sample report “Top Retailers by Country or Region” on page 532 in the Sales and Marketing (cube) package includes a line chart. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Pie Charts

Pie charts are useful for highlighting proportions.


They use segments of a circle to show the relationship of parts to the whole. To highlight actual values, use another chart type, such as a stacked chart.

Pie charts plot a single data series. If you need to plot multiple data series, use a 100 percent stacked chart.

Reports in PDF or HTML format show a maximum of 16 pies or gauges per chart.

Note: The Returns by Failed Orders in 2012 sample report “Returns by Failed Orders in 2012” on page 537 in the GO Data Warehouse (analysis) package includes a pie chart. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

The following example shows that the largest proportion of revenue comes from the Americas, followed by the Asia Pacific region.



Pie charts can plot data using standard, 100 percent, and three-dimensional configurations.

Related tasks:

“Set the Position of the First Slice in a Current Default Pie Chart” on page 152

You can specify the angle in a pie chart where the first pie slice starts. You can also change the direction of the slices so they appear clockwise or counter-clockwise.

“Creating a Donut Chart from a Current Default Pie Chart” on page 152

You can add a hole to the middle of your pie chart to create a donut chart.

“Pull Out Pie Slices in a Current Default Pie Chart” on page 153

You can highlight pie slices by pulling them out from the rest of the pie. For example, the following chart shows revenue by product line with slices of less than 1,000,000,000 in revenue pulled out by 25%.

Bar Charts

Bar charts are useful for showing trends over time and plotting many data series.

Bar charts use horizontal data markers to compare individual values.

Note: The Manager Profile sample report “Manager Profile” on page 535 in the GO Data Warehouse (analysis) package includes a bar chart. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

The following example shows revenue for every country or region.




Figure 6. Bar chart

Bar charts can plot data using standard, stacked, and 100 percent stacked configurations.

Area Charts

Area charts are useful for emphasizing the magnitude of change over time. Stacked area charts are also used to show the relationship of parts to the whole.

Area charts are like line charts, but the areas below the lines are filled with colors or patterns.

Do not use standard area charts to show multiple data series because it is possible for areas with lower values to be covered by others. For multiple data series, use a stacked area chart.

The following example is a stacked area chart that shows the quantity of products that were sold over a four-year period in multiple territories.




Figure 7. An example area chart

Area charts can plot data using standard, stacked, 100 percent stacked, and three-dimensional configurations.

Point Charts

Point charts are useful for showing quantitative data in an uncluttered fashion.

Point charts use multiple points to plot data along an ordinal axis. A point chart the same as a line chart without the lines. Only the data points are shown.

The following example shows the revenue for each product line.





Figure 8. An example point chart

Combination Charts

Combination charts plot multiple data series by using combinations of columns, areas, and lines within one chart. They are useful for highlighting relationships between the various data series.

Note: The Quantity Sold vs. Shipped and Inventory sample report in the GO Data Warehouse (analysis) package includes a combination chart. For more information about the Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

The following example shows a combination chart that includes planned revenue as a line chart and actual revenue as a column chart.



Combination charts can plot data using standard, stacked, 100 percent stacked, and three-dimensional configurations.

Scatter Charts


Scatter charts use data points to plot two measures anywhere along a scale, not only at regular tick marks.

You can also specify a default measure. For example, you might need to specify a default measure to give context to a calculated measure in the chart. For more information about the default measure, see “Specify the Default Measure” on page 77.

Scatter charts are useful for exploring correlations between different sets of data.

Note: The Employee Satisfaction 2012 sample report in the GO Data Warehouse (analysis) package includes a scatter chart. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

The following example shows the correlation between production cost and gross profit for each product line.



Related tasks:

“Defining color by value in current default scatter or bubble charts” on page 150
In a scatter or bubble chart you can specify that data points or bubbles appear in different colors that are based on an additional measure or fact. The color of the points or bubbles helps you to see relationships in large amounts of data.

Bubble Charts

Bubble charts, like scatter charts, use data points and bubbles to plot measures anywhere along a scale. The size of the bubble represents a third measure.

You can also specify a default measure. For example, you might need to specify a default measure to give context to a calculated measure in the chart. For more information about the default measure, see “Specify the Default Measure” on page 77.

Bubble charts are useful for representing financial data. These charts are not supported for Microsoft Excel output.

The following example plots quantity and revenue by product line. The size of the bubble represents the amount of gross profit.




Figure 9. Bubble chart

Related tasks:

“Defining color by value in current default scatter or bubble charts” on page 150
 In a scatter or bubble chart you can specify that data points or bubbles appear in different colors that are based on an additional measure or fact. The color of the points or bubbles helps you to see relationships in large amounts of data.

“Specify the Bubble Size in a Current Default Bubble Chart” on page 151
 In a bubble chart, you use a measure or fact to determine the size of the bubbles.

Quadrant Charts


Quadrant charts are bubble charts with a background that is divided into four equal sections. Quadrant charts are useful for plotting data that contains three measures using an X-axis, a Y-axis, and a bubble size that represents the value of the third measure.

You can also specify a default measure. For example, you might need to specify a default measure to give context to a calculated measure in the chart. For more information about the default measure, see “Specify the Default Measure” on page 77.

Legacy quadrant charts use baselines to create the quadrants. Current default charts use colored regions.

Use a quadrant chart to present data that can be categorized into quadrants, such as a SWOT (strengths, weaknesses, opportunities, and threats) analysis.

The following example shows the relationship between production cost and gross profit. The size of the bubble represents the quantity of units sold.



Bullet Charts

Bullet charts are a variation of bar charts. They compare a featured measure (the bullet) to a targeted measure (the target). They also relate the compared measures against colored regions in the background that provide additional qualitative measurements, such as good, satisfactory, and poor.

Bullet charts are often used instead of gauge charts in executive dashboards. Bullet charts can be horizontal or vertical.

Note: This chart type applies only to the current default charts, and does not apply to the legacy charts.

The following figure is an example of a bullet chart.




Figure 10. An example bullet chart

A bullet chart contains the following components:

- A bullet measure.
The bullet measure, Revenue, appears as the blue bar in the example.
- A target measure.
The target measure, Planned revenue, appears as the black indicator in the example.
- From zero to five colored regions along the numeric scale to provide information about the featured measures' qualitative state.
The example contains three colored regions, 0-50%, 50-75%, and 75-100%.

- A label that identifies the measures.
- A numeric scale.

Related tasks:

“Customize a Current Default Bullet Chart” on page 156

After you create a bullet chart, you can customize the shape, color, and size of the bullet and target indicators.

Gauge Charts

Gauge charts, also known as dial charts or speedometer charts, use needles to show information as a reading on a dial.

On a gauge chart, the value for each needle is read against the colored data range or chart axis. This chart type is often used in executive dashboard reports to show key business indicators.

Gauge charts are useful for comparing values between a small number of variables either by using multiple needles on the same gauge or by using multiple gauges.

Reports in PDF or HTML format are limited to show a maximum of 16 pies or gauges per chart. These charts are not supported for Microsoft Excel output.

A gauge chart consists of a gauge axis (which contains the data range, color ranges, and intervals markers), needles, and a center pivot point. The following example shows a basic gauge chart with default attributes. It is a degree dial chart with two axes.




Figure 11. An example gauge chart

Related tasks:

“Customize a Current Default Gauge Chart” on page 147

When you create a gauge chart, you can choose from a variety of chart templates, which offer different shape, axis, and border options.

“Customize a Legacy Gauge Chart” on page 149

You can customize the colors and threshold boundaries of the gauge axis areas and whether they use numbers instead of percentages. You can also change the colors of the gauge face and outline and hide gauge labels. By default, the legacy gauge chart uses a band divided into thirds that runs from green to red.

Pareto Charts

Pareto charts help you to improve processes by identifying the primary causes of an event. They rank categories from the most frequent to the least frequent. These charts are frequently used for quality control data, so that you can identify and reduce the primary cause of problems.

Pareto charts include a cumulation line, which shows the percentage of the accumulated total of all the columns or bars.

You can create before and after comparisons of Pareto charts to show the impact of corrective actions. These charts are not supported for Microsoft Excel output.

The following example shows that the most frequent reason for product returns is unsatisfactory product.




Figure 12. An example pareto chart

You can also create Pareto charts using horizontal bars.

Related tasks:

“Define the Cumulation Line in a Current Default Pareto Chart” on page 154

The cumulation line on a Pareto chart displays the percentage of the accumulated total of all the columns or bars. For example, if your chart displays revenue by product line by year, the cumulation line at the second year’s column would be the total revenue of the first and second years.

“Define the Cumulation Line in a Legacy Pareto Chart” on page 155

The cumulation line on a Pareto chart displays the percentage of the accumulated total of all the columns or bars. For example, if your chart displays revenue by product line by year, the cumulation line at the second year’s column would be the total revenue of the first and second years.

Progressive Column Charts

Progressive column charts, also known as waterfall charts, are like stacked charts with each segment of a single stack displaced vertically from the next segment.

Progressive column charts are useful for emphasizing the contribution of the individual segments to the whole.

These charts are not supported for Microsoft Excel output.

The following example analyzes the contribution of each product line to revenue.




Figure 13. An example progressive column chart


Progressive column charts can plot data using standard and three-dimensional configurations. You can also create progressive charts using horizontal bars.

Microcharts

Microcharts are smaller versions of column charts, bar charts, and line charts that you can use in crosstabs and dashboards. Microcharts include column microcharts and bar microcharts, which are available in stacked and 100 percent stacked configurations, and win-loss charts and modified line charts that contain the following:

- A closing value marker.
- Opening, closing, high, and low value markers.
- A reference line.

Note: If you specify custom labels for a microchart, the custom labels appear in the tooltips, not on the chart itself. For more information about custom labels, see “Specify Custom Label Text” on page 122.



Win-loss charts are microcharts in which the value of each column is either 1 or -1, often denoting a win or loss.

Win-loss charts use two measures (the default and the win-loss measure) and no series. The win-loss measure is the measure or calculation that you define. You can also specify a default measure. For example, you might need to specify a default measure to give context to a calculated measure in the chart. For more information about the default measure, see “Specify the Default Measure” on page 77.

The following example shows the quarters that have a margin of less than 10,000 in red.



Marimekko Charts

Marimekko charts are 100 percent stacked charts in which the width of a column is proportional to the total of the column's values. Individual segment height is a percentage of the respective column total value.

The following example shows the contribution of revenues for product lines in different regions.




Figure 14. An example Marimekko chart

Radar Charts

Radar charts integrate multiple axes into a single radial figure. For each figure, data is plotted along a separate axis that starts at the center of the chart.

The following example shows the revenue from multiple retailer types in multiple territories.




Figure 15. An example radar chart

Radar charts can plot data using standard and stacked configurations.


Polar Charts

Polar charts are useful for showing scientific data.

They are circular charts that use values and angles to show information as polar coordinates.

You can specify a default measure. For example, you might need to specify a default measure to give context to a calculated measure in the chart. For more information about the default measure, see “Specify the Default Measure” on page 77.

The following example shows the revenue and quantity for each product line. The distance along the radial axis represents quantity, and the angle around the polar axis represents revenue.




Range Indicator Charts

Range indicator, or metrics range, charts are useful for showing a target range and a tolerance range.

A range indicator chart adds a target and range marker to a column, line, or area chart.

The following example shows actual revenue versus planned revenue. The markers indicate the planned revenue, and the range and tolerance lines are defined by the chart author.



You can also insert IBM Cognos Metric Studio diagrams in your report to show the relationship between metrics. For more information, see “Add a Static Metric Studio Diagram to a Report” on page 162 and “Add a Data-driven Metric Studio Diagram to a Report” on page 163.

Chart Configurations

Chart configurations specify the grouping type of the columns, bars, lines, and areas in a chart. Some examples are standard, stacked, and 100 percent stacked charts.

Standard Charts

Standard or absolute charts are useful for comparing specific values and for representing discrete data, such as data for different regions or individual employees. For example, a standard column chart that plots regional sales emphasizes the actual value that each region achieves in sales.

Standard charts plot the actual value of each data series from a common axis.

When you create charts using multiple data series, you can distinguish each series by the color or pattern of its data marker. Related data series are shown together in clusters for easy comparison.

In standard area and radar charts that have multiple data series, the colored areas that represent lower values might be covered by the larger colored areas that represent higher values. Use the stacked configuration for area and radar charts with multiple data series.

The following example shows the revenue values for each product line within each territory.




Figure 16. An example standard chart that compares specific values

Stacked Charts

Stacked charts are useful for comparing proportional contributions within a category. They plot the relative value that each data series contributes to the total. For example, a stacked column chart that plots product line sales will emphasize the proportion that each product line contributes to the total in each territory.

You can distinguish each data series by the color or pattern of its section in the stack. The top of each stack represents the accumulated totals for each category.

Do not use the stacked configuration in line charts that have multiple data series because it is difficult to distinguish between unstacked and stacked configurations, and your chart consumers might misunderstand your data.

The following example shows that camping equipment contributed a large proportion of the actual revenue in most sales territories.




Figure 17. An example stacked chart

100 Percent Stacked Charts

100 percent stacked charts are useful for comparing proportional contributions across all categories. They plot the relative contribution of each data series to the total as a percentage. For example, a 100 percent stacked column chart that plots product line sales emphasizes the percentage within each region without referring to actual values.

You can distinguish each data series by the color or pattern of its section in the stack. Each stack represents 100 percent.

100 percent stacked charts highlight proportions. When actual values are important, use another chart configuration.

The following example shows the percentage of sales for each product line in each region.




Figure 18. An example 100 percent stacked chart

Three-dimensional Charts

Three-dimensional charts provide a visually effective display that is suitable for presentations.

Three-dimensional column, bar, line, and area charts plot data by using three axes.

Three-dimensional pie charts have a three-dimensional visual effect.

Do not use three-dimensional charts when you need to show exact values, such as for control or monitoring purposes. The distortion in three-dimensional charts can make them difficult to read accurately. For example, the following chart shows actual revenue for each product line in each territory, but some data labels are omitted because there is not enough room to display them all.




Figure 19. An example three-dimensional chart

Convert Charts From One Type to Another

You can convert a chart from one type (for example, a bar chart) to another type (for example, a line chart).

When you convert an existing chart to a new chart type, IBM Cognos Report Studio keeps the properties from the existing chart if those properties exist in the new chart type. For example, if you convert a pie chart to a bar chart, Report Studio maps your chart palette to the new chart, but does not map the exploding slices, because the exploding slices property does not exist in a bar chart.

Note: Report Studio converts legacy charts to the current default chart types automatically if you change the chart type unless you select the **Use legacy chart authoring** option. You can convert legacy charts to current default charts, but you cannot convert current default charts back to legacy charts.

Procedure

1. Right-click a chart and click **Convert Chart**.
2. Select a new chart type, and click **OK**.

If some chart properties cannot be converted, the **Chart Property Changes** dialog box appears notifying you of the properties that cannot be converted.

Convert Legacy Charts to Current Default Charts

You can convert charts from the legacy charts to the current default charts. When you convert a legacy chart, select the template that most closely matches your legacy chart in order to preserve as many settings as possible.

Note: You can convert legacy charts to current default charts, but you cannot convert current default charts back to legacy charts.

Procedure

1. From the **Tools** menu, click **Options**.
2. From the **Advanced** tab, clear the **Use legacy chart authoring** check box.
3. Right-click the legacy chart and click **Convert Chart**.
4. Select a new chart type, and click **OK**.

If some chart properties cannot be converted, the **Chart Property Changes** dialog box appears notifying you of the properties that cannot be converted.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Limitations When Converting Legacy Charts

When you convert a legacy chart to the current default chart, some chart types or chart properties might not be migrated properly. For example, clustered area charts and 100% stacked line charts are not available in the current default charts. If your exact chart configuration is not available, select the closest matching template.

The following legacy chart properties are not migrated to the current default charts:

- **Conditional Palette**

- **Style Variable**
- **Visual Angle**
- **Rotate Values**
- **Conditional Style, Style Variable, and Drill-Through Definitions** on pie labels and gauge labels
- **Connecting Lines** on combination charts
- line styles; only four line styles are supported in the current default charts

The following table outlines some behavior differences between legacy charts and the current default charts.

Legacy Charts	Current Default Charts
Combination charts are always ordered from back to front - area, bar, and line.	Combination charts support any order.
In bar charts, multiple bar definitions for the Y1-axis are placed side-by-side.	In bar charts, multiple bars are placed on top of one another and you can control the width of the bars.
In combination charts, the color palette is continued over multiple bars, lines, and areas.	In combination charts, color palettes are restarted for each bar, line, and area.
The legend order respects the order in which bars, lines, and areas are specified. For example, bars can appear before areas in the legend.	The legend order is the same as the order specified in the chart.

The following chart types continue to use the legacy chart technology and therefore cannot be upgraded to the current default chart technology. If you want to convert these chart types to the current default charts, upgrade them to a different chart type, such as a column or line chart.

- Win loss
- Radar
- Polar
- 3-D Bar, 3-D Line, 3-D Area, and 3-D Combination
- 3-D Scatter
- Metrics range
- Marimekko

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Customizing Chart Properties

After you create a chart, you can customize it by changing its properties.

You select the chart object in IBM Cognos Report Studio to view its properties. Some properties are dependent on the existence of other properties.


If you are familiar with using conditional variables, you can customize the chart to change its appearance or provide information in response to expressions or conditions.

As you edit the chart properties, Report Studio provides you with a preview of your chart, using simulated data. This allows you to view your style changes without running the report. You can disable the chart preview in the options.

The following table shows some of the properties you can change in charts. These properties are available when you select the chart object unless specified otherwise in the **Action to perform in the Properties pane** column.

Goal	Action to perform in the Properties pane
Hide or show the title, subtitle, or footer	Select the chart. Under Chart Titles , set the Title , Subtitle , or Footer property.
Hide or show the legend	Select the chart. Under Chart Annotations , set the Legend property. For more information, see “Customize the Legend in a Current Default Chart” on page 128.
Hide or show baselines	Select the chart. Under Chart Annotations , set the Baselines property. For more information, see “Add a Baseline to a Current Default Chart” on page 134.
Hide or show trendlines or regression lines	Select the chart. Under Chart Annotations , set the Trendlines or Regression Line property. For more information, see “Display Trendlines in Current Default Charts” on page 138 or “Display Regression Lines in Legacy Scatter or Bubble Charts” on page 139.
Hide or show markers	Select the chart. Under Chart Annotations , set the Markers property. For more information, see “Add a Marker to a Current Default Chart” on page 136.
Hide or show notes	Select the chart. Under Chart Annotations , set the Notes property. For more information, see “Add a Note to a Current Default Chart” on page 131.
Hide or show the axes	Select the chart. Under Axes , set the Y1 Axis , Y2 Axis , or Category Axis property. For more information, see “Customize the Axes of a Current Default Chart” on page 123.
Hide or show the axis title or axis line	Select the axis. Under General , set the Axis Line or Axis Title property. For more information, see “Customize the Axes of a Current Default Chart” on page 123.


Goal	Action to perform in the Properties pane
Change an axis title	<p>Select the axis title. Under General, set the Default Title property to No, and then double-click the axis title and type a new title.</p> <p>Tip: You can use the Properties pane to change the axis title properties, such as font, positioning, color, and so on.</p> <p>For more information, see “Customize the Axes of a Current Default Chart” on page 123.</p>
Change axis properties, such as range, scale interval, and so on	<p>Select the numeric axis. Under General, set the Minimum Value, Maximum Value, Scale Interval, or Scale property.</p> <p>For more information, see “Change the Axis Scale of a Current Default Chart” on page 124.</p>
Hide or show the tooltips	<p>Select the chart. Under Chart Labels, set the Tooltips property.</p> <p>When you pause your pointer over a data marker in the report output, the corresponding absolute or cumulative value appears in a tooltip.</p> <p>Tooltips are not supported in PDF output.</p>
Change the data format	<p>Select the numeric axis. Under Data, set the Data Format property.</p>
Change the white space around the chart	<p>Select the chart. Under Box, set the Padding or Margin property.</p> <p>For more information, see “Apply Padding to an Object” on page 355 and “Set Margins for an Object” on page 356.</p>
Change the color or pattern in the palette for columns, lines, and areas	<p>Select the chart object. Under Color & Background, set the Palette or Conditional Palette property.</p> <p>For more information, see “Customizing the Color Palette of a Chart” on page 112 and “Create a Simple Conditional Palette for a Current Default Chart” on page 115.</p>
Change the chart orientation	<p>Select the chart. In the Properties pane, under Chart Orientation, select Vertical or Horizontal.</p>

Goal	Action to perform in the Properties pane
Change the default color or font for all chart objects	<p>Select the chart. Under Color & Background, set the Background Color, Foreground Color, or Fill Effects property.</p> <p>For more information, see “Change a Chart Background in a Legacy Chart” on page 119.</p> <p>Under Font & Text, set the Font or Relative Alignment property.</p> <p>Tip: The 2011 Quarterly Sales Forecast sample report in the GO Sales (analysis) package includes text alignment. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.</p>
Override the default font or color for axes and chart values	<p>Click the unlock button  in the toolbar to unlock the chart object, select the chart body by clicking between the axes, and set the Font, Background Color, Foreground Color, or Fill Effects property.</p>
Change the three-dimensional appearance of a chart	<p>Select the chart. Under General, set the Depth or Visual Angle property.</p> <p>For example, for a pie chart, a Depth value of 0 (zero) leaves the pie flat, or two-dimensional. A value of 100 raises the pie almost to a round ball shape.</p> <p>Tip: You can select a value from the Depth list or type a value that is not listed.</p>
Insert a background image or watermark in the chart body.	<p>Click the lock button in the toolbar to unlock the chart object, select the chart body by clicking between the axes.</p> <p>Under Color & Background, set the Background Image property.</p> <p>For more information, see “Change a Chart Background in a Legacy Chart” on page 119.</p>
Go to another report	<p>Select the chart. Under Data, set the Drill-Through Definitions property.</p> <p>For more information, see Chapter 19, “Using Drill-through Access,” on page 431.</p>
Specify which labels and values to use when generating the text shown on the chart	<p>Select the chart. Under Chart Labels, set the Values property.</p> <p>Note: When you show all the labels and values on some chart types, such as scatter charts, bubble charts, and polar charts, the text shown might be too long.</p>

Resize a Current Default Chart

You can change the size of a current default chart by dragging the resize handle in the lower right corner of the chart.

Procedure

1. Select the chart object.
2. Click the resize handle in the lower right corner of the chart .
Use Shift+drag to maintain the aspect ratio of the chart.
3. To see the actual size of the chart as it will appear in the report output, collapse the chart objects with the minus (-) button in the upper left corner of the chart.

Results

The new chart size appears in the **Size & Overflow** property. You can also edit the chart size with this property.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83
IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Resize a Legacy Chart

You can resize a legacy chart by defining the height and width in the **Size & Overflow** property.

The options available with this property are detailed in “Specify the Height and Width of an Object” on page 362.

Procedure

1. Select the chart object.
2. In the **Properties** pane, double-click the **Size & Overflow** property and specify the height and width.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83
IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Customizing the Color Palette of a Chart

You can use the chart palette to control the colors or patterns used in the columns, lines, data markers or areas in a chart. For example, if "Telephone" is the first in a data series of order methods, and you want it to appear in blue, use the palette to make the first item in the series blue.

You can customize the color palette for area, bar, bubble, gauge, Pareto, pie, and scatter charts.

You can also apply background effects to chart objects or change the colors of specific chart elements.

Related tasks:

“Add Background Effects to a Chart Object in a Legacy Chart” on page 120
You can change the look of certain charts and chart objects by applying visual effects such as drop shadows, borders, fills, texture effects, and bevel effects.

Customize the Color Palette of a Current Default Chart


You can use the chart palette to control the colors or patterns used in the columns, lines, data markers or areas in a chart.

Progressive charts and legacy charts have different steps.

If specified, the default color is used for outputs that do not support the palette definition. For example, if the palette is defined to use a radial rectangle gradient and you run the report as PDF output, the default color is used because radial rectangle gradients are not supported in PDF output.

Procedure

1. Select the chart object. For combination charts, select the bar, line, or area objects.

2. To choose a preset color palette, click the chart palette presets button  on the style toolbar, and then click a palette.

3. To change the existing color palette:

- In the **Properties** pane, under **Color & Background**, double-click the **Palette** property.
- On the **Entries** tab, click the palette entry that you want to change.
- Under **Fill**, select fill type, color, transparency, and other fill settings. The options in the **Fill type** list depend on the chart type you are using.

Linear Gradient displays a gradient that changes color horizontally. You can specify the position of each color in the gradient and add or remove colors from the gradient.

Radial Line Gradient displays a gradient that changes color outwards from a central point, or focus. You can specify the position of each color in the gradient and the size and position of the focus. You can also add or remove colors from the gradient.

Radial Rectangle Gradient displays a gradient that changes color outwards from a rectangle. You can specify the position of each color in the gradient and the size of the rectangle. You can also add or remove colors from the gradient.

Pattern displays a colored pattern that you choose from a preset list. You can specify the foreground and background colors.

Color displays a solid color. You can specify the transparency.

Image displays an image. You can specify the image to use.

- To change the color of this palette definition, click the color in the **Colors** list, click **Color**, specify the color properties, and click **OK**.
4. Under **Style**, depending on the chart type you are customizing and the fill type you chose in step 2, you can change the marker shape, line style, default color, and line weight.

5. To add a new palette entry, click the new button  and specify the new palette settings.

6. To change the order in which the colors, gradients, or patterns appear in the chart, use the arrow buttons under the **Palette** box to change their position.

7. To copy and paste a palette, open the palette dialog box and press Ctrl+C to copy the palette to the clipboard. Close the palette dialog box. Select another chart, open the palette dialog box, and press Ctrl+V to paste the palette from the clipboard.

8. To customize the data markers, on the **Properties** tab, depending on the chart type you are customizing and the fill type you chose in step 2, you can specify whether data markers are shown and change their color and size.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83
IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Customize the Color Palette of a Current Default Progressive Chart

You can use the chart palette to control the colors or patterns used in the columns, lines, data markers or areas in a chart.

Legacy charts and other types of current default charts have different steps.

If specified, the default color is used for outputs that do not support the palette definition. For example, if the palette is defined to use a radial rectangle gradient and you run the report as PDF output, the default color is used because radial rectangle gradients are not supported in PDF output.

Procedure

1. Select the progressive chart object.
2. In the **Properties** pane, double-click the **Progressive Palette** property.

You can specify the following:

- **Positive value fill** defines the appearance of the positive bars or columns on the chart.
- **Negative value fill** defines the appearance of the negative bars or columns on the chart.
- **First value fill** defines the appearance of the first bar or column on the chart.
- **Total value fill** defines the appearance of the total bar or column on the chart, if a total bar or column is present.

3. To change the appearance of a fill:

- Click the colored box beside the fill name.
- Click a fill type from the **Fill type** list.

Linear Gradient displays a gradient that changes color horizontally. You can specify the position of each color in the gradient and add or remove colors from the gradient.

Radial Line Gradient displays a gradient that changes color outwards from a central point, or focus. You can specify the position of each color in the gradient and the size and position of the focus. You can also add or remove colors from the gradient.

Radial Rectangle Gradient displays a gradient that changes color outwards from a rectangle. You can specify the position of each color in the gradient and the size of the rectangle. You can also add or remove colors from the gradient.

Pattern displays a colored pattern that you choose from a preset list. You can specify the foreground and background colors.

Color displays a solid color. You can specify the transparency.

Image displays an image. You can specify the image to use.

- To change the color of this fill, click the color in the **Colors** list, click **Color**, specify the color properties, and click **OK**.

4. To change the text of the label that appears next to a bar, double-click the text box beside the fill name and specify the text.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83
IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Customize the Color Palette of a Legacy Chart

You can use the chart palette to control the colors or patterns used in the columns, lines, data markers or areas in a chart.

Current default charts have different steps.

Procedure

1. Select the chart object.
 2. In the **Color & Background** section of the **Properties** pane, double-click the **Palette** property.
 3. In the **Palette** dialog box, click the new palette entry button to define a new palette entry:
 - To apply color, click **Color**, specify the color properties, and click **OK**.
 - To apply a gradient, click **Gradient**, specify the **Direction**, **From color**, and **To color** properties, and click **OK**.
 - To apply a pattern, click **Pattern**, specify the **Pattern**, **Foreground color**, and **Background color** properties, and click **OK**.
- Tip:** You can also select a predefined palette from the **Palettes** box.
4. To change the order in which the colors, gradients, or patterns appear in the chart, use the arrow buttons under the **Palette** box to change their position.
 5. To copy and paste a palette, open the palette dialog box and press Ctrl+C to copy the palette to the clipboard. Close the palette dialog box. Select another chart, open the palette dialog box, and press Ctrl+V to paste the palette from the clipboard.
 6. Repeat step 3 for each chart series.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83
IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Creating a Conditional Color Palette in a Chart

You can create a conditional palette to color data items in your chart in different ways depending on a condition. For example, in a column chart that shows revenue per month, you want to make the columns for the months that have a revenue greater than \$1000000 green.

You can also use conditional styles to highlight exceptional data and use conditions to control the layout of your report.

Related concepts:

Chapter 15, “Using Conditions,” on page 381



You can define conditions to control what users see when they run a report. Conditions can apply to specific items in a report. For example, you can define a conditional style to highlight exceptional data, such as product revenue that exceeds your target.

Create a Simple Conditional Palette for a Current Default Chart


You can create a simple conditional palette based on a string data item or a numeric data item. For example, if you want to create a condition to display only


Revenues over one million dollars, you can create a numeric condition; whereas, if you want to create a condition to display only product codes with the letter A in them, you can create a string condition.

Procedure

1. Select the chart series to which you want to apply the conditional palette.
2. In the **Properties** pane, under **Color & Background**, double-click the **Conditional Palette** property.
3. Click the new button  and click **New Condition**.
4. If you want to create a conditional palette based on a string, do the following:
 - a. Select the string data item to determine the condition.
 - b. In the **Type of conditional style** list, click **String**, and click **OK**.
 - c. Click the new button and select how to define the condition:
 - To select more than one individual value, click **Select Multiple Values** and click the values.
 - To type specific values, click **Enter Values** and type the values.
 - To specify your own criteria, such as values that begin with the letter A, click **Enter String Criteria** and specify the condition.
 - d. Under **Palette Entry**, beside the new condition, click the edit button .
 - e. Define the palette entry fill type, colors, and angle, and click **OK**.
5. If you want to create a conditional palette based on a numeric range, date/time range, interval range, date range, or time range, do the following:
 - a. Select a numeric data item to determine the condition.
 - b. In the **Type of conditional style** list, click the type of condition you want to create, and click **OK**.
 - c. Click the new button and type a value to define a threshold.
The value appears in the **Range** column, and two ranges are created.
 - d. For each range, under **Style**, click the edit button to define the palette entry fill type, colors, and angle, and then click **OK**.
 - e. Repeat the previous substeps to add other conditions.

Tip: Under **Style**, pause the pointer over each range  to see the condition produced for that range.

- f. If you want to use the default palette for the lowest range instead of specifying a conditional palette select the **Use default palette for lowest range** check box.
 - g. To move a value above or below a threshold, click the arrow button  next to the value.
For example, you insert a threshold value of five million. By default, the ranges are less than or equal to five million and greater than five million. Moving the five million value above the threshold changes the ranges to less than five million and greater than or equal to five million.
6. To customize the label for a conditional palette, do the following:
 - a. Click **Label** beside the palette entry.
 - b. In the **Conditional Palette Entry Label** dialog box, click **Specified text** and click the ellipsis button.

- c. Type the default label text in the **Label** text box.
 - d. To add customized labels for other languages, click the add button , select the other languages, and click the language to define the customized label for that language.
7. Specify the order in which to evaluate the conditions by clicking a condition and then clicking the move up or move down arrow.
Conditions are evaluated from top to bottom, and the first condition that is met is applied.

Related concepts:




“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Create an Advanced Conditional Palette for Current Default Charts

Advanced conditions allow you to use a calculations or expression to evaluate the condition. If multiple advanced conditions are met, only the first conditional style is applied.

Procedure

1. Select the chart series to which you want to apply the conditional palette.
2. In the **Properties** pane, under **Color & Background**, double-click the **Conditional Palette** property.
3. Click the add button  and click **Advanced Condition**.
4. Click the new advanced condition button  and specify the expression that defines the condition.
The new advanced condition appears in the **Conditional Palette - Advanced** dialog box.
5. Under **Palette Entry**, beside the new advanced condition, click the edit button .
6. Define the palette entry fill type, colors, and angle, and click **OK**.
7. Specify the order in which to evaluate the conditions by clicking a condition and then clicking the move up or move down arrow.
Conditions are evaluated from top to bottom, and the first condition that is met is applied.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Create a Conditional Color Palette for a Legacy Chart

You can create a color palette that appears differently depending on a yes or no answer, an expression or calculation, or the report language.

Procedure


1. Click the chart object.
2. In the **Properties** pane, under **Color & Background**, double-click the **Conditional Palette** property.


3. If you want to create a variable that has only two possible values, **Yes** and **No**, do the following:
 - a. Under **Variable**, click **New boolean variable**.
 - b. In the **New Variable** dialog box, type a name for the variable.
 - c. In the **Expression Definition** box, define the condition and click **OK**.
 For example, the following expression returns the value **Yes** if revenue is less than one million and the value **No** if revenue is greater than or equal to one million:

```
[Revenue]<1000000
```

 For information about creating expressions, see “Using Relational Calculations” on page 262 or “Using Dimensional Calculations” on page 316 and Appendix F, “Using the expression editor,” on page 575.
 - d. In the **Value** box, select whether the expression evaluates to **Yes** or **No**.
 - e. Under **Effects**, specify the color palette to use for the condition.
4. If you want to create a variable whose values are string-based, do the following:
 - a. Under **Variable**, select **New string variable**.
 - b. In the **Expression Definition** box, define the condition and click **OK**.
 For example, the following expression returns the value **high** if revenue is greater than one million and the value **low** if revenue is less than or equal to one million:

```
if ([Revenue]>1000000) then ('high') else ('low')
```

 For information about creating expressions, see “Using Relational Calculations” on page 262 or “Using Dimensional Calculations” on page 316 and Appendix F, “Using the expression editor,” on page 575.
 - c. Click the add button  in the **Values** pane.
 - d. For each value that the variable can assume, type the name of the value that corresponds with the possible outcomes defined in the expression.
 For example, in the previous expression, you must create two values for the variable, high and low.

Tip: You can create a group by clicking two or more values and then clicking the group values button . For example, you can create a group that includes the available French languages.
5. If you want to create a variable whose values are different languages, do the following:
 - a. Under **Variable**, select **Report Language Variable**.
 - b. In the **Languages** dialog box, select the languages to support.
6. Click **OK** to close the expression editor and leave the **Conditional Palette** dialog box open.
7. Under **Effect**, click **Pattern**.
8. Under **Pattern**, select a pattern and click **OK**.
9. In the **Box** section of the **Properties** pane, set the **Borders** property to **Show**.

Related concepts:


“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Change a Chart Background in a Current Default Chart

You can use a gradient, pattern, color, or image to customize the chart background.

Procedure

1. Click the chart object.
2. Click the unlock button , select the chart body by clicking between the axes, and, in the **Properties** pane, under **Color & Background**, double-click the **Plot Area Fill** property.
3. Click a fill type from the **Fill type** list.
 - **Linear Gradient** displays a gradient that changes color horizontally. You can specify the position of each color in the gradient and add or remove colors from the gradient.
 - **Radial Line Gradient** displays a gradient that changes color outwards from a central point, or focus. You can specify the position of each color in the gradient and the size and position of the focus. You can also add or remove colors from the gradient.
 - **Radial Rectangle Gradient** displays a gradient that changes color outwards from a rectangle. You can specify the position of each color in the gradient and the size of the rectangle. You can also add or remove colors from the gradient.
 - **Pattern** displays a colored pattern that you choose from a preset list. You can specify the foreground and background colors.
 - **Color** displays a solid color. You can specify the transparency.
 - **Image** displays an image. You can specify the image to use.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83


IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Change a Chart Background in a Legacy Chart

You can use a solid color, a pattern, or a gradient fill effect to customize the chart background.

You can also use an image as a background for a chart.

Procedure

1. Click the chart object.
2. Click the unlock button , select the chart body by clicking between the axes, and, in the **Properties** pane, under **Color & Background**, double-click the **Fill Effects** property.
3. In the **Effect** box, choose a color, a gradient fill effect, or a pattern:
 - To apply a color, click **Color** and specify the color properties.
 - To apply a gradient fill effect, click **Gradient** and then specify the **Direction**, **From color**, and **To color** properties.
 - To apply a pattern effect, click **Pattern** and specify the **Pattern**, **Foreground Color**, and **Background Color** properties.

The foreground color is the color of the selected pattern. The background color is the color of the area behind the pattern.
4. To remove a background fill effect, click **None**.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83
IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.


Related tasks:

“Insert a Background Image in an Object” on page 348
You can insert a background image for objects in a report. For example, use a background image to add a watermark to a page.

Add Background Effects to a Chart Object in a Legacy Chart

You can change the look of certain charts and chart objects by applying visual effects such as drop shadows, borders, fills, texture effects, and bevel effects.

Procedure

1. Select the chart object.
2. To apply a preset background fill effect, from the toolbar, click the background effects presets  button.
3. To add a custom fill effect and border do the following:
 - a. In the **Properties** pane, under **Color & Background**, double-click the **Background Effects** property.
 - b. Click **Border** and specify settings for border style, width, color, corner radius for rounded rectangles, and transparency.
If the object also includes a fill with a transparency setting, select the **Allow transparent bleed** check box to apply the same transparency to the border.
 - c. Click **Fill** and specify the settings.
The fill effect can either be a solid color, a gradient, or a pattern.
4. To add a texture effect, in the **Properties** pane, under **Color & Background**, select an option under **Material Effects**.
5. To add a drop shadow, do the following:
 - a. In the **Properties** pane, under **Color & Background**, double-click the **Drop Shadow** property.
 - b. Select the **Drop shadow** check box.
 - c. From the **Shadow color** list, click a color.
 - d. Under **Blur**, click an intensity to set the drop shadow's blur.
 - e. Under **Offset**, enter a value and a unit to define the width and height of the drop shadow.
 - f. Under **Transparency**, type a percentage to determine the transparency of the shadow.
6. To add a bevel, in the **Properties** pane, under **Color & Background**, double-click the **Bevel** property and click a bevel effect.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83
IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

“Customizing the Color Palette of a Chart” on page 112

You can use the chart palette to control the colors or patterns used in the columns, lines, data markers or areas in a chart. For example, if "Telephone" is the first in a data series of order methods, and you want it to appear in blue, use the palette to make the first item in the series blue.

Related tasks:

“Add Color to an Object” on page 368

You can add background and foreground color to objects in the report. The foreground color applies to the text within objects.

Add Colored Regions in a Current Default Chart

You can define colored regions in the body of a chart. For example, you can divide the background of a scatter chart into quadrants and color each quadrant.

You can add colored regions to bubble, bullet, combination, Pareto, progressive column, and scatter charts.

In bullet charts, colored regions are automatically added.


You can use the following criteria to position the colored regions.

Option	Position
Percent on Axis (%)	Uses a percentage of the full range of the axis. For example, if the axis range is -500 to 1100, a Percent on Axis value of 25% puts the baseline at -100 (25% of the range, 1600).
Numeric Value	Uses a static numeric value.
Mean	Uses the statistical mean plus or minus a number of standard deviations based on all charted data values on the specified axis.
Percentile (%)	Uses a specified percentile.
Statistical Maximum	Uses the following expression: <i>25th percentile value - 1.5 * (75th percentile value - 25th percentile value)</i> For example, if 2.5 is the 25th percentile and 7.5 is the 75th percentile, the statistical minimum is -5 [2.5 - 1.5(5) = -5].
Statistical Minimum	Uses the following expression: <i>75th percentile value + 1.5 * (75th percentile value - 25th percentile value)</i> For example, if 2.5 is the 25th percentile and 7.5 is the 75th percentile, the statistical maximum is 15 [7.5 + 1.5(5) = 15].
Query Calculation	Uses a query calculation from the same query or from a different query. For more information, see “Using Relational Calculations” on page 262.
Layout Calculation	Uses a layout calculation. For more information, see “Using Relational Calculations” on page 262.


Option	Position
Category Index	<p>Specifies a position based on the index value of the data item in the categories axis. The value must be between 0 and 100.</p> <p>For example, a Category index value of 1 indicates that the position is located at the first data item. This is the default.</p>

You can also combine colored regions with gridlines.

Procedure

1. Click the chart object.
2. In the **Properties** pane, under **Color & Background**, double-click the **Colored Regions** property.
3. Click the new button .
4. Under **Region label**, type a name for the region.
5. Under **Label location**, specify whether the label should appear in the legend or in the chart.
6. If your chart includes multiple charts, such as in a combination chart, under **Based on**, select the chart to which the colored regions apply.
7. Under **Region fill**, click the color box to specify the color and fill effects.
8. Specify the start and end of the category and numeric positions.
9. If you want to add more colored regions, repeat steps 3 to 5.
10. If you add more than one colored region, specify their order using the up and down arrows.

The regions are drawn in the same order that they appear in this list. The first region is drawn first, on the bottom, and the last region is drawn on top of the other regions.

Tip: To delete a colored region, click the colored region icon and text and click the delete button .

Results

The new region appears in the **Colored regions** box.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Specify Custom Label Text

By default, chart labels use the name of the underlying data item label. You can change the label text to make it more meaningful. For example, you can rename a chart item labeled **ISO_3_Letter_Code** to **Country or Region**.

If you specify custom labels for a microchart or win-loss charts, the custom labels appear in the tooltips, not on the chart itself.

Procedure

1. Click the chart node member or measure.
2. In the **Properties** pane, under the **Chart Labels**, set the **Custom Label** property to **Show**.

A new chart text item appears above the default measure or below the chart node member.

3. Do one of the following:
 - To change the text of the label, double-click the chart text item and type the text.
 - To change the source of the label text, select the new chart text item. In the **Text Source** section of the **Properties** pane, set the **Source Type** property. If nothing is specified in the new chart text item, the label appears blank.

Tip: To remove a custom label, set the **Custom Label** property to **Hide**.

Customizing the Axes of a Chart

Chart axes are lines that border the chart area and provide a reference for measurements. They act as a vehicle for tick marks and scales and form a frame around the chart. The Y-axis is usually the vertical axis and contains data. The X-axis is usually the horizontal axis and contains categories.

To make your chart data easier to understand, you can do the following to customize each axis:

- show or hide the axis labels (data values)
- show or hide the axis line
- change the color, style, and weight of the axis line
- show or hide major and minor tick marks and specify where to display them

In HTML/PDF, if you have a report with a line chart, you can use the **Include Zero For Auto Scale** property to adjust the scale of the Y-axis of the chart. If the difference between your measure's maximum/minimum values is much less than the difference between your measure's minimum value and zero, using this property will make the chart Y-axis begin at something closer to your measure's minimum value, making the line utilize all of the chart's vertical space. In some cases this is significant in improving the readability of the chart.

Related concepts:

"Axes" on page 86

Axes are lines that provide references for measurement or comparison.

Customize the Axes of a Current Default Chart

You can customize the axis labels, axis lines, and minor and major tick marks.

You can change the scale for the major and minor tick mark using the **Axis Range** property.

Procedure

1. Select the Y-axis or the X-axis of the chart.
2. To show or hide the axis labels, in the **Properties** pane, set the **Axis Label** property.
3. If your chart includes nested categories, to change how the category axis labels are displayed, set the **Nested Label Display** property.

4. To show or hide axis lines, in the **Properties** pane, double-click the **Axis Line** property, and select or clear the **Axis line** check box.
5. To change the color, style, and weight of the axis line, in the **Properties** pane, set the **Axis Line** property.
6. To show or hide minor and major tick marks and specify their location, in the **Properties** pane, set the **Axis Line** property.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Related tasks:

“Change the Axis Scale of a Current Default Chart”

By default, IBM Cognos Report Studio automatically determines the minimum and maximum scale values for the axes in a chart. For example, a Y-axis showing revenue values might have an axis range of zero dollars to one million dollars. You can customize the axis scale, or range, to make your chart easier to understand.

Customize the Axes of a Legacy Chart

You can customize the axis labels and axis line.

Procedure

1. Select the Y-axis or the X-axis of the chart.
2. To show or hide the axis labels, in the **Properties** pane, set the **Axis Label** property.
3. Select the **Axis line** check box.
4. Click **Line color** and choose a color for this axis line.
5. To show or hide axis lines, in the **Properties** pane, double-click the **Axis Line** property, and select or clear the **Axis line** check box.
6. To change the color, style, and weight of the axis line, in the **Properties** pane, double-click the **Axis Line** property.

Change the Axis Scale of a Current Default Chart

By default, IBM Cognos Report Studio automatically determines the minimum and maximum scale values for the axes in a chart. For example, a Y-axis showing revenue values might have an axis range of zero dollars to one million dollars. You can customize the axis scale, or range, to make your chart easier to understand.

You can specify the following for each axis:

- the maximum and minimum values of the range
- whether to include zero in an automatic axis range
- whether to use a logarithmic scale, if the values in the chart cover a very large range
- how often major and minor gridlines appear

Logarithmic scales can be useful when some of the data you are displaying is much less or much more than the rest of the data or when the percentage or ratio differences between values are important.

A logarithmic scale in Report Studio shows the base value of 10 raised to the power of a value. For example, 10 has a logarithm of 1 because 10 raised to the power of 1 is 10, 100 has a logarithm of 2 because 10 raised to the power of 2 is 100, and so on.

For example, the following chart is using a normal scale:




Figure 20. Chart with a normal axis range

In this chart, the Y-axis shows values up to 2,000,000,000 with evenly spaced intervals of 400,000,000. However, the Outdoor Protection column is so much less than the other columns that it is difficult to compare them.

The following is the same chart using a logarithmic scale:




Figure 21. Chart with a logarithmic axis range

In this chart, the Y-axis still shows the same revenue values, but the intervals reflect a logarithmic scale, which increases exponentially. You can now compare all the product lines because none of the product lines have much higher or much lower values than the others.

Logarithmic scales can also be useful when the percentage or ratio differences between values are important. For example, if the logarithmic scale chart above represents data from 2011, and you add data from 2012 as a second set of colored bars, you could see the differences between the 2011 revenue and 2012 revenue. In a logarithmic scale, differences between values on the Y-axis represent the same percentage for each bar. So if the 2011 and 2012 data differs by the same distance for each product line, you could deduce that your revenue went up by the same percentage for each product line. This would not be clear on a normal scale.

Procedure

1. Select the Y-axis or the X-axis of the chart.
2. In the **Properties** pane, under **General**, double-click the **Axis Range** property.
3. To set a maximum value for this axis, under **Maximum**, click **Manual**, and then type a maximum value in the **Manual** box.

Note: You can use either a positive or negative value as the maximum value.

4. To set a minimum value for this axis, under **Minimum**, click **Manual**, and then type a minimum value in the **Manual** box.

Note: You can use either a positive or negative value as the minimum value.

5. To include zero on this axis, select the **Include zero** check box.
6. To use a logarithmic scale for this axis, select the **Logarithmic scale** check box.

Note: If you choose to use a logarithmic scale, ensure that your chart consumers know that the scale is logarithmic by including that information in the axis title or in a note on the chart.

7. To set the position of major gridlines and tick marks, under **Major interval**, click **Manual**, and then type the distance between major gridlines and tick marks in the **Manual** box.

The distance between major gridlines and tick marks is measured in the units of that axis. For example, if the axis is revenue in dollars, type the dollar value in the **Manual** box.

8. To add minor gridlines, type the number of minor gridlines that you want to see between each major gridline in the **Number of minor intervals** box.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Related tasks:

“Customize the Axes of a Current Default Chart” on page 123

You can customize the axis labels, axis lines, and minor and major tick marks.

“Show Gridlines in a Current Default Chart” on page 127

You can also show alternating bands of color in the chart background that correspond to your axis gridlines.

Showing Gridlines in a Chart

To make the data in a chart that includes axes easier to read, you can show horizontal and vertical gridlines. You can show gridlines for the major or minor intervals on the axes.

You cannot show gridlines for chart types that do not display axes, such as pie and donut charts.

Show Gridlines in a Current Default Chart

You can also show alternating bands of color in the chart background that correspond to your axis gridlines.

You can change the scale for the major and minor gridlines using the **Axis Range** property.

Procedure

1. Select the Y-axis or the X-axis of the chart.
2. To show alternating bands of color as your chart background, do the following:
 - a. In the **Properties** pane, double-click the **Gridlines** property.
 - b. Select the **Show alternating color bands** check box.
 - c. Set the color and transparency of the first and second colors.
3. To show major gridlines as your chart background, do the following:
 - a. In the **Properties** pane, double-click the **Gridlines** property.
 - b. Select the **Show major gridlines** check box.
 - c. Set the color, style, and weight of the major gridlines.
 - d. If you are working with a gauge chart, specify the length of the gridline.
4. To show minor gridlines as your chart background, do the following:
 - a. In the **Properties** pane, double-click the **Minor gridlines** property.
 - b. Select the **Show minor gridlines** check box.
 - c. Set the color, style, and weight of the minor gridlines.
 - d. If you are working with a gauge chart, specify the length of the gridline.
 - e. To specify by how many minor intervals to divide the major intervals, in the **Properties** pane, type a number in the **Number of Minor Intervals** property.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Related tasks:

“Change the Axis Scale of a Current Default Chart” on page 124

By default, IBM Cognos Report Studio automatically determines the minimum and maximum scale values for the axes in a chart. For example, a Y-axis showing revenue values might have an axis range of zero dollars to one million dollars. You can customize the axis scale, or range, to make your chart easier to understand.

Show Gridlines in a Legacy Chart

Gridlines are the lines on a chart that show the intervals along the axes.

Procedure

1. Select the Y-axis or the X-axis of the chart.
2. In the **Properties** pane, under **General**, double-click the **Gridlines** property.
3. To specify the color, style, and weight of major gridlines do the following:
 - a. Select the **Show major gridlines** check box.
 - b. Click **Line color** and choose a color for the major gridlines.
 - c. To specify the thickness of the gridlines, click **Point size** and select a line weight from the list.
 - d. Click a line style in the **Line style** list.

4. To specify the color, style, and weight of minor gridlines:
 - a. In the **Properties** pane, under **General**, double-click the **Minor Gridlines** property.
 - b. Select the **Show minor gridlines** check box.
 - c. Click **Line color** and choose a color for the minor gridlines.
 - d. To specify the thickness of the gridlines, click **Point size** and select a line weight from the list.
 - e. Click a line style in the **Line style** list.
 - f. To change the transparency of the gridlines, type a percentage in the **Transparency** box.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Customize the Legend in a Current Default Chart

You can hide or show the legend and change its position relative to the chart area, chart body, or a data item. For example, in a bar chart showing revenue for each product line by country or region, you could use the expression [Country or Region] = 'Canada' to position the legend relative to the Canada bar.

Note: When you choose a preset legend position, that position appears inside any padding that you have added to the chart object. Customized legend positions do not include any chart padding.

Procedure

1. Select the chart object.
2. In the **Properties** pane, under **Chart Annotations**, double-click the **Legend** property.
3. To show the legend on the chart, select the **Show Legend** check box.
4. To choose a preset legend position, click **Preset** and click a position from the diagram.
5. To choose a customized legend position, do the following:
 - a. Click **Advanced** and click the ellipsis button.
 - b. To display the legend at a set distance from the sides of the chart area, from the **Anchor** list, click **Relative to Chart**.
 - c. To display the legend at a set distance from the sides of the chart body, from the **Anchor** list, click **Relative to Chart Body**.
 - d. To display the legend at a set distance from a data item, such as a specific pie slice in a pie chart, from the **Anchor** list, click **Report Expression**, click the ellipsis button beside **Expression**, and enter an expression in the **Report Expression** dialog box.
 - e. Set the horizontal and vertical distances from the anchor.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Customize the Items in the Legend of a Current Default Chart

If your legend includes items that are too long, you can truncate long legend items at a specific number of characters.

For example, if you want an ellipsis to appear at the end of each truncated legend item, type ... in the **Truncation text** box.

You can also show the values of the data items in your legend.

Procedure

1. Select the legend.
2. To truncate the legend
 - a. In the **Properties** pane, under **General**, double-click the **Text Truncation** property.
 - b. To specify the number of characters at which the legend items are truncated, click **Manual** and type the number of characters in the **Maximum characters** box.
 - c. To shrink the font of the legend item text until all the text fits in the legend, select the **Shrink font as needed** check box.
 - d. To specify some text to appear at the end of truncated legend items, in the **Truncation text** box, type the text that you want to appear at the end of truncated items.
3. To show the values of legend items within the legend
 - a. In the **Properties** pane, under **General**, set the **Show Values** property.
First Value and **Last Value** refer to the first and last item in the child set under the legend data item. **Minimum Value** and **Maximum Value** refer to the lowest and highest value in the child set under the legend data item.
 - b. If you want to change the separator between the legend item and value, type a new separator in the **Legend Separator** property.
4. To customize the title of the legend
 - a. Click the default legend title area in the work area.
 - b. In the **Properties** pane, under **General**, set the **Default Title** property to **No**.
 - c. Double-click the default legend title area in the work area and type the new title.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Customize the Items in the Legend of a Legacy Chart

If your legend includes items that are too long, you can truncate long legend items at a specific number of characters. For example, if you want an ellipsis to appear at the end of each truncated legend item, type ... in the **Truncation text** box.

You can also show the values of the data items in your legend and customize the legend title.

Procedure

1. Select the legend.
2. To truncate the legend text, do the following:
 - a. In the **Properties** pane, under **General**, set the **Auto Truncation** property to **Yes**.
 - b. In the **Properties** pane, under **General**, set the **Auto Truncation** property to **Yes**.

- c. In the **Maximum Characters** property, type the number of characters to appear before the text is truncated.
 - d. In the **Truncation Text** property, type the characters to append when the text is truncated.
 - e. To shrink the font of the legend item text until all the text fits in the legend, select the **Shrink font as needed** check box.
 - f. To specify text to appear at the end of truncated legend items, type it in the **Truncation text** box.
3. To show the values of legend items within the legend, do the following:
 - a. In the **Properties** pane, under **General**, set the **Show Legend Values** property.
First Value and **Last Value** refer to the first and last item in the child set under the legend data item. **Minimum Value** and **Maximum Value** refer to the lowest and highest value in the child set under the legend data item.
 - b. If you show multiple values and want to change the separator between the values, type a new separator in the **Separator** property.
 4. To customize the title of the legend, do the following:
 - a. Click the default legend title area in the work area.
 - b. In the **Properties** pane, under **General**, set the **Default Title** property to **No**.
 - c. Double-click the default legend title area in the work area and type the new title.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Adding a Note to a Chart

Add a note to a chart to provide additional detail. Notes appear as text in a chart.

By default, notes are aligned with the upper left corner of the chart object. When you add a note to a chart, you can set the note's position relative to the sides of the chart area or chart body. You can also use a report expression to position the note next to a data item within the chart. For example, in a bar chart showing revenue for each product line by country or region, you could type [Country or Region]='Canada' to position the note relative to the Canada bar.

Notes overwrite whatever is under them so you must position them properly.

If you apply more than one note, ensure that each note has a different position in the report so that they do not overwrite each other. You can also specify the order that they should be drawn in when the report runs. If you have two notes with the same coordinates, the first one in the list is drawn first and the next one is drawn on top of the first.

Tip: The Top 10 Retailers for 2011 sample report in the GO Data Warehouse (analysis) package includes a note.

Related concepts:


Appendix C, “Sample Reports and Packages,” on page 525


Sample reports are included with IBM Cognos Business Intelligence. When installed, you can find them in the **Public Folders** tab in IBM Cognos Connection.



Add a Note to a Current Default Chart

You can add and position multiple notes on your chart.

Procedure

1. Select the chart object.
2. In the **Properties** pane, under **Chart Annotations**, double-click the **Notes** property.
3. Click the new button .
4. Type the note text in the **Text** box and click **OK**.

Tips: To delete a note, click the note and click the delete button . To move a note up or down in the list, click the up or down arrows.

5. In the **Notes** dialog box, click **OK**.
6. To position the note, do the following:
 - a. Click the note icon  in the list of notes.
 - b. In the **Properties** pane, under **Positioning**, double-click the **Position** property.
 - c. To align the note horizontally, click the left, center, or right alignment button.
 - d. To align the note vertically, click the top, middle, or bottom alignment button.
 - e. To set the margins around the chart body, type margin values and choose margin units.
 - f. To display the note at a set distance from the sides of the chart area, from the **Anchor** list, click **Relative to Chart**.
 - g. To display the note at a set distance from the sides of the chart body, from the **Anchor** list, click **Relative to Chart Body**.
 - h. To display the note at a set distance from a data item, from the **Anchor** list, click **Report Expression**, click the ellipsis button beside **Expression**, and enter an expression in the **Report Expression** dialog box.
7. To edit the text, double-click the text next to the note object  in the chart.

Related concepts:


“Current Default Charts and Legacy Charts” on page 83


IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Add a Note to a Legacy Chart


You can add and position multiple notes on your chart.

Procedure

1. Click the chart object.
2. In the **Properties** pane, under **Chart Annotations**, double-click the **Notes** property.
3. Click the new button .
4. Type the note text in the **Text** box and click **OK**.

Tip: To delete a note, click the note and click the delete button . To move a note up or down in the list, click the up or down arrows.

5. In the **Notes** dialog box, click **OK**.

6. Click the note icon  and set the note position, size, and border in the **Properties** pane.

You set the location of the note by defining number of pixels from the bottom left corner of the chart area.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Adding a Baseline to a Chart

Baselines are horizontal or vertical lines that cut through the chart to indicate major divisions in the data. For example, you can add a baseline to show a sales quota or break-even point.

Each baseline represents a value on an axis.

Depending on the type of chart, you can use the following options to position the baseline.

Option	Description
Numeric Value	Uses a static numeric value.
Query Calculation	Uses a query calculation from the chart query or from a different query. For more information, see “Using Relational Calculations” on page 262.
Layout Calculation	Uses a layout calculation. For more information, see “Using Relational Calculations” on page 262.
Category Index	<p>Uses the index value of the data item in the categories axis.</p> <p>For example, a Category index value of 1 indicates that the baseline is located at the first data item. This is the default.</p> <p>Note: This option applies only to the current default charts, and does not apply to the legacy charts.</p>

Option	Description
Member Value	When working with dimensional data sources, uses a position relative to a member. For example, a member calculation that uses an expression similar to [Query1].[Current year]=2011 places the baseline in the middle of the chart object that represents 2011. To place the baseline between 2011 and 2012 on the chart, a half member width to the right, set the Member Offset property to 50%. To place the baseline between 2010 and 2011, set the Member Offset property to -50%. You can also type in 100, -200, and so on to place the baseline on the chart.
Statistical Limit	<p>Statistical maximum uses the following expression:</p> $25\text{th percentile value} - 1.5 * (75\text{th percentile value} - 25\text{th percentile value})$ <p>For example, if 2.5 is the 25th percentile and 7.5 is the 75th percentile, the statistical minimum is -5 [2.5 -1.5(5) = -5].</p> <p>Statistical minimum uses the following expression:</p> $75\text{th percentile value} + 1.5 * (75\text{th percentile value} - 25\text{th percentile value})$ <p>For example, if 2.5 is the 25th percentile and 7.5 is the 75th percentile, the statistical maximum is 15 [7.5 +1.5(5) = 15].</p> <p>Statistical minimum and Statistical maximum use percentiles to determine values, so the baseline might not appear on the chart if its value is off the axis.</p>
Mean	Uses the statistical mean plus or minus a number of standard deviations based on all charted data values on the specified axis.
Percentile (%)	Uses a specified percentile.
Percent on Axis (%)	<p>Uses a percentage of the full range of the axis.</p> <p>For example, if the axis range is -500 to 1100, a Percent on Axis value of 25% puts the baseline at -100 (25% of the range, 1600).</p>

If you apply more than one baseline, you can specify the order in which they should be drawn when the report runs. If you have two baselines with the same coordinates, the first one in the list is drawn first and the next one is drawn on top of the first one.

By default, the baseline and its label appear in the legend.

Baselines do not support color transparency.

Tip: The Positions to Fill sample report in the GO Data Warehouse (analysis) package includes a baseline.

Related concepts:

Appendix C, “Sample Reports and Packages,” on page 525


Sample reports are included with IBM Cognos Business Intelligence. When installed, you can find them in the **Public Folders** tab in IBM Cognos Connection.

Add a Baseline to a Current Default Chart

When working with current default charts, you can define baselines by values on the numeric axis or the category axis.

Procedure

1. Click the chart object.
2. Depending on your chart and the type of baseline you want to add, in the **Properties** pane, under **Chart Annotations**, double-click the **Numeric Baselines** or **Category Baselines** property.

3. Click the new button  and choose the type of baseline from the list.
4. Specify the necessary criteria for the baseline position
5. Under **Baseline Properties**, type a label for the baseline and specify the line style.

Tip: To remove the baseline from the legend, delete the label.




6. If you add more than one baseline, specify their order using the up and down arrows.

The new baselines appear in the **Markers, notes, baselines, and trendlines** box.

7. To change the label that appears next to the baseline, under the **Markers, notes, baselines, and trendlines** box, double-click the placeholder text next to the

baseline icon   and type your text.

8. To change the line style, select the chart and in the **Properties** pane, under **Chart Annotations**, double-click the **Baselines, Numeric Baselines, or Category Baselines** property.

9. To delete a baseline, select the baseline icon   and click the delete button .

Related concepts:


“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Add a Baseline to a Legacy Chart



When working with legacy charts, you can define baselines by the values on the numeric axis.

Procedure

1. Click the chart object.
2. In the **Properties** pane, under **Chart Annotations**, double-click the **Baselines** property.
3. Click the new button  and choose the type of baseline from the list.
4. Specify the necessary criteria for the baseline position.

- If you use a calculation to determine the baseline, define an expression.
- If you add more than one baseline, specify their order using the up and down arrows.
 - Click **OK**.

A baseline icon appears in the **Markers, notes, and baselines** box.

- To define the line style, click the baseline icon  and set the **Line Styles** property.
- To define the text style, click the baseline text and make changes in the **Properties** pane.
- To delete a baseline, click its baseline icon and click the delete button .

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Adding Markers to Charts

Markers are symbols that you add to a chart to designate points of significance that can help you analyze or understand the data.

For example, you might want to add a marker to designate the time when a significant event happened, such as the date when a new product was launched.

You can add a marker to combination, progressive column, Pareto, scatter, and bubble charts.

When you define the position of the marker, you define the X- and Y-axis coordinates for the placement of the symbol. You can position the marker in the chart using the following options.

Option	Position
Numeric Value	Uses a static numeric value.
Query Calculation	Uses a query calculation from the same query or from a different query. For more information, see “Using Relational Calculations” on page 262.
Layout Calculation	Uses a layout calculation. For more information, see “Using Relational Calculations” on page 262.
Statistical Minimum	<p>Uses the following expression:</p> $25th\ percentile\ value - 1.5 * (75th\ percentile\ value - 25th\ percentile\ value)$ <p>For example, if 2.5 is the 25th percentile and 7.5 is the 75th percentile, the statistical minimum is -5 [2.5 - 1.5(5) = -5].</p> <p>Statistical minimum uses percentiles to determine values, and might not always appear in the chart if the values are off the axis.</p>

Option	Position
Statistical Maximum	<p>Uses the following expression:</p> $75th\ percentile\ value + 1.5 * (75th\ percentile\ value - 25th\ percentile\ value)$ <p>For example, if 2.5 is the 25th percentile and 7.5 is the 75th percentile, the statistical maximum is 15 $[7.5 + 1.5(5) = 15]$. Statistical maximum uses percentiles to determine values, so the marker might not always appear on the chart if its value is off the axis.</p>
Mean	Uses the statistical mean plus or minus a number of standard deviations based on all charted data values on the specified axis.
Percentile	Uses a specified percentile.
Percent on Axis	Uses a percentage of the maximum axis value.


If you apply more than one marker, you can specify the order in which they should be drawn when the report runs. If you have two markers with the same coordinates, the first one in the list is drawn first and the next one is drawn on top of the first.

Add a Marker to a Current Default Chart

Markers are symbols that you add to a chart to designate points of significance that can help you analyze or understand the data.

Note: Current default scatter charts have a different set of steps.

Procedure

1. Select the chart object.
2. In the **Properties** pane, under **Chart Annotations**, double-click the **Markers** property.
3. Click the new button , and then set the marker properties
4. In the **Based on** box, select the chart object that will determine the marker position.
5. In the **Numeric position** box, specify how you want to define the position on the numeric (Y) axis.
6. In the **Category position** box, specify how you want to define the position on the category (X) axis.
7. In the **Marker label** box, type the label that you want to give to the marker.
8. In the **Marker size** box, specify the size of the marker symbol.
9. To specify the color, fill, and shape of the marker symbol, click the **Color and style** box.
10. If you add more than one marker, specify their order by using the up and down arrows.

The new markers appear in the **Markers, notes, and baselines** box.

Tip: To delete a marker, click the marker icon and text and click the delete button .

11. Run the report.

Related concepts:


“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Add a Marker to a Current Default Scatter Chart

Markers are symbols that you add to a chart to designate points of significance that can help you analyze or understand the data.

Procedure

1. Select the scatter chart object.
2. In the **Properties** pane, under **Chart Annotations**, double-click the **Markers** property.
3. Click the new button , and then set the marker properties.
4. In the **X-axis position** box, specify how you want to define the position on the X-axis.
5. In the **Y-axis position** box, specify how you want to define the position on the Y-axis.
6. In the **Marker label** box, type the label that you want to give to the marker.
7. In the **Marker size** box, specify the size of the marker symbol
8. To specify the color, fill, and shape of the marker symbol, click the **Marker color and style** box.
9. If you add more than one marker, specify their order using the up and down arrows.

The new markers appear in the **Markers, notes, and baselines** box.

Tip: To delete a marker, click the marker icon and text and click the delete button .

Related concepts:


“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Add a Marker to a Legacy Chart

Markers are symbols that you add to a chart to designate points of significance that can help you analyze or understand the data.

Procedure

1. Select the chart object.
2. In the **Properties** pane, under **Chart Annotations**, double-click the **Markers** property.
3. Click the new button , and then set the **Numeric position type**, **Marker label**, **Marker shape**, **Numeric value**, and **Color** properties.
4. If you add more than one marker, specify their order by using the up and down arrows.

The new markers appear in the **Markers, notes, and baselines** box.

Tip: To delete a marker, click the marker icon or marker label and click the delete button .

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Display Trendlines in Current Default Charts

You can display or hide trendlines in the current default bar, line, area, bubble, or scatter charts.

Trendlines, also known as lines of best fit or regression lines, graphically illustrate trends in data series and are commonly used when charting predictions. A trendline is typically a line or curve that connects or passes through two or more points in the series, showing a trend.


You can specify the following types of trendlines:

- **Linear**
Use a linear trendline when your data increases or decreases along a straight line at a constant rate. For example, if your chart displays a steady increase in revenue by product line over time, you could use a linear trendline.
- **Exponential**
Use an exponential trendline when your data values increase or decrease exponentially, or at an increasingly higher or lower rate. For example, if your chart displays an exponential increase in revenue by product line over time, you could use an exponential trendline.
- **Polynomial**
Use a polynomial trendline when your data values both increase and decrease. For example, if your chart displays both increases and decreases in revenue by product line over time, you could use a polynomial trendline.
- **Logarithm or Natural Logarithm**
Use a logarithmic trendline when your data values increase or decrease rapidly and then level out. For example, if your chart displays a rapid decrease in revenue by product line over time and then a plateau, you could use a logarithmic trendline.
- **Power**
Use a power trendline when your data values increase or decrease in a curve at a steady rate. For example, if your chart displays a steady increase in revenue by product line over time and your data points will fit a curved line, you could use a power trendline.
- **Moving Average**
Use a moving average trendline when your data values fluctuate and you want to smooth out the exceptions to see trends. For example, if your chart displays wild fluctuations in revenue by product line over time, but you know that some data points are exceptions, you could use a moving average trendline.

If you are not sure which trendline type to use, try each type to see which one best fits most of your data points. For example, a linear trendline will not fit most points on a scatter chart with widely spread data points.

Trendlines do not support color transparency.

Procedure

1. Select the chart object.
2. In the **Properties** pane, under **Chart Annotations**, double-click the **Trendlines** property.
3. Click the new button  and click a trendline type.
4. Define the trendline by specifying the following options. The options that are available depend on the type of trendline you chose.
 - To set the order, or degree, of a polynomial trendline, in the **Order** box, type a value between 2 and 6.
 - To set the number of periods to go back in a moving average trendline, in the **Periods** box, type a value.
 - If you have more than one series on your chart, in the **Based on** list, click the data you want to use for the trendline.
 - Click either **One trendline for all series items** or **A trendline for each series item**.
 - To customize the style of the trendlines, click **Line Styles** and customize the line color, weight, and style.
 - To customize the trendline labels in the legend, click **Label** and choose **None**, **Automatic**, or **Custom**.
 - To display the trendline equation, click **Show equation**, and then click **Show in legend** or **Show on chart**, and then click **Position** to define the equation's position on the chart.
 - To display the R-squared value of the trendline, click **Show R-squared value**, and then click **Show in legend** or click **Show on chart** and then click **Position** to define the position of the value on the chart.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Display Regression Lines in Legacy Scatter or Bubble Charts

When using legacy charts, you can display or hide regression lines on scatter charts and bubble charts. Regression lines, also known as lines of best fit or trend lines, graphically illustrate trends in data series. Regression lines are commonly used when charting predictions. A regression line is typically a line or curve that connects or passes through two or more points in the series, showing a trend. Legacy scatter and bubble regression lines are calculated using a numerical algorithm that isn't guaranteed to be optimal. Regressions may or may not match current default chart regressions.

You can specify the following types of regression lines to determine the position and slope of the line:

- **Linear**
Use a linear regression line when your data increases or decreases at a consistent rate. For example, if your chart displays a steady increase in revenue by product line over time, you could use a linear regression line.
- **Common Log** or **Natural Log**

Use a logarithmic regression line when your data increases or decreases rapidly and then levels out. For example, if your chart displays a rapid decrease in revenue by product line over time and then a plateau, you could use a logarithmic regression line.

- **Exponential**


Use an exponential regression line when your data increases or decreases exponentially, or at steadily increasing or decreasing rate. For example, if your chart displays an exponential increase in revenue by product line over time, you could use an exponential regression line.

- **Polynomial Fit**

Use a polynomial fit regression line when your data both increases and decreases. For example, if your chart displays both increases and decreases in revenue by product line over time, you could use a polynomial fit regression line.

If you are not sure which regression line type to use, try each type to see which one best fits most of your data points. For example, a linear regression line is not going to fit most points on a scatter chart with widely spread data points.

Procedure

1. Select the scatter or bubble chart.
2. In the **Properties** pane, under **Chart Annotations**, set the **Regression Line** property to **Show**.
3. Click the regression line icon  in the report layout.
4. In the **Properties** pane, under **General**, set the **Line Styles**, **Regression Type**, and **Number of Regression Lines** properties.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83
IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Showing data labels or values in current default charts

You can show the data labels or data values within the chart so that the data values are clearer.

For example, you can display the data values above each column in a column chart to show the exact height of each column.

Procedure

1. For a bar, column, line, or area chart, under **Series**, select the chart type icon.
2. For a bubble, scatter, Pareto, or progressive chart, click the chart.
3. In the **Properties** pane, under **Chart Labels**, double-click the **Show Values** property.
4. For bar, column, line, area, Pareto, or progressive charts, to specify the data label format, in the **Values** list, select what values to display.
 - **None** does not display data values.
 - **Values** displays the non-cumulative value of the data.
 - **Cumulative values** displays the cumulative value of the data.

5. For bubble or scatter charts, to specify the data label format, in the **Show** box, select whether to show values or values and labels for the category, series, and measure.
6. For bar, column, line, area, Pareto, or progressive charts, to show lines that point from data labels to data marker they apply to, select the **Show leader lines** check box.
7. For bubble or scatter charts, to show lines that point from data labels to data marker they apply to, select the **Leader lines** check box.
8. To specify where values and labels are to be rendered in the chart, click the **Value Location** list and choose the location that you want.
9. To specify how to display the labels if their positions on the chart overlap, in the **Collision Mode** list, click one of the following modes:
 - **None** specifies that labels appear in default positions and might overlap.
 - **Normal** (for pie and donut charts) specifies that labels are placed just above their corresponding data markers or chart objects. There is no collision detection, so labels can overlap.
 - **Coarse Stagger** specifies that labels are placed close to their data markers and staggered so that they do not overlap. This collision mode takes less time to render than **Fine Stagger** but might result in labels that are farther away from their corresponding data markers.
 - **Fine Stagger** specifies that labels are staggered so that they do not overlap. The labels are as close to the data markers as possible without overlapping. This collision mode takes more time to render than **Coarse Stagger** but might result in labels that are closer to their corresponding data markers.

Showing data values in current default pie and donut charts

You can show the data labels or data values within the chart so that the data values are more clear.

For example, in a pie chart, show the data values within each pie slice, so that you know the exact size of each pie slice.





Procedure

1. Select the chart object.
2. In the **Properties** pane, double-click the **Show values** property.
3. To display data labels for each slice of the pie, under **Show**, select the **Slice names** check box.
4. To show lines pointing from data labels to the slices they apply to, select the **Show leader lines** check box.
5. To specify the data label format, in the **Values** list, select what values to display.
 - **Hide** does not display data values.
 - **Absolute** displays the absolute value of the data.
 - **Percentage** displays the slice's percentage of the whole pie.
 - **Absolute and Percentage** displays the slice's percentage of the whole pie as an absolute value.
6. In the **Position** list, select the placement of data labels.

Define Query Context When Customizing Legend Entries, Legend Titles, or Axis Labels

You want to use a revenue expression as a chart legend title. If you get an error message saying that the query context of a layout object cannot be determined, you must define the property list for the item to which it refers. You must first add the desired data item to the query before you can define its property list.

Procedure

1. Open the chart to customize.
2. Pause the pointer over the query explorer button  and click the query.
3. From the **Source** tab , drag the desired item to the **Data Items** window to add it to the query.
4. Pause the pointer over the page explorer button  and click the chart page.
5. From the **Source** tab , drag the desired item to the layout object.
6. In the **Properties** pane, under **Data**, double-click the **Properties** property.
7. Select the check box for the data item to define.

Related tasks:

“Specify a List of Data Items for an Object” on page 298

Specify the list of data items for an object when you must reference a data item that is in a query but is not in the layout.

Summarize Small Slices, Bars, or Columns in Current Default Charts

You can summarize the smaller slices or bars in charts to avoid having many tiny slices or bars. For example, if your pie chart shows revenue by product and 10 of your products have less than 1% of the pie, you can summarize these 10 slices into one larger slice and name that slice Other.

Similarly, you can summarize small items in a column, bar, area, and line chart.

You cannot summarize small slices or items in charts that have matrix edges or in charts that have multiple numeric axes.

Procedure

1. Select the chart object.
2. In the **Properties** pane, under **General**, double-click the **Summarize Small Slices** or **Summarize Small Items** property.
3. To summarize small slices or items up to a maximum number, select the **Maximum number of slices** or **Maximum number of items** check box and type the maximum number.
4. To summarize all the slices or bars that are smaller than a specific value, select the **Summarize slices smaller than a value** or **Summarize items smaller than a value** check box, type a value that represents the upper size limit, and choose whether the value is a percentage or absolute.
5. Under **Small slice summarization type** or **Small item summarization type**, choose whether to summarize the slices or items as a **Total** or **Average**.

Note: Averages are calculated using only the summarized items in the report.

6. Under **Slice label** or **Item label**, type a label for the one large slice, bar, area, or line that summarizes the smaller ones.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Customizing Lines and Data Points in a Line Chart

You can customize the lines in a line chart to show only lines, only data points, or both. Data points represent series values for each category on the Y-axis. You can show special data markers that represent statistically significant values, such as open, high, low, and close values.

You can also add markers at other positions on the chart. For more information, see “Add a Marker to a Current Default Chart” on page 136.

You can also change the shape of the line that connects the data points to one of the following:

- **Point to Point** shows data points connected by straight lines.
- **Step at Point** shows data points connected by steps that start and end at the data points.
- **Step Between Points** shows data points connected by steps that start and end between the data points.
- **Smooth** shows data points connected by smooth curves.

Related tasks:

“Add a Marker to a Current Default Chart” on page 136

Markers are symbols that you add to a chart to designate points of significance that can help you analyze or understand the data.

Customize Lines and Data Points in a Current Default Line Chart

You can change the color and shape of the line or data markers in a line chart. You can also show or hide data labels, the line, and data markers.

You cannot show value markers when the **Data points** option is selected or when the configuration of the line chart is stacked or 100 percent stacked.

Procedure

1. Select the chart object.
2. In the chart area, under **Series**, click the line chart icon to view the line properties.
3. To select whether to show only the line, the line and data markers, or only the data markers, in the **Properties** pane, select an option from the **Line and Markers** list.
4. To show special data markers, double-click the **Value Markers** property. Select the check box for the special data markers that you want to add and for each marker, specify the color and shape.

The options you specify in **Value Markers** overwrite the options for **Line and Markers**.

5. To change the shape of the line that connects data markers, select an option from the **Line Shape** list.
6. To show data labels for the data points, double-click the **Data Labels** property.

7. To change the color of the lines, double-click the **Palette** property.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

“Customizing the Color Palette of a Chart” on page 112

You can use the chart palette to control the colors or patterns used in the columns, lines, data markers or areas in a chart. For example, if "Telephone" is the first in a data series of order methods, and you want it to appear in blue, use the palette to make the first item in the series blue.

Customize Lines and Data Points in a Legacy Line Chart

You can change the color and shape or the line or data markers in a line chart. You can also show or hide data labels, the line, and data markers.

You cannot show value markers under the following conditions:

- The **Data points** option is selected.
- The configuration of the line chart is stacked or 100 percent stacked.
- The **Show line** property is set to **No**, creating a point chart.

Procedure

1. Select the chart object.
2. In the chart area, under **Series**, click the line chart icon to view the line properties.
3. To select whether to show only the line, the line and data markers, or only the data markers, in the **Properties** pane, under **General**, select an option from the **Line Type** list.
4. To show or hide the line, select an option from the **Show line** list.
5. To show data points or value markers, double-click the **Show Data Points** property:
 - To show or format data points, click **Data points** and specify the point shape and point size.
The point color is defined by the chart palette.
 - To show or format value markers, click **Value markers** and specify the markers to show. For each marker, specify the shape and marker size. Click **Color** to change the marker color.

Tip: To remove all data points and value markers, in the **Show Data Points** dialog box, select **None**.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

“Customizing the Color Palette of a Chart” on page 112



You can use the chart palette to control the colors or patterns used in the columns, lines, data markers or areas in a chart. For example, if "Telephone" is the first in a data series of order methods, and you want it to appear in blue, use the palette to make the first item in the series blue.

Customize a Current Default Combination Chart


Combination charts show data series using two or more types of charts - area, bar, and line. The different charts are overlaid on top of each other. You can customize the order in which the charts appear along with the type of charts and their configurations.

You can also customize which numeric axes to show and which chart to show on each axes.

Procedure

1. Select the combination chart object.
2. In the **Properties** pane, under **General**, double-click the **Combinations** property.
3. Under **Numeric axes**, select which axes to show.
4. Under **Combinations**, add  or remove  data series.
5. If you want to change the order in which the series appear, use the up and down arrows.

The series appear in the order they are listed. Each chart appears in the foreground of any previous charts.

6. If you want to change the configuration type of the series, such as changing clustered bars to stacked bars, under **Combinations**, select the series, click the edit button  and select the type.
7. If you use the same data series for multiple charts and want to synchronize the data marker colors, under **Color & Background**, set the **Series Color** property to **Match**.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Create a Matrix of Current Default Charts

You can view a complex chart that includes nested series or categories into a matrix, or crosstab, that shows multiple small charts arranged in rows and columns.

The charts in the rows represent the outer nested levels of the series and categories and, the charts in the columns represent the categories. Each data item in the outer nested levels of the series and categories becomes a separate chart. The numeric scale of all the charts is the same so that you can easily compare.

When working with pie, gauge, and bullet charts, if you include a data item in the categories, you automatically create a matrix of charts. One chart appears for each data item in the category. When working with progressive and bullet charts, if you include a data item in the series, you also automatically create a matrix of charts.

For example, the following column chart shows the revenue for each year (in the categories or X-axis) for all the regions and product lines (in the series or Y-axis). This chart is very complex and difficult to understand.




Figure 22. Complex column chart

The following chart contains the same series and categories. However, when converted to a matrix of charts, the information is much easier to analyze. The columns show charts for each year and the rows show charts for each the product lines. The bars represent the revenue for each region.




Figure 23. Matrix chart

Procedure

1. Select the chart object.
2. In the **Properties** pane, under **General**, double-click the **Matrix rows and columns** property.
3. Select the **Show outer nested series as matrix rows** or **Show outer nested categories as matrix columns** check boxes (or both).
4. In the **Matrix levels** box, select the number of nested levels to include in the matrix columns or rows.

The remaining nested levels are represented in the chart bodies in the matrix if the chart supports additional categories. The pie, gauge, and bullet charts do not support additional categories. The bullet and progressive column charts do not support additional series.

For example, in the above chart, Regions are nested under Product Line. In the matrix chart, a **Matrix level** of 1 is specified. Therefore, Product Line appears as the matrix rows (series) and Regions appear within the chart bodies.

5. If you want labels for the matrix rows and columns to appear on each chart, select the **Show row labels** or **Show column labels** check box.
6. In the **Labels location** list, select where the nested labels should appear on each chart.
The default position is on the left for rows and on the bottom for columns.
7. If the labels are too long, click **Truncation** and specify where to truncate text or select the **Size fonts automatically** check box to resize the text to fit.
8. To change the font, color, and data format of the labels, click **Style**.
9. To show the title in the row or column axis, select the **Show row title** or **Show column title** check box.
10. If you want to hide or show the axes, select the axis object, and in the **Properties** pane, under **Miscellaneous**, set the **Show in Matrix** property.
11. If your matrix chart includes only rows or columns, and you want them to wrap, select the **Wrap rows or columns if possible** check box.
12. If you want to show the axes and axis labels for each small chart in the matrix, select the **Repeat row and column axis labels** check box.
When this option is cleared, axes and axis labels appears only along the outer edge of the matrix.

Related concepts:


“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Customize a Current Default Gauge Chart

When you create a gauge chart, you can choose from a variety of chart templates, which offer different shape, axis, and border options.


You can customize the following aspects of your gauge chart. As you modify properties, the chart preview shows you what your chart will look like.



Unless indicated in the user interface, all sizes are a percentage of the maximum allowed.

If your gauge chart includes a border, long axis labels, such as 250,000,000, may overlap the gauge border and be difficult to read. To avoid this problem, customize the data format of your gauge chart measure and reduce the scale so that less zeros are displayed. Or change the gauge border color or size or remove the border.

Procedure

1. Click the gauge chart object.
2. If you want to change the shape of the gauge, modify the start and end angles of the gauge axes and border, as follows:
 - a. In the **Properties** pane, under **General**, double-click the **Gauge Axes** property and specify the start and end angles and the direction of the axes.
 - b. Double-click the **Gauge Border** property and specify the style and the start and end angles of the border.
For example, a border start angle of 0 degrees and end angle of 180 degrees produces a semi-circular gauge.
3. If you want to add an additional axes to a gauge chart, do the following:
 - a. In the **Properties** pane, under **General**, double-click the **Gauge Axes** property.
 - b. Click the new button  and specify the start and end angles and the direction of the new axis.
4. If you want to change the size, shape, and color of the center pivot point, double-click the **Gauge Pivot** property and specify the style.
5. If you want to change the indicators in the gauge axis, click the **Gauge Axis** object in the chart and do the following:
 - a. To change the needle, under **Axes**, double-click the **Gauge Needle** property and specify the style.
 - b. To change, add, or remove color bands that indicate the data range positions, under **Color & Background**, double-click the **Gauge Axis Colors** property and specify the color palette.
 - c. If you want to change the size or thickness of the gauge axis and color bands, under **Axes**, specify a percentage size for the **Gauge Axis Inner Radius** and **Gauge Axis Outer Radius** properties.

- d. If you want to change the gridlines, under **General**, double-click the **Gridlines** or **Minor Gridlines** properties and specify the style.
- e. If you want to change the appearance of the gauge axis line, under **General**, double-click **Axis Line**.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.


“Gauge Charts” on page 98

Gauge charts, also known as dial charts or speedometer charts, use needles to show information as a reading on a dial.

Customize a Legacy Gauge Chart

You can customize the colors and threshold boundaries of the gauge axis areas and whether they use numbers instead of percentages. You can also change the colors of the gauge face and outline and hide gauge labels. By default, the legacy gauge chart uses a band divided into thirds that runs from green to red.

Procedure

1. Click the gauge chart object.
2. If you want to customize the color of the gauge face or outline, in the **General** section of the **Properties** pane, double-click the **Face Color** or **Dial Outline Color** property.
3. If you want to hide the gauge labels, in the **Chart Labels** section of the **Properties** pane, set the **Gauge Labels** property to **Hide**.
4. If you want to customize the colors and boundaries of the gauge areas, do the following:
 - a. In the **Color & Background** section of the **Properties** pane, double-click the **Gauge Palette** property.
 - b. To change the color of a boundary area, under **Palette**, select the color, click **Color**, specify the color properties, and click **OK**.
 - c. To change the value of a boundary area, under **Palette**, select the boundary value, and type a new value.
 - d. To add a new boundary area, click the new button .
 - e. To choose a pre-defined threshold style, click the **Palette** drop-down menu. You can choose whether to use discrete colors or continuous colors. To use a number instead of a percentage as a boundary, clear the **Percentage** check box, and then type a number in the **Numeric boundary** box.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

“Gauge Charts” on page 98

Gauge charts, also known as dial charts or speedometer charts, use needles to show information as a reading on a dial.

Defining color by value in current default scatter or bubble charts

In a scatter or bubble chart you can specify that data points or bubbles appear in different colors that are based on an additional measure or fact. The color of the points or bubbles helps you to see relationships in large amounts of data.

For example, the following bubble chart shows the relationship between the unit cost and unit sale price. The size of the bubbles shows the gross profit and the color of the bubbles shows whether the quantity sold is above (yellow) or below (green) 1,000,000 units.




Figure 24. Example of a bubble chart that shows values in different colors


In a bubble chart, you can combine the color by value and bubble size to create a more meaningful chart.

Procedure

1. Drag a measure to the **Color** drop zone under **Measures** and then select the measure.
2. In the **Properties** pane, under **Color & Background**, double-click the **Color by Value** property.
3. To define the colors by percentages instead of actual values, select the **Percentage** check box.

For example, if you select the **Percentage** check box and your values range from 25 (red) to 50 (green), the bottom 25 percent of values are red and the top 50 percent of values are green. The values between 25 percent and 50 percent are an interpolated color, such as yellow.

4. If you want to use a preset color palette, click **Palette**, and select the palette that you want to use.
5. If you want to customize a palette color or boundary value, select the palette entry in the **Palette** box and specify the color, transparency, and type a new boundary value.

6. To add a palette entry, select the palette entry below which you want to add the new entry, click the new palette entry icon , and click **Color**.
7. If your chart has lines or markers, under **Style**, set the marker shape, line style, and line weight.
8. To choose a color and transparency for missing or null values, under **Missing Values**, click **Color** and type a value in the **Transparency** box.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

“Scatter Charts” on page 94

Scatter charts use data points to plot two measures anywhere along a scale, not only at regular tick marks.

“Bubble Charts” on page 95

Bubble charts, like scatter charts, use data points and bubbles to plot measures anywhere along a scale. The size of the bubble represents a third measure.

Specify the Bubble Size in a Current Default Bubble Chart

In a bubble chart, you use a measure or fact to determine the size of the bubbles.

You can use the **Bubble Measure** in the **Measures** drop zone of the chart to specify bubble size. You can then specify the size range of the bubbles in the chart. You can also specify what value the smallest bubbles represent. For example, your bubble measure is revenue, and you set the minimum and maximum bubble size to 5 pt and 20 pt, respectively. You set the smallest bubble to represent the value zero. All the bubbles on your chart will be between 5 and 20 pts and any bubbles between 0 and 5 pts on this scale will appear at 5 pt.

You can combine bubble size with colors by value to create a chart that shows multiple dimensions.

Procedure

1. Select the chart object.
2. In **Properties** pane, under **General**, double-click the **Bubble Size** property.
3. Under **Smallest bubble**, select what value the smallest bubbles represent:
 - To show data items with a value of zero at the minimum bubble size, click **Zero**.

Tip: This setting is consistent with Microsoft Excel 2003.

- To show data items with a value of zero at the minimum bubble size and show negative bubbles as hollow, select the **Zero. Negatives shown as hollow** check box.

Tip: This setting is consistent with Microsoft Excel 2007.

- To set the minimum bubble size to the minimum data value, click **Minimum data value**, and type a size for the minimum and maximum bubble size.

Note: The minimum data value can be positive or negative.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

“Bubble Charts” on page 95

Bubble charts, like scatter charts, use data points and bubbles to plot measures anywhere along a scale. The size of the bubble represents a third measure.

Set the Position of the First Slice in a Current Default Pie Chart

You can specify the angle in a pie chart where the first pie slice starts. You can also change the direction of the slices so they appear clockwise or counter-clockwise.

The default starting position of the first slice is **90**, which displays the first slice beginning at the 12 o'clock position. By default, the slices appear clockwise around the pie, so a starting position of **90** displays the first slice at the 12 o'clock position, a starting position of **180** displays the first slice at the 9 o'clock position, and so on.

Procedure

1. Select the pie chart object.
2. In the **Properties** pane, under **General**, beside the **First Slice Angle** property, enter the angle at which you want the first slice to appear.
3. To change the directions in which slices appear, change the **Slice Direction** property.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

“Pie Charts” on page 90

Pie charts are useful for highlighting proportions.

Creating a Donut Chart from a Current Default Pie Chart

You can add a hole to the middle of your pie chart to create a donut chart.

About this task


You can display something in the hole of donut charts, such as a company logo or the legend.

Procedure

1. Select the pie chart object.
2. In the **Properties** pane, under **General**, set the **Hole size (%)** property to the percentage of the pie that you want the hole to take up.

Tip: You can select a value from the **Hole size (%)** list or type a value that is not listed.

3. To display the legend in the donut hole, do the following steps:
 - a. Select the chart.
 - b. In the Properties window, double-click the **Legend** property.
 - c. In the **Position** box, click the **Advanced** radio button and then click the ellipsis button.
 - d. In the **Position** box, click the **Center** and **Middle** icons.
 - e. In the **Anchor** box, click the menu and select **Relative to Chart Body**.
 - f. Click **OK** twice.

4. To display an image in the donut hole, do the following steps:
 - a. Click the **Unlock** icon  to unlock the report.
 - b. Click the chart body. In the Properties window, **Properties - Chart Body** appears.
 - c. Double-click the **Background Effects** property.
 - d. Select the **Images** check box.
 - e. Under URL, click **Browse** and select the image that you want to display in the donut hole.
 - f. Under **Position**, click the **Align Middle Center** icon.
 - g. Click **OK**.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

“Pie Charts” on page 90

Pie charts are useful for highlighting proportions.

Pull Out Pie Slices in a Current Default Pie Chart

You can highlight pie slices by pulling them out from the rest of the pie. For example, the following chart shows revenue by product line with slices of less than 1,000,000,000 in revenue pulled out by 25%.





Figure 25. Exploding slices in a pie chart

Procedure

1. Select the pie chart object.
2. In the **Properties** pane, under **General**, double-click the **Exploded Slices** property.
3. In the **Exploded Slice** dialog box, click the new button .

4. In the **Exploded amount** box, type the percentage by which the slice should appear away from the rest of the pie.
0% displays the pie slice in the pie; 100% displays the pie slice as far out from the rest of the pie as possible.
5. Define which slice to pull out:
 - To select a slice to pull out using its slice index, under **Exploded slice**, click **Slice number** and type the slice number.
The slice number refers to the order of the slice in the legend. In the previous example, Camping Equipment has a slice number of 1 and Personal Accessories has a slice number of 5.
 - To select a slice to pull out using a calculation, under **Exploded slice**, click **Expression** and click the ellipsis beside the **Expression** box to define an expression.
In the previous example, the expression that defines which slices to pull out is as follows: **[Query1].[Revenue] < 100000000**.
The slice definitions appear in the **Exploded Slices** list.
6. To pull out other slices, repeat steps 3 to 5.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83
IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.


“Pie Charts” on page 90
Pie charts are useful for highlighting proportions.

Define the Cumulation Line in a Current Default Pareto Chart

The cumulation line on a Pareto chart displays the percentage of the accumulated total of all the columns or bars. For example, if your chart displays revenue by product line by year, the cumulation line at the second year's column would be the total revenue of the first and second years.

You can customize the appearance of the cumulation line and its data points.

Procedure

1. Select the Pareto chart.
2. To hide or show the cumulation line, in the **Properties** pane, under **Chart Annotations**, set the **Cumulation Line** property.
3. To customize the cumulation line, click the cumulation line icon , and in the **Properties** pane, under **General**, set the following properties:
 - **Line Styles** defines the cumulation line color, style, and weight.
 - **Cumulation Label** defines the label in the legend for the cumulation line. You can use the default label from the data source or type a custom label. The color and marker shape of the cumulation line still appears in the legend when this property is set to **None**.
 - **Data Points** defines whether to show or hide data points along the cumulation line, whether to show or hide data point borders, the color of data point borders, and the data point size and shape.
 - **Data Labels** specifies whether to show or hide the labels for the data points along the cumulation line.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83
IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

“Pareto Charts” on page 99


Pareto charts help you to improve processes by identifying the primary causes of an event. They rank categories from the most frequent to the least frequent. These charts are frequently used for quality control data, so that you can identify and reduce the primary cause of problems.

Define the Cumulation Line in a Legacy Pareto Chart

The cumulation line on a Pareto chart displays the percentage of the accumulated total of all the columns or bars. For example, if your chart displays revenue by product line by year, the cumulation line at the second year's column would be the total revenue of the first and second years.

You can customize the appearance of the cumulation line and its data points.

Procedure

1. Select the Pareto chart.
2. To hide or show the cumulation line, in the **Properties** pane, under **Chart Annotations**, set the **Cumulative Line** property to **Show**.
3. To customize the cumulation line, click the cumulation line icon  and in the **Properties** pane, under **General**, set the following properties:
 - **Cumulation Axis** displays or hides the cumulation line's axis on the right of the Pareto chart.
 - **Cumulation Label** displays or hides the cumulation line label in the legend. The color and marker shape of the cumulation line still appears in the legend when this property is set to **No**.
 - **Line Styles** defines the cumulation line color, style, and weight.
 - **Marker Size (pt)** defines the size of the markers along the cumulation line in points.
 - **Marker Shape** defines the shape of the markers along the cumulation line.
 - **Values** specifies whether to show or hide the values for the markers along the cumulation line.
 - **Value Location** defines the location of the marker values.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83
IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

“Pareto Charts” on page 99

Pareto charts help you to improve processes by identifying the primary causes of an event. They rank categories from the most frequent to the least frequent. These charts are frequently used for quality control data, so that you can identify and reduce the primary cause of problems.

Insert a Microchart into a Crosstab

You can use microcharts to improve the visualization of data in crosstabs.

Procedure

1. Select a crosstab row or column.

2. From the right-click menu, click **Insert Chart for Row Data** or **Insert Chart for Column Data**.
3. From the **Insert Chart** dialog box, select a chart and click **OK**.
4. Specify the data to plot in the microchart.
The chart automatically plots the data in the specified rows or columns. You can change this if necessary.

Customize a Current Default Bullet Chart

After you create a bullet chart, you can customize the shape, color, and size of the bullet and target indicators.

By default, the bullet chart includes three gray colored regions in the background. You can edit the colored regions (**Properties** pane, **Colored Regions**).

Procedure

1. Select the bullet chart object.
2. To change the shape, color, and size of the bullet or target, do the following:
 - a. In the **Properties** pane, under **General**, double-click the **Bullet Indicators** property.
 - b. Under **Bullet**, specify how to show the bullet.
The **Bar width** setting specifies the width of the bullet bar as a percentage of the space available. For example, if you specify 50 percent, the bar uses half of the space available. If you specify 100 percent, the bar uses all the available space.
 - c. Under **Target**, specify how to show the target.
3. To change the chart orientation, in the **Properties** pane, under **General**, set the **Chart Orientation** property.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

“Bullet Charts” on page 97

Bullet charts are a variation of bar charts. They compare a featured measure (the bullet) to a targeted measure (the target). They also relate the compared measures against colored regions in the background that provide additional qualitative measurements, such as good, satisfactory, and poor.

Related tasks:

“Add Colored Regions in a Current Default Chart” on page 121

You can define colored regions in the body of a chart. For example, you can divide the background of a scatter chart into quadrants and color each quadrant.

Changing the number of hotspots in a chart

To improve performance, you can limit the number of hotspots that are generated for Report Studio charts.

About this task

A hotspot in a chart appears when you pause a pointer over it. For example, a hotspot on a drill-down symbol or a tooltip gives details about the column, line, or pie slice. The browser response time increases with the number of hotspots. When

charts with many members are generated, the hotspots can become an additional burden for the system resources, which can freeze the browser.

When you limit the number of hotspots, priority is given to items such as axis labels and legend labels before individual graphical elements such as bars, pie slices, and so on. Depending on the number of items in a chart and the setting for maximum number of hotspots, some axis items may have hotspots while other axis items and all graphical elements do not, or all axis items and some graphical elements may have hotspots while other graphical elements do not.

The maximum hotspot setting in Report Studio overrides the default set by the administrator. For more information, see the *IBM Cognos Business Intelligence Administration and Security Guide*.

Procedure

1. Select the chart object.
2. In the **Properties** pane, under **Miscellaneous**, specify a number for the **Maximum Hotspots** property.

Create a Drill-up and Drill-down Chart

If you use a dimensionally-modeled data source, you can create a chart that allows you to drill down to lower-level data or drill up to higher-level data.

Drilling up and down allows you to view more general or more detailed information on your data within a predefined dimensional hierarchy.

This is an example of a dimensional hierarchy:

Years - Year - Quarter - Month

Before you begin

Before you begin, ensure that you are using a dimensionally-modeled data source.

Procedure

1. Open a chart that uses a dimensionally-modeled data source.
2. From the **Data** menu, click **Drill Behavior**.
3. On the **Basic** tab, under **Report output drill capabilities**, select the **Allow drill-up and drill-down** check box.

By default, the system determines which items can be drilled on based on the dimensional structure.

On the **Basic** tab, you can make drilling unavailable for any data item by selecting the item in either the **Disable drill-up for** box or the **Disable drill-down for** box.

On the **Advanced** tab, you can change the drill-up or drill-down behavior for any parameter by selecting the parameter and then choosing one of the desired behaviors.

Results

The chart generates links for any item that can be drilled down on.

You can drill down or drill up by right-clicking and choosing the action from the context menu. The menu items are unavailable if an item cannot be drilled up or down on.

Related tasks:

“Create a Drill-up and Drill-down Report” on page 322

You can link groups of data items from different queries so that when you drill up or drill down in one query, the data item also drills up or drills down in the linked queries.

Example - Creating Drill-through Access in a Legacy Chart

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a chart that shows the revenue for each product line and allows the reader to drill through from the revenue chart to view the product details for any item selected. You create a drill-through report to link two reports containing related information. You can then access related or more detailed information in one report by selecting a value in the chart. You create two reports: a target list report that contains the details for the item and a source report that contains the chart that shows the product line revenue.

Related concepts:

“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.


“Set Up Drill-through Access in a Report” on page 439

Set up drill-through access in a source report to link two reports containing related information.

Create the target report


This example has three parts: creating the target report, creating the source report, and defining the drill behavior.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **List** and click **OK**.
4. From the **Source** tab , expand **Sales and Marketing (query)**, **Sales (query)**, and **Product**.
5. Double-click the following data items to add them to the list:
 - **Product line**
 - **Product type**
 - **Product name**
 - **Introduction date**
 - **Product image**

Now you must create a filter to use as a drill-through parameter. A drill-through parameter begins and ends with a question mark (?) symbol.


6. Click the filters button .

7. Click the add button  and type the following in the **Expression Definition** window:
`[Sales (query)].[Product].[Product line]=?p_PL?`
8. Save the report as **Product Line Details**.

Create the Source Report

This example has three parts: creating the target report, creating the source report, and defining the drill behavior.


Procedure

1. Create a new report.
2. In the **New** dialog box, click **Chart** and click **OK**.
3. In the **Chart group** pane, click **Column**.
4. In the **Chart type** pane, click **Column**.
5. Click **OK**.
6. From the **Source** tab , expand **Sales and Marketing (query)** and then **Sales (query)**.
7. Expand **Sales fact** and drag **Revenue** to the **Measure (Y-axis)** drop zone.
8. Expand **Order method** and drag **Order method** to the **Series** drop zone.
9. Expand **Product** and drag **Product Line** to the **Categories (X-axis)** drop zone.

Define the Drill Behavior

This example has three parts: creating the target report, creating the source report, and defining the drill behavior.

Procedure

1. From the **Data** menu, click **Drill Behavior**.
2. On the **Basic** tab, under **Report output drill capabilities**, select the **Allow this report to be a package-based drill-through source** check box and click **OK**.
3. Right-click the chart object and click **Drill-Through Definitions**.
4. Click **New Drill Through**.
5. Under **Report**, click the ellipsis button.
6. Select the **Product Line Details** report you created and click **Open**.
7. Under **Action**, click **Run the Report**.
8. Under **Format**, click **HTML**.
9. Click the edit button .

Any existing drill-through parameters appear. You see the parameter you created for **Product Line Details**.
10. For item **p_PL**, under **Method**, click **Pass data item value**, and under **Value**, click **Product line**.
11. Save the chart as **Product Revenue**.
12. Run the report.

Results

The chart shows the product lines as clickable links. When you click a product line, the second report runs for that product line.

Example - Creating and Customizing a Metrics Range Legacy Chart

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are asked to create a chart that shows revenue compared to planned revenue by quarter by product line. You also want to highlight revenues that were below target.

This example has three parts: creating a metrics chart, customizing it, and customizing the legend labels.

Related concepts:



“Current Default Charts and Legacy Charts” on page 83

IBM Cognos Report Studio has a new default chart technology as of version 10.1.0.

Create a Metrics Range Chart

This example has three parts: creating a metrics range chart, customizing it, and customizing the chart legend labels.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **Chart** and click **OK**.
4. In the **Chart group** pane, click **Metrics Range**.
5. In the **Chart type** pane, click **Column Chart with Range Indicators** and click **OK**.
6. From the **Source** tab , expand **Sales and Marketing (query)**, **Sales (query)**, and **Sales fact**.
7. Drag **Revenue** to the **Actual (Y-axis)** drop zone.
8. Drag **Planned Revenue** to the **Target (marker)** drop zone.
9. Expand **Time dimension**, and drag **Quarter** to the **Categories (X-axis)** drop zone.
10. From the **Toolbox** tab , drag a query calculation to the **Tolerance (marker)** drop zone.
11. In the **Create Calculation** dialog box, type **Tolerance**.
12. In the **Expression Definition** box, type **[Planned revenue] * 0.1** and click **OK**.
13. Run the report and then pause the pointer over each bar to see the revenue for that quarter.

Customize the Chart

This example has three parts: creating the metrics range chart, customizing it, and customizing the legend labels.

Procedure

1. Select the chart body.
2. In the **Properties** pane, under **Target Markers**, ensure that the **Performance Pattern** property is set to **On Target**.
3. Double-click the **Marker Color** property, click **Lime** and click **OK**.
4. Set the **Upper Range Skew (%)** property to **0%**.

This option removes the upper tolerance line. In this example, you do not need to see the upper tolerance line because the revenue is always below the planned revenue target.
5. Ensure that the **Target Range (%)** property is set to **50%**.

This option sets the size of the range around the planned revenue target. The percentage you choose is the percentage of the tolerance measure. In this example, a 50% target range would display 50% of the tolerance calculation you created, which is 50% of 10% of planned revenue.
6. Double-click the **Target Color** property, click **Red** and click **OK**.
7. Double-click the **Target Marker Border Color** property, click **Green** and click **OK**.
8. Run the report.

Customize the Chart Legend Labels

This example has three parts: creating the metrics range chart, customizing it, and customizing the legend labels.

Procedure

1. Under the chart legend select **Marker**.
2. In the **Properties** pane, under **Text Source**, double-click the **Text** property.
3. Replace the text in the **Text** dialog box with **Planned revenue** and click **OK**.
4. Under the chart legend select **Tolerance**.
5. In the **Properties** pane, under **Text Source**, double-click the **Text** property.
6. Replace the text in the **Text** dialog box with **Tolerance: 10% of planned revenue** and click **OK**.
7. Under the chart legend, select **Range**.
8. In the **Properties** pane, under **Text Source**, double-click the **Text** property.
9. Replace the text in the **Text** dialog box with **Planned revenue range = 50%** and click **OK**.
10. Run the report.

Results

The report now shows customized legend labels for the markers, tolerances, and ranges as shown in the following chart.




Figure 26. Metrics range chart with customized legend labels for the markers, tolerances, and ranges

Adding a Metric Studio Diagram to a Report

You can add IBM Cognos Metric Studio impact or custom diagrams in your reports. Impact diagrams show cause-and-effect relationships between metrics. Custom diagrams allow you to monitor your metrics using a predefined visual representation, such as a process diagram or strategy map.

The diagrams are added as images within your report.

You can add a diagram in the following ways:

- as a static image with the **Metric Studio Diagram** object
- as a dynamic image from a metrics package

You can also add range indicator charts.


You must first create custom diagrams in Metric Studio before you can add them in an IBM Cognos Report Studio report. Impact diagrams are automatically created in the metrics package. For information about creating Metric Studio diagrams, see the *Metric Studio User Guide*.

Add a Static Metric Studio Diagram to a Report

You insert the image using the diagram identifier from Metric Studio. The identifier is converted to an image URL and the image appears in your report output.

Because the diagram is a static image, any changes to the metrics will not appear in the diagram image within your report.

Procedure

1. From the **Toolbox** tab , drag a **Metric Studio Diagram** object to the report.
2. Select the Metric Studio diagram object.
3. In the **Properties** pane, paste the diagram identifier in the **Diagram Identifier** box.

Tip: Copy the identifier from Metric Studio (**Diagrams** tab, **View the Diagram Identifier** button in the **Actions** column).

4. In the **Description** box, type a description for the diagram.
5. If you want to make the diagram image accessible, in the **Alternate Text** box, type a description for the image.

Related tasks:

“Add Alternate Text to Images and Charts” on page 488


You can add alternate text for images, maps, and charts to make your reports accessible. When a screen reader encounters one of these objects, it reads the alternate text that you added to the object.

Add a Data-driven Metric Studio Diagram to a Report

If you use a metrics package (which is a relational data source), you can insert a Metric Studio diagram directly from the **Toolbox** tab. Because you add the diagram from the metrics store, any changes to the metrics will appear in the diagram image when you re-run your report.

If you add diagrams from the **Metric History** table of the metrics package, one diagram is added for each metric per time history. As a result, your report could contain a large number of diagrams. To improve the performance of your report, consider adding a filter to limit the time period.

Procedure

1. Open IBM Cognos Report Studio with a metrics package.
2. From the **Toolbox** tab , insert a diagram query item to the report.
3. If you want to make the diagram image accessible, select the image object for the diagram, and in the **Alternate Text** box, type a description for the image.

Related tasks:

“Add Alternate Text to Images and Charts” on page 488

You can add alternate text for images, maps, and charts to make your reports accessible. When a screen reader encounters one of these objects, it reads the alternate text that you added to the object.

Chapter 7. Extensible visualizations

You can use extensible visualizations in IBM Cognos reports to visualize data.

Visualizations must be imported into IBM Cognos Administration. The Visualization Gallery is empty until your administrator imports the visualizations and makes them available to you. Your administrator can set permissions to restrict access to only certain report authors.

The visualizations come from the site AnalyticsZone (<https://www.analyticszone.com>). For more information about administration and visualizations, see the *IBM Cognos Business Intelligence Administration and Security Guide*.

Because visualizations are extensible, they can be customized by an author with the necessary skills. You can create client-side visualizations that report consumers can run when they are not connected to the web. You can also use visualizations on mobile devices.

Some of the visualizations that you can add to your reports are treemaps, heatmaps, packed bubble visualizations, and network diagrams.

You can set properties that are available for each visualization type. These properties are determined by the visualization definition. Typically, you can set such properties as width, height, animation effect, and fixed-axis scaling.

Extensible visualizations support all Active Report interactivity. For example, you can use Active Report controls to dynamically filter visualizations to view only the data that you want to analyze.

For more information about visualizations and their uses, go to Many Eyes® (<http://www-958.ibm.com>).

Attention: If you use Microsoft Internet Explorer to view visualizations, you must have Microsoft Silverlight 5 installed on your computer. Firefox or iPad users do not need Silverlight.

Adding a visualization to a report

You can add a visualization to a report to efficiently represent your data.

Before you begin

Your administrator must make the visualizations available in the Visualization Gallery.

If you use Microsoft Internet Explorer to view visualizations, you must have Microsoft Silverlight 5 installed on your computer. Firefox or iPad users do not need Silverlight.

About this task




You add data to a visualization by inserting data items in drop zones.

When you add a visualization to an IBM Cognos Active Report, you can choose to render visualizations on the IBM Cognos server or on the client. When you choose to render visualizations on the client, additional drop zones appear for extra categories or values when all the required drop zones contain data items. You can use extra categories and extra values to filter data or set variables. Extra items are not visible in the visualization.

When working with dimensional data sources, if the visualization does not contain a measure against which to plot data, you must provide one. For example, if you add a single member to the values drop zone, such as '2012', the default measure drop zone appears in which you must insert a measure.

Attention: The supported properties for a visualization are determined by the visualization definition.

Procedure

1. Create a new report or open an existing report.
2. From the **Toolbox** tab , drag a **Visualization** icon  to the work area.
3. From the Visualization Gallery, select a visualization and click **OK**.
4. From the **Source** tab , drag items to the appropriate location in the data container.
5. Run the visualization.

Adding a treemap visualization

You can use a treemap visualization in reports to identify patterns and exceptions.

Treemaps show relationships among large numbers of components by using size and color coding in a set of nested rectangles.

A treemap that is colored by category identifies the level 1 category by color. The sizes of the rectangles represent the values. In a treemap that is colored by value, the sizes of the rectangles represent one of the values and the color represents a second set of values.

Attention: The supported properties for a visualization are determined by the visualization definition.




Figure 27. A treemap visualization

Before you begin

Your administrator must make the visualizations available in the Visualization Gallery.

If you use Microsoft Internet Explorer to view visualizations, you must have Microsoft Silverlight 5 installed on your computer. Firefox or iPad users do not need Silverlight.

About this task




You add data to a visualization by inserting data items in drop zones.

When you add a visualization to an IBM Cognos Active Report, you can choose to render visualizations on the IBM Cognos server or on the client. When you choose to render visualizations on the client, additional drop zones appear for extra categories or values when all the required drop zones contain data items. You can use extra categories and extra values to filter data or set variables. Extra items are not visible in the visualization.

When working with dimensional data sources, if the visualization does not contain a measure against which to plot data, you must provide one. For example, if you add a single member to the values drop zone, such as '2012', the default measure drop zone appears in which you must insert a measure.

Attention: The supported properties for a visualization are determined by the visualization definition.

Procedure

1. From the **Toolbox** tab , drag a **Visualization** icon  to the work area.
2. From the Visualization Gallery, select a Treemap icon:
 - If you are plotting a single measure, select a treemap colored by category.
 - If you are plotting two measures, select a treemap colored by value.
3. Click **OK**.
4. From the **Source** tab , drag items to the appropriate location in the data container:
 - a. Under **Values**, drag items to define the size and color of the rectangles to **Size** and **Color**.
 - b. Under **Categories**, drag items to the different levels. Each level represents the category within which the subsequent levels are nested. For example, the levels might be Year, Product Line, and Product Type.

Adding a heatmap visualization

Heatmaps use colors to represent the individual values that are contained in a matrix.

Similar to treemaps, you can use heatmaps to identify patterns and exceptions. Unlike treemaps, the sizes of the rectangles are not proportionate to values.




Figure 28. A heatmap visualization

Before you begin

Your administrator must make the visualizations available in the Visualization Gallery.

If you use Microsoft Internet Explorer to view visualizations, you must have Microsoft Silverlight 5 installed on your computer. Firefox or iPad users do not need Silverlight.

About this task




You add data to a visualization by inserting data items in drop zones.

When you add a visualization to an IBM Cognos Active Report, you can choose to render visualizations on the IBM Cognos server or on the client. When you choose to render visualizations on the client, additional drop zones appear for extra categories or values when all the required drop zones contain data items. You can use extra categories and extra values to filter data or set variables. Extra items are not visible in the visualization.

When working with dimensional data sources, if the visualization does not contain a measure against which to plot data, you must provide one. For example, if you add a single member to the values drop zone, such as '2012', the default measure drop zone appears in which you must insert a measure.

Attention: The supported properties for a visualization are determined by the visualization definition.

Procedure

1. From the **Toolbox** tab , drag a **Visualization** icon  to the work area.
2. From the Visualization Gallery, select the **Heatmap** icon and click **OK**.
3. From the **Source** tab , drag items to the appropriate location in the data container:
 - a. Under **Values**, drag a measure or a single value to define the color shading of the rectangles.
 - b. Under **Categories**, drag items to the Y Category and X Category.

Tip: Ensure that the items in the Y Category and X Category come from different dimensions.

Adding a packed bubble visualization

A packed bubble visualization is similar to a bubble chart in which the bubbles are tightly packed rather than spread over a grid. You can use a packed bubble visualization to display a large amount of data in a small space.




Figure 29. A packed bubble visualization

Before you begin

Your administrator must make the visualizations available in the Visualization Gallery.

If you use Microsoft Internet Explorer to view visualizations, you must have Microsoft Silverlight 5 installed on your computer. Firefox or iPad users do not need Silverlight.

About this task




You add data to a visualization by inserting data items in drop zones.

When you add a visualization to an IBM Cognos Active Report, you can choose to render visualizations on the IBM Cognos server or on the client. When you choose to render visualizations on the client, additional drop zones appear for extra categories or values when all the required drop zones contain data items. You can use extra categories and extra values to filter data or set variables. Extra items are not visible in the visualization.

When you work with dimensional data sources, if the visualization does not contain a measure against which to plot data, you must provide one. For example, if you add a single member to the values drop zone, such as '2012', the default measure drop zone appears in which you must insert a measure.

Attention: The supported properties for a visualization are determined by the visualization definition.

Procedure

1. From the **Toolbox** tab , drag a **Visualization** icon  to the work area.
2. From the Visualization Gallery, select the **Packed Bubble** icon and click **OK**.
3. From the **Source** tab , drag items to the appropriate location in the data container:
 - a. Drag a measure or a single value to the data container, under **Values**.
 - b. Under **Categories**, drag an item to plot as the bubbles.
 - c. Under **Series**, drag an item to apply as a category. Each item in the category gets a different color from the color palette.

Adding a network diagram

You can create a network diagram in reports. The nodes data container defines the items that you want to link together. The links data container defines relationship between the items that you want to link together.




Figure 30. A network diagram in an active report showing employees by region

Before you begin

Network node drop zones only take numeric data items. Not all data sources have the appropriate data to create a network diagram.

Your administrator must make the visualizations available in the Visualization Gallery.

If you use Microsoft Internet Explorer to view visualizations, you must have Microsoft Silverlight 5 installed on your computer. Firefox or iPad users do not need Silverlight.

About this task




You add data to a visualization by inserting data items in drop zones.

When you add a visualization to an IBM Cognos Active Report, you can choose to render visualizations on the IBM Cognos server or on the client. When you choose to render visualizations on the client, additional drop zones appear for extra categories or values when all the required drop zones contain data items. You can use extra categories and extra values to filter data or set variables. Extra items are not visible in the visualization.

When working with dimensional data sources, if the visualization does not contain a measure against which to plot data, you must provide one. For example, if you add a single member to the values drop zone, such as '2012', the default measure drop zone appears in which you must insert a measure.

Attention: The supported properties for a visualization are determined by the visualization definition.

Procedure

1. From the **Toolbox** tab , drag a **Visualization** icon  to the work area.
2. From the Visualization Gallery, select the Network diagram icon and click **OK**.
3. From the **Source** tab , drag items to the appropriate location in the data container:
 - a. In the **Nodes1** data container, drag items to **Node (Numeric)** and **Name**. The nodes data container defines the items that you want to link together, such as Employees, defined by an employee code.
 - b. In the **Links1** data container, drag items to **From node (Numeric)** and **To node (Numeric)**. The links data container defines relationship between the items that you want to link together, such as Employees and Managers.

Related tasks:

“Example - Network diagram visualization” on page 222

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a visualization in IBM Cognos Active Report that shows the hierarchies of employee by region.

Visualization properties

The properties that you can set for each visualization affect how you work with visualizations that are inserted in a report.

All extensible visualizations have properties in common and properties that are specific to each visualization. Properties that are specific to a visualization are defined by the visualization author in the visualization definition. By default, properties that are defined by the visualization author appear in a group that is named Custom in the Properties window, unless the author created property groups in the visualization definition.

To set properties for multiple visualizations, press Ctrl while you click the visualizations in the report. When multiple visualizations are selected, only the common properties appear in the Properties window.

Choosing where visualizations are rendered

When you add a visualization to an IBM Cognos Active Report, you can choose to render the visualization on the IBM Cognos server or on the client.

About this task

Visualizations that are added to regular reports are always rendered on the Cognos server. Visualizations that are rendered on the Cognos server are rendered as static images. Client-side visualizations are rendered as JavaScript code. Report size and performance are affected by whether visualizations are rendered on the server or on the client. For example, static images might increase the report size when there are many of them, but performance might be better.

Some visualization properties are available for only one of the render methods, and other properties are modified when you change the render method. For example, the **Container Filter** property, extra values drop zones, and extra categories drop zones are not supported when you choose to render visualizations on the Cognos server.

If you want to enable client-side filtering in the visualization, you must choose to render the visualization on the client.

Note: In the visualization definition, visualization authors can specify to render a visualization only as JavaScript or only as a static image. When a visualization supports only one output type, the visualization property **Render Method** is not available. In addition, visualizations that can be rendered only in JavaScript do not appear in the Visualization Gallery when you author regular reports.

Procedure

1. In the active report, select the visualization.
2. In the Properties window, click the **Render Method** property and choose the render method that you want.

Resizing a visualization

You can change the size of a visualization.

Procedure

1. Click and drag the lower right corner of the visualization.
2. To maintain the aspect ratio, press the Shift key while you resize the visualization.

You can view the changing height and width of the resized visualization in the **Properties** pane, under **Positioning**.

Changing the nesting order

When you create a visualization in an IBM Cognos Active Report, you can change the nesting order so that extra items are ordered properly in the query. If the items are not ordered properly in the query, the report might not run.

About this task

Extra items are data items that are used for filtering or setting variables. These items are not visible in the visualization. By default, extra categories are nested below other categories, so as not to affect sorting. However, if the extra categories are from the same dimension as a category, they must be in the correct hierarchical order: Years, Quarters, and Months. You can change the nesting order.

For example, you have Quarters and Months as categories. You then add Years as an extra category. You add an Active Report control and connect to Years as a filter. You might have to change the nesting order of the data items for the report to run.

Note: Extra items are available only when you choose to render the visualization on the client. You cannot add extra items to a visualization when you choose to render the visualization on the IBM Cognos server.

Procedure

1. Select the data container that contains the data set in which you want to change the nesting order.
2. From the **Properties** pane, under **General**, click **Change Nesting Order**.
3. In the Change Nesting Order window, select the extra category and use the arrow icon to reorder it.

Tip: You can click **Show Data Container** to view the new nesting order when the report is run.

Related tasks:

“Sorting a category field by a measure in visualizations” on page 178

You can sort a category field by a measure in visualizations that are inserted in IBM Cognos Active Report.

Specifying the range values that are displayed

You can specify the range of values that you want to display in a visualization.

About this task

You can specify the range of values and categorical data that is displayed in visualizations. Some of the options that are available depend on whether you choose to render the visualization on the IBM Cognos server or on the client. When the visualization is rendered on the Cognos server, more choices are available when the visualization is in a master-detail relationship.

To control the range of values that is displayed, the following choices are available to calculate the minimum and maximum values of the range.

- All data

With this choice, minimum and maximum values are calculated to span the values of the inserted measure.

When the visualization is added to an active report, the values are calculated to span the values of all controls that are connected to the visualization.

Note: In visualizations that are added to active reports, the aggregation method that is specified in the **Rollup Method** property also affects the range of values.

- All detail data

This choice is available only when the visualization is in a master-detail relationship and is rendered on the Cognos server. With this choice, the range of data that is displayed is the same in each detail visualization.

- Filtered data

This choice is available only when the visualization is rendered on the client.

With this choice, minimum and maximum values are calculated from values that users select in Active Report controls that are connected to the visualization.

- Specified values

With this choice, you specify the minimum and maximum values that you want to display in the visualization.

Note: The minimum and maximum values that are displayed in the visualization might differ from the values that you specify. For example, if you specify a range of 0 to 195, IBM Cognos BI might display a range of 0 to 200.

To specify the categorical data that is displayed, the following choices are available.

- All data

This choice is available only when the visualization is rendered on the client. With this choice, all categorical data that spans the values of all Active Report controls that are connected to the visualization is displayed.

- Filtered data

This choice is available only when the visualization is rendered on the client. With this choice, only the filtered data is shown in the legend and on axes.

The choice that you make for displaying categorical data can affect elements in the visualization, such as the legend and axes. For example, when all data is selected, all legend items are always shown in the visualization, and the color of each legend item stays the same in the visualization. When a category is inserted on an axis, space is reserved on the axis for all data. When filtered data is selected, the color of each legend item can change when users select different values in a control that is linked to the visualization. When a category is inserted on an axis, the axis shows only the values that are selected in the control.

Procedure

1. To specify the categorical data that is displayed, follow these steps.
 - a. In the visualization data container, select the category that you want.
 - b. In the Properties pane, click the **Category Range** property and select the choice that you want.
2. To specify the range of values that is displayed, follow these steps.
 - a. In the visualization data container, click the data item in the **Values** section that represents the values in the visualization. For example, in a packed bubble visualization, click the data item that is inserted in the **Size** box.
 - b. In the Properties pane, double-click the **Value Range** property.
 - c. In the **Range type** box, click one of the available choices.
 - d. If you clicked **All data**, **Filtered data**, or **All detail data**, and you want the range of values to include zero, select the **Range includes zero** check box.
 - e. If you clicked **Specified**, type the minimum and maximum values of the range in the **Minimum** and **Maximum** boxes.

Related tasks:

“Choosing where visualizations are rendered” on page 172

When you add a visualization to an IBM Cognos Active Report, you can choose to render the visualization on the IBM Cognos server or on the client.

“Sorting a category field by a measure in visualizations” on page 178

You can sort a category field by a measure in visualizations that are inserted in IBM Cognos Active Report.

Summarizing data in a visualization

When a visualization is added to an IBM Cognos Active Report, you can specify how the data is summarized when users select multiple values in a control that filters the data in the visualization.

About this task

You can specify how data is summarized in a visualization only when you choose to render the visualization on the client. The **Rollup Method** property is not available when you choose to render a visualization on the IBM Cognos server.

In addition to summarizing data, the aggregation method that you choose affects the range of values that is displayed. For example, if the visualization is filtered by a single select control, Maximum is usually the appropriate aggregation method. With this choice, the range of values is based on the maximum of all values across the filtered items.

Set the aggregation method to the aggregation type of the data item. For example, if the data item is Margin, set the aggregation method to Average. When you are using an OLAP data source, IBM Cognos BI cannot retrieve the aggregation type of a measure. As a result, IBM Cognos BI sets the aggregation method to Total by default.

Procedure

1. In the visualization data container, in the **Values** section, click the box that represents the data values in the visualization. For example, in a heatmap, click the **Color** box.
2. In the Properties pane, click the **Rollup Method** property and select the aggregation method that you want to use to summarize data in the visualization.

Populating a visualization with data from the visualization definition

In IBM Cognos Report Studio, you can populate a visualization with data that is specified in the visualization definition instead of adding data items from a package.

About this task

You can use data that is specified in the visualization definition to test a visualization before you add your own data. Using data from the visualization definition is also a way to bring external data into a visualization.

Procedure

1. Select the visualization.
2. In the Properties pane, double-click the **Use Embedded Data** property.
3. Select the check box of the data container for which you want to use data that is defined in the visualization specification.

Tip: Some visualizations have more than one data container.

Results

The data container is removed from the visualization. The data container is not required when the visualization is using data from the visualization definition.

Updating visualizations

Update visualizations when a change was made to the visualization definition.

About this task

You can update the visualizations in a report by opening the report in a new Report Studio window. In an existing Report Studio window, you can update visualizations by clicking **Update Visualizations** in the **Tools** menu.

If any part of a visualization is invalidated by changes that were made to the visualization definition, the invalidated part is removed. For example, if a field is renamed, the data items in the field are removed. You must add the data items to the renamed field for the visualization to run.

For visualizations that are rendered on the client, if you do not update visualizations when the visualization definition is changed, the old visualization definition is used when you run the report. Visualizations that are rendered on the IBM Cognos server always use the latest visualization definition. As a result, server-side visualizations might not run if they are not updated.

Procedure

1. Open the report that contains the visualizations that you want to update.
2. Click **Tools > Update Visualizations**.

Converting visualizations from one type to another

You can convert a visualization from one type to another type.

About this task

The following list describes the conversion process.

- Data items are mapped to fields with the same name.
- If no field with the same name exists, the first field of the same type is used. Value fields are mapped to value fields. Category fields are mapped to category fields. Category fields that are ID fields are only mapped to other category fields that are also ID fields.
- In active reports, for visualizations that are rendered on the client, extra values and category items are used to fill any empty fields in the converted visualization.
If you convert to a visualization that has fewer fields than the original visualization, the extra data items are kept as extra values or category items.
- Common properties that are not specific to visualizations, such as **Data format**, are preserved.
- No warnings appear for properties that are dropped during the conversion.

When you convert a visualization to a new visualization type, you can preserve properties that have the same ID and the same type. Or you can choose to use only the default properties of the new visualization.

If you convert a visualization to a visualization type that has more fields than the original visualization, you must populate the empty fields in the converted visualization. For example, if you convert a column chart to a combination chart that has columns and lines, there are empty fields for the line data container.

You cannot convert a visualization to a current default chart and vice versa.

Procedure

1. Right-click a visualization and click **Convert Visualization**.
2. Select a new visualization type.
3. To preserve properties that have the same ID and the same type, under **Visualization properties**, click the **Preserve existing visualization properties** radio button.
4. To use only the default properties of the visualization type that you are converting to, under **Visualization properties**, click the **Use new visualization default properties** radio button.
5. Click **OK**.

Sorting a category field by a measure in visualizations

You can sort a category field by a measure in visualizations that are inserted in IBM Cognos Active Report.

About this task

In visualizations, you can sort a data item by the overall totals or by the totals in the context of an extra category. While Cognos Active Report supports client-side filtering for visualizations, sorting always occurs on the Cognos server. As a result, you must construct the visualization so that the underlying crosstab reflects your filtering options and provides the correct sorting. As you construct the visualization, you can view the underlying crosstab by right-clicking the visualization data container and clicking **Show Container Data**.

This task describes how to maintain the sorting of a category by a measure when the visualization is filtered by a single selection control. For example, an active report contains a data drop-down list control with Quarter as the data item, and a clustered bar visualization that shows quantity that is sold by retailer type. In the visualization, Retailer type appears as the series, Quantity appears as the measure, and no data item is specified for the categories. You want to sort the visualization by quantity that is sold, and filter by quarter. To have the sorting applied for each quarter, place Quarter on the same edge as Retailer type in the underlying crosstab, which is accomplished by inserting the Quarter data item as an extra category for the series. In addition, Quarter must be nested outside of Retailer type in the underlying crosstab. Otherwise, Retailer type is sorted according to the quantity that is sold for all quarters.

This technique does not work when a visualization is filtered by multiple controls, or by a control that accepts multiple selections, such as a check box group control.

Procedure

1. In the visualization, select the category field that you want to sort. In the preceding example, select Retailer type.
2. In the **Properties** pane, set the **Category Range** property to **Filtered Data**.
3. Double-click the **Sorting** property.

4. In the **Data Items** box, drag the measure that you want to sort the category by to the **Sort List** box. In the preceding example, drag Quantity.
5. To specify the sort order, click the **Sort Order** icon.
6. Click **OK**. A warning message appears that informs you that sorting is applied when the report is run, and does not reflect client-side filtering.
7. Click **OK**.
8. Select the clustered bar data container.
9. In the **Properties** pane, double-click the **Nesting Order** property, and change the nesting order of the extra category as needed. In the preceding example, for the series, move Quarter above Retailer type.
10. Optional: To view the data in the underlying crosstab, click **Show Container Data**. The data in the crosstab is sorted by the sort order that you specified in step 5.
11. Click **OK**.

Related tasks:

“Specifying the range values that are displayed” on page 174

You can specify the range of values that you want to display in a visualization.

“Changing the nesting order” on page 173

When you create a visualization in an IBM Cognos Active Report, you can change the nesting order so that extra items are ordered properly in the query. If the items are not ordered properly in the query, the report might not run.

Chapter 8. Maps

IBM Cognos Report Studio provides a set of maps that you can use to represent tabular data in a spatial context. For example, on a map of the world, countries and regions can be colored to represent the level of revenue.


Maps are not supported for reports run in Microsoft Excel format.

The Report Studio Map Object

Maps are most often used to show geographical areas, but they can be used to show other spatial information, such as a floor plan in a building, seats in an airplane, or parts of the human body.

Maps are similar to crosstabs in the way their data is organized. The display is different, but maps show the intersection of data the same ways as crosstabs; for example, you can see the revenue for golf equipment in Canada.

A map in IBM Cognos Business Intelligence consists of a collection of layers. Each layer contains different information and acts like a transparency that is placed on top of the map. Each layer adds more information to the map. For example a map of the world may contain information related to countries or regions on one layer and information related to cities on another level.



IBM Cognos Report Studio maps provide the following three types of layers:


- **Region layer**
Specifies the regions on a map to be differentiated according to values in the data source. For example, to show the revenue level for each country and region on a map of the world, choose Country and Region as the region layer and then specify that the color of each country and region is based on the revenue value for that country and region. Areas can be set up for drilling through to other reports.
- **Point layer**
Specifies the points to be placed on a map. The color and size of the points is based on the data that you select. For example, you choose to show cities as points on a map and set the color of each point by revenue and the size of each point by profit. Points can be set up for drilling through to other reports.

- Display layer
You can show or hide items such as grid lines or capital cities. This layer is determined in the map file and not in the data source.

Note: If you intend to create CSV or XML output from your map, use only a point layer or a region layer. CSV and XML do not support the simultaneous use of both layers in the same map. Only one layer will be rendered in the output.

Parts of Map Reports

The following shows the parts of a map as they appear in the IBM Cognos Report Studio interface.



New maps in IBM Cognos BI 10.2.2

IBM Cognos Business Intelligence 10.2.2 contains new maps that replace the maps that are in previous releases.

If you have reports that were created in previous versions of IBM Cognos BI, and those reports contain maps, the maps are missing when you run the reports in IBM Cognos BI 10.2.2 or later. To resolve the problem, follow one of the choices below.

1. You can continue to use the maps that are in earlier versions IBM Cognos BI. Ask your administrator to copy the map files from the earlier version of IBM Cognos BI to the current version of IBM Cognos BI that you are using. The map files are found in the `install_location\maps` folder, and they have the file extension `.cmf`.

Tip: If you decide to continue to use the older maps, ask your administrator to delete the new maps to avoid confusion. The new maps in IBM Cognos BI 10.2.2 have file names that end with `_10_2_2.cmf`.

2. You can upgrade your reports so that they use the new maps by modifying the **Map & Layers** property of each map so that it references one of the new maps.

Related concepts:

“Additional Maps” on page 190

IBM Cognos supplies a set of standard maps that can be used directly with IBM Cognos Report Studio as well as IBM Cognos Map Manager.

Example - Create a Map Report

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are asked to show how revenue for the company is distributed throughout the world. This information can be shown in tabular format using a list report, but a map will create a more meaningful presentation. You decide to create a report that contains a map of the world showing the distribution of revenue by country and region.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **Map** and click **OK**.
4. In the **Choose Map** dialog box, in the **Maps** pane, expand the **World** folder and click **World**.
5. In the **Region layers** box, click **Countries and Regions + Territories**.
6. In the **Point layers** box, click **None**.
7. In the **Display layers** box, click **Oceans**.

Tip: You can select or deselect multiple display layers by Ctrl+clicking.

Tip: You can return to the **Choose Map** dialog box at any time by double-clicking the map background.

8. Drag the following data items to the map:
 - **Revenue** (in **Sales fact**) to the **Color** drop zone.
 - **Retailer country and region** (in **Retailer site**) to the **Location** drop zone.
9. Run the report.

Results




Figure 31. World map

Set Map Properties

When you select an element in a map, you can view its properties in the **Properties** pane. Some properties are dependent on the existence of other properties.

If you are familiar with using conditional variables, you can customize the map to change appearance or provide information in response to expressions or conditions.

When you change a map property, you usually do not see the change until you run the report. Changes to the properties of labels and titles are reflected immediately.

These are some of the properties you can change in maps. These properties are available when you select the map object, unless specified otherwise in the **Action to perform in the Properties pane** column.

Goal	Action to perform in the Properties pane
Hide or show the title, subtitle, footer, or axis title	Under Chart Titles , set the Title , Subtitle , Footer , or Axis Title property.
Hide or show the legend	Under Chart Annotations , set the Legend property.
Hide or show region and point layer values and labels on the map	Select the region or point layer. Under Chart Labels , double-click the Show Values property and select the options that you want. To hide overlapping labels, select the Hide overlapping labels check box.
Hide or show display layer labels on the map	Select the display layer. Under Chart Labels , double-click the Show Labels property and select the option that you want. To hide overlapping labels, select the Hide overlapping labels check box.

Goal	Action to perform in the Properties pane
Hide or show the border around the legend	Select the legend icon. Under Box , set the Borders property.
Change the border around the map object	Under Box , set the Border property.
Hide or show the tooltips Note: Some versions of Acrobat Reader do not support tooltips.	Under Chart Labels , set the Tooltips property.
Change the amount of white space around the map	Under Box , set the Padding or Margin property.
Change the default colors for all map elements	Under Color & Background , set the Background Color , Foreground Color , or Fill Effects property.
Change the font and the alignment of text	Under Font & Text , set the Font or Relative Alignment property. Tip: The 2011 Quarterly Sales Forecast sample report in the GO Sales (analysis) package includes text alignment. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.
Resize the map	Under Positioning , set the Size & Overflow property.
Change the font for the legend	Select the legend icon. Under Font & Text , set the Font property.
Change the format of values in the legend	Select the value in the region or point layer. Under Data , set the Data Format property.
Ignore data with no features	Under Data , set the Ignore Data with No Features property.
Specify the size of points	In the point layer, click the measure in the Size drop zone and set the Minimum Size and Maximum Size properties.
Add titles, subtitles, footers, or axis titles	Set the Title , Subtitle , Footer , or Axis Title property.

Procedure

1. Select the map object or map element to change:
 - To change general properties, such as size and color, click the map object.
 - To change specific map elements, such as a layer or title, click the element itself.

Tip: To cancel a selection, press the Esc key.


2. In the **Properties** pane, set the property value.
An ellipsis button indicates that a dialog box provides further options.

Note: You may have to scroll to see all the properties.

Example - Define Data Values for the Region Layer

The map that you created in the previous topic is not yet linked to a data source. You will now specify the data values from your data source that will determine the color of each region.

Procedure

1. From the **Source** tab , expand **Sales and Marketing (query)**, **Sales (query)**, and **Sales fact**.
2. Drag **Revenue** to the **Color** drop zone.
3. Expand **Employee by organization**.
4. Drag **Country or Region** to the **Location** drop zone.
5. Run the report.

Results




Figure 32. Map showing revenue by country or region

Match Data Values to Names in the Map File


If the **Ignore Data with No Features** property is set to **No**, then each object that is called from the data source must have a matching label in the specified layer of the map file. For example, if your data source has a country and region named United States and the layer in the map file labels the same country and region USA, then there is a mismatch that must be corrected. IBM Cognos Report Studio only makes you aware of a mismatch if each object in your data source does not have a corresponding label in the map file. If there are extra labels in the map file that do not have a match in the data source, the report will run without an error message.

A mismatch between your data and the map file must be corrected by the report author. It can not be corrected by a consumer of the map report at run time. There are two ways to correct a mismatch between your data and the labels in the map files. You can use IBM Cognos Map Manager to edit the labels in the layers of the map file, or you can use the dictionary property to create an alias for each

mismatched object. When you use the dictionary property, it resolves the mismatch only for a single report, and is not shared with other reports. If you intend to continue using a map with the same data source, it is best to edit the map in Map Manager so that the labels match the objects in your data source.

For information about using Map Manager, see the Map Manager *Installation and User Guide*.

Procedure


1. Select the map object.
The title bar of the **Properties** pane now shows the word **Map**.
2. In the **General** section of the **Properties** pane, double-click the **Dictionary** property.
3. Click the new button .
4. In the **Dictionary Entry** dialog box, click **Search**.
5. In the **Search string** box, type a word or part of a word for which to search.
For example, if you are searching for United States, type in part or all of the name.
6. In the **Search map layer** box, click the layer to search and click **Search**.
7. In the **Matching features** box, click the label to which to match your data source and click **OK**.
8. In the **Alias** box, type the name as it appears in the data source and click **OK**.
For example, if the country and region in your data source is named USA, type USA as the alias.

Note: To find out the name for the objects in your data source, run a list report. For example, you can run a list report to show the names of all the countries and regions in your data source. For more information see Chapter 4, "Lists," on page 67.

Define Data Values for the Point Layer

The Point layer in a map is used to visually represent data for point locations, such as cities or sales outlets. Both the color and size of points can be based on data from your data source.

Procedure


1. Open the **Choose Map** dialog box:
 - When you create a new map report, this dialog box appears automatically.
 - If you are already in a map report, double-click the map background.
2. In the **Point Layers** box, select the layer containing the points to show on the map.
For example, on a map of the world, you may want the points to represent cities.
3. From the **Source** tab , drag a data item to the **Color** drop zone in the **Point Layer**.
For example, to have the color of the point based on revenue, drag **Revenue** from the **Source** tab to the **Color** drop zone.

4. From the **Source** tab, drag a data item to the **Size** drop zone in the **Point Layer**.
5. From the **Source** tab, drag a data item to the **Location** drop zone in the **Point Layer**.
The object must be supported in the map file as a point location. For example, in the World sample map, city is supported as a point location but country or region is not.
6. If you need to refine the location, drag an object to the **Refine Location** drop zone.
Use this drop zone when there is more than one location with the same name. For example, if you try to run a report with cities in the point layer, and there is more than one city in your data source with the same name, the report does not run. An error message indicates that there are cities in your data source with duplicate names. You can differentiate the cities by using the data object **Region** to refine the location.

Add Colors to the Region or Point Layer

You can add colors for regions or points and specify values to determine when those colors are shown.

Procedure


1. In the report, click the **Region Layer** or **Point Layer**.
2. In the **Color & Background** section of the **Properties** pane, double-click the **Palette** property.
3. Click the new button  and click **Color**.
A new color is added to the list of colors.
4. To view the palette colors as a continuous spectrum in which colors blend into one another, click **Continuous Colors**.
5. With the new color selected, click **Color** in the right pane of the dialog box and select a color.
6. Change the percentage boundaries for the colors.


Tip: To specify absolute values rather than percentages, clear the **Percentage** check box.

Add a Legend Title to a Map

There are legend titles for the entire legend, for the color of the regions, for the color of the points, and for the size of the points.

Procedure



1. If the legend title is not showing, click the legend icon .
2. In the **General** section of the **Properties** pane, set the **Legend Title** to **Show**.
3. In the report, double-click the legend title and type the title.
4. By default, the legend titles are taken from the object you have selected from the data source. To change the legend title for the region color, point color, or point size, do one of the following:

- From the **Toolbox** tab , drag a text or calculation object to the **Color Legend Title** drop zone in the Region Layer or Point Layer, or the **Size Legend Title** drop zone in the Point Layer.
- Double-click the **Color Legend Title** or **Size Legend Title** drop zone, to change from the default legend title, then double-click the drop zone again. In the **Text** dialog box, type text for the legend title.

Add a Note to a Map

You can add one or more notes, determine their position in the map report, and specify borders around notes.


Procedure

1. Select the map object.
2. In the **Chart Annotations** section of the **Properties** pane, double-click the **Notes** property.
3. Click the new button , and click **OK** twice.
A note icon with the words **New Note** appears in the report.
4. Click **New Note** next to the note icon .
5. In the **Text Source** section of the **Properties** pane, double-click the **Text** property.
6. Type the text to appear in the note and click **OK**.
7. In the report, click the note icon.
8. In the **Positioning** section of the **Properties** pane, type values to specify the bottom position, left position, height, and width for the note.
The location of the note is defined by the number of pixels.
9. Set the **Note Border** property to specify a border around the note.
10. Run the report to view the note.
If necessary, change the position again.


Drill Through to Another Report From a Map

You can link regions or points on a map to another report. For example, on a map of the world, you can specify that when you click on China, a map of China opens.

Procedure

1. Open the target report.
2. From the **Data** menu, click **Filters**.
3. On the **Detail Filters** tab, click the add button .
4. In the **Available Components** box, click the **Source** or **Data Items** tab to select the data item to use.
For example, to open the target report when Canada is clicked in the source report, expand **Countries and Regions** and double-click **Country and Region**.
5. In the **Expression Definition** box, type an operator after the data item or select an operator from the **Functions** tab and then enter a value.
For example, to open the report when Canada is clicked in the source report, the expression would be as follows:

[Country and Region]='Canada', where [Country and Region] is the name of the data item in the package.

6. Save the target report.
7. Open the source report.
8. Select the region layer or the point layer.
9. In the **Data** section of the **Properties** pane, double-click the **Map Drills** property.
10. In the **Map Drills** dialog box, click the new button .
11. In the **Search string** box, type the name of the feature to use for the drill-through link.
For example, to open a report when you click on Canada in the map, search on all or part of the word **Canada**.
12. Click **Starts with** to search for features that start with the search string or click **Contains** to search for feature names that include the search string.
13. To include a parent layer's name in the results of your search, select a layer in the **Include parent layer** list.
For example, if you searched for **Oslo** and you included the parent layer of **Countries and Regions + Territories**, the search result would be **Oslo (Norway)**.
14. Click **Search**.
15. Select a feature from **Matching features** box and click **OK**.
16. In the **Drill-Through Definitions** dialog box, click the new button.
17. Click the ellipsis button beside the **Report** box, and select the target report.
18. Run the report.

Results

When you click the selected feature in the source report, the target report will open.

Edit a Map

With IBM Cognos Map Manager you can edit the labels in maps to be consistent with the object names in your database.

Administrators and modelers use a Microsoft Windows operating system utility named Map Manager to import maps and update labels for maps in IBM Cognos Report Studio. For map features such as country or region and city names, administrators and modelers can define alternative names to provide multilingual versions of text that appears on the map.

For instructions, see the Map Manager *Installation and User Guide*.

Additional Maps

IBM Cognos supplies a set of standard maps that can be used directly with IBM Cognos Report Studio as well as IBM Cognos Map Manager.

If you already have proprietary geographic data, you can also convert them to .TAB and .XML files that can be imported into Map Manager. Map Manager uses the files to generate .CMF map files, which you can use in Report Studio. For more

information about the required .TAB and .XML files format and how to generate .CMF map files with Map Manager, see the Map Manager *Installation and User Guide*.

Related concepts:

“New maps in IBM Cognos BI 10.2.2” on page 182

IBM Cognos Business Intelligence 10.2.2 contains new maps that replace the maps that are in previous releases.

Location Intelligence

Sophisticated mapping functionality, known as location intelligence, can be used for a broad range of business applications that extend the mapping capability of IBM Cognos Business Intelligence. These include the ability to dynamically create geographic filters and custom areas for aggregating data for ad-hoc analysis. Examples of business applications of location intelligence are listed in the following table.

Business application	Benefits
Target marketing	Learn who your best clients are and find more like them.
Network optimization and site location analysis	Put stores near your customers and look for gaps in geographical coverage.
Routing and work force optimization	Reduce the number of trucks you need and make your drivers more efficient.
e-government	Provide citizens with self-service opportunities.
Sales territory creation	Create balanced sales territories.
Economic development	Plan the development of your community.
Communications network planning	Avoid costly mistakes by putting cell towers in the right locations. Identify the locations of clients in your service area.

Chapter 9. Active Reports

You can use IBM Cognos Report Studio to create active reports. IBM Cognos Active Report is a report output type that provides a highly interactive and easy-to-use managed report. Active reports are built for business users, allowing them to explore their data and derive additional insight.

Active reports make business intelligence easier for the casual user. Report authors build reports targeted at their users' needs, keeping the user experience simple and engaging. Active reports can be consumed by users who are offline, making them an ideal solution for remote users such as the sales force.

Active reports are an extension of the traditional IBM Cognos report. You can leverage existing reports and convert them to active reports by adding interactive behavior, providing end users with an easy-to-consume interface.

Like existing IBM Cognos reports, you can execute active reports from IBM Cognos Connection as well as schedule and burst them to users.

You build active reports with the same objects that you use to build other report types. However, there are objects that are specific to active reports. These objects fall into two categories:

- active report controls
- active report variables

For tips about building active reports, see the Business analytics proven practices page (<http://www.ibm.com/developerworks/analytics/practices.html>).

Note: Cognos Active Report does not support JavaScript.

Active Report Controls

You use active report controls to create the layout of an active report as well as filter, sort, and navigate through data in the report.

Layout

The following controls are used to build the layout of an active report:

- Tab controls, which are used for grouping similar report items.
- Decks of cards, which are used for layering report items.
- Hiding or showing list columns, which allows users to control the data they see by using check boxes.
- Row numbers, which show the number of rows of data in a control.

Filtering and Sorting

To help report authors deliver the content in the most consumable way possible, IBM Cognos Report Studio provides several new filtering controls:

- List and drop-down list controls
- Interactions with charts

For example, clicking a category in a chart filters the data in a list.

- Radial buttons
- Check boxes
- Toggle buttons
- Push button controls

Navigation

To help users navigate through data in a report, report authors can add the following controls:

- Iterators
- Sliders

Data Containers

Data containers, such as lists, crosstabs, charts, visualizations, and repeater tables, are also considered controls in an active report, as you can add interactive behavior to them.

Related concepts:

“Adding Controls to a Report” on page 197

IBM Cognos Active Report offers several active report controls. For many controls, two different versions are available, a static version and a data-driven version.

Active Report Variables

Active report variables work in conjunction with active report controls to add interactivity to a report.

Actions performed on a control, such as selecting an item in a control or selecting a control itself, can set the value of a variable. In turn, controls can respond to changes in the value of a variable, such as filtering data in a control.

Related tasks:

“Create and Manage Active Report Variables” on page 196

Create active report variables to allow controls in a report to interact with each other. Active report variables pass information from one control to another control.

Convert an Existing Report to an Active Report

You can leverage existing reports by converting them to active reports.

Procedure

1. Open the report that you want to convert.
2. From the **File** menu, click **Convert to Active Report**.

Results

IBM Cognos Active Report menu items, objects, and properties become available in IBM Cognos Report Studio. Objects in the report that are not supported in active reports, such as prompt controls in report pages, are removed.

Related tasks:



“Converting a Report to a Template” on page 469

Convert a new or existing report to a template so it can be reused. You can use sample reports that are provided with IBM Cognos Report Studio.

Specify Active Report Properties

You can specify properties for active reports, such as the text that appears in the browser window title bar, the maximum number of rows that a report can contain, and an access code that users must enter to view a report.

Procedure

1. From the **File** menu, click **Active Report Properties**.
2. To specify the title that will appear in the browser window title bar when the report is viewed, under **Window Title**, type the title that you want.
3. If you want to specify the window title in other languages, do the following:
 - Under **Window Title**, click the ellipsis button.
 - Click the add button .
 - Select the languages that you want.
 - In the **Language** column, click one of the languages that you selected.
 - Click the edit button  and type the window title for that language.
4. In the **Window Startup Size** box, choose among the available options to specify the size of the browser window when an active report is viewed.
5. In the **Maximum query rows** box, specify the maximum number of rows of data that the report can contain.

If the number of rows of data returned when the report is run exceeds this value, an error message appears, and users will not be able to view the report.
6. If you do not want to compress the MHT file that is produced when the active report is run, clear the **Compress the active report output** check box.

Compressing the output reduces the size of MHT files so that active reports can support more data and load faster in browsers and mobile devices.
7. If you made changes to the **Window Startup Size**, **Maximum query rows**, or **Compress the active report output** properties and you want those changes to become the default values when you create new active reports, click **Change defaults**.
8. To specify an access code that users will have to enter to view the report, enter the code in the **Access code** box.

You can use any Unicode character in the access code, and there is no limit to the number of characters an access code can contain.

The access code will not be hidden or treated like a password when entered (* will not appear as the code is entered). Users will have three attempts to enter the correct code, after which the active report will shut down. To try again, users have to reopen report.

Note: The access code is a tool to help prevent the unauthorized consumption of an active report within an organization. It is not an enterprise grade security solution.

Adding Interactivity to a Report

You create an active report by adding interactive behavior to controls in the report. Adding interactive behavior links controls to each other, allowing an action performed on a control to change the state of another control.

Create and Manage Active Report Variables

Create active report variables to allow controls in a report to interact with each other. Active report variables pass information from one control to another control.

About this task

You can also create active report variables when you define connections between controls. However, you may want to modify these variables, such as changing the name or defining default values.

In addition, active report variables allow active reports inserted in a workspace in IBM Cognos Workspace to interact with each other. For example, selecting a product line in one active report causes another active report to show the data for the selected product line. In addition, variables allow check boxes and sliders in a workspace in Cognos Workspace to drive active reports in the workspace.



To work in Cognos Workspace, active report variables must meet the following criteria:

- The variables must be public.
When you make a public variable, the variable can be consumed in other IBM Cognos products.
- For active reports to listen to each other in a workspace, each report must have a public variable with the same name.
- For a Cognos Workspace slider to drive an active report, a range variable must be defined in the active report.

The data item of the slider and the range variable in the active report must have the same name.

Two variables are used to define the minimum and maximum values of the range variable. The two variables are used to define the minimum and maximum values of the slider.

Procedure

1. Click the **Active Report Variables** tab .
2. Create a variable by following these steps:
 - a. Click **Create a New Variable**.
 - b. In the **Name** box, type the name of the variable.
 - c. Click the **Data Type** drop-down menu and click the type of variable that you want to create.
 - d. To make the variable public, select the **Public (External)** check box.
 - e. If you want to specify a default value for the variable, click **Set Default Value(s)** and define or specify the values that you want.
To define your own default values, in the **Variable Values Source** list, click **Enter Value(s)**, and then click the new icon .

To specify default values that come from a data item in a control, in the **Variable Values Source** list, click **Select Value(s)**. Specify the control and the data item from which you want to select default values, and then select the values that you want from the **Values** box.


Tip: Define multiple default values when you want more than one item selected in a control that allows multiple selections, such as a check box group.

3. To modify an existing variable, right-click the variable and click **Edit Variable**.
4. To add a default value, click **Set Default Value(s)**.

To change a default value, click the name of the current default value specified for the variable.

5. Create a range variable by following these steps:
 - a. Create the variables that will define the minimum and maximum values of the Cognos Workspace slider.
The variables must have the number data type.

Tip: Range variables are automatically set as public variables. Do not make the variables that are used to define the minimum and maximum values of the slider public.

- b. Click **Manage Ranges**.
- c. Click the new icon .
- d. In the **Name** box, type the name of the range variable.
- e. Click the **Minimum Variable** list and select the variable that will be used to set the minimum value of the slider.
- f. Click the **Maximum Variable** list and select the variable that will be used to set the maximum value of the slider, and then click **OK** twice.

Note: If you later delete the minimum or maximum variable, the range variable is also deleted.


Related tasks:

“Define a Connection Between Controls” on page 204

Define a connection between controls to link them together. When you link controls, an action performed on one control affects the behavior of the other control.

Adding Controls to a Report

IBM Cognos Active Report offers several active report controls. For many controls, two different versions are available, a static version and a data-driven version.

Use the static version of a control when you want to manually define the values that the control can contain. Use the data-driven version of a control when you want the values that the control can contain to come from a data item. Controls are available on the **Toolbox** tab .


Tip: To view only toolbox items that are specific to active reports, right-click anywhere in the **Toolbox** tab and click **Active Report Toolbox Items**.

When you add a control to an active report, you can convert the control to another type of control that is compatible by right-clicking the control and selecting **Convert Control**. For example, you can convert a data drop-down list control to a data iterator control.

Variable Text Items

Use variable text items to insert active report variables in a report. Variable text items are useful to show the value of a variable when an item in another control is selected. For example, you can use a variable text item as a title for a list that is linked to a drop-down list control. When an item is selected from the drop-down list, the item appears as the title of the list.

Row numbers

The active report row number tool  adds row numbers that reflect the visible row number in the report. This is different from the report row number tool, which reflects the server calculated row number.

Repeater tables

Use static repeater tables and data repeater tables to build a repeating structure of content. Repeater table controls allow you to create button bars or grids of custom content to control the content that appears in other controls. In data repeater table controls, the content that appears in the repeater table is driven by a data item that you insert in the control.

The following image shows a static repeater table when it is inserted in an active report.



Figure 33. Static repeater table control

The data repeater table is the repeater table data container that is available for all report types. The static repeater table is available in the **Toolbox** tab only when you are authoring an active report.

Decks and Data Decks

Use decks and data decks to show different objects and different data respectively based on a selection in another control. For example, in a deck, clicking a radio button in a radio button group control shows a list object while clicking a different radio button shows a chart object.

The following image shows a deck control when it is inserted in an active report.



Figure 34. Deck control

Decks are composed of cards. In static decks, you define the number of cards in the deck and you insert the objects that you want in each card. This allows you to create cards that can contain different objects, such as pie chart in one card and a crosstab in another card. In data decks, the cards are defined by a data container or data items inserted in the deck, and a data item determines which card appears.

Tab Controls and Data Tab Controls

Use tab controls and data tab controls to define multiple pages for the same area of a report. In data tab controls, the tabs are driven by a data item that you insert in the control.

The following image shows a tab control when it is inserted in an active report.



Figure 35. Tab control

Button Bars and Data Button Bars

Use button bars and data button bars to add a group of push buttons. In data button bars, the buttons are driven by a data item that you insert in the control.

The following image shows a button bar control when it is inserted in an active report.




Figure 36. Button bar control

In reports, users can click only one button at a time.

Toggle Button Bars and Data Toggle Button Bars

Use toggle button bars and data toggle button bars to add a group of buttons that change appearance when pressed. In data toggle button bars, the buttons are driven by a data item that you insert in the control.

The following image shows a toggle button bar control when it is inserted in an active report.



Figure 37. Toggle button bar control

In reports, users can click one or more buttons simultaneously.

Radio Button Groups and Data Radio Button Groups

Use radio button groups and data radio button groups to group a set of buttons that have a common purpose. In data radio button groups, the radio buttons are driven by a data item that you insert in the control.

The following image shows a radio button group control when it is inserted in an active report.




Figure 38. Radio button group control

In reports, users can click only one radio button at a time.

Check Box Groups and Data Check Box Groups

Use check box groups and data check box groups to group a set of check boxes. In data check box groups, the check boxes are driven by a data item that you insert in the control.

The following image shows a check box group control when it is inserted in an active report.




Figure 39. Check box group control

In reports, users can select one or more check boxes simultaneously.

Drop-Down Lists and Data Drop-Down Lists

Use drop-down lists and data drop-down lists to provide a list of items that users can choose from. In data drop-down lists, the lists are driven by a data item that you insert in the control.

The following image shows a drop-down list control when it is inserted in an active report.



Figure 40. Drop-down list control

In reports, users can select only one item at a time.

List Boxes and Data List Boxes

Use list boxes and data list boxes to provide a list of items that users can choose from. In data list boxes, the lists are driven by a data item that you insert in the control.

The following image shows a list box control when it is inserted in an active report.




Figure 41. List box control

In reports, users can select one or more items in a list box.

Iterators and data iterators

Use these controls to allow users to navigate or filter values in a control by clicking buttons such as previous and next. In data iterators, the iterations are driven by a data item that you insert in the control.

The following image shows an iterator control when it is inserted in an active report.



Figure 42. Iterator control

Discrete values sliders, continuous values sliders, and data discrete values sliders

These controls allow users to navigate or filter data using a slider bar. Discrete and data discrete values sliders allow users to slide between individual values, such as months. In data discrete values sliders, the values are driven by a data item that you insert in the control. With continuous values sliders, users slide through numeric values between minimum and maximum values that you define, such as 0 and 100.

The following image shows a discrete value slider control when it is inserted in an active report.



Figure 43. Discrete values slider control

Buttons

Use buttons to add individual push buttons to a report.

The following image shows a button control when it is inserted in an active report.




Figure 44. Button control

Data Containers

Lists, crosstabs, charts, maps, visualizations, and repeater tables are also controls in an active report, as you can add interactive behavior to them.


Add Data to a Control

For every control that you insert in a report, you must add the data that you want to appear in the control.


Add data to a data-driven control

For data-driven controls, you insert data items from the package.

Procedure

1. On the **Source** tab , drag query subjects or query items to the control.
2. To add an image to the data in the control, drag the appropriate data item to the **Icon** box.
3. If the data that will appear in the control depends on other data that you do not want to show, drag the appropriate data item to the **Extra Items** box.
For example, you add Product type to a data list box control and you want to filter the product types that appear in the control based on a product line selected in another control. To filter the data, you must drag Product line to the **Extra Items** box.

Tip: IBM Cognos Report Studio can automatically copy data items from other controls when you create connections between controls.

4. If the control is a data deck and you want to create a default card that will appear when no other card matches the variable value passed to the deck, in the **Properties** pane, click **Yes** for the **Default Card** property. Then click the **No Data Contents** tab  for the deck and insert the objects that you want to appear on the default card.

Related tasks:

“Define a Connection Between Controls” on page 204

Define a connection between controls to link them together. When you link controls, an action performed on one control affects the behavior of the other control.

Add data to a static control

For static value driven controls, you manually define the data in a data table.





Procedure

1. In the report, click the definition icon  of the control.

Tip: The definition icon is visible only when the visual aid **Show Interactive Object Controls** is enabled.

2. To add a new object, such as a card in a deck or a button in a button bar, under **Data Table**, click the new button.
3. In **Data Table**, define the values that you want to appear in the control.


Values are organized by data item. In addition to the default data item (Label) and values provided, you can create your own data items and values. For example, to add an icon to each value, you must create a data item for the icons.

- To define a new data item, click the new button  and type the name of the data item that you want to create.
 - Click inside each table row and type the name of the value.
 - To add translations for the values, to support users in multiple languages, click the ellipsis button, choose the languages that you want to support by clicking the add button , and type the translated text for each language added.
 - If you created new data items, in the **Definition** box, click the **Label** drop-down list and select the data item that you want to use in the control.
 - To add an icon to each value, select the **Icon** check box, click the drop-down list, and select the data item that contains the icons that you want to use. You cannot add an icon to values in static decks and discrete values sliders. To add an icon to values in a static repeater table, insert the **Image** object from the **Toolbox**. Then specify the data item for the icons by referencing the data item in the **Properties** pane.
4. Optional: If you want to copy all data values to another static control, click the copy control definition icon . After you have copied the data values of the control, click the definition icon of another static control, and then click the paste control definition icon  to copy the data values.

Tip: You can also drag data items from one control and drop them in another control. This action moves the data item from one control to another control instead of copying the item. You can drag and drop data items only to static controls that can contain objects, such as a deck, tab control, and repeater table. In addition, the data table of the target control must contain a data item with the same name as the data item you are moving, such as Label.

5. If the control is a deck, click the arrows to navigate to each card of the deck and insert the objects that you want to appear on each card.

To create a default card that will appear when no other card matches the variable value passed to the deck, in the **Properties** pane, click **Yes** for the

Default Card property. Then click the **No Data Contents** tab  for the deck and insert the objects that you want to appear on the default card.

Related tasks:

“Referencing data items defined in a static control”

If you insert an object in a static control, such as an image in a static repeater table, you can use a data item in the control to populate the object.

Referencing data items defined in a static control

If you insert an object in a static control, such as an image in a static repeater table, you can use a data item in the control to populate the object.

Before you begin

You must create the data item in the data table of the control before you can reference the item.

About this task

You can reference data items only for text items, images, hyperlinks, and HTML items inserted in decks, tab controls, and repeater tables.

Procedure

1. In the static control, click the object for which you want to reference a data item.
2. In the **Properties** pane, click the **Source Type** property and choose **Control Data Item Value**. The **Control Data Item Value** property appears.
3. Click the **Control Data Item Value** property and select the data item that you want to reference.

Tip: If the object is a hyperlink, you can specify the data item to be used to populate the hyperlink text as well as the data item to be used to populate the URL of each link.

Related tasks:

“Add data to a static control” on page 202

For static value driven controls, you manually define the data in a data table.

Define a Connection Between Controls

Define a connection between controls to link them together. When you link controls, an action performed on one control affects the behavior of the other control.

Procedure

1. Click the create a new connection icon  of a control that you added to the report.

Tip: The create a new connection icon is visible only when the visual aid **Show Interactive Object Controls** is enabled.

2. In the **Source Control** drop-down list, select the source control for which you want to define a connection.
3. Click the **Data Item** drop-down list under the source control and select the data item that will drive the behavior of the target control.
4. In the **Target Control** drop-down list, select the target control for which you want to define a connection.

If the target control is a visualization, select a visualization data container.

5. Click the **Data Item** drop-down list under the target control and select the data item that will determine what appears in the target control.

If the data item that you want to use is not in the query of the target control, and the source control is a data-driven control, select **Copy Data Item from Source** to copy the source data item specified in the previous step to the target control query. If the source control is a static control, select **Use Source Definition**.

If the target control is a data container, the copied data item appears shaded in the container to indicate that the column visibility property for the item is set to **Hidden**.



6. Click the **Behavior** drop-down list between the source and target controls and specify the type of relationship that you want to define between the two controls:
 - To select data in the target control based on what will be selected in the source control, click **Select**.
 - To filter data in the target control based on what will be selected in the source control, select **Filter**.
7. Below the **Behavior** area, click the active variable drop-down list and choose to create a new variable for the connection or use an existing variable.

Tip: If there are no variables defined in the report, you cannot click the active variable drop-down list.

- a. If you create a new variable, type a name for the variable and specify its data type. You can also specify its default values.
 - b. If you choose to use an existing variable, choose the variable that you want. You can also specify its default values.
8. Click **Connect**.

Results

When a connection is defined, IBM Cognos Report Studio creates the appropriate conditions for the selection behavior and reaction behavior of the source and target controls.

Tip: The interactive behavior icon  of a control changes to indicate that a connection was defined. The **Active Report Controls** tab  shows the controls and variables inserted in a report and their relationships to one another. You can click a control in this tab to quickly locate the control in the report as well as set default values for variables.

Related tasks:

“Show or Hide a Column or Row” on page 209

You can show or hide a column in a list or a column or row in a crosstab when the report is viewed.

“Add data to a data-driven control” on page 202

For data-driven controls, you insert data items from the package.

“Add data to a static control” on page 202

For static value driven controls, you manually define the data in a data table.

Specify the Selection Behavior of a Control

Specify the selection behavior of a control to determine what interactive behavior should occur when the control is clicked or when an object in the control, such as a button, check box, or data item, is selected.

Specifying the selection behavior of a control sets the value of active report variables defined in the report. The active report variable values are then used to specify the reaction behavior of controls. For example, you add two drop-down list controls to a report and you create a connection between them. The first drop-down list shows product lines and the second drop-down list shows product

types. When a product line is selected in the first drop-down list box, you want to pass that information to the second drop-down list box so that it shows only the product types of the selected product line.

You can specify a selection behavior for any control, except for decks and data decks.


IBM Cognos Report Studio automatically sets active report variable values when you define a connection between controls. However, you may need to set the value of other variables to specify additional interactive behavior.

Procedure

1. Click the interactive behavior icon  of the source control.

Tip: The interactive behavior icon is visible only when the visual aid **Show Interactive Object Controls** is enabled.

The **Report Behavior** box shows the relationship between the source and target controls when you defined a connection between the controls. You can specify default values for the variable associated with the control by clicking **Set Default Value(s)**.

2. In the **Behavior on Select** box, click inside the **Set Variable Values** box and then click the edit button  that appears.
3. For each active report variable that you want to set as part of the selection behavior of the control, click the **Value** drop-down list and select one of the following choices:
 - If you want to clear the current value of the variable, click **Set to Empty**.

Tip: Clearing the current value of a variable is useful when you have cascading controls. For example, if the parent control is reset to a default value, you want to reset the child control to a default value as well.

- If you want to specify your own value, click **Type in a value** and type the value that you want to use.
 - If you want the variable values to be driven by a data item in the report, click the data item that you want to use.
 - If you do not want the variable to be used for the control, click **Do not set**.
4. To create a new active report variable, click **Create a New Variable**.

Related tasks:

“Specify the Reaction Behavior of a Control”

Specify the reaction behavior of a control to determine how a control will react when another control, or an object in the control, is selected.

Specify the Reaction Behavior of a Control

Specify the reaction behavior of a control to determine how a control will react when another control, or an object in the control, is selected.

About this task

You can specify the following reaction behaviors:

- Select an item in a control.

You can specify this reaction behavior for any control, except for single button controls.

For example, you specify a default value for a variable, and the variable drives a drop-down list control. When the report is run, you want the default value to appear in the control.

You can also specify to select the first or last item in a control by default. For example, an active report contains two data radio button groups that are connected to each other. The first data button group is driven by Product line and the second data button group is driven by Product type. When a user clicks on a product line, the product types that belong to the selected product line appear in the second radio button group, and you want the first or last radio button in the product type radio button group to be selected.

- Filter data in a control.

For example, you want to filter the product types in a drop-down list control based on the product line selected in another drop-down list control.

You can specify this reaction behavior for drop-down lists, data drop-down lists, list boxes, data list boxes, radio button groups, data radio button groups, check box groups, data check box groups, lists, and crosstabs.

- Enable a control.


For example, you want to make a control interactive only when a selection is first made in another control.

You can specify this reaction behavior for any control, except for decks, data decks, tabs, data tabs, lists, crosstabs, charts, and maps.

In addition to these behaviors, you can specify the item to appear when nothing is selected in a list control, hide or show a column, and whether to allow data to be sorted in a list.

IBM Cognos Report Studio automatically sets the reaction behavior when you define a connection between controls. However, you may want to change the reaction behavior or specify additional interactive behavior.

Procedure

1. Click the interactive behavior icon  of the control.
2. If you want to specify the select an item in a control reaction behavior, and you want to specify to select the first item or the last item in the control by default, click the **Auto Select** menu and choose **First Item** or **Last Item**.
3. In the **Reaction Behavior** box, click the reaction behavior box that you want,

such as **Container Selection**, and click the edit button  that appears.

If a condition is not yet defined, two dialog boxes appear. The second dialog box prompts you to define the condition expression that you want to use to specify the reaction behavior.

Note: If the reaction behavior that you are setting is **Container Selection**, and you previously clicked an option other than **None** in the **Auto Select** menu, defining a condition sets the **Auto Select** menu to **None**. Similarly, if you define a condition in the **Container Selection** box, and you then set the **Auto Select** menu to an option other than **None**, the condition is deleted.

4. In the first **Item** box, define the left side of the condition expression.
 - To use a data item, click the **Data Item** radio button and then click the item that you want to use.

The data items that are available in the drop-down list depend on the data items that you inserted into the control.

- To use a static item, click the **Value** radio button, type the value that you want to use, and then specify the value's data type.

The value must be defined as a value of the selected active report variable in the next step.

- If you want to set the value of an active report variable to null, click the **Empty Variable** radio button.

5. Click the **Operator** drop-down list and select the operator that you want to use.

6. In the second **Item** box, define the right side of the condition expression.

- To use a value in an active report variable, click the **Active Report Variable** radio button and then click the variable that you want to use.

The variables that are available in the drop-down list depend on the variables that you defined in the report.

- To use a static item, click the **Value** radio button, type the value that you want to use, and then specify the value's data type.
- To use null as the value, click the **Empty Data Item** radio button.

Use null as the value to specify the reaction behavior when no data exists for the value selected in the source control.

7. If you want to apply the condition when no item is selected in the source control, clear the **Drop this condition if the variable is empty** check box.

Clearing the check box can improve performance and prompt users to perform an action. For example, a report contains a list with many rows of data, and the list is filtered by another control. When the check box is cleared, no data will appear in the list until an item is selected in the other control.

Related concepts:

“Recommendation - use master detail relationships when authoring decks” on page 210

When authoring deck controls in active reports, use master detail relationships to improve performance.

Related tasks:

“Specify the Selection Behavior of a Control” on page 205

Specify the selection behavior of a control to determine what interactive behavior should occur when the control is clicked or when an object in the control, such as a button, check box, or data item, is selected.

“Set the No Value List Item”

Set the no value list item to show a specific item in a control when no value is selected.

“Show or Hide a Column or Row” on page 209

You can show or hide a column in a list or a column or row in a crosstab when the report is viewed.

“Sort Data in a List” on page 210



You can specify whether users can sort data in a list in the report output.

Set the No Value List Item

Set the no value list item to show a specific item in a control when no value is selected.

For example, a report contains a drop-down list control that contains product lines. You create a no value list item named (All) to show all product lines when the report is initially viewed.


Procedure

1. Select the control.
2. In the **Properties** pane, for the **No Value List Item** property, click **Show**.
A text item representing the no value list item appears in the control.
3. In the **Properties** pane, double-click the **Label** property.
4. In the **Default text** box, type the name of the no value list item.
5. To specify the text for other languages, do the following:
 - Click the add button .
 - Select the languages that you want.
 - In the **Language** column, click one of the languages that you selected.
 - Click the edit button  and type the name of the no value list item for that language.
 - Repeat for all remaining languages.
6. In the **Properties** pane, click the **Position in List** property and specify where you want the no value list item to appear in the control.

Show or Hide a Column or Row

You can show or hide a column in a list or a column or row in a crosstab when the report is viewed.

Procedure

1. Click the title of the column or row that you want to show or hide.
2. If the data container is a crosstab, in the **Properties** pane, click the **Visible** property and click **Yes** or **No**.
3. If the data container is a list, in the **Properties** pane, double-click the **Column Visibility** property.
4. To make the list column visible when the report is viewed, click the **Visible** radio button.
5. To hide the list column when the report is viewed, click the **Hidden** radio button.
6. To make the list column visible based on a condition, click the **Visible based on condition** radio button, click the edit condition button , and specify the condition.
 - If you want to specify a value to use for the condition, click the **Value** radio button, type the value, and in the **Data Type** drop-down list, select the value's data type.
 - If you want to use null as the value for the condition, click the **Empty Variable** radio button instead.
 - Click the **Operator** drop-down list and select the operator that you want to use for the condition.
 - In the **Active Report Variable** drop-down list, select the active report variable that you want to use for the condition.
 - If you want to apply the condition when no item is selected in a control that is connected to the list, clear the **Drop this condition if the variable is empty** check box.

Sort Data in a List

You can specify whether users can sort data in a list in the report output.

Procedure

1. Select the column that you want users to be able to sort.
2. In the **Properties** pane, for the **Allow Sorting** property, click **Yes**.

Recommendation - use master detail relationships when authoring decks

When authoring deck controls in active reports, use master detail relationships to improve performance.

Decks offer greater flexibility in active reports by allowing you to show different objects in each card of a deck. In data decks, the number of cards that are created depends on data items inserted in the deck. As a result, a data deck can contain many cards, which may reduce performance when the report is run and viewed. For example, if a data deck contains Product line and Years, there can be up to 20 cards in the deck (five different product lines multiplied by four different years). In addition, filtering data in a data deck can affect performance when there are many rows of data in the deck.

To improve performance, use a master detail relationship to filter data in a data container inserted in a data deck control. A master detail relationship defined between a data deck and a data container inserted in the deck results in a specific number of cards generated for the deck, which serves as a way to filter the data in the data container. For example, a data deck contains a list object that has many rows of data, and you want to filter the list by product line. Creating a master detail relationship between the deck and the list using Product line produces five cards in the deck, one for each product line. When you filter by product line, the appropriate card appears in the data deck.

In addition, specify **Select** as the behavior instead of **Filter** when defining the connection between the data deck control and the control you want to use to filter the data in the deck.


Tip: If the data container in the data deck is a chart, you must use a master detail relationship if you want to filter data in the chart.

Formatting an active report in the preview view

IBM Cognos Active Report has a preview view that you can use to format an active report and immediately see the layout changes. You no longer have to run the report whenever you make a formatting change.


About this task

In the Active Report preview view, you can toggle between two different modes. To format elements in the report, you must enter the edit mode. When you are in the edit mode, a dotted blue square appears when you hover over a selectable element in the report. You click an element to select it, after which you can format the element. When you enter the Preview mode, you can test active report behavior by clicking elements in the report.

You can also make non-formatting changes to the report. When a non-formatting change is made, a message appears that notifies you that you must refresh the report. The report is refreshed when you click **OK**. You can also refresh the report by clicking the **Refresh** icon .

You can view the report in different screen sizes and orientation. Changing the screen size provides a guideline as to how the report will look on screens of various sizes. When you change the screen size, the Active Report preview view shows the report at the size that you specified. On a mobile device, the IBM Cognos Mobile application zooms out the report to fit the width of the mobile device screen, eliminating the need for horizontal scrollbars.

Procedure

1. To enter the active report preview mode, in the Explorer bar, click the Active Report Preview icon .

Tip: You can also click **View > Active Report Preview**.

2. To enter the edit mode, in the toolbar, click the **Edit** icon.
3. In the edit mode, format the elements in the report that you want.
4. To enter the preview mode, in the toolbar, click the **Preview** icon.
5. To view the report in different screen sizes, in the toolbar, click the **Screen Size** menu and choose one of the preset sizes, or click **Add custom size** to specify your own screen size.
6. If you specified a screen size in the previous step, click the **Orientation** menu to change the report orientation.

Summarizing Data in the Active Report Output

You can add an output summary to a list or crosstab control that reflects the data that appears in the control when an active report is viewed.


About this task

You can add two types of summaries to an active report. The summaries that you can add to regular reports are also available in active reports. Output summaries are specific to active reports. Output summary values are calculated from the data that users see in the output. For example, an active report contains a check box group control and a list control. You add two summaries to the list. The first summary is the aggregation method Total that is available in all reports. The second summary is the output summary Total that is available only in active reports. The data that users see in the list is filtered by selecting items in the check box group control. The Total output summary value is calculated from the items that are selected in the check box group control. The value for the Total aggregation method that is available in all reports remains the same, regardless of what items are selected in the check box group control. This value is the total of all items in the list.

Only a subset of the aggregation methods that are available in all reports is available as output summaries.

Procedure

1. In a list or crosstab, click the column or row for which you want to add an output summary.

2. In the toolbar, click the summarize button  and then, under **Summarize in Output**, choose the summary that you want to add to the active report output.

Tip: After you add an output summary, you can specify a different aggregation method. Select the summary data item in the list or crosstab, click the **Output Aggregation Method** property, and choose the aggregation method that you want.

Run or Save an Active Report

You can run an active report in HTML format or save it as a MIME HTML (MHT) file so that you can send the report to your consumers. MHT files are viewable in the Microsoft Internet Explorer or Mozilla Firefox browsers.

Before you begin

To view an active report in MHT format in Mozilla Firefox, you must first download an UnMHT add-on.

If you are using Microsoft Internet Explorer 6.0, you cannot open an active report in MHT format as a file. You can view the report only by using a URL.

If an active report contains an extensible visualization, and you are using Internet Explorer 9 or 10, you must have Microsoft Silverlight 5 installed on your computer.

About this task

To assist you in resolving problems when you are authoring an active report, a run option that shows the state of active report variables in the report as you click various controls is available. By default, this option is enabled.

Active reports require the same web browser settings as Report Studio.

Procedure

1. To disable the run option that can show the state of active report variables when the report is viewed, from the **Run** menu, click **Run Options**, and clear the **Enable right-click debug menu** check box.
2. To run a report, from the **Run** menu, click **Run Active Report**.
3. To save a report, from the **Run** menu, click **Download Active Report**, and when prompted, choose to save the report as an MHT file.

Results

When running a report with the **Enable right-click debug menu** check box selected, right-clicking in the report output window allows you to choose to view the active report variables in the report, reset variables, or print the report.

Tip: The right-click debug menu is not available if you run the report from IBM Cognos Connection.

Related concepts:

“Web Browser Settings” on page 41

IBM Cognos Report Studio can be used in the Microsoft Internet Explorer and Mozilla Firefox Web browsers.

Related tasks:

“Drill-through links in active reports do not work” on page 524
When viewing an active report that contains drill-through links in Microsoft Internet Explorer 8 and later, the links do not work.

Example - Create an Active Report Showing Revenue Data for Core Products

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create an active report showing revenue data for the core products Camping Equipment and Golf Equipment.


The revenue data is specific to countries and regions in the Americas. The report will allow users to filter data by product or by country or region.

To create this report, you will need to add two data drop-down list controls and a list container. The first data drop-down list control will contain the core products that users can select. The second data drop-down list control will contain countries and regions that users can select. The list will show revenue data for each core product and country or region. When users click different products or different countries and regions, the data in the list will be filtered based on the selections made.

Create the active report

Create a new active report and add the objects that you need to build the core products revenue report.


Procedure


1. Open IBM Cognos Report Studio with the **GO Data Warehouse (analysis)** package.
2. In the **Welcome** page, click **Create new**.
3. In the **New** dialog box, click **Active Report**.
4. Double-click the report title and type
Core Products Revenue
5. Click the **Toolbox** tab  and drag the **Table** object to the report.
6. Clear the **Maximize width** check box and then click **OK** to create a table with two columns and one row.
7. Drag the **Data Drop-Down List** object to each cell in the table.
8. Drag the **List** object to the report so that it appears under the table.




Add data to the data drop-down list controls

This task adds the required data items to the two drop-down list controls in the report.

Procedure

1. Right-click the first data drop-down list control and click **Go to Query**.
Query1 opens in the Query Explorer.
2. Click the **Source** tab  and do the following:
 - Expand the **Sales and Marketing (analysis)** folder and the **Sales** namespace.

- Expand the **Products** dimension and then the **Products** hierarchy.
 - Drag **Product line** to the **Data Items** area.
3. Click **Product line** and in the **Properties** pane, do the following:
 - Click the **Name** property, delete the existing name, and type
Core products
 - Double-click the **Set Definition** property.
 - Click the new button  and then click **Exclude**.
 - In the **Available members** box, expand **Sales and Marketing (analysis)**, **Sales**, and **Products**.
 - Drag the **Mountaineering Equipment**, **Personal Accessories**, and **Outdoor Protection** members to the **Members** box.





The Core products member set now contains only Camping Equipment and Golf Equipment.
 4. Click **OK** twice.
 5. Pause the pointer over the page explorer button  and click **Page1**.
 6. Click the **Data Items** tab  and drag **Core products** from **Query1** to the drop-down list box in the control.
 7. Click the control and in the **Properties** pane, for the **No Value List Item** property, click **Show**.
The **Properties** pane for the no value list item property appears.
 8. Double-click the **Label** property, type Core products in the **Default text** box, and click **OK**.
 9. Right-click the second data drop-down list control and click **Go to Query**.
Query2 opens in the Query Explorer.
 10. Click the **Toolbox** tab  and drag **Data Item** to the **Data Items** area.
 11. In the **Expression Definition** box, type
children ([Sales].[Retailers].[Retailers].[Region]->[Retailers].[710])

Tip: This expression returns the children of the **Americas** member. The **MUN** for **Americas** is used instead of the member name.
 12. In the **Properties** pane, click the **Name** property, delete the name and type
Countries and regions
 13. Pause the pointer over the page explorer button and click **Page1**.
 14. Click the **Data Items** tab and drag **Countries and regions** from **Query2** to the drop-down list box in the control.
 15. Click the control and in the **Properties** pane, for the **No Value List Item** property, click **Show**.
The **Properties** pane for the no value list item appears.
 16. Double-click the **Label** property, type Countries and regions in the **Default text** box, and click **OK**.

Add data to the list

This task adds the required data items to the list.



Procedure

1. Pause the pointer over the query explorer button  and click **Query1**.
2. Copy the **Core products** data item.
3. Pause the pointer over the query explorer button and click **Query3**.
4. Paste the **Core products** data item into Query3.
5. Repeat steps 1 to 4 to copy the **Countries and regions** data item from Query2 to Query3.
6. Pause the pointer over the page explorer button  and click **Page1**.
7. Click the **Data Items** tab  and drag **Core products** and **Countries and regions** from **Query3** to the list.
8. Click the **Source** tab  and do the following:
 - Expand the **Products** dimension and then the **Products** hierarchy.
 - Drag **Product type** to the list, inserting it between **Core products** and **Countries and regions**.
 - Expand **Sales fact**.
 - Drag **Revenue** and **Planned revenue** to the list, after **Countries and regions**.

Add interactivity to the report

This task defines connections between the various controls and sets an active report variable so that the controls can interact with each other when users view the report.

Procedure


1. Click the interactive behavior icon  of the first data drop-down list control.
2. Click **Create a New Connection**.
3. Click the **Target Control** drop-down list and click **List1**.
4. Ensure that the following information appears in the dialog box and click **Connect**.
 - In the **Behavior** drop-down list, **Filter** is selected.
 - In the **Data Item** drop-down list for both controls, **Core products** is selected.
 - In the **Active Report Variable** box, type Core products Variable 1.
5. In the **Control** drop-down list, click **Data Drop-Down List2**.
6. Click **Create a New Connection**.
7. Click the **Target Control** drop-down list and click **List1**.
8. Ensure that the following information appears in the dialog box and click **Connect**.
 - In the **Behavior** drop-down list, **Filter** is selected.
 - In the **Data Item** drop-down list for both controls, **Countries and regions** is selected.
 - In the **Active Report Variable** box, type Countries and regions Variable 1.
9. In the **Control** drop-down list, click **Data Drop-Down List1**.
10. In the **Behavior on Select** section, click the edit button .

11. Set **Countries and regions Variable 1** to **Set to Empty** and click **OK** twice.
When users select a different product in the first data drop-down list control, the second data drop-down list value will reset to the no value list item.

Specifying default values for the data drop-down list controls

This task specifies default values for the two drop-down list controls in the report.

Procedure

1. Click the **Active Report Variables** tab .
2. Expand **Core products Variable 1** and click **Set Default Values**.
3. In the **Values** box, double-click **Camping Equipment** and click **OK**.
4. Expand **Countries and regions Variable 1** and click **Set Default Values**.
5. In the **Values** box, double-click **United States** and click **OK**.

Revenue data for core products report output

When initially viewed, the revenue data for core products active report shows a list containing data for all core products in all countries and regions.

Selecting a product from the core product drop-down list or selecting a country or region from the country and region drop-down list filters the list to the selections made.

The following image shows the data that appears in the list when **Camping Equipment** and **United States** are selected in the two drop-down lists.



Core products	Product type	Countries	Revenue	Planned revenue
Camping Equipment	Cooking Gear	United States	43,152,191	47,952,594.23
Camping Equipment	Tents	United States	90,663,037.65	95,695,990.84
Camping Equipment	Sleeping Bags	United States	50,338,776.21	54,345,028.43
Camping Equipment	Packs	United States	57,520,074.37	61,360,321.97
Camping Equipment	Lanterns	United States	21,597,711.83	23,090,549.81

Figure 45. Revenue data for core products report

Example - Sales analysis active report

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create an active report analyzing sales by region and by product line.


You will use a list to show sales by region, with a slider control to allow users to move between different regions. Users will have the option to show or hide the slider control by respectively selecting or clearing a check box.

You will use a pie chart to show sales by product line. Users will be able to click product lines in the chart legend to highlight sales in the chart.

Creating a new active report

Create a new active report and add the objects that you need to build the sales analysis report.

Procedure

1. Open IBM Cognos Report Studio with the **GO Sales (query)** package.
2. In the **Welcome** page, click **Create new**.
3. In the **New** window, double-click **Active Report**.
4. Double-click the report title and type
Sales Analysis
5. Click the **Toolbox** tab , drag **Table** to the report, specify two columns and one row, and click **OK**.
6. Drag **Check Box Group** to the first table cell.
7. Select the second and third check boxes and delete them.
Only one check box is required for this report.
8. Drag **Deck** to the second table cell.
9. Drag **Data Discrete Values Slider** to the deck, in the space under **Card 1**.
The slider control becomes the first card in the deck.
10. Select the slider control and in the **Properties** pane, click the **Track Length** property, change the length of the slider track to 500 px, and click **OK**.
11. Optional: To animate the movement of the slider when users view the report, set the **Animate** property to **Yes**.
12. Optional: To update active report variables associated with the slider when users move the slider thumb, set the **Update Variables Live** property to **Yes**.
The report will be updated live when the thumb is moved. If set to **No**, the report is updated only when the thumb is stopped and released.
13. Drag the **Block** object under the table.
14. Drag the **List** object under the block.
15. Insert another block under the list.
16. Click the second block and in the **Properties** pane, double-click the **Padding** property.
17. In **Top padding**, specify 20 px and click **OK**.
18. Drag the **Data Deck** object under the block.
19. Drag the **Chart** object to the data deck.
 - a. In the Insert Chart window, click **Pie, Donut**, and then click the **Exploded Pie with 3-D Effects and Flat Bevel** chart type.

Tip: This pie chart type is available only when the **Use legacy chart authoring** check box (**Tools > Options > Advanced** tab) is cleared. To find this specific pie chart type, hover over each choice to view its tooltip.
 - b. Click **OK**.

Results

The active report now contains all of the objects that you need to build the sales analysis report. In the following tasks, you will add data to each control and define connections between controls so that they can interact with each other.

Adding data to the check box group control

This task defines the data that will appear in the check box group control. The data will appear as the check box label.

Procedure

1. Click the **Check Box Definitions** icon .
2. Under **Data Table**, click **Check Box Label 1** and then click the ellipsis button.
3. In the **Default text** box, type Show Region and click **OK** twice.

Adding a default card to the deck and data to the data discrete values slider



This task adds a default card to the deck and defines the data that will appear in the data discrete values slider control.

No content will be added to default card so that the slider will be hidden when the check box in the check box group control is cleared. The slider control is in the first card of the deck.

Procedure

1. Click the container selector (three orange dots) of the deck so that the entire deck is selected.


Tip: The container selector is visible only when the visual aid **Show Container Selectors** is enabled.

2. In the **Properties** pane, set the **Default Card** property to **Yes**.
A **No Data Contents** tab is created for the deck.
3. Click the **Deck** tab .
4. Click the **Source** tab  and do the following:
 - a. Expand **Sales (query)** and then **Retailers**.
 - b. Drag **Region** to the **Label** box of the slider.

Defining a connection between the check box group and the deck

This task defines a connection between the check box group control and the first deck control that you inserted in the report. The connection will allow users to show or hide the slider control when the check box is selected or cleared.

Procedure

1. In the check box group control, click the **Create a New Connection** icon .
2. Ensure that the following information is specified:
 - **Deck1** appears in the **Target Control** list.
 - **Select** appears in the **Behavior** list.
 - **Label** appears in the **Data Item** list for the source control.
3. Under **Target Control**, click the **Data Item** list and select **Use Source Definition**.




The data value defined for the check box group, Show Region, is copied to the deck control.

4. Optional: In the **Active Report Variable** box, change the default name to a more meaningful name.
5. Click **Connect**.




Adding data to the list object

This task adds data items and an active report summary to the list object.

Procedure

1. Click the **Source** tab  and drag the following data items to the list:
 - **Sales (query) > Retailers > Region.**
 - **Sales (query) > Products > Product line.**
 - **Sales (query) > Sales > Quantity.**
 - **Sales (query) > Sales > Revenue.**
 - **Sales (query) > Sales > Planned revenue.**
2. Pause the pointer over the **Query Explorer** icon  and click **Query2**.
3. Click the **Toolbox** tab  and drag **Data Item** to the **Data Items** pane. The **Data Item Expression** window appears.
4. Copy and paste the following expression into the **Expression Definition** box and click **OK**:



```
([Revenue] - [Planned revenue]) / abs([Planned revenue])
```

This data item calculates the percentage difference between revenue and planned revenue.
5. In the **Properties** pane of the data item, modify the following properties:
 - a. In the **Name** property, delete the default name and type % Difference.
 - b. Change **Aggregate Function** to **Calculated**.
6. Pause the pointer over the **Page Explorer** icon  and click **Page1**.
7. Click the **Data Items** tab  and drag % **Difference** from **Query2** to the end of the list.
8. Click the % **Difference** column body in the list.
9. In the **Properties** pane, double-click the **Data Format** property and do the following:
 - a. Click the **Format type** list and select **Percent**.
 - b. In the list of properties, click the **No. of Decimal Places**, select 2, and click **OK**.
10. With the % **Difference** column still selected, in the toolbar, click the **Summarize** icon  and under **Summarize in Output**, click **Total**.

Defining a connection between the slider and the list object

This task defines a connection between the slider control and the list object. The connection will allow users to filter data in the list as the slider thumb is moved.


Procedure

1. In the slider control, click the **Create a New Connection** icon .
2. Specify the following information:
 - a. In the **Target Control** list, click **List1**.
 - b. In the **Behavior** list, click **Filter**.
 - c. Ensure that **Region** appears in the **Data Item** list for both the source and target controls.
3. Optional: In the **Active Report Variable** box, change the default name of the variable that will be created when the connection is defined to a more meaningful name.
4. Click **Connect**.

Adding a title to the list

This task adds a title to the list. The title will change according to the region selected in the slider.




Procedure

1. Click the **Toolbox** tab  and drag **Text Item** to the first block that you inserted when you created the active report.
2. Type **Sales by Region:**, add a blank space, and then click **OK**.
3. Select the text item in the report and in the **Properties** pane, modify the following properties:
 - a. For the **Foreground Color** property, specify blue and click **OK**.
 - b. For the **Font** property, specify 12 pt as the size and bold as the weight and click **OK**.
4. From the **Toolbox** tab, drag **Variable Text Item** after the text item.
5. Select the name of the variable that you created when you defined the connection between the slider and the list.
6. Repeat step 3 for the variable text item.

Adding data to the data deck and chart

This task adds data items to the data deck and to the pie chart.

Procedure

1. Click the **Source** tab  and drag the following data item to the **Values** box of the data deck:
Sales (query) > Products > Product line
2. Drag the following data items to the chart:
 - **Sales (query) > Sales > Quantity** to the **Default measure** box.
 - **Sales (query) > Products > Product line** to the **Series (pie slices)** box.
 - **Sales (query) > Retailers > Region** to the **Categories (pies)** box.
3. With the pie chart selected, in the **Properties** pane, click the **Exploded Slices** property and do the following:
 - a. Select the default value and click the **Delete** icon .
 - b. Click the **New** icon .


- c. Change **Exploded amount** to 25.
- d. In the **Exploded slice** section, click **Expression** and then click the ellipsis.
- e. In the **Expression Definition** box, type the following, and click **OK** three times.


```
[Query3].[Product line]=[Query4].[Product line]
```
4. In the **Properties** pane, click the **Clickable Regions** property, select the **Legend Labels** check box, and click **OK**.
By default, the **Intersections** check box is selected. By making the legend labels clickable, users will be able to click different pie slices in the chart or different product lines in the legend.
5. Optional: If you do not want to use the pie chart default colors, specify the colors that you want by clicking the available properties in the **Color & Background** property group.
For example, you can change the color palette for the chart by clicking the **Palette** property.

Defining a connection between the chart and the data deck

This task defines a connection between the pie chart and the data deck. The connection will create an active report variable that will be used to update the chart title. The title is described in the next topic.


Procedure

1. In the pie chart, click the **Create a New Connection** icon .
2. Specify the following information:
 - a. In the **Target Control** list, click **Data Deck1**.
 - b. Ensure that **Select** appears in the **Behavior** list.
 - c. Ensure that **Product line** appears in the **Data Item** list for both the source and target controls.
3. Optional: In the **Active Report Variable** box, change the default name of the variable that will be created when the connection is defined to a more meaningful name.
4. Set **Camping Equipment** as the default value for the variable by doing the following:
 - a. In the **Active Report Variable** box, click **Set Default Value(s)**.
 - b. In the **Values** box, double-click **Camping Equipment** and then click **OK**.
5. Click **Connect**.

Adding a title to the chart

This task adds a title to the pie chart. The title will change according to the product line selected in the chart legend.

Procedure

1. Click the **Toolbox** tab  and drag **Text Item** to the second block that you inserted when you created the active report.
2. Type **Sales by Product Line:**, add a blank space, and then click **OK**.
3. Select the text item in the report and in the **Properties** pane, modify the following properties:
 - a. For the **Foreground Color** property, specify blue and click **OK**.

- b. For the **Font** property, specify 12 pt as the size and bold as the weight and click **OK**.
4. From the **Toolbox** tab, drag **Variable Text Item** after the text item.
5. Select the name of the variable that you created when you defined the connection between the chart and the data deck.
6. Repeat step 3 for the variable text item.

Sales analysis report output

When initially viewed, the Sales Analysis active report shows a Show Region check box that is cleared, a list, and a pie chart with Camping Equipment selected in the chart legend.

Selecting the Show Region check box shows the region slider. Moving the slider thumb filters the list to the specified region. Clicking a product line in the pie chart legend highlights the product line in the chart.

The following image shows the Sales Analysis report with the Show Region check box selected, the slider thumb moved to Northern Europe, and with Camping Equipment selected in the chart legend.



Figure 46. Sales Analysis active report

Example - Network diagram visualization

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a visualization in IBM Cognos Active Report that shows the hierarchies of employee by region.

You will use a network diagram visualization to show employees by region, with a data drop-down list to allow users to move between different regions.

Related tasks:



“Adding a network diagram” on page 171

You can create a network diagram in reports. The nodes data container defines the items that you want to link together. The links data container defines relationship between the items that you want to link together.

Adding a new visualization in IBM Cognos Active Report

Create a visualization and add the objects that you require to build the network diagram.

Procedure

1. Open IBM Cognos Report Studio with the **GO Sales (query)** package.
2. In the **Welcome** page, click **Create new**.
3. In the **New** window, double-click **Active Report**.
4. Double-click the report title and type
Employees by Region
5. Click the **Toolbox** tab , drag a **Visualization** icon  to the work area.
6. From the Visualization Gallery, select a **Network diagram** icon.
7. Click **OK**.
8. From the **Toolbox** tab, drag a **Data Drop-Down List** to the report.

Results

The visualization now contains the objects that you require to build the network diagram. In the following tasks, you will add data to each control and define connections between controls so that they can interact with each other.

Adding data to the nodes data container

In IBM Cognos Active Report, the nodes data container defines the items that you want to link together.

Procedure


Click the **Source** tab , and complete the following steps:

1. Expand **Sales (query)** and then **Sales staff**.
2. Drag **Sales staff code** to the **Nodes1** data container, under **Node (numeric)**.
3. Drag **Staff name** to the **Nodes1** data container, under **Name**.
4. Drag **Sales region** to the **Nodes1** data container, under **Extra categories**.

Adding data to the links data container

In IBM Cognos Active Report, the links data container defines relationship between the items that you want to link together.

Procedure




Click the **Source** tab , and complete the following steps:

1. Expand **Sales (query)** and then **Sales staff**.
2. Drag **Manager code** to the **Links1** container, under **From node (numeric)**.
3. Drag **Sales staff code** to the **Links1** data container, under **to node (numeric)**.
4. Drag **Sales region** to the **Links1** data container, under **Extra categories**.

Defining a connection between the data drop-down list and the visualization object

This task in IBM Cognos Active Report defines a connection between the data drop-down control and the visualization object. The connection will allow users to filter data in the list as different regions are selected.

Procedure

1. From the **Source** tab , expand **Sales (query)** and drag **Sales region** to the data-drop-down list box of the data-drop-down list control.
2. In the data-drop-down control, click the **Create a New Connection** icon .
3. Complete the following steps:
 - a. In the **Source Control** list, click **Sales region**.
 - b. In the **Behavior** list, click **Filter**.
 - c. In the **Target Control** list, leave the default as **Links1**.
4. Click **Connect**.
5. In the data-drop-down control, click the **Create a New Connection** icon again.
6. Complete the following steps:
 - a. In the **Source Control** list, click **Sales region**.
 - b. In the **Behavior** list, click **Filter**.
 - c. From the variable drop-down list, click **Reuse an existing variable**.
 - d. In the **Target Control** list, select **Nodes1**.
7. Click **Connect**.
8. Select the **Links1** data container.
9. In the content pane, click the **Active Report Controls** tab .
10. In the Active Report Controls pane, expand and click **Data Drop-Down List1** and click **Set Default Value(s)**.
11. In the Default Variable Values window, under **Values**, select **Northern Europe** and use the arrow icon to move it to **Selected values**.
12. Click **OK**.
13. Run the report.

Network diagram visualization output

When initially viewed, the network diagram visualization in IBM Cognos Active Report shows the employee network for the Americas region.

Select different regions from the drop-down list and the employee network for that region is displayed.

The following image shows the Employees by Region report with the drop-down list selected for the Northern Europe sales region.




Figure 47. Network diagram visualization

Chapter 10. Relational Reporting Style

The relational reporting style is recommended for relational data sources. Relational data is best represented by lists. This data is organized in IBM Cognos Report Studio by query items.

In relational reporting, you summarize data by using headers and footers in lists, summary functions, and within detail aggregation. You focus data in relational reporting with summary or detail filters.

IBM Cognos Query Studio is also available to work with relational data.

Add Relational Data to a Report


Select the data items to appear in the report.

Note: We recommend using relational data in the relational reporting style. However, if you are using dimensional data, see “Add Dimensional Data to a Report” on page 267.



If you frequently use items from different query subjects or dimensions in the same reports, ask your modeler to organize these items into a folder or model query subject and then to republish the relevant package. For example, if you use the product code item in sales reports, the modeler can create a folder that contains the product code item and the sales items you need.

Procedure

1. From the **Source** tab , drag each query item to the report.

Note: A flashing black bar indicates where you can drop an item. Items inserted in the report appear on the **Data Items** tab .

Other ways to select data items are to double-click each item or to right-click each item and click **Insert**.

2. If you want to remove a data item from the report, select it and click the delete button . To remove the data item from the report but keep it on the **Data Items** tab , click the cut button instead.
3. For more information about a query item, right-click the item in the **Source** tab and click **Properties**. For example, when working with relational data sources, the **Usage** property identifies the intended use for the data represented by the data item. You can also obtain more information by clicking **Lineage**.

Group Relational Data

Group data items in a list report to remove duplicate values. For example, you have a report that shows all the products purchased and their product type. You group the Product type column so that each product type cell spans the products purchased cells.

You can specify whether grouping a column automatically makes it the first column in the list by selecting **Group and automatic summary behavior for lists** in the IBM Cognos Report Studio options. With this option selected, if the list contains any fact or measure columns, footers that show the summary values for the columns are automatically created for each group. Grouping a second column makes it the second column. When you ungroup a column, that column becomes the first column after the grouped column.

After a column is grouped, you can move it elsewhere in the report.

You can also group data items in repeaters and in page sets.

In addition to grouping, you can specify the sort order of data items. In lists, you can sort data items within groups as well as ungrouped items. In crosstabs, you can sort row and column items. For more information, see “Perform Advanced Layout Sorting” on page 249.


Tip: The Succession Report sample report in the GO Data Warehouse (analysis) package includes grouping. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure

1. Click the column on which to group.

You can click either the column title or one of the column cells.

Tip: To perform multiple groupings at once, use Ctrl+click or Shift+click.

2. From the **Structure** menu, click **Group/Ungroup** .

Results

A symbol appears indicating that the column is grouped. You can control when its values appear by setting the group span, and the column appears in the list of headers and footers that you can add to the report.

Note: Grouping all columns in a list is equivalent to creating a single-edge crosstab.

Perform Advanced Grouping

You can perform more advanced groupings in a list to get the results you want.

For example, you can

- view the entire grouping structure and make changes to the grouping order
- group a data item that appears in a query but not in the layout
- specify a list of properties for a group

You can also perform advanced sorting.

Procedure

1. Click a column in the list.
2. Click the select ancestor button  in the title bar of the **Properties** pane and click **List**.

Tip: You can also click the container selector (three orange dots) of the list to select it.

3. In the **Properties** pane, double-click the **Grouping & Sorting** property.
4. To change the grouping order, in the **Groups** pane, click the grouped item in the **Groups** folder and drag it to the grouping hierarchy.
5. To create a new grouping, in the **Data Items** pane, click the data item and drag it to the **Groups** folder in the **Groups** pane.
6. To specify a list of data items for a group, do the following:
 - Click the group.

Tip: Click **Overall** to specify a list of data items for the overall group. The overall group is the grouping of all data into one group. You can specify a list of data items for the overall group to add overall totals to the list.

- Click the properties button .
- Select the appropriate check boxes.

Creating relational custom groups

Create custom groups to classify existing data items into groups that are meaningful to you.


You can use custom groups to convert numeric values into broader categories. For example, you can break down sales results into low, medium, and high categories. Or you can reduce the number of values into a smaller, more meaningful groups. For example, you can change a list of employees into separate teams or departments.

When you create custom groups in a list, a new column is added to the report, with the name *data item* (Custom). You can use this new column to group or sort the report. If you want to show only the new groups, you can delete the original column.

Procedure

1. Click the column that you want to group on and, from the **Data** menu, click **Calculate > Define Custom Groups**.

Tip: You can click either the column heading or one of the column cells.

2. Click the **New Group Entry** icon .
3. To group by values that you select, click **New Select Values Group**, type a **New group name**, select the required values from the **Values** box, and move the values to the **Selected values** box.
4. To group by a range of values, click **New Range Group**, type a **New group name**, and enter the **From** and **To** values.
5. If you do not want a group name to appear for remaining values, select **Do not show remaining values**. Clicking this option will produce empty cells for remaining values.
6. If you want the group name for remaining values to match each value, select **Use each remaining value as a group name**.
7. If you want to specify your own group name for all remaining values, select **Group remaining values into a single group** and type the name that you want.

8. If you are adding custom groups in a list, under **New data item name**, select either the default data item name or type a new data item name.

Set the Group Span for a Column

When columns are grouped, you can choose how often to show column names by changing the group spanning.

For example, when country or region and city are both grouped, you can choose to show the country or region name each time

- the country or region changes, by spanning Country or Region by Country or Region
- the city changes, by spanning Country or Region by City
- there is a new record, by specifying no spanning

Spanning one grouped column by another column is helpful if the second column contains many items.


Procedure

1. Click the column that will span the other column(s).
2. In the **Properties** pane, set the **Group Span** property to the column to span.

Example - Remove Identical Values in a List

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a report that lists all product orders organized by order number. To make the report easy to read, you group the Order number column so that only one instance of each order number appears. However, because each order contains different products, the same order date appears for each product. You decide to show the order date only when the order number changes.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **List** and click **OK**.
4. In the **Source** tab , expand **Sales and Marketing (query)** and **Sales (query)**.
5. Expand **Sales order** and add **Order number** by double-clicking it.
6. Expand **Time dimension** and add **Date** by double-clicking it.
7. Expand **Product** and add **Product name** by double-clicking it.
8. Expand **Sales fact** and add **Quantity** and **Revenue** by double-clicking them.
9. Group the **Order number** column.
10. Click the **Date** column.
11. In the **Properties** pane, set the **Group Span** property to **Order number**.

Results


When you run the report, the first row of the **Order date** column appears for each **Order number** row.


Order number	Date	Product	Quantity	Revenue
100001	Jan 12, 2010	Flicker Lantern	256	8,624.64
		Polar Ice	92	9,411.6
100002	Jan 12, 2010	Edge Extreme	162	18,032.22
		Bear Edge	172	6,690.8
		Glacier GPS Extreme	74	24,747.82
		Mountain Man Deluxe	90	6,825.6
		Insect Bite Relief	422	2,532
100003	Jan 12, 2010	BugShield Extreme	3,252	21,170.52
		Sun Shield	1,107	6,376.32
		Polar Extreme	19	2,733.15
		Seeker 50	88	10,975.36
100004	Jan 12, 2010	Star Gazer 2	139	75,289.35
		TrailChef Deluxe Cook Set	279	33,658.56
		Star Lite	261	89,841.42
		Hibernator Lite	354	29,658.12
100005	Jan 12, 2010	Bear Survival Edge	120	10,299.6
		Mountain Man Combination	44	4,139.96
		Mountain Man Extreme	24	6,711.84
		Double Edge	382	6,165.48
		Lady Hailstorm Titanium Woods Set	26	32,878.04

Example - Repeat a Column Value in a List

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a report that lists all products sold by the company, organized by the product line and product type. To make the report easier to read, you group the Product line and Product type columns so that only one instance of each column appears. However, because some product lines contain many different product types and products, you decide to show the product line for each product type.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **List** and click **OK**.
4. In the **Source** tab , expand **Sales and Marketing (query)**.
5. Expand **Sales (query)** and **Product** and add the following data items by double-clicking them:
 - **Product line**
 - **Product type**
 - **Product name**
6. Expand **Sales fact** and add **Product cost** by double-clicking it.
7. Group the **Product line** and **Product type** columns.
8. Click the **Product line** column.
9. In the **Properties** pane, set the **Group Span** property to **Product type**.

10. Click any part of the list and then click the select ancestor button  in the title bar of the **Properties** pane.

11. Click **List**.

Tip: You can also click the container selector (three orange dots) of the list to select it.

12. In the **Properties** pane, double-click the **Font** property.

13. In the **Size** box, click **8pt**.

Results

When you run the report, the product line appears whenever the product type changes.

Product line	Product type	Product	Product cost
Camping Equipment	Cooking Gear	TrailChef Canteen	6,607,904.78
		TrailChef Cook Set	28,305,454.21
		TrailChef Cup	1,545,089.31
		TrailChef Deluxe Cook Set	35,527,805.84
		TrailChef Double Flame	18,416,925.00
		TrailChef Kettle	11,373,514.16
		TrailChef Kitchen Kit	13,608,439.00
		TrailChef Single Flame	31,839,545.34
		TrailChef Utensils	8,611,463.50
		TrailChef Water Bag	11,292,005.38
Camping Equipment	Lanterns	EverGlow Butane	4,792,227.24
		EverGlow Double	1,421,083.75
		EverGlow Kerosene	6,304,040.00
		EverGlow Lamp	13,459,561.68
		EverGlow Single	10,363,144.02
		Firefly 2	9,088,038.23
		Firefly 4	4,968,302.40
		Firefly Extreme	4,838,898.69
		Firefly Lite	3,717,927.00
		Firefly Mapreader	5,734,965.00

Figure 48. List showing product line, product type, product name, and product cost


Divide Data into Sections

Create sections in a report to show a data item as the heading of a section. When you run the report, separate sections appear for each value.

Creating sections is similar to creating headers by grouping on a data item. The difference is that section headers appear outside the list, crosstab, chart, or repeater. In addition, you can group data items only in lists.

When working with dimensional data, you can also create page layers to show values on a separate page for each member.



Procedure

1. Click the column to make a section heading.
2. Do one of the following:
 - From the **Structure** menu, click **Section** .
If the column is in a list or repeater, this menu option will create sections without creating a master detail relationship. This can improve performance when running the report.
If the column is in a crosstab or chart, this menu option will create sections using a master detail relationship.
 - From the **Structure** menu, click **Section Using Master/Detail**.
This menu option creates sections using a master detail relationship.
Sections are created, and a section header appears. The data container that contains the column used to create sections is embedded in a list.
3. To add or remove section headers and footers, from the **Structure** menu, click **Headers & Footers**, click **List Headers & Footers**, and select or clear the appropriate check boxes.
The section header and footer check boxes appear under **Overall header**.

Remove Sections

You can remove sections and reinsert the data item that was used to create the sections in the data container.

Procedure

1. From the **View** menu, click **Page Structure**.
2. Expand the page containing the data container with the section.
3. Expand **Page Body** until you see the data container in which you added the section.
The data container is nested in the **List Column Body** object of the **List** object that is created when you add a section.
4. Drag the data container to **Page Body**.
The data container appears as a node of **Page Body**.
5. Delete the **List** object.
6. From the **View** menu, click **Page Design**.
7. From the **Data Items** tab , drag the data item that was used as a section header back into the data container.
8. If you created sections in a list without creating a master detail relationship, click the data item, and then click the group/ungroup button  to ungroup the item.

Summarizing Data Relationally

Summarize data in your reports to obtain totals, averages, and so on.

In a report, you can add both detail and summary aggregation. Detail aggregation, which is supported only for relational data sources, specifies how a data item is totaled at the lowest level in a report. In lists, detail aggregation specifies how the values that appear in the rows are totaled. In crosstabs, detail aggregation specifies how the values in the cells are totaled. For example, detail aggregation for a

measure like Revenue might be Total in both lists and crosstabs. In the following list report, this means that the values you see for the Revenue column represent the total revenue for each product type.

Product line	Product type	Revenue
Camping Equipment	Cooking Gear	272,835,984.18
	Lanterns	126,925,660.64
	Packs	351,880,402.84
	Sleeping Bags	309,172,888.35
	Tents	528,221,728.02
Golf Equipment	Golf Accessories	51,514,343.88
	Irons	254,814,337.99
	Putters	106,184,271.37
	Woods	313,898,414.65

Figure 49. A list showing product line, product type, and revenue

Summaries, which are supported for all data sources, specify how data items are totaled in the headers and footers of a list and in the total rows and columns of a crosstab. For list reports, these summaries only summarize the data that is visible on that page of the report.

You can specify detail and summary aggregation in different ways by using any of the following:

- aggregation properties that are specified in the model
- the **Auto Group & Summarize** property
- the summarize button in the toolbar
- aggregation properties for a data item
- summary functions in data item expressions
- the solve order of calculations

Tip: When you add a summary by clicking the summarize button in the toolbar, a data item is created in the query for the summary. In lists, the data item that is created is called a list summary. In crosstabs and charts, the data item that is created is called an edge summary.

Limitation

If a summary is applied to a report that contains binary large object (BLOB) data, such as images or multimedia objects, you cannot also perform grouping or sorting.

The Type of Data

How data is aggregated also depends on the type of data that you are aggregating. Aggregation rules are applied differently to facts, identifiers, and attributes. For example, if you aggregate a data item that represents part numbers, the only aggregate rules that apply are count, count distinct, count non-zero, maximum, and minimum. For information about how to determine the type of data that a data item represents, see “Add Relational Data to a Report” on page 227 and “Add Dimensional Data to a Report” on page 267.

Add a Simple Summary

You can add simple summaries to the groups in a report by using the summarize button in the toolbar. This button provides a subset of the summary functions available in IBM Cognos Report Studio. For list reports, a **Custom** option is also available so that you can add your own summary function in the expression of the data item.

The summarize button sets the rollup aggregate property for the data item to the selected summary, and places the data item into an appropriate footer. A footer is created for each group as well as an overall footer, unless they already exist.


In lists, the summary appears as a footer. If the column to which you added a summary is grouped, group and overall summaries appear. In crosstabs and charts, the summary appears as a node.

To change a summary, select it and, in the **Properties** pane, under **Data Item**, click **Rollup Aggregate Function** and choose a different function.

In crosstabs, you can add multiple summaries at the same level. For example, you have a crosstab with Product line as rows, Order year as columns, and Revenue as the measure. For Product line, you can add the **Total** summary as a header, which will total all revenue for each order year. You can then add the **Average** summary as a footer, which will give the average revenue of all product lines for each order year.

For information about adding a rolling or moving average, see “Rolling and Moving Averages” on page 286.

Procedure


1. Click the column to which to add a summary.
2. Click the summarize button  and click a summary type.
3. To change the summary label, do the following:
 - Click the label.
 - In the **Properties** pane, under **Text Source**, set the **Source Type** property to the source type to define the label.
For example, set it as **Data Item Value** to produce a dynamic label for the summary based on data item values.
 - Set the property under **Source Type** to specify the label.
This property depends on the source type you chose. For example, if you chose **Data Item Value** as the source type, set the **Data Item Value** property to the data item to use to define the label.

Set the Auto Group & Summarize Property

Set the **Auto Group & Summarize** query property to specify whether IBM Cognos Report Studio should group non-fact data items (identifiers and attributes) and apply aggregate functions to aggregate fact data items in lists.

If you are using an OLAP data source, data is always summarized regardless of how this property is set.

Procedure

1. Pause the pointer over the query explorer button  and click a query.
2. In the **Properties** pane, set the **Auto Group & Summarize** property:
 - To group non-aggregate fact data items and apply aggregate functions to aggregate fact data items in lists, set this property to **Yes**.
 - To render detail rows, set this property to **No**.

Specify Detail or Summary Aggregation in the Model

When working with relational or dimensionally-modeled relational (DMR) data sources, you can use the aggregation properties specified for the query item in the IBM Cognos Framework Manager model instead of specifying detail or summary aggregation in the report. The model specifies the default summary function for each query item.

Aggregation functions are mapped between data sources, Framework Manager, and IBM Cognos Report Studio.

Specify Aggregation Properties for a Data Item

When working with relational data sources and list reports, for each data item in a report, you can specify detail and summary aggregation properties to manage summaries without having to create complex data item expressions.

Procedure

1. Click the data item for which to set detail or summary aggregation.
2. In the **Properties** pane, set the **Aggregate Function** or the **Rollup Aggregate Function** property to a function.

Use Summary Functions in Data Item Expressions

You can use summary functions in data item expressions. The summary functions in the expression editor that have the same name as the summary functions available through the **Aggregate Function** and **Rollup Aggregate Function** properties operate the same way. For example, in a relational report, setting the **Aggregate Function** property to **Total** is the same as changing the expression of the data item to `total ([Revenue])`.

In general, report maintenance is easier if the **Aggregate Function** and **Rollup Aggregate Function** properties are used rather than adding summary functions to data item expressions. Use summary functions in expressions if the required summary is not supported as an aggregate or rollup aggregate property or if the complexity of the expression cannot be managed using the data item properties. Add a summary function to a data item expression if one of the following conditions applies:

- The underlying data source is relational, and you want to use database vendor-specific summary functions.
- You want to use summary functions that require more than one parameter, such as percentile.
- You require summary expressions that are not available in the aggregation properties, such as a `for` clause. You should use `for` clauses only in relational style reports (list reports).

For example, your report uses Product line, Product type, and Quantity. You want to calculate the percentage of the parent quantity that is represented by each product type. This requires you to compare the total quantity for each product type to the total quantity for the parent product line. In other words, your expression requires summaries at different group levels. You use summary functions, such as aggregate, in the data item expression with a for clause to specify the group level as follows:

[Quantity] / aggregate ([Quantity] for [Product line])

Product line	Product type	Quantity	% of Product Line
Camping Equipment	Cooking Gear	13,400,351	49%
	Lanterns	4,826,755	18%
	Packs	2,756,540	10%
	Sleeping Bags	3,153,218	12%
	Tents	3,164,285	12%
Camping Equipment - Summary		27,301,149	100%
Golf Equipment	Golf Accessories	3,119,747	61%
	Irons	391,445	8%
	Putters	1,284,570	25%
	Woods	317,939	6%
Golf Equipment - Summary		5,113,701	100%

In some cases, you may need a summary that is different from the default. For example, if the default summary for Quantity is total, you can calculate the average as follows:

[Quantity] / average (aggregate ([Quantity]) for [Product line])

Product line	Product type	Quantity	% of Product Line Average
Camping Equipment	Cooking Gear	13,400,351	245%
	Lanterns	4,826,755	88%
	Packs	2,756,540	50%
	Sleeping Bags	3,153,218	58%
	Tents	3,164,285	58%
Camping Equipment - Summary		27,301,149	100%
Golf Equipment	Golf Accessories	3,119,747	244%
	Irons	391,445	31%
	Putters	1,284,570	100%
	Woods	317,939	25%
Golf Equipment - Summary		5,113,701	100%

The inner summary gives you the expected Quantity values at the Product Type level, which are then averaged to the Product Line level. This two-stage aggregation is required for OLAP data sources and recommended for relational data sources also.

Why is this necessary? Here's what would happen if you simply averaged Quantity, as follows:

[Quantity] / average([Quantity] for [Product line])

Product line	Product type	Quantity	% of Product Line Average
Camping Equipment	Cooking Gear	13,400,351	2,538,352%
	Lanterns	4,826,755	914,305%
	Packs	2,756,540	522,156%
	Sleeping Bags	3,153,218	597,296%
	Tents	3,164,285	599,392%
Camping Equipment - Summary		27,301,149	5,171,500%
Golf Equipment	Golf Accessories	3,119,747	1,205,327%
	Irons	391,445	151,236%
	Putters	1,284,570	496,299%
	Woods	317,939	122,837%
Golf Equipment - Summary		5,113,701	1,975,700%

The denominator is now computed as the average of the detail Quantity rows in the underlying fact table. Since these values are much smaller than the pre-summarized Quantity values you see in the report, the resulting percentage is far too big, and not what we wanted.

Tip: The Total Revenue by Country or Region sample report in the GO Data Warehouse (query) package includes a total summary function. For more information about The Sample Outdoors Company samples, see Appendix C, "Sample Reports and Packages," on page 525.

Procedure

1. Click a data item.
2. In the **Properties** pane, double-click the **Expression** property and add summary functions to the expression for the data item.


Related concepts:

"Limitations When Using Clauses in Summary Functions" on page 550

A summary function that uses a for clause may yield unexpected results. These may include error messages, warnings, incorrect numbers, and more or fewer than expected rows, columns, or chart points and lines.

Summary Functions

This section describes the summary functions that are available in IBM Cognos Report Studio. Some functions, such as **Custom**, are available only when you click

the summarize button  on the toolbar. Additional summary functions are available in the expression editor.

Automatic Summary

Depending on the type of data item, applies the function **None**, **Summarize**, or **Calculated** based on the context in which the data item appears.

Calculated is applied if the data item expression

- contains a summary function
- is an if then else or case expression that contains a reference to at least a modeled measure in its condition
- contains a reference to a model calculation or to a measure that has the **Regular Aggregate** property set to a value other than **Unsupported**
- contains a reference to at least one data item that has the **Rollup Aggregate Function** property set to a value other than **None**

If the underlying data source is relational and if the data item expression contains no summary functions and a reference to at least one fact that has the **Regular Aggregate** property set to a value other than **Unsupported**, **Summarize** is applied.

In all other contexts, **None** is applied.

For relational and dimensionally modeled relational (DMR) data sources, if this function is applied to a data item expression that has the average function, weighted averages are computed based on the lowest level detail values in the data source.

Note: This is the default function.

Average

Adds all existing values and then divides by the count of existing values.

Calculated

Specifies that all the terms within the expression for a data item are aggregated according to their own rollup rules, and then the results of those aggregations are computed within the overall expression.

For example, a list contains the data item Quantity with the **Aggregation** property set to **Total**. You add a query calculation named Quantity Calculated. You define its expression as Quantity + 100 and you set its **Aggregation** property to **Calculated**. When you run the report, the values for Quantity Calculated are computed by first adding all values for Quantity and then adding 100 to each value.

Note: In crosstabs, this function overrides any solve orders that are specified.

Count

Counts all existing values.

If the underlying data source is dimensionally modeled relational (DMR), Count behaves as follows if it is specified in the **Aggregate Function** or **Rollup Aggregate Function** property for a data item.

Object	Behavior
Level	Count distinct is used. A warning appears when you validate the report.
Member set	Count distinct is used. A warning appears when you validate the report.
Attribute	Supported.
Measure	Supported.

If you add the count summary to a non-fact column in a list and then group the column, the column will not be grouped when you run the report. To resolve this issue, group the column first before adding the count summary.

Count Distinct

Returns the total number of unique non-null records.

If the underlying data source is dimensionally modeled relational (DMR), count distinct is supported for levels, member sets, attributes, and measures when it is specified in the **Aggregate Function** or **Rollup Aggregate Function** property for a data item.

Custom

Summarizes data based on an expression that you define.

Maximum

Selects the largest existing value.

Median

Returns the median value of the selected data item.

Minimum

Selects the smallest existing value.

None

Does not aggregate values.

If the underlying data source is relational, the data item is grouped when the query property **Auto Group & Summarize** is set to **Yes**.

Not Applicable

This function is available only for the **Aggregate Function** property. It specifies that the aggregate attribute is ignored. For example, the calculation will be applied after the data is aggregated.

This function differs from the **Calculated** function, which applies aggregation to the rows and then performs the calculation.

For example, for the average ([Quantity]) + 5 expression, when the **Aggregate Function** property is set to **Not Applicable**, five is added to the average of the single Quantity value. When the function is set to **Calculated**, five is added to the average of a set of numbers.

This setting should not be applied to a simple model reference.

This setting is relevant only for reports that are upgraded from IBM Cognos ReportNet 1.x.

Standard Deviation

Returns the standard deviation of the selected data item.

Note: From a mathematical perspective, this function is not useful for small numbers of items and is not supported if the query property **Auto Group & Summarize** is set to **Yes**.

Summarize

Aggregates data based on model or data type information. This function can be thought of as a calculate and then aggregate rule. Data is aggregated using the following rules:

If the underlying data source type is relational and the data item or calculation is a reference to a single fact query item in the model that has the **Regular Aggregate** property set to **Sum**, **Maximum**, **Minimum**, **Average**, or **Count**, aggregate data using this function. Otherwise, data is aggregated according to the data type of the data item as follows:

- **Total** is applied for numeric and interval values.
- **Maximum** is applied for date, time, and date-time values.
- **Count** is applied for everything else.

The underlying data source type can be dimensional and the data item or calculation a reference to a single item in the model. In this case, if the **Regular Aggregate** property of the model item is not **unknown**, the summary function that corresponds to the **Regular Aggregate** property is applied. If the **Regular Aggregate** property is **unknown**, set the function to **Calculated**.

For example, a list contains the data item Quantity with the **Aggregation** property set to **Average**. You add a query calculation named Quantity Summarize. You define its expression as Quantity + 100 and you set its **Aggregation** property to **Summarize**. When you run the report, the values for Quantity Summarize are computed by first adding 100 to each value for Quantity and then calculating the total. The total is calculated because Quantity contains numeric values and the expression for Quantity Summarize is not a simple data item reference. If Quantity Summarize is defined as Quantity, the function **Average** is applied to each value.

Total

Adds all existing values.

Variance

Returns the variance of the selected data item.

Note: From a mathematical perspective, this function is not useful for small numbers of items and is not supported if the query property **Auto Group & Summarize** is set to **Yes**.

Mapping Aggregation Functions From Data Sources to Framework Manager and Report Studio

The summary functions available in IBM Cognos Framework Manager and IBM Cognos Report Studio reflect summary functions supported by relational and dimensional data sources. The following table shows how summary functions in data sources are mapped to Framework Manager and Report Studio.

Data source	Framework Manager	Report Studio
None specified, or none	Unsupported	None
average (avg)	Average	Average
count	Count	Count
count distinct	Count Distinct	Count distinct
maximum (max)	Maximum	Maximum
minimum (min)	Minimum	Minimum
median	Median	Median
standard deviation (stddev)	Standard Deviation	Standard Deviation
sum	Sum	Total
variance (var)	Variance	Variance
count non zero	Count Non-Zero	Automatic
average non zero	unknown	Automatic
external	unknown	Automatic
any	unknown	Automatic
calculated	unknown	Automatic
unknown	unknown	Automatic
first_period	unknown	Automatic
last_period	unknown	Automatic

The following summary functions exist only in either Framework Manager or Report Studio. There is no corresponding summary function in data sources.

Framework Manager	Report Studio
Automatic	Automatic
Calculated	Calculated
No corresponding summary function	Summarize
No corresponding summary function	Not Applicable

Focusing Relational Data

You can limit the data in your report with filters or query parameters. The method you choose should depend on the capabilities of the data source, the performance requirements, the persistence of the dataset, and how complex you want the report to be.

In IBM Cognos Report Studio, summary and detail filters are best for list reports in the relational reporting style. Summary filters are applied to summaries and detail filters are applied to details. These filters remove rows and columns from your reports.

You can also use prompts, or prompt controls, to allow report users to provide input for the filter.

Create a Detail or Summary Filter

Add a filter expression to focus a report and minimize processing time by excluding unwanted data. For example, you can filter data to show only customers who placed purchase orders that were valued at over one thousand dollars during the past year. When you run the report, you see only the filtered data.

Detail filters are applied only to detail data items from the data source, and not to summary data items. Examples of detail data items include customer names, product numbers, and order numbers. Detail filters are Boolean expressions that apply one or more conditions and evaluate to either true or false. If the conditions are true for a row of data, the row is retrieved from the data source and appears in your report. If the conditions are false, the row is not retrieved and does not appear in your report. You can specify whether detail filters are applied before or after summaries using the **Application** property.

Tip: The 2011 Sales Summary sample report in the GO Sales (analysis) package includes a detail filter. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Summary filters are applied to summary data items in a report. They are also Boolean expressions, however they are used to exclude specific groups of data items based on the group summaries. They are based on summary calculations.

You can combine multiple conditions using AND, OR, and NOT operators. By default, multiple conditions are combined with an AND operator, which means that all conditions must be met for the filter to take effect.



For relational data sources, if a filter expression is used in multiple reports or by different report authors, ask your modeler to create the filter as a standalone object in the model and include it in the relevant package. For information about creating filters in the package, see the IBM Cognos Framework Manager *User Guide*.

If you are filtering a multiple-fact query, you should understand the differences between using a detail filter and summary filter.

If you filter values that are floating-point numbers, you may encounter imprecise filtering results due to rounding or data truncation. Floating-point numbers may appear differently in the report than how they are stored in the data source. To ensure accurate results, your filter criteria should account for any rounding issues.

If you are working with a Microsoft SQL Server 2005 Analysis Services (SSAS) data source, we recommend that you not use OR filters in summaries. Doing so causes error characters (--) to appear in summaries instead of values.

Procedure


1. To add a filter that was already created in the package, from the **Source** tab , drag the filter  to the report.


You must drag the filter to a data container object that is linked to a query, such as a list, crosstab, or chart.

2. To create your own filter, from the **Data** menu, click **Filters** , and click **Edit Filters**.

To create a simple filter condition based on only one data item, click **Create Custom Filter**.

If more than one query is defined in the report, you must first select a data container object that is linked to a query.

Tip: You can also define filters in **Query Explorer**. Pause the pointer over the query explorer button  and click a query.

3. In the **Filters** dialog box, decide what type of filter to create:
 - To add a filter that will apply to detail values, click the **Detail Filters** tab.
 - To add a filter that will apply to summary values, click the **Summary Filters** tab.
4. Click the add button .
5. In the **Create Filter** dialog box, decide what conditions to include in the filter:
 - To create a simple filter condition based on only one data item, click **Custom based on data item**, select a data item from the query, and click **OK**.
 - To combine multiple filter conditions, click **Combined**, and click **OK**.
 - To create a filter condition that uses advanced calculations, click **Advanced**, and click **OK**.
6. If you create a simple filter condition based on one data item, do the following:
 - a. In the **Filter Condition** window, under **Condition**, select the type of condition that you want.
 - b. If you want to parameterize the filter so that users are prompted when they run the report, select the **Prompt for values when report is run in viewer** check box.
 - c. To choose specific data item values for the filter condition, in the **Values** box, click **Specific values** and choose the values that you want to filter on.

Tip: You can search for values by typing a string in the **Keywords** box. Click the arrow beside **Search** and select the search parameter that you want to use. If you select **Use Tab as keyword delimiter**, you can add a tab in the **Keywords** box only by copying and pasting a tab (or the string you want to search on with a tab in it), from another application, such as Notepad.

- d. To filter values based on a pattern, in the **Values** box, click **Starts with**, **Ends with**, **Contains**, or **Matches SQL pattern**, and type the pattern in the **Value** box.






With the **Matches SQL pattern** choice, you can filter values by using standard SQL syntax to create a SQL supported pattern. You can use a % (percent) symbol to substitute for zero or more characters, or _


(underscore) to substitute for one single character. For example, the pattern '%a_b_c%' returns every value that contains the sequence 'a, any character, b, any character, c' anywhere in the string.


If you search for patterns that include the '%' or '_' characters, specify an escape character in the **Escape character (optional)** box. The value must be a single character. When specified, each occurrence of the escape character causes the next character to be treated as text and not as a special character. For example, if you specify '\\' as the escape character, entering TEST\% in the **Value** box searches for the string 'TEST%' rather than a string that begins with 'TEST' followed by any other characters. Similarly, entering TEST\\% searches for strings that begin with 'TEST%'.

You can specify whether the filter condition is case sensitive or not. A case-sensitive filter is applied only when the data source supports case-sensitive filtering.


Note: When a filter based on a pattern is converted into a prompt, users are prompted to specify a pattern when the report is run.

- e. If you want the filter to include null values, select the **Include missing values (NULL)** check box.
 - f. Click **OK**.
7. If you create a **Combined** filter, do the following:
- a. In the **Create Filter** dialog box, select the data item for the first filter condition and click **OK**.
 - b. In the **Filter Conditions** dialog box, specify the details for the first condition and click **OK**.
 - c. Click the new condition button  and, in the **Create Filter** dialog box, select the data item for the second filter condition and click **OK**.
 - d. In the **Filter Conditions** dialog box, specify the details for the second condition and click **OK**.
 - e. In the **Combined Filter** dialog box, use the AND, OR, and NOT operators to combine the filter conditions. Select the conditions that you want to combine, and click an operator. To change an operator, double-click the operator to toggle among available ones or select the operator and then select a different one from the list.
 - f. Click **OK**.
8. If you create an **Advanced** filter condition, in the **Filter Expression** dialog box, define the filter expression:
- a. To add data items that are not shown in the report, on the **Source** tab , double-click data items.
 - b. To add data items that are in the report but not necessarily in the model (such as calculations), on the **Data Items** tab , double-click data items.
 - c. To add data items from a specific query in the report, on the **Queries** tab , double-click data items.
 - d. To add functions, summaries, and operators, on the **Functions** tab , double-click elements. You can insert only functions that return a Boolean value (true or false). For example, you cannot insert the function topCount because it returns a set of data. Filter expressions must resolve to a Boolean in order to be valid.

e. To add a value that is derived from a parameter, on the **Parameters** tab , double-click the parameter. Parameters define prompts, drill-through reports, and master detail relationships.

f. To add a macro, on the macros tab , double-click the parameter maps, session parameters, or macro functions you want to add to the macro expression.

Tip: Use **Insert macro block** to get you started with creating the macro expression. **Insert macro block** inserts number signs in the expression. Make sure that the macro expression you create is between the number signs.

g. Click the validate button  and click **OK**.

h. Click **OK**.

Tip: You can also type the filter expression directly in the **Expression Definition** box. When typing date values, use the YYYY-MM-DD format. For more information about creating expressions, see “Using Relational Calculations” on page 262.

9. In the **Usage** box, specify whether the filter is required, optional, or not to be used.
10. If you create a detail filter, under **Application**, click one of the following options:
- To apply the filter to individual records in the data source, click **Before auto aggregation**.

For example, for a specific product type within a product line, you want to filter out individual orders that generated less than one thousand dollars in revenue.

- To apply the filter to data after the query has grouped and summarized at the lowest level of detail, click **After auto aggregation**.

For example, you want to filter out the product types that generated less than ten thousand dollars in revenue within a product line.

For example, you have a list that contains the data items Product line, Product type, and Revenue. The revenue values you see are aggregated to the product type level. If you create a detail filter on Revenue and you choose to filter values before auto aggregation, you are filtering non-aggregated revenue values. If you choose to filter values after auto aggregation, you are filtering revenue values aggregated to the product type level.

11. If you create a summary filter, under **Scope**, click the ellipsis button and select the grouping level at which to apply the filter.

For example, a revenue report is grouped on product line and product type. You can choose to filter total revenue for either the product line or product type level.

If the query in which you are creating the summary filter is linked to more than one data container, the data item that you select as the grouping level must be grouped in all data containers linked to the query. Otherwise, the report will not run successfully.



Tip: To filter at the overall level, do not click a level. For example, if a report has an overall footer that shows the total revenue for all products, by not choosing a level you will apply the filter to the footer. In addition, if you are


using a dimensional data source, excluding a parent level excludes its children, and excluding all children excludes the parent.

Edit or remove a filter

After you created filters, you can edit or remove them.

Procedure



1. Click a data container object that contains a filter.
2. To remove all filters from the object, from the **Data** menu, click **Filters** , and click **Remove all Filters**.
3. To edit a filter or remove a single filter, from the **Data** menu, click **Filters** , and click **Edit Filters**.

Tip: You can also edit filters from **Query Explorer**. Pause the pointer over the query explorer button  and click the query that contains your filter.


Browse or Search the Values of a Data Item


When building expressions in the expression editor, you can browse the data of a data item. This is useful when you do not know how a particular value is stored in the database. For example, you want to filter a report so that it shows data for only New South Wales. The actual value in the database for New South Wales is NSW, and this is what you must insert in the filter expression to obtain the correct results.

Procedure

1. In the source, data items, or query tab, right-click the data item you want to browse.
2. If you want to insert a single value, click **Select Value** .
3. If you want to insert multiple values, click **Select Multiple Values** .
4. In the **Values** box, click the value you want to insert in the expression.

Tip: Use the **Keywords** box to search for specific values. If you select **Use Tab as keyword delimiter**, you can add a tab in the **Keywords** box only by copying and pasting a tab (or the string you want to search on with a tab in it), from another application, such as Notepad. If the data source is case sensitive and you want to perform a case insensitive search, click the **Search** arrow and then click **Case Insensitive**.

5. If you clicked multiple values, click the right arrow button  to add them to the **Selected values** box.
6. Click **Insert**.

Tip: To control where values appear in the **Expression Definition** box, you can click the copy button  if you selected a single value or the copy all button if you selected multiple values instead. The values are copied to the clipboard, and you can then paste them where you want.

Related concepts:

“Searching for values might return unexpected results” on page 500

In the expression editor, when searching for values for a data item, the results you obtain might contain unexpected results if the data item is not a string data type. Because you can edit the expression for a data item, IBM Cognos Business Intelligence cannot determine with certainty what the data type is.

Ignoring the Time Component in Date Columns

Database systems use Date, Time, and Timestamp to represent date and time values. While a timestamp type holds a date and time component, an application may allow the RDBMS to default the time component. When rows are inserted, updated, or queried, the application may specify only a date value and leave the RDBMS to extend the value to include a default time (usually 00:00:00.000).

The challenge with a timestamp is when the application has no immediate interest in the time component. For example, the business question How many orders were taken today? implies all orders taken irrespective of what time the order was booked. If the application defaulted the time component as it stored rows, the query that was used to answer the question returns the count of orders taken today. If the application stored the actual time component, the query likely returns no data, because the number of orders entered at midnight is probably zero.

Relying on the time defaults can be dangerous if the application changes and starts to capture actual times. To avoid this problem, you can

- truncate the time by creating a derived column
- convert the timestamp to a date
- create a hi-low filter

Truncating the Time by Creating a Derived Column

In the IBM Cognos Framework Manager model, create a derived column using a calculated expression that truncates the time from a timestamp, and returns a timestamp containing the original date and a default time. For example, if you use an Oracle data source, the following expression creates the derived column DATEONLY from COL1, where COL1 contains the values as stored by the application while DATEONLY contains the dates with the default time of 12:00:00 AM:

```
Select COL1,trunc(COL1) as DATEONLY from [SCOTT_TIGER].DATES
```

Tip: You can change the data format of the column to show only the date value by setting the **Date Style** property to **Short**.

You can then apply filters to the DATEONLY column that would return the correct results. If you create a parameter in IBM Cognos Report Studio that filters on this column, the default prompt will present a date and time control because the data type is still a timestamp.

Converting the Timestamp to a Date

In the IBM Cognos Framework Manager model, define a calculation that uses the cast function to convert the timestamp to a date. For example, the following expression converts the data type of the column COL1 to date:

```
cast ([SCOTT_TIGER].[DATES].[COL1],DATE)
```

If you create a parameter in IBM Cognos Report Studio that filters on this calculation, the default prompt presents a date control.

Ignoring the Time by Creating a Hi-Low Filter

You can create a hi-low filter to ignore the time. In the IBM Cognos Framework Manager model, create a filter in the form date-column between date-lowtime and date-hightime. For example, the following expression returns all values between 00:00:00:000 and 23:59:59:000 for a given day:

```
[SCOTT_TIGER].[DATES].[COL1] between?p1? and  
cast(substring(?p1?,1,10), '23:59.59.000', timestamp)
```

Sorting Relational Data

You can sort items to view them in your preferred order. By default, IBM Cognos Report Studio retrieves items in the order defined in the data source. OLAP data sources always have a defined order. Relational and dimensionally-modeled relational data sources may not always have a defined order. The data modeler defines the sorting options in the model.

For more information about data modeling, see the IBM Cognos Framework Manager *User Guide*. Sorting applied in Report Studio applies only to the layout within the report.

You can sort items in a list in ascending or descending order based on a value or a label, such as revenue or employee name. You can also perform advanced sorting to sort columns within groups or to sort a row or column using another data item.

Tip: The Sales Growth Year Over Year sample report in the GO Data Warehouse (analysis) package includes sorting. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure

1. Click the column or row on which to sort.

2. Click the sort button  and click **Ascending** or **Descending**.

An arrow appears beside the data item to indicate that a sort order was set.

When you specify a sort order for more than one column, the columns are sorted in the order in which they were inserted in the report. For example, you add columns A, B, and C to a report and specify a sort order for each. When you run the report, column A is sorted first, then column B, and then column C. You can change the order in which the columns are sorted in the **Edit Layout Sorting** options.

Tip: To remove a sort order, click **Don't Sort**.


Perform Advanced Layout Sorting

If you use relational data, in a list, you can sort columns within groups and change the sort order of columns. In a crosstab, you can sort a row or column by another item, such as Order year by Revenue.


Procedure

1. Click a column.

In a crosstab, click the sorted row or column on which to perform advanced sorting.

2. Click the sort button  and click **Edit Layout Sorting**.
3. To sort a list column within a group, do the following:
 - In the **Groups** pane, under the **Groups** folder, expand the folder of the grouped column.
 - In the **Data Items** pane, drag the data items to sort to the **Sort List** folder.

Tip: You can also drag data items from the **Detail Sort List** folder.

- Click the sort order button  to specify ascending or descending order.
4. To change the sort order of columns, in the **Groups** pane, change the order of columns in the **Sort List** folder of a group or in the **Detail Sort List** folder.

Tip: Add items to the **Detail Sort List** folder to sort items that are not groups.

5. If you are sorting a crosstab, do the following:
 - From the **Data Items** pane, drag the item on which to sort to the **Sort List** pane.
For example, you have a crosstab with Product line as rows, Order year as columns, and Revenue as the measure. To sort Order year by Revenue, drag Revenue to the **Sort List** pane.
 - Click the sort order button to specify ascending or descending order.

Working with Relational Queries

Queries specify what data appears in the report. In IBM Cognos Report Studio, you create and modify queries using **Query Explorer**.

Query Explorer provides an alternative way to modify existing reports or to author new reports. You can use **Query Explorer** to perform complex tasks and other tasks that are more difficult to do in the report layout. For example, use **Query Explorer** to

- improve performance by changing the order in which items are queried from the database, or by changing query properties to allow the report server to execute queries concurrently where possible

Note: Only queries that are referenced in the report layout can be executed concurrently. If a query is defined in Query Explorer by joining two or more existing queries, IBM Cognos Business Intelligence cannot execute the source queries concurrently. By default, queries run sequentially. Your administrator must enable the concurrent query execution feature. For more information, see the IBM Cognos Business Intelligence *Administration and Security Guide*.

- view or add filters and parameters and modify their properties
- view or add dimensions, levels, and facts
- incorporate SQL statements that come from other reports or reports that you write
- create complex queries using set operations and joins

Related concepts:

“Queries” on page 35

Queries determine what data items appear in the report. Sometimes you want detailed rows of data, which you obtain by using a simple SELECT statement. Other times you must calculate totals or averages using summary functions and grouped columns or must apply filters to show only the data you want.

Specify a List of Data Items for an Object

Specify the list of data items for an object when you must reference a data item that is in a query but is not in the layout.

For example, you want to add a layout calculation to a list that uses a data item that is in the query definition. If the data item does not appear in the list, you must reference it in order to make the layout calculation work. You must also specify the list of data items if you apply conditional formatting that uses a data item that is not in the query.

Procedure

1. Click a layout object.

Tip: For a list of layout objects for which you can specify a list of properties, see the **Properties** property in Appendix G, “Report Studio Object and Property Reference,” on page 799.


2. In the **Properties** pane, double-click the **Properties** property and select data items.

Relate a Query to a Layout

Queries and layouts work together. After you decide the type of data that you need, you must create a layout in which to show the results. Each column of data must be both selected for the query and shown in a layout unless there are some columns that you do not want to show. The query and layout portions of a report must be linked to produce a valid report.

IBM Cognos Report Studio automatically links query and layout. For example, when you use Report Studio and the list report layout, query and layout are automatically linked.

Procedure

1. Select a data container.
2. In the **Properties** pane, set the **Query** property to a query.
3. From the **Data Items** tab , drag data items from the query to the data container.

Connecting Queries Between Different Data Sources

This section lists the data sources between which you can and cannot connect queries.

IBM Cognos Business Intelligence supports the following:

- RDBMS to RDBMS joins
- set operations of any two queries
- master detail relationships between any two queries
- drill from any query to any other query

You cannot create the following types of joins:

- cube-to-cube (homogeneous)
- cube-to-cube (heterogeneous)
- cube-to-RDBMS



- cube-to-SAP BW
- SAP-BW-to-RDBMS

Add a Query to a Relational Report

You can create multiple queries in **Query Explorer** to suit your particular needs. For example, you can create a separate query for each data container in a report to show different data.


Tip: The Briefing Book sample report in the GO Sales (analysis) package and the Top 10 Retailers for 2011 sample report in the GO Data Warehouse (analysis) package include multiple queries. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure


1. Pause the pointer over the query explorer button  and click **Queries**.
2. From the **Toolbox** tab , drag one of the following objects to the work area.

Object	Description
Query	Adds a query.
Join	Adds a join relationship.
Union	Adds a union operator.
Intersect	Adds an intersect operator.
Except	Adds an except (minus) operator.
SQL	Adds SQL commands.

Note: When adding queries to the report

- right-click the work area and click **Show Package Sources** to see the queries that use data items from a package
 - right-click the work area and click **Expand References** to see the relationships that exist between queries in the report, which is useful when you are creating complex queries
3. In the **Properties** pane, set the object properties.
For example, if you added a join, set the **Join Relationships** property to define the join.
 4. Double-click a query.
 5. From the **Source** tab , drag data items to the **Data Items** pane.

Tip: You can add data items to the query that you do not want to appear in the layout. For example, to filter on Product line code and show Product line in the layout, you must add both data items to the query.

6. To create a new data item, from the **Toolbox** tab , drag **Data Item** to the **Data Item** pane.
7. To add a filter, from the **Toolbox** tab, drag **Filter** to the **Detail Filters** or **Summary Filters** pane and define the filter expression.

Tip: You can also create a filter by dragging a data item from the **Source** tab to one of the filters panes and completing the filter expression.

Create a Union Query

Create a union query to combine two or more queries into one result set.




You can combine queries that use different data sources. For example, you can combine a query that returns data from a dimensional data source with a query that returns data from a relational data source.

Before you begin

To combine two queries, the following conditions must be met:

- The two queries must have the same number of data items.
- The data items must have compatible types and appear in the same order.
For numeric data types, integer, float, double, and decimal are compatible.
For string data types, char, varChar, and longVarChar are compatible.
For binary data types, binary and varBinary are compatible.
Date data types must match exactly.

Procedure

1. Pause the pointer over the query explorer button  and click **Queries**.
2. From the **Toolbox** tab , do the following:
 - Drag **Query** to the work area.
 - Drag **Union**, **Intersect**, or **Except** to the right of the query.
Two drop zones appear to the right of the operator.
 - Drag a **Query** object to each drop zone.
Two queries are created in the work area, and a shortcut to each query appears in the drop zones.
3. Double-click each query that makes up the union query and add data items to the query.
4. Return to the **Queries** work area.
5. Click the set operator that you added in step 2.
6. In the **Properties** pane, set the **Duplicates** property to remove or preserve duplicate rows.
7. Double-click the **Projection List** property.
The projection list shows the list of projected data items for the set operation.
8. To automatically produce the list of projected data items, click **Automatically generated**.
IBM Cognos Report Studio generates the projection list using only one of the two queries in the union.
9. To add, delete, move, or rename data items in the projection list, click **Manual** and make the changes.
10. Double-click the union query.
11. From the **Source** tab , drag data items to the **Data Items** pane.







Results


The union query is complete. You can now link the union query to a data container in the layout.



Example - Create a Two-column List Report for Three Data Items




You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a list report that shows revenue for all product lines and order methods. However, you want the product lines and order methods to appear in a single column. To create this report, you use a union query to join the Product line and Order method data items.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **Blank**.
4. Pause the pointer over the query explorer button  and click **Queries**.
5. From the **Toolbox** tab , do the following:
 - Drag **Query** to the work area.
 - Drag **Union** to the right of the query.
Two drop zones appear to the right of the operator.
 - Drag a **Query** object to each drop zone.
Query2 and **Query3** are created in the work area, and a shortcut to each query appears in the drop zones.
6. Double-click **Query2**.
7. From the **Source** tab , open **Sales and Marketing (query)**, then open **Sales (query)**. Then drag the following data items to the **Data Items** pane:
 - from the **Products** folder, drag **Product line**
 - from the **Sales fact** folder, drag **Revenue**
8. From the **Toolbox** tab , drag **Data Item** to the **Data Items** pane.
The data item will be used to sort product lines and order methods in the report.
9. In the **Expression Definition** box, type 'A' and click **OK**.
10. In the **Properties** pane, set the **Name** property to
Sort key
11. On the toolbar, press the back button  to return to the Queries work area.
12. Double-click **Query3**.
13. From the **Source** tab , drag the following data items to the **Data Items** pane:
 - from the **Order method** folder, drag **Order method type**
 - from the **Sales fact** folder, drag **Revenue**
14. Repeat steps 8 to 10 to create a Sort key data item in Query3 with 'B' as its definition.


15. On the toolbar, press the back button  to return to the Queries work area.
16. Click the **Union** operator.
17. Double-click the **Projection List** property.

The **Product line** item in the projection list contains both product lines and order methods.
18. Click **Manual**.
19. Click **Product line**, and then click the edit button .
20. In the **Edit** box, type the following after **Product line**:
& Order method
21. Click **OK** twice.
22. Double-click **Query1**.
23. From the **Source** tab , drag the following data items to the **Data Items** pane:
 - **Product line & Order method**
 - **Revenue**
 - **Sort key**
24. Select the **Sort key** data item and, in the **Properties** pane, set the **Pre-Sort** property to **Sort ascending**.

When you run the report, all product lines will appear first followed by all order methods.
25. Pause the pointer over the page explorer button  and click **Page1**.
26. From the **Toolbox** tab , drag **List** to the work area.
27. Click the list.
28. Click the select ancestor button  in the title bar of the **Properties** pane and click **List**.

Tip: You can also click the container selector (three orange dots) of the list to select it.
29. In the **Properties** pane, set the **Query** property to **Query1**.

The list is linked to the union query.
30. Double-click the **Properties** property.
31. Select the **Sort key** check box and click **OK**.

Since the Sort key data item does not appear in the list, you must make it a property of the list before it can sort product lines and order methods.
32. From the **Data Items** tab , drag the following items from Query1 to the list:
 - **Product line & Order method**
 - **Revenue**
33. Run the report.

Results

A list report with two columns is produced. All product lines and order methods appear in the first column.




Product line & Order method	Revenue
Camping Equipment	1,589,036,664.03
Golf Equipment	726,411,367.89
Mountaineering Equipment	409,660,132.9
Outdoor Protection	75,994,296.25
Personal Accessories	1,885,673,307.78
E-mail	179,843,044.16
Fax	70,073,542.01
Mail	46,091,338.97
Sales visit	310,194,834
Special	27,351,320.25
Telephone	340,985,781.06
Web	3,712,235,908.4

Create a Join Relationship

You can create a join relationship to join two queries.


In general, join relationships should be created in the IBM Cognos Framework Manager model. Create a join relationship in IBM Cognos Report Studio if what you are trying to do cannot be modeled in Framework Manager.

Procedure

1. Pause the pointer over the query explorer button  and click **Queries**.
2. From the **Toolbox** tab , do the following:
 - Drag **Query** to the work area.
 - Drag **Join** to the right of the query.
Two drop zones appear to the right of the operator.
 - Drag a **Query** object to each drop zone.
Two queries are created in the work area, and a shortcut to each query appears in the drop zones.
3. Double-click each query that makes up the join query and add data items to the query.
4. On the toolbar, press the back button  to return to the Queries work area.
5. Click **Join**.
6. In the **Properties** pane, double-click the **Join Relationships** property.
7. Click **New Link**.
8. To create the link, click a data item in the left query, and then click a data item in the right query.

9. For each query, click **Cardinality** and click a cardinality option.
10. Click **Operator** and click an operator.
11. To convert the join relationship to an expression, click **Convert to expression**.
Convert the join relationship to an expression to make changes to the join definition.

Note: After you convert the relationship to an expression, you cannot change it back to a relationship.

12. Double-click the join query.
13. From the **Source** tab , drag data items to the **Data Items** pane.



Results

The join query is complete. You can now link the join query to a data container in the layout.

Reference a Package Item in a Child Query

When you create a child query in IBM Cognos Report Studio, you can only reference items from its parent or from other queries. For example, if you add a filter to a child query, the only items that you can insert into the expression are items that exist in other queries defined in the report. To add an item from the package, you must unlink the child query from its parent.

Procedure

1. Pause the pointer over the query explorer button  and click **Queries**.
2. Unlink the child query from its parent by selecting the parent query shortcut to the right of the child query and clicking the delete button .
3. Double-click the child query.

Package items are now available on the **Source** tab .

4. Add package items.
For example, to create a detail filter that references a package item, drag the filter object from the **Toolbox** tab to the **Detail Filters** pane, and then add the items in the **Expression Definition** box.
5. Click the up arrow button in the toolbar to return to the queries work area.
6. Recreate the link between the child query and the parent query by dragging the parent query to the right of the child query.
7. If necessary, double-click the child query to complete it.
For example, if you created a filter, you may need to complete the filter expression.

Create a Master Detail Relationship

Create a master detail relationship to deliver information that would otherwise require two or more reports. For example, you can combine a list with a chart. The list can contain product lines and the chart can show details for each product line.

Master detail relationships must appear in nested frames to produce the correct results. You can create a master detail relationship in two ways:

- Use a parent frame for the master query and a nested frame for the detail query.

- Associate a report page with the master query and use a data container, such as a list or crosstab, for the detail query.

You cannot display parent data in the child frame or child data in the parent frame. Also, you cannot perform calculations across master detail queries.





You can use a master detail relationship to show data from separate data sources in a single report. However, the data sources must be contained in the same package.

If you are working with an SAP BW data source, you cannot use a data item from the master query that contains non-ASCII values.

Before you begin

To create a master detail relationship using queries that reference two different dimensional data sources, you must first link the members by aliasing the levels that contain the members.

Procedure

1. To use a parent frame for the master query and a nested frame for the detail query:
 - From the **Toolbox** tab , drag a **List**, **Repeater Table**, or **Repeater** to the report.
 - Add a second data container to the object you inserted.
You can insert a list, crosstab, chart, repeater table, or repeater into a list.
You can add a list to a repeater table or repeater.
 - Add data items to both data containers.
2. To associate a report page with the master query and use a data container for the detail query:
 - Click anywhere in the report page.
 - In the **Properties** pane, click the select ancestor button  and click **Page**.
 - Set the **Query** property.
 - From the **Toolbox** tab, drag a data container to the report.
3. To link a data item in the master query to a parameter in the detail query instead of to another data item, create the parameter in the detail query.
Use parameters to filter values at a lower level in the detail query.
 - Pause the pointer over the query explorer button  and click the detail query.
 - From the **Toolbox** tab, drag the **Filter** object to the **Detail Filters** box.
 - In the **Expression Definition** box, create the parameter.
4. Pause the pointer over the page explorer button  and click the report page.
5. Click anywhere in the report page.
6. In the **Properties** pane, click the select ancestor button and click **Page**.
7. Click the data container containing the details.
8. From the **Data** menu, click **Master Detail Relationships**.
9. Click **New Link**.

10. In the **Master** box, click the data item that will provide the primary information.
11. To link the master query to a data item, in the **Detail** box, click the data item that will provide the detailed information.
12. To link the master query to a parameter, in the **Parameters** box, click the parameter that will provide the detailed information.

Tip: To delete a link, select the link and press the Delete key.

13. If your detail query object is a chart, you can disconnect a chart title from the master query.
 - Click the chart title, and then, from the **Data** menu, click **Master Detail Relationships**.
 - Clear the **Use the master detail relationships from the chart** check box.
14. If your master detail relationship includes a chart as the detail and you are using automatic axis ranges, you can set the same axis range for all the detail charts:
 - Select the axis.
 - In the **Properties** pane, under **General**, double-click the **Axis Range** property.
 - Under **Maximum** and **Minimum**, click **Automatic**.

The master detail report option is only available with automatic axis ranges.

 - Under **Master detail reports**, select the **Same range for all instances of chart** check box.

For more information about axis ranges, see “Change the Axis Scale of a Current Default Chart” on page 124.

Tip: To avoid seeing the same data item twice in the report, click the data item in the data container driven by the detail query and click the cut button. This removes the item from the report display but keeps it in the query.

Master Detail or Burst Reports with Charts or Crosstabs May Result in Denial of Service

When running a master detail or burst report that includes a chart or crosstab, disk space exhaustion may cause the report or other requests to fail. A large set of burst keys or master rows may produce one or more charts per detail, resulting in many master detail executions. This may cause the temp folder to accumulate many gigabytes of temporary files containing data required for successful chart rendering.

To avoid this issue, we recommend that you test large master detail or burst reports that include charts or crosstabs to determine the potential peak disk requirements for the report.

Working with Queries in SQL

For each query in a report, you can work with the SQL that is executed when you run a report.

You can

- view the SQL for an entire report or a query
- build a report using your own SQL
- convert a report to use SQL directly
- edit the SQL

When working with a relational data source, the SQL that is produced by IBM Cognos Report Studio depends on the report output selected.

Note: MDX is not available with relational or DMR data sources.

View the SQL for an Entire Report or a Query


View the SQL to see what is passed to the database when you run a report.

Procedure

1. To view the SQL for the entire report, from the **Tools** menu, click **Show Generated SQL/MDX**.

This option shows the SQL that will be executed in the data source. The SQL is organized by query and by query result. If a query is used in more than one data container, a query result is generated for each data container.

2. To view the SQL for a specific query, do the following:

- Pause the pointer over the query explorer button  and click the query.
- In the **Properties** pane, double-click the **Generated SQL/MDX** property.

The **Generated SQL/MDX** property shows the SQL that is executed when you view tabular data (from the **Run** menu, click **View Tabular Data**). Tabular data shows the data that is produced by the query in the form of a list. You can use this property to help you build advanced queries.

Results

The SQL for the query appears in the **Generated SQL/MDX** dialog box. You can choose to view native SQL, which is the SQL that is passed to the database when you execute the query, or Cognos SQL, which is a generic form of SQL that IBM Cognos Report Studio uses. Cognos SQL is converted to native SQL before the query is executed.

Related tasks:

“Showing prompt values in generated SQL or MDX” on page 340



You can show prompt values when viewing the generated SQL or MDX of a query or report.

Build a Report Using Your Own SQL

You can build a report by adding SQL from an external source, such as another report.



If you edit the SQL of a query, you must change the **Processing** property for that query to **Limited Local**.

Procedure


1. From the **File** menu, click **New**.
2. Click **Blank**.
3. Pause the pointer over the query explorer button  and click **Queries**.
4. From the **Toolbox** tab , drag **Query** to the work area.
5. From the **Toolbox** tab, to build an SQL query, drag **SQL** to the right of the query.

Tip: You can drag **SQL** anywhere in the work area, and IBM Cognos Report Studio will automatically create a query.

6. In the **Properties** pane, double-click the **Data Source** property and click a data source.
7. If required, set the **Catalog** property to the name of the catalog.
8. Double-click the **SQL** property and type the SQL.
9. Click **Validate** to check for errors.
10. In the **Properties** pane, set the **Processing** property to **Limited Local**.
11. Double-click the query.
If the SQL is valid, the data items defined in the SQL appear in the **Data Items** pane.

12. Pause the pointer over the page explorer button  and click a report page.
13. From the **Toolbox** tab, drag an object to the work area.
For example, drag a list, crosstab, chart, or repeater.
14. Click the data container.
15. In the **Properties** pane, click the select ancestor button  and click the container you just created.
For example, if you created a list, click **List**.

Tip: You can also click the container selector (three orange dots) of the container to select it.


16. Set the **Query** property to the query for the report type.
17. From the **Data Items** tab , drag the items from the query you chose in the previous step to the data container.

Convert a Query to SQL

You can convert a query to SQL to edit it. You may want to do this to improve performance or to use SQL features that are not supported directly by IBM Cognos Report Studio.

Converting a query to SQL is an irreversible process.


Procedure

1. Pause the pointer over the query explorer button  and click the query.
2. In the **Properties** pane, double-click the **Generated SQL** property.
3. Click **Convert**.
4. Click **Validate** to check for errors.
5. In the **Properties** pane, set the **Processing** property to **Limited Local**.

Edit the SQL

You can edit the SQL for a query that has been created as an SQL query or that has been converted to SQL.

Procedure

1. Pause the pointer over the query explorer button  and click the SQL item under the query.
2. Double-click the SQL item.

3. Make changes in the text box.
4. Click **Validate** to check for errors.

First-Rows Optimization

The SQL produced by IBM Cognos Report Studio depends on the report format you choose. For example, if you specify HTML format, first-rows optimization is requested. All-rows is requested if you specify PDF.

It is important for database administrators and programmers to remember that Report Studio does not always use first-rows optimization. If you assume first-rows optimization is always requested, this can cause the RDBMS optimizer to process the query differently than you expect.

Using Relational Calculations

Insert a calculation to make your report more meaningful by deriving additional information from the data source. For example, you create an invoice report, and you want to see the total sale amount for each product ordered. Create a calculated column that multiplies the product price by the quantity ordered.

You build calculations in the expression editor using functions.

If a calculation is used in multiple reports, or by different report authors, ask your modeler to create the calculation as a standalone object in the model and include it in the relevant package.

You can add calculations to lists, crosstabs, and all other data containers. You can also add calculations directly to a page header, body, or footer. However, you must first associate a query to the page. For more information, see “Add a Page to a Report” on page 453

Units of Measure

When creating calculations in IBM Cognos Report Studio and IBM Cognos Query Studio, you may encounter problems with the units of measure. For example, the calculation $Cost * Cost$ returns the unit of measure * instead of a currency unit of measure. To avoid this problem, change the format of the corresponding column to obtain the desired unit of measure.

Calculation Solve Order

When calculations in the rows and columns of a report intersect, calculations are performed in the following order: addition or subtraction, multiplication or division, aggregation (rollup), and then the remaining arithmetic functions.

The remaining functions are as follows:

- absolute, round, round down, average, minimum, maximum, medium, count
- percentage, % difference (growth) or % of total
- rank, quartile, quantile, or percentile

If both calculations have the same precedence, for example, if they are both business functions, then the row calculation takes precedence.


Limitations of Calculations

You should use only the expressions and functions available in Report Studio, and follow their syntax.

Minimal checking exists for calculations. If your calculation uses an invalid expression, your report results may contain unexpected values.

In addition, you should define member summaries as follows:

summary_function (*currentMeasure* within set *set_reference*)

where *set_reference* is a level or set inserted from the **Source** tab .

Unless otherwise required, *summary_function* should be the aggregate function. If you use an explicit summary function, you may encounter problems with measures and scenario or account dimension members (such as profit margin, distinct count, and so on) that have complex rollup rules, or members that do not roll up.

Know your data, and confirm with the owner of the cube where overriding the automatic aggregation is safe.

Because of these limitations, summaries of calculations may not provide reliable values. For convenience, you may have to build reports where row summaries and calculated member columns intersect. In such reports, these intersections may contain unexpected values. In contrast, row calculations intersecting with column aggregates using the aggregate function are safe because the calculation is performed on the reliably summarized values.

Create a Simple Calculation


You can select items in your report and create simple calculations.

In addition to simple arithmetic calculations, you can perform the following calculations:

Calculation	Description
Rollup	Summarizes, or rolls up, all the values in a hierarchy.
%	Calculates the value of a selected item as a percentage of another item.
% Growth	Calculates the difference between two items as a percentage.

Calculation	Description
% Of Base	<p>This calculation is only available if you select two members from different hierarchies, each from a different edge.</p> <p>This calculation takes the first selected member from edge A and the second selected member from edge B. The calculation result of a percent of base should be such that all the values for member A will compare itself to the intersect value of member A and B.</p>
Custom	<p>Allows you to specify your own value when performing a simple arithmetic calculation. Also allows you to change the order of operands or type a custom name for the new calculated row or column.</p>

Procedure

1. Select the items in your report to calculate.
2. Click the insert calculation button  and select the calculation to perform.

Tip: Calculations that are not applicable to the items you selected are greyed out.
3. To change the order of the operands, the name of the calculated item added to the report, or to create a custom calculation, click **Custom**.

Results

The calculation appears as a new row or column in your report.

Insert a Query Calculation

Insert a query calculation into your report to add a new row or column with values that are based on a calculation.

For example, you create a query calculation named Euros that converts dollars to euros by multiplying an existing dollar measure by a conversion rate. Euros can then be displayed to end users in a separate row or column.

Note: When creating an expression that will be used in a double-byte environment, such as Japanese, the only special characters that will work are ASCII-7 and ~ - | | - \$ ¢ £ ¤.

Not all data sources support functions the same way. The data modeler can set a quality of service indicator on functions to give a visual clue about the behavior of the functions. Report authors can use the quality of service indicators to determine which functions to use in a report. The quality of service indicators are:

- not available (X)

The function is not available for any data source in the package.
- limited availability (!!)

The function is not available for some data sources in the package.

- limited support (!)

The function is available for all data sources in the package but is not naturally supported for that data source. IBM Cognos Business Intelligence uses a local approximation for that function. Because an approximation is used, performance can be poor and the results may not be what you expect.

- unconstrained (check mark)

The function is available for all data sources.

When inserting literal strings in an expression, you must enclose the string in single quotation marks. If the string contains a quotation mark, it must be escaped. For example, if you want to insert the string ab'c, you must type 'ab"c'.







Procedure

1. From the **Toolbox** tab , drag **Query Calculation** to the report.

2. Type a meaningful name for your expression in the **Name** box.

For example, if you are calculating the difference between 2012 revenue and 2011 revenue, you could name your expression **2012 - 2011 Revenue**.

3. In the **Available Components** pane, define the calculation:

- To add data items that are not shown in the report, on the source tab , double-click the data items.
- To add data items that are in the report but not necessarily in the model, such as calculations, on the data items tab , double-click the data items.
- To add data items from a specific query, on the queries tab , double-click data items.
- To add functions, summaries, and operators, on the functions tab , double-click elements.
- To add a value that is derived from a parameter, on the parameters tab , double-click a parameter.
Parameters define prompts, drill-through reports, and master detail relationships.
- To add a macro, on the macros tab , double-click the parameter maps, session parameters, or macro functions you want to add to the macro expression.

Tip: Use **Insert macro block** to get you started with creating the macro expression. **Insert macro block** inserts number signs in the expression. Make sure that the macro expression you create is between the number signs.

You can also type the calculation directly in the **Expression Definition** box.

When typing date values, ensure that the date format is correct for your database type.

To copy and paste expression components in the **Expression Definition** pane,

you can use the copy button  and the paste button .

For information about specific functions, see Appendix F, “Using the expression editor,” on page 575.

4. Click the validate button .

Any validation errors appear on the **Errors** tab of the **Information** pane.

Related concepts:

Chapter 18, “Using Query Macros,” on page 419






A macro is a fragment of code that you can insert in the Select statement of a query or in an expression. For example, add a macro to insert a new data item containing the user's name.

Create a Layout Calculation

Create a layout calculation to add run-time information to your report, such as current date, current time, and user name.

When creating layout calculations, only report functions are available to you in the expression editor. These functions are executed in the report layout, as opposed to the other functions which are executed in the query.

Procedure

1. From the **Toolbox** tab , drag **Layout Calculation** to the report.
2. In the **Available Components** box, define the calculation:
 - To add data items that are not shown in the report, on the source tab , double-click data items.
 - To add data items from a specific query, on the queries tab , double-click data items.
 - To add functions, summaries, and operators, on the functions tab , double-click elements.
 - To add a value that is derived from a parameter, on the parameters tab , double-click a parameter.

Parameters define prompts, drill-through reports, and master detail relationships.

Tip: You can also type the expression directly in the **Expression Definition** box.

For more information about creating expressions, see Appendix F, “Using the expression editor,” on page 575.

3. Click the validate button .



Chapter 11. Dimensional Reporting Style

The dimensional reporting style is recommended for dimensionally-modeled relational (DMR) and Online Analytical Processing (OLAP) data sources. Dimensional data is best represented by crosstabs, maps, and charts. This data is shown in IBM Cognos Report Studio in dimensions, hierarchies, levels, and members.


In dimensional reporting, you summarize data by using member summaries and within set aggregation. You focus data in dimensional reporting by adding only the relevant members to the edge of a crosstab or to the context filter. You can also enable drilling up and drilling down in dimensional reports.


IBM Cognos Analysis Studio and IBM Cognos Workspace Advanced are also available to work with dimensional data.

Add Dimensional Data to a Report

For dimensional and mixed model data sources, you can view the full data tree by clicking the view package tree button  in the **Source** tab. You can switch to the dimensional-only data tree by clicking the view members tree button .

Note: We recommend using dimensional data in the dimensional reporting style. However, if you are using relational data, see “Add Relational Data to a Report” on page 227.

If you are working with a dimensional data source, data items are organized hierarchically. Dimensional data sources include OLAP and dimensionally-modeled relational (DMR) data sources. The **Source** tab  shows a metadata-based view of the data.



Note: The names of levels and members in a dimension come from the model. It is the responsibility of the modeler to provide meaningful names.

1. Package

Packages are subsets of a model containing items that you can insert in a report.

2. Dimension

Dimensions are broad groupings of descriptive data about a major aspect of a business, such as products, dates, or markets.

3. Level hierarchy

Level hierarchies are more specific groupings within a dimension. For example, for the **Years** dimension, data can be organized into smaller groups, such as **Years**, **Current Month**, and **Last Month**.

4. Members folder

Members folders contain the available members for a hierarchy or level. For example, the **Members** folder for the **Years** level hierarchy contains everything found in the **Year**, **Quarter**, and **Month** levels.

5. Level

Levels are positions within the dimensional hierarchy that contain information at the same order of detail and have attributes in common. Multiple levels can exist within a level hierarchy, beginning with a root level. For example, the **Years** level hierarchy has the following related levels.

Level	Level name	Description
Root	Years	The root level.
First	Year	Years in the Years root level. For example, 2013, 2012, and 2011.
Second	Quarter	Quarters for each year in the Year level. For example, 2013 Q1, 2013 Q2, and 2013 Q3.

Level	Level name	Description
Third	Month	Months for each quarter in the Quarter level. For example, Jan., Feb., and Mar.

Tip: The **Measures** dimension contains the measures available in the data source.

6. Member property

Member properties are attributes that each member possesses. For example, gender could be a property for all employee members. For more information about member properties, see “Insert a Member Property” on page 272.

Related concepts:

“Limited Support for Relational Functions When Used with OLAP Data Sources” on page 551




When working with an OLAP data source, we recommend that you not use relational functions, such as `substring` and concatenation functions, in a report that also contains a measure with the **Aggregate Function** property set to **Calculated** or **Automatic** in the model. If you do so, you may encounter unexpected results. For example, some summaries are calculated using the **Minimum** function instead of the aggregate function derived from the individual query items.

Customize the Source Tree

When using dimensional data, you can customize how you see data in the source tree. You can select a full package tree view that shows dimensions, hierarchies, levels, an optional members folder, and member properties.

Or you can select a members-only tree view, such as the one in IBM Cognos Analysis Studio. This view allows you to add only members in your report.

Procedure

1. Click the **Source** tab .
2. To view the members-only tree view, click the view members tree button .
3. To view the full package tree, click the view package tree button .
4. To change what is included in the tree, right-click and click **Package Tree Settings**.

Use the **Preview** pane to choose the appropriate settings.

Insert a Member




By default, when you insert members from the source tree into your report with IBM Cognos Report Studio, single members are inserted without any details or children. You can change how members are inserted. For example, you may want to insert a member along with all its children or insert only the member's children. Or you may want to insert members as a set.

When you double-click a member that you have already inserted in your report, by default, its children are inserted after the parent member. You can control whether the children are inserted before or after, nested, or not inserted at all: from the **Tools** menu, click **Options**, and then choose a setting on the **Edit** tab.

When inserting members into a crosstab, ensure that you insert members from the same hierarchy on only one of the crosstab edges. If you insert members from the same hierarchy on both edges of the crosstab, you may encounter unexpected results. For example, a report that uses members from years in the rows and Quarters in the columns is very difficult to read because the useful numbers are distributed over a large area of mostly blank cells.

Calculated members from the data source also appear in the source tree. However, calculated members in Microsoft SQL Server Analysis Services (SSAS) cubes do not appear in the list of descendants in the query. If you want these calculated members to appear in a report or a prompt, you must insert them explicitly.

Procedure




1. From the **Source** tab , click the insert single member button  and select how to insert members.
2. If you want to insert members within a set instead of inserting individual members, click the create sets for members button .
3. Do one of the following:
 - To insert a member above or below another member, drag the new member above or below a cell.
A flashing black bar appears where you can drop the new member.
 - To replace a member, drag the new member to the cell with the member to replace.
A flashing black box appears where you can drop the new member.

Search for a Member


You can perform a member search to quickly find data.

You can control the number of members that are returned in a search by specifying a value for the **Member display count limit (in source tree)** option (**Tools, Options, Advanced** tab).

Procedure

1. From the **Source** tab , select and then right-click a hierarchy  or level  and click **Search**.
2. In the **Words** box, type the words or characters for which to search.
3. Click the search parameter to use.
4. To search all descendants instead of just the immediate children, select the **Search all descendants** check box.
For example, when performing a search in a hierarchy, selecting this check box returns members found in all the levels of the hierarchy.
5. Click **Search**.

Results

The search results appear in a hierarchical structure on the **Search** tab . You can browse the hierarchy to explore members at lower levels.

Tip: You can insert members directly from the **Search** tab into a report. This can save you time, because you do not have to define a filter. For example, instead of inserting **Product line** from the **Source** tab and adding a filter for **Camping Equipment**, you can insert **Camping Equipment** from the **Search** tab.

Nest Members

When you insert members in your report, you may want to nest them in another row or column to make your report easier to use. You can nest members from different dimensions. You can also nest sets.


For example, in the following report, the quarters (Q1 to Q4) were selected from the Time dimension and nested only for the GO Americas member, which is from a different dimension.

Amount (year to date)		<#2010#>
<#GO Americas#>	<#Q1 2010#>	<#1234#>
	<#Q2 2010#>	<#1234#>
	<#Q3 2010#>	<#1234#>
	<#Q4 2010#>	<#1234#>
<#GO Consolidated corporate#>		<#1234#>
<#GO Consolidated eliminations#>		<#1234#>
<#GO CONSOLIDATED#>		<#1234#>
<#GO Asia Pacific#>		<#1234#>

Figure 50. Crosstab showing the year to date amount for all four quarters nested beside GO Americas

When you filter out children from nested sets, the parent set still appears in your report. To avoid this, filter only the top level set and nest only the complete set of descendants at the desired levels.

Procedure

From the **Source** tab , drag the members to the work area. A flashing black bar indicates where you can drop an item.

Insert a Hierarchy



You can quickly insert entire hierarchies in a report.

When using an IBM Cognos PowerCube, a SSAS cube, or a dimensionally-modeled relational data source, you can insert multiple hierarchies from the same dimension in a crosstab. For example, you can place one hierarchy from a dimension on an edge of the crosstab and nest another hierarchy from the same dimension on the same edge, on another edge, or in the **Context filter** area.

You can also perform arithmetic, percentage, and ranking calculations using multiple hierarchies.

Summary or analytic calculations that refer to different hierarchies from the same dimension, such as total, count, average, minimum, and maximum, are not supported. These calculations cause an OP-ERR-0250 error.

Procedure

1. From the **Source** tab , drag the hierarchy  to the report.
2. In the **Insert Hierarchy** dialog box, choose which members to insert:
 - To insert only the root members of the hierarchy, click **Root members**.
 - To insert all members of the hierarchy, click **All members**.

Tip: The default **Level Indentation** property for all members is to show the hierarchical structure when the report is run.

Insert a Member Property



You can insert member properties, which are attributes of a member, in your report. Member properties provide additional information about the member. For example, an employee level may have a property named gender.

About this task

In the data tree of the **Source** tab , member properties are identified by the icon .

You can only insert properties. You cannot group them. Do not insert member properties in the series or categories of a chart because by default, IBM Cognos Report Studio groups items that are inserted in these areas. Grouping member properties produces a warning when you validate the report.

Procedure

From the **Source** tab , drag the member property  to the report.



Create a Set of Members

Use sets to group members that are logically related for various actions, such as formatting, nesting, and sorting. Creating sets is also useful when members may be dynamic over time. For example, the child accounts of a total assets account may change from year to year. By creating a set, you do not have to modify the report each time accounts are added or removed.

After you create a set of members, you can add or remove members within the set.

You can perform operations on the set such as excluding specific members, moving members within the set, showing only the top or bottom members, filtering the set, and expanding or collapsing the members within a set. You can view the set definition to see and edit operations that are performed on the set.

Procedure

1. From the **Source** tab , click the create sets for members button  to toggle between adding individual members and creating sets for members.
2. From the **Source** tab, select the items to include in the set and drag them to the work area.
3. To add or remove members from the set, right-click the set and click **Edit Members**.

Tip: you can also select the set and, in the **Properties** pane, double-click the **Members** property.

Sharing sets between reports

When you are working with dimensional data, you can share a set to make it available for inclusion in multiple reports.




You must first create a set in a source crosstab report, create a shared set definition, then refer to it in a target report.

A shared set definition is copied from one report to another. As a result, the set definition must not depend on any context from the source report. For example, it must meet the following criteria:

- It cannot reference other shared sets.
- It cannot reference other data items.
- It cannot contain calculated members.

You cannot change the definition of a shared set from within the target report. However, you can carry out other set operations on it, such as excluding a member or creating a top 10 list.

Procedure

1. In the source crosstab report, create a set that you want to share.
2. Select the set. In the Properties pane, in the **Sharing** property, enter a name and description for the set.
3. Save the report.
4. In the **Source** tab , right-click the model. Click **Add Shared Set Report**.
5. In the **Open** box, select the source report that contains the shared set definition. If it does not exist, a new folder that is called **Shared Sets** is created. It is displayed at the bottom of the source tree.
6. Optional: To add, delete, or change the order of reports in the **Shared Sets** folder, right-click the folder and click **Manage Shared Set Reports**.
7. Create or open a crosstab target report that you want to refer to the shared set definition.
8. In the **Source** tab , open the **Shared Sets** folder. Open the source report that contains the shared set definition that you want to use.
9. Add the shared set definition into your target report.
10. Right-click the shared set in the target report and click **Edit Set**.
11. In the **Set Definition** box, select the shared set.
12. Click **Edit** . The Set Reference Properties window opens.
13. Set the **Inclusion** property.
 - a. Select **Run time** to retrieve the latest shared set definition every time that the report runs.
 - b. Select **Design time** to store the shared set definition in the target report. This definition is used until you refresh it.
14. Click **OK**, then save the report.

Managing shared set references



After you share a set to make it available for inclusion in multiple reports, you can manage references to it. You can also copy it locally.

You can manage set references in the following ways:

- Create a copy of a shared set to be used in a report.
Converting a shared set reference into a copy replaces the reference with a set definition that is stored in the report. The report does not reference the shared set from the source report. Any changes that are made to the shared set in the source report are not reflected in the target report. Instead of converting the reference to a copy, you can change the **Inclusion** property of the reference to **Design time**. Design time references use a static stored version of the shared set definition. However, you can later change the **Inclusion** property to be **Run time** to use the latest shared set definition.
- Modify the properties of a set reference in the target report, including its **Inclusion** property. You can also modify a set reference in the target report by changing the set definition it refers to.
- Refresh an existing set reference after a set changed in a source report and you want to use the updated set. To use the updated set if the **Inclusion** property is set to **Design time**, you must refresh its reference.
- Review problems with an existing set reference.

Procedure

1. Open the target report that contains the reference to the shared set that you want to work with.
2. Click **Tools > Manage Shared Set References**.
3. To create a copy of a shared set to be used in a report, do the following steps:
 - a. Select the shared set reference that you want to copy.
 - b. Click **Convert Reference to Copy**. The Confirm Convert window is displayed.
 - c. If you want to convert the set reference into a copy that is stored in this report, click **Yes**. If you do not want to create a copy, click **No**.

Important: If you convert the set reference into a copy, it is not updated when the set in the original report changes.
4. To modify an existing set reference in a target report, do the following steps:
 - a. Select the shared set reference that you want to modify.
 - b. Click **Edit Reference**.
 - c. To modify the set reference properties, select the reference, then click **Edit** . The Set Reference Properties window opens. You can now modify the set reference properties.
 - d. To modify the definition of the set, click **New** . The Set Definition window opens. You can now modify the set definition.
5. To refresh an existing set reference after a set changed in a source report, do the following steps:
 - a. Select the set reference that you want to refresh.
 - b. Click **Refresh Reference**.
6. To review problems with an existing set reference in a target report, do the following steps:

- a. Select the set reference that is causing the problem.
 - b. Review and act upon the message that is displayed.
7. Save the report.

Edit a Set



After you create a set, you can view its definition to see, change, add, or delete operations, such as the following, that are performed on the set:

- excluding a member
- moving members to the top or bottom of a set
- applying a top or bottom filter
- filtering the set
- expanding or collapsing members in a set

The definition of a set shows you, in the graphical tree, the history of all the operations that are performed on the set.

You can see and change the order in which the operations are performed. For example, you apply a top three filter and then exclude one member. Your set now contains only two members. You can choose to exclude the member before the top three filter so that your set still contains three members.


Procedure

1. Right-click a set and click **Edit Set**.
A graphical tree shows all the operations that are performed on the set of members.
2. To see the details of an operation, hover your mouse over an operation node.
3. To change the order of an operation, click the operation node, and click the right or left arrow.
4. To edit an operation, click the operation node and click the edit button .
5. To add a new operation, click the new button .

Exclude Members from a Set

You can choose to remove individual items that are not needed in your analysis.


Procedure

1. Right-click the set and click **Edit Set**.
2. Click the new button  and click **Exclude**.
3. In the **Exclude** box, choose the members to exclude and use the right arrow to move them to the **Members** pane.

Move Members Within a Set

You can move one or more members to the top or bottom of a set.

Procedure

1. Right-click the set and click **Edit Set**.
2. Click the new button  and click **Move to Top** or **Move to Bottom**.
3. In the **Available members** list, select the member to move to the top or bottom and click the right arrow.

The members appear in the order shown in the **Members** list.

Limit Data to Top or Bottom Values

You want to focus your report on the items of greatest significance to your business question. For example, you want to identify your top 100 customers and what that group of customers is worth.

You can limit the data to the top or bottom values of a set. This keeps the amount of data shown in the work area small, even when using large data sources.


You can define a top or bottom rule by specifying

- a number, such as the 50 top or bottom performing sales people
- a percentage, such as customers who contribute to the top 10% of overall revenue
- a cumulative sum, such as customers who contribute to the first ten million dollars of overall revenue

If the selected set contains a user-defined filter, the top or bottom rule applies only to the included values. For example, if you apply a filter to show only retailers with revenue greater than one million dollars, the bottom rule applies to the lowest values within those results.

You can filter a set of members to show only those at the top or bottom and base the filter on the measure you are using and the set of members on the opposite edge. You can also specify a custom filter.

Procedure

1. Right-click the set and click **Edit Set**.
2. Click the new button  and click **Top** or **Bottom**.
3. Under **Type**, select whether to filter the **Top** or **Bottom** values.
4. To choose how and how much you want to filter, under **Number of items**, click **Count**, **Percent**, or **Sum** and type the number of data items to show, the percent of data items to show, or the value to sum.
5. Choose the intersection on which to base your filter by clicking the ellipsis button and selecting the members and measure for the intersection from either the **Source** tab or the **Calculated Members and Measures** tab.

For more information, see “Create an Intersection (Tuple)” on page 320.

Filter the Members Within a Set





You can remove members from within a set by specifying filter conditions so that only the members that you require remain. You can filter a set based on

- member captions
For example, your set includes employee names and you want to keep only the employees with names that begin with a specific letter.
- properties that are numeric or strings
For example, your set includes employee names and you want to filter employees using the gender property.
- intersection of values (tuple)
For example, you want to keep only the employees who used less than ten sick days for the year 2012.

If you want to create a more complex filter, you can combine multiple conditions using AND, OR, and NOT operators. By default, multiple conditions are combined with an AND operator, which means that all conditions must be met for the filter to take effect.

Filtering the members in a set is not the same as relation detail or summary filters.


Procedure

1. Right-click the set and click **Edit Set**.
2. Click the new button  and click **Set Filter**.
3. Select how you want to filter.
 - If you want to filter the set using a caption, click **Caption**.
 - If you want to filter the set using a member property, click **Property** and select from the drop-down list.
 - If you want to filter the set using an intersection of members, or tuple, click **Intersection (tuple)** and click the ellipsis button. Then, from **Available members and measures**, select the desired items and click the right arrow to move them to the **Intersection members and measures** list.
4. Specify the **Operator** and **Value** to complete your condition and click **OK**.
5. To add additional conditions, click the new button .
6. If you include multiple conditions in your filter, use the AND, OR, and NOT operators to combine them.
 - To add an operator, select the conditions that you want to combine, and click an operator.
 - To change an operator, double-click the operator to toggle among available ones or select the operator and then select a different one from the list.
 - To remove an operator, select it in the condition string, and then click the delete button .
7. To change a condition, click the edit button .

Expand and Collapse a Member Within a Set

You can expand a member to add its child members below it as new rows, and you can collapse expanded members to remove the expanded member's child members.

Procedure

1. Right-click the set and click **Edit Set**.
2. Click the new button  and click **Expand** or **Collapse**.
3. In the **Available members** list, select the member to expand or collapse and click the right arrow to move it to the **Members** list.


Extended Data Items

Extended data items differ from the traditional, expression-based text strings by enabling you to add children, view details, select sets, sort sets, and apply contextual calculations.

Note: Extended data items do not apply to relational packages or non-dimensionally modeled packages.

You can do the following with extended data items that are not available with traditional data items:

- Add an extended data item's child members
You can double-click an extended data item to insert its child members beside it in the report object.
- View an extended data item's details
You can select an extended data item and see where the data item appears in the package in the **Properties** pane under **Data Item**.
- Select member sets
You can select a member in a set to highlight it as the primary selection and the other members as secondary selections.
- Sort sets

You can select an extended data item, click the sort button , and click **Advanced Set Sorting** to sort a set in ascending or descending order, to sort hierarchically, and to sort by caption, by a property, or by an intersection (tuple).

- Apply contextual calculations
You can select an extended data item and then, from the **Data** menu, click **Calculate** to see a contextual list of calculations that are available for this extended data item.

Extended data items are optional. If you use extended data items in a report, we recommend that you use them for the entire report instead of mixing them with expression-based data items. For information about turning on extended data items, see “Specify Report Properties” on page 364.

Note: In IBM Cognos Workspace Advanced, extended data items are always used. Therefore, if you are authoring a report in IBM Cognos Report Studio for report consumers who are working in Cognos Workspace Advanced, you should use extended data items.

Tips for Working with Ragged or Unbalanced Hierarchies

In ragged or unbalanced hierarchies, some members that are not at the lowest level of the hierarchy may have no descendants at one or more lower levels. Support for these hierarchy gaps in relational data sources is limited. More complete support is provided for OLAP data sources, but some reports may still result in unexpected behavior.

For example, the following may occur:

- Groups corresponding to missing members may appear or disappear when grouped list reports are pivoted to a crosstab. This happens with set expressions using the `filter` function, and detail filters on members.
- Ragged and unbalanced sections of the hierarchy are suppressed when set expressions in that hierarchy are used on an edge.
- When a crosstab is sectioned or is split into a master detail report, sections corresponding to missing members become empty.
- Cells that were suppressed may still appear in the report output for reports with ragged or unbalanced hierarchies.

Some of these behaviors may be corrected in a future release, while others may be codified as supported behavior. To avoid these behaviors, do not use levels from ragged or unbalanced hierarchies. Instead of using levels, use the descendants, children, or ancestors.

We consider the following scenarios to be safe:

- One or more nested level references on an edge with no modifying expression.
- A hierarchy reference on only one level of one edge.
- One or more explicit members or sets of explicit members as siblings on only one level of one edge.
- Summaries of the previous three scenarios.

In all cases, you should test reports based on ragged and unbalanced hierarchies to confirm that hierarchy gaps are handled correctly.

For more information about ragged or unbalanced hierarchies, see the IBM Cognos Framework Manager *User Guide*.

Related concepts:

“Creating Sections on Reports That Access SAP BW Data Sources” on page 498
SAP BW data sources may have problems with sections in reports under different circumstances:

Creating dimensional custom groups

Create custom groups to classify existing data items into groups that are meaningful to you.

You can reduce the number of values into smaller, more meaningful groups. For example, you can change a list of employees into my team and others.

When you are working with dimensional data and crosstabs or charts, you can create custom groups only on sets of members. After you create a custom group in a set, the members in the set are replaced by the custom groups.



When you create custom groups in a list, a new column is added to the report, with the name *data_item (Custom)*. You can use this new column to group or sort the report. If you want to show only the new groups, you can delete the original column.


When you are creating custom groups on sets of members, consider the following constraints:

- Members included in a custom group must be from the same level in a hierarchy.
- If you insert a hierarchy that is used in a custom group elsewhere in the data container, it must be inserted as a sibling of the custom group.
- Automatic aggregation on a custom group might not work as expected. For example, you might encounter error cells (- -).

Procedure

1. To add custom groups in a crosstab or chart that includes sets of members, do the following steps:
 - a. Right-click a set and click **Edit Set**.

- b. Click **New**  and select **Custom Grouping**.
 - c. In the Custom Grouping window, click **New Custom Group** .
 - d. Type a New group name.
 - e. Select members from the **Available members** list and move them to the **Members** list.
2. To add custom groups to a list, do the following steps:
 - a. Click the column that you want to group on and from the **Data** menu, select **Calculate > Define Custom Groups**.

Tip: You can click either the column heading or one of the column cells.
 - b. Click **New Group Entry** .
 - c. To group by values that you select, click **New Select Values Group**, type a **New Group Name**, select the required values from the **Values** box, and move the values to the **Selected Values** box.
 - d. To group by a range of values, click **New Range Group**, type a **New Group Name**, and enter the **From** and **To** values.
 3. If you do not want a group name to be displayed for remaining values, select **Do not show remaining values**. Clicking this option produces empty cells for remaining values.
 4. If you want the group name for remaining values to match each value, select **Use each remaining value as a group name**.
 5. If you want to specify your own group name for all remaining values, select **Group remaining values into a single group** and type the name that you want.
 6. If you are adding custom groups in a list, under **New data item name**, select either the default data item name or type a new data item name.

Summarizing Data Dimensionally

Summarize data in your reports to obtain totals, averages, and so on.

The summary options that you can use depend on the type of data source that you are using. If you are querying an OLAP data source, all measure values that appear in reports are pre-summarized because the data source contains rolled up values. The type of summary that is used is specified in the data source itself. As a result, we recommend that you use the Automatic summary when creating dimensional style reports. This ensures that the report always uses the type of summary that the data modeler specified in the data source.

For example, the modeler may have specified that the rollup for revenue is total and the rollup for stock prices is average.

If you use other types of summaries with dimensional style reports, you may encounter unexpected results.

You can also add summaries, which are supported for any data source. Summaries specify how data items are totaled in the headers and footers of a list and in the total rows and columns of a crosstab. For list reports, these summaries only summarize the data that is visible on that page of the report.

Revenue	2010	2011	2012	2013	Total
Camping Equipment	\$332,986,338.06	\$402,757,573.17	\$500,382,422.83	\$352,910,329.97	\$1,589,036,664.03
Personal Accessories	\$391,647,093.61	\$456,323,355.90	\$594,009,408.42	\$443,693,449.85	\$1,885,673,307.78
Outdoor Protection	\$36,165,521.07	\$25,008,574.08	\$10,349,175.84	\$4,471,025.26	\$75,994,296.25
Golf Equipment	\$153,553,850.98	\$168,006,427.07	\$230,110,270.55	\$174,740,819.29	\$726,411,367.89
Mountaineering Equipment		\$107,099,659.94	\$161,039,823.26	\$141,520,649.70	\$409,660,132.90
Total	\$914,352,803.72	\$1,159,195,590.16	\$1,495,891,100.90	\$1,117,336,274.07	\$4,686,775,768.85

Figure 51. Crosstab showing automatic summaries for rows and columns

You can specify summary aggregation in different ways by using any of the following:

- aggregation properties that are specified in the model
- the **Auto Group & Summarize** property
- the summarize button in the toolbar
- aggregation properties for a data item
- the solve order of calculations

Tip: When you add a summary by clicking the summarize button in the toolbar, a data item is created in the query for the summary. In lists, the data item that is created is called a list summary. In crosstabs and charts, the data item that is created is called a dimensional edge summary.

Limitation

If a summary is applied to a report that contains binary large object (BLOB) data, such as images or multimedia objects, you cannot also perform grouping or sorting.

The Type of Data

How data is summarized also depends on the type of data that you are summarizing. Summary rules are applied differently to facts, identifiers, and attributes. For example, if you summarize a data item that represents part numbers, the only summary rules that apply are count, count distinct, count non-zero, maximum, and minimum. For information about how to determine the type of data that a data item represents, see “Add Relational Data to a Report” on page 227 and “Add Dimensional Data to a Report” on page 267.

For information about how null or missing values are handled in summaries, see “Null (Missing) Values in Calculations and Summaries” on page 560.

Limitations on Measure Rollups

For all OLAP data sources except IBM Cognos PowerCube and Microsoft SQL Server 2005 Analysis Services (SSAS), aggregation and re-aggregation are supported only for calculations and measures that use the following rollups: Sum (Total), Maximum, Minimum, First, Last, and Count.

All other types of rollup either fail or return error cells, which typically appear as two dash characters (--).

This problem occurs in, but is not limited to, the following:

- footers

- aggregate function
- context filters that select more than one member of a hierarchy that is used elsewhere on the report

Summarizing Sets

When working with Microsoft SQL Server Analysis Services (SSAS) data sources, we recommend that you not summarize values for sets which contain members that are descendants of other members in the same set. If you do so, SSAS double-counts values for automatic summaries and all data sources double-counts values for explicit summaries.

Related concepts:

“Limitations When Summarizing Measures in DMR Data Sources” on page 552
 There are limitations when summarizing dimensionally-modeled relational (DMR) measures and semi-additive measures in crosstabs using the aggregation function `count distinct`, `median`, `standard-deviation`, or `variance`. The following limitations can produce empty or error cells when the report is run:

Add a Simple Summary

You can add simple summaries in a report by using the summarize button . This button provides a subset of the summary functions available in IBM Cognos Report Studio.


The summarize button sets the rollup aggregate property for the data item to the selected summary, and places the data item into an appropriate footer. A footer is created for each set, hierarchy, or level.

In crosstabs and charts, the summary appears as a node.

In crosstabs, you can add multiple summaries at the same level. For example, you have a crosstab with Product line as rows, Order year as columns, and Revenue as the measure. For Product line, you can add the **Total** summary as a header, which will total all revenue for each order year. You can then add the **Average** summary as a footer, which will give the average revenue of all product lines for each order year.

For information about adding a rolling or moving average, see “Rolling and Moving Averages” on page 286.

Procedure

1. Click the item to which to add a summary.
2. Click the summarize button  and click a summary type.
3. To change the summary label, do the following:
 - Click the label.
 - In the **Properties** pane, under **Text Source**, set the **Source Type** property to the source type to define the label.
 For example, set it as **Data Item Value** to produce a dynamic label for the summary based on data item values.
 - Set the property under **Source Type** to specify the label.

This property depends on the source type you chose. For example, if you chose **Data Item Value** as the source type, set the **Data Item Value** property to the data item to use to define the label.

- To change a summary, select it and, in the **Properties** pane, under **Data Item**, click **Aggregation Method** and choose a different function.

Summarizing Values in Crosstabs

In crosstabs, summaries are calculated using two summary expressions.

The expressions used to summarize data are:

- aggregate (*[measure within set [data item]]*) summarizes the member values from the data source within the current content.
- aggregate (*[measure within detail [data item]]*) summarizes the lowest level of details in the report.

The expression that is used to calculate a summary is controlled by the summary's **Use Set Aggregation** property. For example, in the following crosstab, if you specified **Total** as the summary, the following aggregate expressions are produced when the **Use Set Aggregation** is set to **Yes** and **No** respectively:

		<#Revenue#>
<#Quarter#>	<#Month#>	<#1234#>
	<#Month#>	<#1234#>
<#Total(Quarter)#>		<#1234#>

- Total ([Revenue] within set [Quarter])

This expression totals the quarter values from the data source at the intersecting product line. At the bottom right corner, it totals the aggregate over all product lines for each quarter.

- Total ([Revenue] within detail [Quarter])

This expression totals the month values visible in the report at the intersecting product line. At the bottom right corner, it totals all of the intersecting month - product line values visible in the report.

In simple cases, the members and values visible in the report and the aggregate rules in the report are the same as those in the data source and all of these expressions produce the same results.

For example, for the quarter and month values, if you are totaling the values for all months in all quarters, it makes no difference whether the visible values, the values in the cube, or the month and quarter values are used. The result is the same.

		Revenue
2005 Q 3	2005/Sep	\$5,300,599.08
2005 Q 4	2005/Oct	\$11,778,348.92
	2005/Nov	\$3,353,399.48
	2005/Dec	\$4,645,069.28
2006 Q 1	2006/Jan	\$3,119,227.22
	2006/Feb	\$3,045,478.88
	2006/Mar	\$6,867,919.18
2006 Q 2	2006/Apr	\$8,306,586.26
	2006/May	\$5,129,112.24
	2006/Jun	\$6,927,447.24
2006 Q 3	2006/Jul	\$5,078,789.96
	2006/Aug	\$5,180,166.38
	2006/Sep	\$4,892,742.38
2006 Q 4	2006/Oct	\$15,887,237.28
	2006/Nov	\$3,609,599.42
	2006/Dec	\$6,240,652.88
Total(Quarter)		\$171,576,387.88

Tip: The Total Revenue by Country or Region sample report in the GO Data Warehouse (query) package includes a total summary function. For more information about The Sample Outdoors Company samples, see Appendix C, "Sample Reports and Packages," on page 525.

Different results appear when you start filtering, changing aggregation types, or using set expressions or unions.

For example, the following crosstab shows the quantity of products sold across all product types for each product line. The bottom of the crosstab has two summary values that show the average quantity of products sold by product line.

		Quantity
Camping Equipment	Cooking Gear	13,400,351.00
	Tents	3,164,285.00
	Sleeping Bags	3,153,218.00
	Packs	2,756,540.00
	Lanterns	4,826,755.00
Mountaineering Equipment	Rope	418,560.00
	Safety	1,135,194.00
	Climbing Accessories	5,850,251.00
	Tools	2,496,086.00
Personal Accessories	Watches	4,299,195.00
	Eyewear	20,311,396.00
	Knives	7,229,314.00
	Binoculars	1,075,087.00
	Navigation	1,992,713.00
Outdoor Protection	Insect Repellents	5,800,964.00
	Sunscreen	5,384,127.00
	First Aid	829,354.00
Golf Equipment	Irons	391,445.00
	Woods	317,939.00
	Putters	1,284,570.00
	Golf Accessories	3,119,747.00
Average - within detail		4,249,385.29
Average - within set		17,847,418.20

Each summary value uses a different expression that is set by the value specified for the **Use Set Aggregation** property.

- Average (Product line) - within detail
This summary is the average of the detail values in the crosstab.
- Average (Product line) - within set
This summary is the average of the product type values rolled up into sets at the Product line level. The values are obtained from the data source. If filters or slicers exist, the values are recomputed using the aggregation rules defined in the data source.

In most cases, you should use the within detail expression because the results are easiest to understand and the same as the results for footers in a grouped list report. The within set expression should be reserved for reports with a purely dimensional focus, such as when there are no detail or summary filters defined in the report.

Summarizing Member Sets

When you work with dimensional data sources and you summarize member sets, if an explicit summary function such as **Total** is used and the set contains

duplicates, the result is double-counted. If you are using an OLAP data source, the result produced for the automatic summary function depends on the data source.

For example, the following product line rows were defined using the expression union ([Product line], [Camping Equipment], ALL)

where [Product line] is the level that contains Camping Equipment.

	Revenue
Camping Equipment	1,589,036,664.03
Mountaineering Equipment	409,660,132.9
Personal Accessories	1,885,673,307.78
Outdoor Protection	75,994,296.25
Golf Equipment	726,411,367.89
Camping Equipment	1,589,036,664.03
Summary	4,686,775,768.85
Total	6,275,812,432.88

Figure 52. Crosstab showing revenue by product line with an aggregate row and a total row

For PowerCubes, Aggregate (Product line) is the sum of the product lines excluding duplicates. For more information about how the aggregate function is processed, see “Summary Functions” on page 287.

Rolling and Moving Averages

Use rolling and moving averages to analyze data for specific time series and to spot trends in that data. When viewing these averages on a line chart, use a longer period of time to reveal long-term trends.

In IBM Cognos Report Studio, to add a rolling or moving average, you must create summary and custom calculations using layout expressions “Insert a Query Calculation” on page 317.

The Rolling and Moving Averages interactive sample report includes rolling and moving calculations. For more information about The Sample Outdoors Company, see Appendix C, “Sample Reports and Packages,” on page 525.

Rolling Average

A rolling average continuously updates the average of a data set to include all the data in the set until that point. For example, the rolling average of return quantities at March 2012 would be calculated by adding the return quantities in January, February, and March, and then dividing that sum by three.

Tip: The Historical Revenue sample report in the Sales and Marketing (Cube) package also includes a rolling average. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Moving Average

A moving average calculates the average of a data set for a specified period. For example, the moving average of return quantities at March 2012 with a specified period of two would be calculated by adding the return quantities in February and March and then dividing that sum by two. In IBM Cognos Report Studio, you can use a prompt to specify the period.


Show Data for Specific Time Periods

Show data for a specific time period to associate a report with a business time period rather than the execution time. For example, you have a monthly report that you run at the beginning of each month, and you want the last business day of the previous month to appear rather than the day on which you run the report.

If the report functions `AsOfDate` and `AsOfTime` are added to the report, they will return a value based on the results of the **As of Time Expression** object. If the **As of Time Expression** object is not added to the report, these two functions return the date and time at which the report is run.

If the **As of Time Expression** object is added more than once in the report, the first occurrence of the object in the layout that returns a valid value is used.

Procedure


1. From the **Toolbox** tab , drag **As of Time Expression** to the report.
2. Double-click **As of Time Expression**.
3. In the **Expression Definition** box, type the expression.
The expression must return a date-time value.

Tip: You can drag a function that returns a constant from the **Constants** folder in the **Functions** tab. You can then change the constant to the value to use.

If you do not specify a time, the default time 12:00:00.000 AM is used.

Summary Functions

This section describes the summary functions that are available in IBM Cognos Report Studio. Some functions, such as **Custom**, are available only when you click

the summarize button  on the toolbar. Additional summary functions are available in the expression editor.

Automatic Summary

Depending on the type of data item, applies the function **None**, **Summarize**, or **Calculated** based on the context in which the data item appears.

Calculated is applied if the underlying data source is OLAP. It is also applied if the data item expression

- contains a summary function
- is an if then else or case expression that contains a reference to at least a modeled measure in its condition
- contains a reference to a model calculation or to a measure that has the **Regular Aggregate** property set to a value other than **Unsupported**

- contains a reference to at least one data item that has the **Rollup Aggregate Function** property set to a value other than **None**

If the underlying data source is relational and if the data item expression contains no summary functions and a reference to at least one fact that has the **Regular Aggregate** property set to a value other than **Unsupported**, **Summarize** is applied.

If the underlying data source is OLAP and if the data item expression contains no summary functions and a reference to at least one fact that has the **Regular Aggregate** property set to a value other than **Unsupported**, **Calculated** is applied.

If the underlying data source is SAP BW, reports containing aggregations and summaries run more efficiently if the aggregation applied to a query item matches the aggregation rule for the underlying key figure on the SAP BW server. In Report Studio, the easiest way to accomplish this is to change the value of the **Aggregate Function** property to **Automatic**.

In all other contexts, **None** is applied.

For relational and dimensionally modeled relational (DMR) data sources, if this function is applied to a data item expression that has the average function, weighted averages are computed based on the lowest level detail values in the data source.

Note: This is the default function.

Average

Adds all existing values and then divides by the count of existing values.

Calculated

Specifies that all the terms within the expression for a data item are aggregated according to their own rollup rules, and then the results of those aggregations are computed within the overall expression.

For example, a list contains the data item Quantity with the **Aggregation** property set to **Total**. You add a query calculation named Quantity Calculated. You define its expression as Quantity + 100 and you set its **Aggregation** property to **Calculated**. When you run the report, the values for Quantity Calculated are computed by first adding all values for Quantity and then adding 100 to each value.

Note: In crosstabs, this function overrides any solve orders that are specified.

Count

Counts all existing values.

If the underlying data source is OLAP, Count behaves as follows if it is specified in the **Rollup Aggregate Function** property for a data item.

Object	Behavior
Level	Count distinct is used. A warning appears when you validate the report.

Object	Behavior
Member set	Count distinct is used. A warning appears when you validate the report.
Attribute	Not supported. An error is returned when you run the report.
Measure	Supported.

If the underlying data source is dimensionally modeled relational (DMR), Count behaves as follows if it is specified in the **Aggregate Function** or **Rollup Aggregate Function** property for a data item.

Object	Behavior
Level	Count distinct is used. A warning appears when you validate the report.
Member set	Count distinct is used. A warning appears when you validate the report.
Attribute	Supported.
Measure	Supported.

If you add the count summary to a non-fact column in a list and then group the column, the column will not be grouped when you run the report. To resolve this issue, group the column first before adding the count summary.

Count Distinct

Returns the total number of unique non-null records.

If the underlying data source is OLAP, count distinct behaves as follows if it is specified in the **Rollup Aggregate Function** property for a data item.

Object	Behavior
Level	Supported.
Member set	Supported.
Attribute	Not supported. An error is returned when you run the report.
Measure	Not supported. An error is returned when you run the report.

If the underlying data source is dimensionally modeled relational (DMR), count distinct is supported for levels, member sets, attributes, and measures when it is specified in the **Aggregate Function** or **Rollup Aggregate Function** property for a data item.

Custom

Summarizes data based on an expression that you define.

Maximum

Selects the largest existing value.

Median

Returns the median value of the selected data item.

Minimum

Selects the smallest existing value.

None

Does not aggregate values.

If the underlying data source is relational, the data item is grouped when the query property **Auto Group & Summarize** is set to **Yes**.

Not Applicable

This function is available only for the **Aggregate Function** property. It specifies that the aggregate attribute is ignored. For example, the calculation will be applied after the data is aggregated.

This function differs from the **Calculated** function, which applies aggregation to the rows and then performs the calculation.

For example, for the average ([Quantity]) + 5 expression, when the **Aggregate Function** property is set to **Not Applicable**, five is added to the average of the single Quantity value. When the function is set to **Calculated**, five is added to the average of a set of numbers.

This setting should not be applied to a simple model reference.

This setting is relevant only for reports that are upgraded from IBM Cognos ReportNet 1.x.

Standard Deviation

Returns the standard deviation of the selected data item.

Note: From a mathematical perspective, this function is not useful for small numbers of items and is not supported if the query property **Auto Group & Summarize** is set to **Yes**.

Summarize

Aggregates data based on model or data type information. This function can be thought of as a calculate and then aggregate rule. Data is aggregated using the following rules:

If the underlying data source type is relational and the data item or calculation is a reference to a single fact query item in the model that has the **Regular Aggregate** property set to **Sum**, **Maximum**, **Minimum**, **Average**, or **Count**, aggregate data using this function. Otherwise, data is aggregated according to the data type of the data item as follows:

- **Total** is applied for numeric and interval values.
- **Maximum** is applied for date, time, and date-time values.

- **Count** is applied for everything else.

The underlying data source type can be dimensional and the data item or calculation a reference to a single item in the model. In this case, if the **Regular Aggregate** property of the model item is not **unknown**, the summary function that corresponds to the **Regular Aggregate** property is applied. If the **Regular Aggregate** property is **unknown**, set the function to **Calculated**.

For example, a list contains the data item Quantity with the **Aggregation** property set to **Average**. You add a query calculation named Quantity Summarize. You define its expression as Quantity + 100 and you set its **Aggregation** property to **Summarize**. When you run the report, the values for Quantity Summarize are computed by first adding 100 to each value for Quantity and then calculating the total. The total is calculated because Quantity contains numeric values and the expression for Quantity Summarize is not a simple data item reference. If Quantity Summarize is defined as Quantity, the function **Average** is applied to each value.

Total

Adds all existing values.

Variance

Returns the variance of the selected data item.

Note: From a mathematical perspective, this function is not useful for small numbers of items and is not supported if the query property **Auto Group & Summarize** is set to **Yes**.

Mapping Summary Functions From Data Sources to Framework Manager and Report Studio

The summary functions available in IBM Cognos Framework Manager and IBM Cognos Report Studio reflect summary functions supported by relational and dimensional data sources. The following table shows how summary functions in data sources are mapped to Framework Manager and Report Studio.

Data source	Framework Manager	Report Studio
None specified, or none	Unsupported	None
average (avg)	Average	Average
count	Count	Count
count distinct	Count Distinct	Count distinct
maximum (max)	Maximum	Maximum
minimum (min)	Minimum	Minimum
median	Median	Median
standard deviation (stddev)	Standard Deviation	Standard Deviation
sum	Sum	Total
variance (var)	Variance	Variance
count non zero	Count Non-Zero	Automatic
average non zero	unknown	Automatic
external	unknown	Automatic
any	unknown	Automatic

Data source	Framework Manager	Report Studio
calculated	unknown	Automatic
unknown	unknown	Automatic
first_period	unknown	Automatic
last_period	unknown	Automatic

The following summary functions exist only in either Framework Manager or Report Studio. There is no corresponding summary function in data sources.

Framework Manager	Report Studio
Automatic	Automatic
Calculated	Calculated
No corresponding summary function	Summarize
No corresponding summary function	Not Applicable

Focusing Dimensional Data

In IBM Cognos Report Studio, there are three approaches to focusing dimensional data in a crosstab:

- drag data items to the edges of your crosstab
- drag data items to the context filter area
- create set expressions on the edges of your crosstab that return members or sets of members, such as the filter function

Note: Summary and detail filters are recommended only for focusing data in relational reporting.

The approach you choose should depend on the capabilities of the data source, the performance requirements, the persistence of the dataset, and how complex you want the report to be.

If you filter values that are floating-point numbers, you may encounter imprecise filtering results due to rounding or data truncation. Floating-point numbers may appear differently in the report than how they are stored in the data source. To ensure accurate results, your filter criteria should account for any rounding issues.

Consider the limitations when filtering dimensional data and when filtering data from SAP BW data sources.

You can also use prompts, or prompt controls, to allow users to provide input for the filter.

Related concepts:

“Limitations When Filtering Dimensional Data Sources” on page 552

Avoid combining context filters (slicers) with dimensional constructs that involve members from hierarchies that are used elsewhere in the report. This combination gives results that are often not what you might expect and that may change in a future release.

Create a Context Filter

When working with dimensional data, you can use context filters, or slicer filters, to quickly focus your report on a particular view of the data.

For example, the following crosstab contains product lines in the rows, years in the columns, and revenue as the measure. We want to filter the values to show us the revenue for only Web orders from Asia Pacific. To change the context, you drag Asia Pacific and Web from the source tree to the **Context filter** section of the overview area. The crosstab then shows the revenue for only Asia Pacific and Web. Changing context changes only the values that appear. It does not limit or change the items in the rows or columns.

Revenue	Asia Pacific			
	2010	2011	2012	2013
Camping Equipment	36,415,479.91	77,222,359.67	121,312,260.99	83,023,522.78
Mountaineering Equipment		18,115,550.83	37,258,799.5	31,810,456.11
Personal Accessories	67,562,845.5	94,998,084.39	136,872,087.64	106,879,947.27
Outdoor Protection	4,135,482.66	4,388,590.73	2,241,092.7	1,107,629.48
Golf Equipment	8,586,746.5	27,061,602.93	49,822,888.09	39,248,971.12

Figure 53. Crosstab showing revenue by product line by year filtered to show only Asia Pacific and web orders


The members that are used as the context filter appear in the report header when you run the report.

Any summary values in the report are recomputed to reflect the results returned by the context filter.

You can create multiple context filters to filter across two or more different hierarchies.

Tip: The Budget vs. Actual sample report in the Sales and Marketing (cube) package includes a context filter. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Note: There are limitations when using context filters:

- Calculated measures do not get suppressed by the filter. To avoid this, drag the desired members from the **Source** tab  directly onto the row or column edge instead of using the members in the context filter.
- Suppression can be slow on large cubes, because all of the data is retrieved and then filtered.

If the desired data in the context filter is from a hierarchy that appears on the crosstab edge, drag the desired members from the **Source** tab directly onto the crosstab edge.

If the desired data is from a hierarchy that does not appear on the crosstab edge, use a context filter in conjunction with other means to limit the data, such as a top or bottom filter.

To use a calculation or expression to define a context filter, create a slicer member set using the query explorer. A slicer member set is an expression that returns a set

of members from the same dimension. For example, you can define a slicer member set that filters for the top five products with the greatest revenue.

Context filters are different from other filters. When you filter data, members that do not meet the filter criteria are removed from the report. A context filter does not remove members from a report. Instead, their values are filtered or you see blank cells.

You can also use context filters as prompts when the report is run.


When creating context filters,

- use only members from hierarchies that are not already projected on an edge of the crosstab
- use only one member per hierarchy

Create a simple context filter

When working with dimensional data, you can use context filters, or slicer filters, to quickly focus your report on a particular view of the data.



Procedure

1. If you do not see the **Context filter** area, show it using the **View** menu (**Panes, Context Area**).
2. From the **Source** tab , select or search for one or more items on which to filter.
3. Drag the item on which to filter into the **Context filter** section of the overview area.
4. To change context, select a new item from the **Context filter** box.

Create an advanced slicer filter

To use a calculation or expression to define a context filter, create a slicer member set using the query explorer. A slicer member set is an expression that returns a set of members from the same dimension. For example, you can define a slicer member set that filters for the top five products with the greatest revenue.

Procedure

1. Pause the pointer over the query explorer button  and click the query to which to add a slicer.
2. On the **Toolbox** tab , drag **Slicer Member Set** to the **Slicer** pane.
3. Drag the members to the **Expression Definition** box.
You must join the members in the expression by using the set function. For example, the following expression contains the Fax and Telephone members from the Order Method dimension:
`set ([Fax],[Telephone])`
4. To add members from another dimension, repeat step 2 to create a separate slicer member set.

Define a Prompt Using a Context Filter

If context filters (or slicers) are defined, you can use these filters to create prompts in the report.

Prompts provide questions that help users to customize the information in a report to suit their own needs. For example, you create a prompt so that users can select a region. Only data for the specified region is retrieved and shown in the report.

Before you begin

Before you define a prompt, you must create context filters.

Procedure

1. In the **Context filter** section of the overview area, click the down arrow next to the filter to use as a prompt.
2. Click **Prompt** and do one of the following:
 - To remove the prompt, click **No Prompt**.
 - To allow users who run the report to select any member from the hierarchy, click **Prompt on Hierarchy**.
 - To allow users who run the report to select from a list of members in the current level, click **Prompt on Level**.

Sorting Dimensional Data

You can sort items to view them in your preferred order. By default, IBM Cognos Report Studio retrieves items in the order defined in the data source. OLAP data sources always have a defined order. The data modeler defines the sorting options in the model.

For more information about data modeling, see the IBM Cognos Framework Manager *User Guide*.

Tip: The Sales Growth Year Over Year sample report in the GO Data Warehouse (analysis) package includes sorting. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Limitations When Sorting SAP BW Data

If you use a SAP BW data source, each level in a hierarchy has an item with the same name as the level and a role of `_businessKey`. Such items are known as level identifiers. You should use only the level identifier of all the time-related characteristics, such as `0CALDAY` and `0CALMONTH`, for sorting. All other (attribute) items in these hierarchies are formatted string representations of the characteristic values with which they are associated. These formatted values sort alphanumerically and not chronologically.

Tip: By level identifier, we are referring to a query item with the same name as the level that has the role of `_businessKey`. Each level in a SAP BW hierarchy has a level identifier.

Sort Sets by Label


You can sort sets of members based on their label (or caption). By default, when you select **Sort by Label, Ascending** or **Descending**, the members within the set are sorted only by their labels. You can also perform advanced sorting to sort sets using an intersection (tuple) or a member property.

For example, a set contains regions and you sort the regions within the set in descending alphabetical order. Only extended data items that represent sets support set sorting.

Before you can perform set sorting, you must create sets for the members in your report.

You cannot sort data items from different dimensions that are intermixed. For example, if you have years and products on the same edge and at the same level in your crosstab, you can sort the years, and you can sort the product lines, but you cannot sort them as combined set because years and products come from different dimensions.

Procedure

1. In a crosstab, select a set to sort.
2. Click the sort button  and under **Sort by Label**, click **Ascending** or **Descending**.

Tip: To remove a sort order, click **Don't Sort**.

Sort Sets in the Opposite Axis by Value

You can sort members in the sets on the opposite axis based on the value of a member or measure that you select.

For example, a crosstab contains years inserted as individual members in the columns, product lines inserted as a member set in the rows, and revenue as the measure. You select the 2012 column and then select **Sort by Value, Descending**. The values in the 2012 column are sorted.

Revenue	2012	2013
Personal Accessories	594,009,408.42	443,693,449.85
Camping Equipment	500,382,422.83	352,910,329.97
Golf Equipment	230,110,270.55	174,740,819.29
Mountaineering Equipment	161,039,823.26	141,520,649.7
Outdoor Protection	10,349,175.84	4,471,025.26


Figure 54. Crosstab showing revenue by year by product line with the 2012 column sorted in descending order

Before you can perform this sorting, you must create sets for the members in your report.

In nested crosstabs, items are sorted based on the values of the innermost nested row or column of the opposite axis. For example, a crosstab contains years in the columns and retailers nested within product line in the rows. Select 2004, sort in descending order, and you see retailers listed from the largest value to the smallest value for each product line.

Procedure

1. In a crosstab, select a member or measure to sort.
For example, to sort a set in the row axis, select a member or measure in the column axis.

2. Click the sort button  and under **Sort by Value**, click **Ascending** or **Descending**.


Tip: To remove a sort order, click **Don't Sort**.

Perform Advanced Set Sorting

If you use dimensional data, you can sort using the property of a member.

For example, your report includes employee names and you want to sort the employees using the gender property. You can also sort using an intersection of members, also known as a tuple. For example, you want to sort the employees using the value of sick days taken for the year 2012.

Procedure

1. Select a set.
2. Click the sort button  and under **Other Sort Options**, click **Edit Set Sorting**.
3. Specify the sorting options.
4. If you are sorting members from different levels and want to preserve the hierarchy, select the **Hierarchized sorting** check box.
5. To sort items using a member property, under **Sort by**, double-click **Property**, navigate the tree, and select the member property to use.
6. To sort items using an intersection of members, or a tuple, under **Sort by**, click **Intersection (tuple)** and click the ellipsis button. Then, from the **Available members and measures** box, select the items to use and click the right arrow to move them to the **Intersection members and measures** box. You can also select items from the **Calculated Members and Measures** tab.

Working with Dimensional Queries

Queries specify what data appears in the report. In IBM Cognos Report Studio, you create and modify queries using Query Explorer.

Query Explorer provides an alternative way to modify existing reports or to author new reports. You can use Query Explorer to perform complex tasks and other tasks that are more difficult to do in the report layout. For example, use Query Explorer to

- improve performance by changing the order in which items are queried from the database, or by changing query properties to allow the report server to execute queries concurrently where possible

Note: Only queries that are referenced in the report layout can be executed concurrently. If a query is defined in Query Explorer by joining two or more existing queries, IBM Cognos Business Intelligence cannot execute the source queries concurrently. By default, queries run sequentially. Your administrator must enable the concurrent query execution feature. For more information, see the IBM Cognos Business Intelligence *Administration and Security Guide*.

- view or add filters and parameters and modify their properties
- view or add dimensions, levels, and facts
- incorporate SQL statements that come from other reports or reports that you write

- create complex queries using set operations and joins

Related concepts:

“Queries” on page 35

Queries determine what data items appear in the report. Sometimes you want detailed rows of data, which you obtain by using a simple SELECT statement. Other times you must calculate totals or averages using summary functions and grouped columns or must apply filters to show only the data you want.

Specify a List of Data Items for an Object

Specify the list of data items for an object when you must reference a data item that is in a query but is not in the layout.

For example, you want to add a layout calculation to a list that uses a data item that is in the query definition. If the data item does not appear in the list, you must reference it in order to make the layout calculation work. You must also specify the list of data items if you apply conditional formatting that uses a data item that is not in the query.

Procedure

1. Click a layout object.

Tip: For a list of layout objects for which you can specify a list of properties, see the **Properties** property in Appendix G, “Report Studio Object and Property Reference,” on page 799.


2. In the **Properties** pane, double-click the **Properties** property and select data items.

Relate a Query to a Layout

Queries and layouts work together. After you decide the type of data that you need, you must create a layout in which to show the results. Each column of data must be both selected for the query and shown in a layout unless there are some columns that you do not want to show. The query and layout portions of a report must be linked to produce a valid report.

IBM Cognos Report Studio automatically links query and layout. For example, when you use Report Studio and the list report layout, query and layout are automatically linked.

Procedure

1. Select a data container.
2. In the **Properties** pane, set the **Query** property to a query.
3. From the **Data Items** tab , drag data items from the query to the data container.

Using Dimensional Data Sources with Queries

When you are working with SAP BW data sources, you can use only a single hierarchy in a query.

Creating queries using a mix of OLAP and relational data is not supported. If you create queries using a database for which you do not know the type, consult your database administrator or modeler.

When performing multi-cube queries using dimensional data sources, the following restrictions apply:

- Only basic operators (+, *, /,-) are available for cross-cube calculations.
- Inner joins are not supported.
- All joins for multi-cube queries are outer joins.
- Viewing MDX using the **Generated SQL/MDX** query property may not show you the actual MDX that is executed. This is because when a multi-cube query is executed, a number of smaller queries are actually executed.

Related concepts:

“Problems with large SAP BW queries” on page 516

When you are working with an SAP BW data source, if your report includes a data set greater than 1,000,000 cells, you might encounter an XQE error.

Connecting Queries Between Different Data Sources

This section lists the data sources between which you can and cannot connect queries.

IBM Cognos Business Intelligence supports the following:

- RDBMS to RDBMS joins
- set operations of any two queries
- master detail relationships between any two queries
- drill from any query to any other query

You cannot create the following types of joins:

- cube-to-cube (homogeneous)
- cube-to-cube (heterogeneous)
- cube-to-RDBMS
- cube-to-SAP BW
- SAP-BW-to-RDBMS

Multiple-fact Queries

You must understand the result of a query on more than one fact table to achieve the results that you want. The result of a multiple-fact query varies depending on whether you are working with conformed or non-conformed dimensions, on the level of granularity, and on the additive nature of the data.

The GO Data Warehouse (analysis) package has characteristics that affect the results if you use a multiple-fact query with the Inventory and Sales namespaces. Granularity for time differs in that inventory levels are recorded monthly and sales are recorded daily. Also, Sales includes a non-conformed dimension, Order method.

The following examples will help you interpret the results of a multiple-fact query and understand the options for changing a query to obtain the results that you want.

Conformed Dimensions

Individual queries on Inventory and Sales by Quarter and Product yield the following results.

Quarter	Product	Opening inventory	Closing inventory	Quantity
Q1 2011	Husky Rope 50	0	4,853	9,259
	Aloe Relief	10,614	6,513	8,805
	Course Pro Umbrella	34,907	37,327	70,256
Q1 2011 - Average		15,174	16,231	
Q1 2011 - Total				88,320
Q2 2011	Husky Rope 50	4,853	5,728	8,725
	Aloe Relief	6,513	7,379	8,266
	Course Pro Umbrella	37,327	39,870	57,964
Q2 2011 - Average		16,231	17,659	
Q2 2011 - Total				74,955

A query on multiple facts and conformed dimensions respects the cardinality between each fact table and its dimensions and returns all the rows from each fact table. The fact tables are matched on their common keys, Product and Time.

Product and Time apply to both Inventory and Sales. However, inventory levels are recorded monthly and sales are recorded daily. In this example, results are automatically aggregated to the lowest common level of granularity. Quantity, which comes from Sales, is rolled up to months.

Nulls are often returned for this type of query because a combination of dimensional elements in one fact table may not exist in the other. For example, if Husky Rope 50 was available in inventory in Q1 2011, but there were no sales of this product in the same time period, Quantity would show a null in the Husky Rope 50 row.

IBM Cognos Business Intelligence does not support conformed dimensions generated by IBM Cognos Framework Manager for SAP BW data sources.

Non-conformed Dimensions

If a non-conformed dimension is added to the query, the nature of the results returned by the query is changed.

Quarter	Product	Order method type	Opening inventory	Closing inventory	Quantity	
Q1 2011	Husky Rope 50	Fax	0	4,853	388	
	Husky Rope 50	Telephone	0	4,853	1,015	
	Husky Rope 50	Mail	0	4,853	240	
	Husky Rope 50	E-mail	0	4,853	210	
	Husky Rope 50	Web	0	4,853	5,031	
	Husky Rope 50	Sales visit	0	4,853	1,961	
	Husky Rope 50	Special	0	4,853	414	
	Aloe Relief	Fax	10,614	6,513	411	
	Aloe Relief	Telephone	10,614	6,513	1,513	
	Aloe Relief	Mail	10,614	6,513	433	
	Aloe Relief	E-mail	10,614	6,513	839	
	Aloe Relief	Web	10,614	6,513	4,740	
	Aloe Relief	Sales visit	10,614	6,513	732	
	Aloe Relief	Special	10,614	6,513	137	
	Course Pro Umbrella	Fax	34,907	37,327	1,568	
	Course Pro Umbrella	Telephone	34,907	37,327	17,120	
	Course Pro Umbrella	Mail	34,907	37,327	2,885	
	Course Pro Umbrella	E-mail	34,907	37,327	7,213	
	Course Pro Umbrella	Web	34,907	37,327	37,123	
	Course Pro Umbrella	Sales visit	34,907	37,327	2,793	
	Course Pro Umbrella	Special	34,907	37,327	1,554	
	Q1 2011 - Average			15,174	16,231	
	Q1 2011 - Total					88,320

Order method type exists only in Sales. Therefore, it is no longer possible to aggregate records to a lowest common level of granularity because one side of the query has dimensionality that is not common to the other side of the query. Opening inventory and Closing inventory results are repeated because it is no longer possible to relate a single value from these columns to one value from Quantity.

Grouping on the Quarter key demonstrates that the result in this example is based on the same data set as the query on conformed dimensions. Summary values are the same. For example, the total quantity for Q1 2011 is 88,320 in both examples.

Filters on Non-conformed Dimensions

By default, to improve performance, filters are applied at the database level. The default behavior can result in unexpected nulls when you add a filter to a multiple-fact query. If you create a filter on the Order method dimension to show only the fax order method and apply the filter at the data source, the report includes nulls.

Quarter	Product	Order method type	Opening inventory	Closing inventory	Quantity
Q1 2011	Husky Rope 50	Fax	0	4,853	388
	Aloe Relief	Fax	10,614	6,513	411
	Course Pro Umbrella	Fax	34,907	37,327	1,568
Q1 2011 - Average			15,174	16,231	
Q1 2011 - Total					2,367
Q2 2011	Husky Rope 50	Fax	4,853	5,728	419
	Aloe Relief	Fax	6,513	7,379	103
	Course Pro Umbrella		37,327	39,870	
Q2 2011 - Average			16,231	17,659	
Q2 2011 - Total					522
Q1 2012	Husky Rope 50	Fax	5,188	9,199	327
	Aloe Relief	Fax	7,093	6,395	277
	Course Pro Umbrella	Fax	39,911	38,343	4,040
Q1 2012 - Average			17,397	17,979	
Q1 2012 - Total					4,644
Q2 2012	Husky Rope 50	Fax	9,199	7,038	424
	Aloe Relief	Fax	6,395	5,085	86
	Course Pro Umbrella		38,343	31,799	
Q2 2012 - Average			17,979	14,641	
Q2 2012 - Total					510
Overall - Average			16,695	16,627	
Overall - Total					8,043

The filter is applied only to one subject area, Sales. Because Order method type does not exist in Inventory, all products still appear in the report. For example, Course Pro Umbrella was in inventory in Q2 2012. Because there were no sales using the fax order method for this product in Q2 2012, Order method type and Quantity are null.

To remove the nulls, change the filter so that it is applied to the result set instead of the data source. By applying the filter to the result set, you get the same results that you would get if you were working with conformed dimensions. Only the products that were ordered using the fax order method appear in the report.

Quarter	Product	Order method type	Opening inventory	Closing inventory	Quantity
Q1 2011	Husky Rope 50	Fax	0	4,853	388
	Aloe Relief	Fax	10,614	6,513	411
	Course Pro Umbrella	Fax	34,907	37,327	1,568
Q1 2011 - Average			15,174	16,231	
Q1 2011 - Total					2,367
Q2 2011	Husky Rope 50	Fax	4,853	5,728	419
	Aloe Relief	Fax	6,513	7,379	103
Q2 2011 - Average			5,683	6,554	
Q2 2011 - Total					522
Q1 2012	Husky Rope 50	Fax	5,188	9,199	327
	Aloe Relief	Fax	7,093	6,395	277
	Course Pro Umbrella	Fax	39,911	38,343	4,040
Q1 2012 - Average			17,397	17,979	
Q1 2012 - Total					4,644
Q2 2012	Husky Rope 50	Fax	9,199	7,038	424
	Aloe Relief	Fax	6,395	5,085	86
Q2 2012 - Average			7,797	6,062	
Q2 2012 - Total					510
Overall - Average			12,467	12,786	
Overall - Total					8,043

The overall summary for Quantity is 8,043 using either filter method, which shows that the results are based on the same data set.

In IBM Cognos Report Studio, there are two types of filters. A detail filter is applied to the data source. A summary filter is applied to the result set.

Related tasks:

“Create a Detail or Summary Filter” on page 243



Add a filter expression to focus a report and minimize processing time by excluding unwanted data. For example, you can filter data to show only customers who placed purchase orders that were valued at over one thousand dollars during the past year. When you run the report, you see only the filtered data.

Add a Query to a Dimensional Report

You can create multiple queries in Query Explorer to suit your particular needs. For example, you can create a separate query for each data container in a report to show different data.


Tip: The Briefing Book sample report in the GO Sales (analysis) package and the Top 10 Retailers for 2011 sample report in the GO Data Warehouse (analysis) package include multiple queries. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure


1. Pause the pointer over the query explorer button  and click **Queries**.
2. From the **Toolbox** tab , drag one of the following objects to the work area.

Object	Description
Query	Adds a query.
SQL	Adds SQL commands.
MDX	Adds MDX commands.

Note: When adding queries to the report

- right-click the work area and click **Show Package Sources** to see the queries that use data items from a package
 - right-click the work area and click **Expand References** to see the relationships that exist between queries in the report, which is useful when you are creating complex queries
3. In the **Properties** pane, set the object properties.
 4. Double-click a query.
 5. From the **Source** tab , drag data items to the **Data Items** pane.

Tip: You can add data items to the query that you do not want to appear in the layout. For example, to filter on Product line code and show Product line in the layout, you must add both data items to the query.

6. To create a new data item, from the **Toolbox** tab , drag **Data Item** to the **Data Item** pane.
7. To add a filter, from the **Toolbox** tab, drag **Filter** to the **Detail Filters** or **Summary Filters** pane and define the filter expression.

Tip: You can also create a filter by dragging a data item from the **Source** tab to one of the filters panes and completing the filter expression. When working with a dimensional data source, you can quickly filter data by dragging a member to a filter pane instead of dragging the level to which the member belongs. For example, dragging the member 2012 from the Years level will filter data for the year 2012. This method is quicker than dragging the Years level and specifying data only for the year 2012 in the filter expression.

Add Dimension Information to a Query

Add dimension information to a query when the data source has no dimension information available or when you want to override, extend, or restrict the information.





Add dimension information if any of the following apply:

- There is no dimension information available in the data source.
For example, the data source contains flat data that you want to model dimensionally.
- You want to override the dimension information in the data source.
- You want to extend or restrict dimension information in the data source.

If you do not add dimension information and the data source contains dimensions, then the dimension structure of the data source is used. If the data source contains no dimensions, IBM Cognos Business Intelligence creates a default dimension structure.

Dimension information is not intended to define the presentation of information, but to help query planning. Dimension information can be considered as a form of query hint. In addition, users will not be able to drill down on dimensions that you add to a report.


Procedure


1. Pause the pointer over the query explorer button  and click a query.
2. In the **Properties** pane, set the **Override Dimension Info** property to **Yes**.
The **Dimension Info** tab appears in the work area.
3. Click the **Dimension Info** tab.
4. To create a dimension from an existing data item, from the **Source** tab , drag the data item to the **Dimensions** pane.
IBM Cognos Report Studio automatically generates the entire dimension.
5. To create a new dimension, from the **Toolbox** tab , drag **Dimension** to the **Dimensions** pane, and then build the new dimension by adding objects to the dimension:
 - To create a level, drag **Level**.
 - To create a level hierarchy, drag **Level Hierarchy**.
 - To create a member hierarchy, drag **Member Hierarchy**.For information about these objects, see “Add Dimensional Data to a Report” on page 267.
6. From the **Source** tab , drag data items to the objects you added in the previous step.
For example, if you created a level, define a key by dragging a data item to the **Keys** folder.
7. To create a fact, from the **Source** tab, drag a data item to the **Facts** pane.

Example - Create a Crosstab Report that Shows Empty Rows

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a crosstab report that shows the total revenue per year for each product line broken down by order method. By default, if no revenue was produced for a particular product line in a specific year, no row appears in the crosstab for that product line and year. You override the dimension information of the crosstab so that empty rows appear in the report.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **Crosstab** and click **OK**.
4. From the **Source** tab , drag the following data items from **Sales and Marketing (query)**, **Sales (query)** to the crosstab:

- from the **Product** folder, drag **Product line** as rows
 - from the **Time dimension** folder, drag **Year** as nested rows
 - from the **Order method** folder, drag **Order method** as columns
 - from the **Sales fact** folder, drag **Revenue** as the measure
5. Right-click the crosstab and click **Go to Query**.
 6. In the **Properties** pane, set the **Override Dimension Info** property to **Yes**.
The **Dimension Info** tab appears at the bottom of the work area.
 7. Click the **Dimension Info** tab.
 8. From the **Source** tab, drag the following items to the **Dimensions** pane:
 - **Product line**
 - **Year****Product line** and **Year** become separate dimensions in the query.
 9. Pause the pointer over the page explorer button  and click **Page1**.
 10. Click **Year**.
 11. In the **Properties** pane, double-click the **Sorting** property.
 12. In the **Data Items** box, drag **Year** to the **Sort List** box.
 13. Run the report.

Results

All order years appear for all product lines, even if no revenue was produced.

Revenue		Telephone	Fax	Mail	Special	Web	E-mail	Sales visit
Camping Equipment	2010	80,467,596.88	9,634,763.39	10,015,621.15	5,844,211.12	125,829,519.92	39,124,634.73	62,069,990.87
	2011	47,562,256.31	6,228,274.27	8,846,759.96	5,012,986.47	270,463,415.88	21,291,005.31	43,352,874.97
	2012	17,715,451.4	5,226,451.57	2,482,266.26	332,095.44	426,353,675.75	10,612,304.02	37,660,178.39
	2013	8,149,587.54	1,964,909.25	3,996.72	1,199,696.41	311,192,071.84	4,871,150.57	25,528,917.64
Outdoor Protection	2010	8,141,169.76	1,435,512.2	1,402,530.23	858,775.41	13,735,716.85	4,135,915.35	6,455,901.27
	2011	3,203,287.7	385,329.2	594,355.43	267,356.86	16,479,270.8	1,406,531.47	2,672,442.62
	2012	507,485.63	123,028.48	101,506.05	10,798.96	8,570,078.91	289,343.01	746,934.8
	2013	76,371.43	22,614.84			4,166,745.33	50,688.04	154,605.62
Personal Accessories	2010	45,940,692.79	11,313,266.47	2,952,291.35	3,497,802.5	284,622,826.47	22,819,708.21	20,500,505.82
	2011	18,428,095.15	3,613,228.75	1,719,745.82	1,390,381.2	411,577,877.16	10,253,053.91	9,340,973.91
	2012	5,979,547.46	2,149,810.49	1,346,338.05	146,195.56	568,668,077.83	5,568,561.15	10,150,877.88
	2013	3,173,298.96	886,679.75	400,981.81	152,249.24	427,367,391.98	4,009,763.27	7,703,084.84
Golf Equipment	2010	44,244,120.93	6,255,930.08	8,396,407.78	3,705,129.72	49,583,401.41	29,322,537.92	12,046,323.14
	2011	27,340,352.57	3,539,563.59	2,355,735	1,259,633.25	116,939,694.38	8,851,232.61	7,720,215.67
	2012	6,411,233.64	2,408,222.14	1,941,144.7		203,385,896.61	5,401,733.78	10,562,039.68
	2013	734,405.51	3,037,587.46			157,698,057.23	4,358,428.85	8,912,340.24
Mountaineering Equipment	2010							
	2011	10,626,292.36	6,129,791.95	2,497,183.28	2,838,822.56	65,855,489.46	2,517,063.13	16,635,017.2
	2012	6,586,124.67	3,538,047.25	1,034,475.38	517,010.05	132,736,443.67	1,829,100.61	14,798,621.63
	2013	5,698,410.37	2,180,530.88		318,175.5	117,010,256.92	3,130,288.22	13,182,987.81

Create a Master Detail Relationship

Create a master detail relationship to deliver information that would otherwise require two or more reports. For example, you can combine a list with a chart. The list can contain product lines and the chart can show details for each product line.

Master detail relationships must appear in nested frames to produce the correct results. You can create a master detail relationship in two ways:

- Use a parent frame for the master query and a nested frame for the detail query.
- Associate a report page with the master query and use a data container, such as a list or crosstab, for the detail query.

You cannot display parent data in the child frame or child data in the parent frame. Also, you cannot perform calculations across master detail queries.

When you are working with dimensional data, IBM Cognos Report Studio does not support master detail relationships that use a custom group.




You can use a master detail relationship to show data from separate data sources in a single report. However, the data sources must be contained in the same package.



If you are working with an SAP BW data source, you cannot use a data item from the master query that contains non-ASCII values.

Before you begin

To create a master detail relationship using queries that reference two different dimensional data sources, you must first link the members by aliasing the levels that contain the members.

Procedure

1. To use a parent frame for the master query and a nested frame for the detail query:
 - From the **Toolbox** tab , drag a **List**, **Repeater Table**, or **Repeater** to the report.
 - Add a second data container to the object you inserted.
You can insert a list, crosstab, chart, repeater table, or repeater into a list.
You can add a list to a repeater table or repeater.
 - Add data items to both data containers.
2. To associate a report page with the master query and use a data container for the detail query:
 - Click anywhere in the report page.
 - In the **Properties** pane, click the select ancestor button  and click **Page**.
 - Set the **Query** property.
 - From the **Toolbox** tab, drag a data container to the report.
3. To link a data item in the master query to a parameter in the detail query instead of to another data item, create the parameter in the detail query.
Use parameters to filter values at a lower level in the detail query.
 - Pause the pointer over the query explorer button  and click the detail query.

- From the **Toolbox** tab , drag the **Filter** object to the **Detail Filters** box.
 - In the **Expression Definition** box, create the parameter.
4. Pause the pointer over the page explorer button  and click the report page.
 5. Click anywhere in the report page.
 6. In the **Properties** pane, click the select ancestor button and click **Page**.
 7. Click the data container containing the details.
 8. From the **Data** menu, click **Master Detail Relationships**.
 9. Click **New Link**.
 10. In the **Master** box, click the data item that will provide the primary information.
 11. To link the master query to a data item, in the **Detail** box, click the data item that will provide the detailed information.
 12. To link the master query to a parameter, in the **Parameters** box, click the parameter that will provide the detailed information.

Tip: To delete a link, select the link and press the Delete key.

13. If your detail query object is a chart, you can disconnect a chart title from the master query.
 - Click the chart title, and then, from the **Data** menu, click **Master Detail Relationships**.
 - Clear the **Use the master detail relationships from the chart** check box.
14. If your master detail relationship includes a chart as the detail and you are using automatic axis ranges, you can set the same axis range for all the detail charts:
 - Select the axis.
 - In the **Properties** pane, under **General**, double-click the **Axis Range** property.
 - Under **Maximum** and **Minimum**, click **Automatic**.

The master detail report option is only available with automatic axis ranges.

 - Under **Master detail reports**, select the **Same range for all instances of chart** check box.

For more information about axis ranges, see “Change the Axis Scale of a Current Default Chart” on page 124.

Tip: To avoid seeing the same data item twice in the report, click the data item in the data container driven by the detail query and click the cut button. This removes the item from the report display but keeps it in the query.

Related concepts:

“Master Detail or Burst Reports with Charts or Crosstabs May Result in Denial of Service” on page 517

When running a master detail or burst report that includes a chart or crosstab, disk space exhaustion may cause the report or other requests to fail. A large set of burst keys or master rows may produce one or more charts per detail, resulting in many master detail executions. This may cause the temp folder to accumulate many gigabytes of temporary files containing data required for successful chart rendering.

Link Members from Two Data Sources

If you create a master detail relationship using queries that reference two different dimensional data sources, you may need to create a relationship between levels with the same member captions but different Member Unique Names (MUNs).

For more information about MUNs, see “Recommendation - Use Member Unique Name (MUN) Aliases” on page 565.

For example, you may want to link the Americas member in the Sales territory level in the Sample Outdoors cube with Americas in the GO Subsidiary level in the Sample Outdoors Finance cube. To create the relationship, you must alias the levels that contain the members to link.

Procedure

1. In the parent frame or the report page, double-click the level that contains the member that will provide the primary information.
The **Data Item Expression** dialog box appears.
2. In the **Expression Definition** box, use the expression in the following function:
caption (*expression*)
For example, caption ([great_outdoors_company].[Sales Territory].[Sales Territory].[Sales territory])
3. Repeat steps 1 to 2 for the level in the data container that contains the details.
A caption alias is created for each level. You can now use the caption alias for each level to create a master detail relationship using member captions, which are the same, instead of MUNs, which are different.

Results

You can now create the master detail relationship between the two levels.

Working with Queries in SQL or MDX

For each query in a report, you can work with the SQL or MDX that is executed when you run a report.


Note: MDX is not available with DMR data sources.

View the SQL or MDX for an Entire Report or a Query

View the SQL or MDX to see what is passed to the database when you run a report.

Only SQL is available when using DMR data sources because these data sources were relational.

Procedure

1. To view the SQL or MDX for the entire report, from the **Tools** menu, click **Show Generated SQL/MDX**.
This option shows the SQL or MDX that will be executed in the data source. The SQL or MDX is organized by query and by query result. If a query is used in more than one data container, a query result is generated for each data container.
2. To view the SQL or MDX for a specific query, do the following:
 - Pause the pointer over the query explorer button  and click the query.

- In the **Properties** pane, double-click the **Generated SQL/MDX** property. The **Generated SQL/MDX** property shows the SQL or MDX that is executed when you view tabular data (from the **Run** menu, click **View Tabular Data**). Tabular data shows the data that is produced by the query in the form of a list. You can use this property to help you build advanced queries.

Results

The SQL or MDX for the query appears in the **Generated SQL/MDX** dialog box. For SQL, you can choose to view native SQL, which is the SQL that is passed to the database when you execute the query, or Cognos SQL, which is a generic form of SQL that IBM Cognos Report Studio uses. Cognos SQL is converted to native SQL before the query is executed.

Related tasks:

“Showing prompt values in generated SQL or MDX” on page 340

You can show prompt values when viewing the generated SQL or MDX of a query or report.

Build a Report Using Your Own SQL or MDX



You can build a report by adding SQL or MDX from an external source, such as another report.

If you are working with MDX, you must be aware of the MDX syntax that IBM Cognos Report Studio supports.

If you edit the SQL of a query, you must change the **Processing** property for that query to **Limited Local**.

You cannot build a report by adding your own MDX if the data source is IBM Cognos TM1®. IBM Cognos TM1 does not support custom MDX.




Procedure

1. From the **File** menu, click **New**.
2. Click **Blank**.
3. Pause the pointer over the query explorer button  and click **Queries**.
4. From the **Toolbox** tab , drag **Query** to the work area.
5. From the **Toolbox** tab, do one of the following:
 - To build an SQL query, drag **SQL** to the right of the query.
 - To build an MDX query, drag **MDX** to the right of the query.

Tip: You can drag **SQL** or **MDX** anywhere in the work area, and Report Studio will automatically create a query.

6. In the **Properties** pane, double-click the **Data Source** property and click a data source.
7. If required, set the **Catalog** property to the name of the catalog.
8. Double-click the **SQL** or **MDX** property and type the SQL or MDX.
9. Click **Validate** to check for errors.
10. If you are working with SQL, in the **Properties** pane, set the **Processing** property to **Limited Local**.
11. Double-click the query.

If the SQL or MDX is valid, the data items defined in the SQL or MDX appear in the **Data Items** pane.


12. Pause the pointer over the page explorer button  and click a report page.
 13. From the **Toolbox** tab, drag an object to the work area.
For example, drag a list, crosstab, chart, or repeater.
 14. Click the data container.
 15. In the **Properties** pane, click the select ancestor button  and click the container you just created.
For example, if you created a list, click **List**.
- Tip:** You can also click the container selector (three orange dots) of the container to select it.
16. Set the **Query** property to the query for the report type.
 17. From the **Data Items** tab , drag the items from the query you chose in the previous step to the data container.

Convert a Query to SQL

You can convert a query to SQL to edit it. You may want to do this to improve performance or to use SQL features that are not supported directly by IBM Cognos Report Studio.

Converting a query to SQL is an irreversible process.


Procedure

1. Pause the pointer over the query explorer button  and click the query.
2. In the **Properties** pane, double-click the **Generated SQL** property.
3. Click **Convert**.
4. Click **Validate** to check for errors.
5. In the **Properties** pane, set the **Processing** property to **Limited Local**.

Edit the SQL or MDX

You can edit the SQL or MDX for a query that has been created as an SQL or MDX query or that has been converted to SQL.

Procedure

1. Pause the pointer over the query explorer button  and click the SQL or MDX item under the query.
2. Double-click the SQL or MDX item.
3. Make changes in the text box.
If you are working with MDX, you must be aware of the MDX syntax that IBM Cognos Report Studio supports.
4. Click **Validate** to check for errors.

First-Rows Optimization

The SQL produced by IBM Cognos Report Studio depends on the report format you choose. For example, if you specify HTML format, first-rows optimization is requested. All-rows is requested if you specify PDF.

It is important for database administrators and programmers to remember that Report Studio does not always use first-rows optimization. If you assume first-rows optimization is always requested, this can cause the RDBMS optimizer to process the query differently than you expect.

Supported MDX Syntax

If you are working with MDX, you must be aware of the syntax that Report Studio supports. IBM Cognos Report Studio supports the MDX grammar as specified in Microsoft Data Access Software Developer Kit version 2.8.

Report Studio supports the following MDX functions. This is a partial list and applies only when you are working with the following data sources:

- cubes
- SAP BW
- IBM Cognos TM1
- DB2[®] OLAP
- IBM Cognos Consolidation
- IBM Cognos Contributor

For these data sources, IBM Cognos Business Intelligence uses a variation of the Microsoft SQL Server Analysis Services syntax.

- Acos
- Aggregate
- Ancestor
- Ancestors
- Asin
- Atan
- Avg
- BottomCount
- BottomPercent
- BottomSum
- Children
- ClosingPeriod
- CoalesceEmpty
- Convert
- Cos
- Cosh
- Count
- Cousin
- Crossjoin
- CurrentMember
- DefaultMember
- Descendants
- Dimension
- Distinct
- Except
- Exp
- Filter

- FirstChild
- FirstSibling
- Generate
- Head
- Hierarchize
- Hierarchy
- IIf
- Intersect
- Is
- IsAncestor
- IsEmpty
- Item
- Lag
- LastChild
- LastPeriods
- LastSibling
- Lead
- Level
- Levels
- LinkMember
- Ln
- Log10
- Max
- Median
- Members
- Min
- Mtd
- Name
- NextMember
- OpeningPeriod
- Order
- Ordinal
- ParallelPeriod
- Parent
- PeriodsToDate
- PrevMember
- PreviousMember
- Properties
- Qtd
- Rank
- Siblings
- Sin
- Sinh
- Stddev
- Subset

- Sum
- Tail
- Tan
- Tanh
- TopCount
- TopPercent
- TopSum
- Union
- Value
- Var
- Wtd
- Ytd

Example - Create a Dynamic Report That Shows Period-to-date Data

When you are working with a dimensional data source, you can use dimensional functions to retrieve data for a specific period-to-date.

In this topic, you learn how to create a dynamic report that retrieves year-to-date revenue for each product line. The report also shows the percentage of the revenue that is generated in the month users select when they run the report.

It should take 15-20 minutes to complete this topic, and your report will look like this.

Revenue	April 2010	YTD Revenue: April 2010	Percent of YTD Revenue
Golf Equipment	11,742,767.4	49,629,733.76	23.66%
Personal Accessories	26,057,935.06	118,968,943.76	21.90%
Camping Equipment	24,764,220	106,693,399.22	23.21%
Outdoor Protection	2,713,436.3	11,690,987.33	23.21%
Mountaineering Equipment			

Figure 55. Crosstab report showing year-to-date revenue for product lines

Procedure



1. Create a crosstab report that uses the **Go Data Warehouse (analysis)** package.
2. Add the following data items to the report:
 - From **Product**, drag **Product line** to the **Rows** drop zone.
 - From **Sales fact**, drag **Revenue** to the **Measures** drop zone.

Tip: Use the **Source** tab .

3. Create the following query calculation named **Selected Month** in the **Columns** drop zone:
`[Sales].[Time].[Time].[Month]->?Month?`
4. Create this query calculation named **Year to Date Set** next to the **Selected Month** column:

periodsToDate([Sales].[Time].[Time].[Year],[Selected Month])

Tip: Information about the periodsToDate function is displayed in the **Information** pane when you click the function in the **Functions** tab. The periodsToDate function is in the **M-Q** folder in the **Dimensional Functions** folder.

5. Click the **Year to Date Set** column and click the cut icon .
6. Create the following query calculation named **YTD Revenue** next to the **Selected Month** column:
total (currentMeasure within set [Year to Date Set])
7. Create the following query calculation named **Percent of YTD Revenue** next to the **YTD Revenue** column:
[Selected Month]/[YTD Revenue]
8. Click the **Unlock** icon  to unlock the report.
9. Add this text item to the left of the text in the **YTD Revenue** column, and add a blank space after the text:
YTD Revenue:
10. Set the font style of the text to italic.
11. In the **YTD Revenue** column, click <#YTD Revenue#> and change the **Source Type** property to **Report Expression**.
12. Double-click the **Report Expression** property and drag the **Month** parameter to the **Expression Definition** box.

Tip: You can find the **Month** parameter in the **Parameters** tab.
13. Click the lock icon to lock the report.
14. Right-click the **Percent of YTD Revenue** column title and click **Select Member Fact Cells**.
15. In the **Properties** pane, double-click the **Data Format** property.
16. Under **Format type**, click **Percent**.
17. Set the **No. of Decimals** property to 2.
18. Run the report to view it.

Results

Users are prompted to select a month. When they click **OK**, the report shows year-to-date revenue for each product line and the percentage of revenue that is generated for the selected month.

For more information, see the following references:

- Creating Report Templates
- Add Relational Data to a Report or Add Dimensional Data to a Report
- Using Dimensional Calculations
- Format Crosstabs
- Specify the Font
- Format Data

Using Dimensional Calculations

Insert a calculation to make your report more meaningful by deriving additional information from the data source. For example, you create an invoice report, and you want to see the total sale amount for each product ordered. Create a calculated column that multiplies the product price by the quantity ordered.

You build calculations in the expression editor using functions.

If a calculation is used in multiple reports, or by different report authors, ask your modeler to create the calculation as a standalone object in the model and include it in the relevant package.

Related concepts:

“Considerations when Creating Calculations” on page 555

Consider the following information and limitations when creating dimensional calculations.

Create a Simple Member Calculation


When working with dimensional data sources, you can select members in your report and create simple calculations.

In addition to simple arithmetic calculations, you can perform the following calculations:

Calculation	Description
Rollup	Summarizes, or rolls up, all the values of the selected items in a hierarchy.
%	Calculates the value of a selected item as a percentage of another item.
% Difference	Calculates the difference between two items as a percentage.
% Of Base	<p>This calculation is only available if you select two members from different hierarchies, each from a different edge.</p> <p>This calculation takes the first selected member from edge A and the second selected member from edge B. The calculation result of a percent of base should be such that all the values for member A will compare itself to the intersect value of member A and B.</p> <p>For example, you have a crosstab showing quantity sold by year by product line. You select 2012 and Camping Equipment, right-click the selection, click Calculate, and then click % of Base (2012, Camping Equipment). The calculated row shows the percentage value of each product line for 2012 as compared to Camping Equipment for 2012.</p>

Calculation	Description
Custom	Allows you to specify your own value when performing a simple arithmetic calculation. Also allows you to change the order of operands or type a custom name for the new calculated row or column.

Procedure

1. Select the items in your report to calculate.
2. Click the insert calculation button  and select the calculation to perform.

Tip: Calculations that are not applicable to the items you selected are greyed out.

3. To change the order of the operands or the name of the calculated item added to the report, click **Custom**.

Results

The calculation appears as a new row or column in your report.

Insert a Query Calculation

When working with dimensional data, insert a query calculation into your report to add a new row or column with values that are based on a calculation. For example, you create a query calculation named Euros that converts dollars to euros by multiplying an existing dollar measure by a conversion rate. Euros can then be displayed to end users in a separate row or column.

In IBM Cognos Report Studio, you can create the following types of calculations:




- Create calculated members or calculated measures where the expression is a member or a tuple-based (as opposed to property-based) value expression. For example, [2013] - [2012] is a calculated member and [Revenue] - [Planned Revenue] is a calculated measure.
- Use set expressions to create calculated sets of members. For example, children ([2012]) is a set expression that displays the child members of 2012.
You must base each set expression on a hierarchy and the set expression must contain only members from this hierarchy.
- Create value expressions when you want to insert a string, number, date, or interval value.





You can also create a calculation that uses an intersection (tuple) that you already defined.


If you are using a DB2 data source, the subtract operator is invalid if you combine the datatypes timestamp2 and packed decimal.



When creating an expression that will be used in a double-byte environment, such as Japanese, the only special characters that will work are ASCII-7 and ~ -- | | - \$ ¢ £ ¨.

Procedure

1. From the **Toolbox** tab , drag **Query Calculation** to the report.
2. In the **Name** box, type a meaningful name for your calculation.
For example, if you are calculating the difference between 2012 revenue and 2011 revenue, you could name your expression **2012 - 2011 Revenue**.
3. Click the type of calculation you want to create and select the hierarchy that contains the data that is the focus of your calculation.
4. In the **Available Components** pane, define the calculation:
 - Specify how you want to view the available data items in your data package by clicking the view member tree button  or the view package tree button .

- To add data items that are not shown in the report, on the source tab , double-click the data items.
- To add data items that are in the report but not necessarily in the model, such as calculations, on the data items tab , double-click the data items.
- To add data items from a specific query, on the queries tab , double-click data items.
- To add functions, summaries, and operators, on the functions tab , double-click elements.

Tip: To filter the visible functions, summaries, and operators in the **Available Components** pane, click the filter button  and filter by the function type, what the function returns, or what the function acts on.

- To add a value that is derived from a parameter, on the parameters tab , double-click a parameter.
Parameters define prompts, drill-through reports, and master detail relationships.
- To add a macro, on the macros tab , drag the parameter maps, session parameters, or functions you want to add to the macro.

Tip: Use **Insert macro block** to get you started with creating the macro expression. **Insert macro block** inserts number signs in the expression. Make sure that the macro expression you create is between the number signs.

You can also type the calculation directly in the **Expression Definition** box.

When typing date values, ensure that the date format is correct for your database type.



To copy and paste expression components in the **Expression Definition** pane,

you can use the copy button  and the paste button .

For information about specific functions, see Appendix F, “Using the expression editor,” on page 575.

5. Click the validate button .

Any validation errors appear on the **Errors** tab of the **Information** pane.

Tip: To copy and paste expression components in the **Expression Definition** pane, you can use the copy button  and the paste button .

Related concepts:

Chapter 18, “Using Query Macros,” on page 419

A macro is a fragment of code that you can insert in the Select statement of a query or in an expression. For example, add a macro to insert a new data item containing the user's name.






Create a Layout Calculation

Create a layout calculation to add run-time information to your report, such as current date, current time, and user name.

When you create layout calculations, unsupported functions do not appear in the **Functions** tab of the expression editor. Specifically, there is no **Summaries** folder, and some operators, constants, and constructs are also unavailable. These functions are not available because only the database can perform them. Report expressions and calculations based on layout expressions are performed in IBM Cognos Report Studio.



To see the complete list of functions available in the expression editor, except for report functions, create a query calculation. All functions are available when you create a query calculation because these calculations are performed in the database and not in Report Studio.

Procedure

1. From the **Toolbox** tab , drag **Layout Calculation** to the report.
2. In the **Available Components** box, define the calculation:
 - To add data items that are not shown in the report, on the source tab , double-click data items.
 - To add data items from a specific query, on the queries tab , double-click data items.
 - To add functions, summaries, and operators, on the functions tab , double-click elements.
 - To add a value that is derived from a parameter, on the parameters tab , double-click a parameter.

Parameters define prompts, drill-through reports, and master detail relationships.

Tips:

- You can also type the calculation directly in the **Expression Definition** box.
- When typing date values, ensure that the date format is correct for your database type.
- To copy and paste expression components in the **Expression Definition** pane, you can use the copy button  and the paste button .

For more information about creating expressions, see Appendix F, “Using the expression editor,” on page 575.

3. Click the validate button .



Create an Intersection (Tuple)

When working with dimensional data, an intersection, also known as a tuple, is useful for obtaining a value from the combination of two or more members that you specify. Each member must be from a different hierarchy. The intersection can include only one measure.

For example, the intersection (Revenue, 2012, Cooking Gear) shows the revenue value for the year 2012 and for the product line Cooking Gear.

Use tuples to avoid report summaries that do not reflect the visible data. For more information about this issue, see “Summaries in a report do not correspond to the visible members” on page 508.

Procedure

1. From the **Toolbox** tab , drag the **Intersection (Tuple)** object to the report.
2. From the **Available members and measures** pane, select items and click the right arrow to move them to the **Intersection members and measures** box. You can also use items from the **Calculated Members and Measures** tab .
3. To define the hierarchy for this intersection, click a parent object in the **Intersection hierarchy** box.

Assigning a Hierarchy or Dimension

You must assign each calculated member, set expression, and intersection (tuple) to a hierarchy or dimension. We recommend that you select the hierarchy or dimension upon which your calculation focuses. For example, if your calculated member is based on years, select the Time hierarchy. If you create a calculated measure, select the Measures dimension.

Select only a hierarchy that cannot affect the value of the calculation. For example, the hierarchy Camping Equipment has the same value no matter what Products context it appears in the report. Therefore,

- the calculation ([Camping Equipment]-[Mountaineering Equipment]) has a well-defined meaning only in the Products hierarchy, so select that hierarchy.
- the calculation tuple ([Revenue], [Camping Equipment]) can be assigned to either the Products or Measures hierarchy, as it is not affected by either context.
- the calculations ([2013] - [Camping Equipment]) and ([Fiscal Year 2013] - [Calendar Year 2013]) do not have a well-defined meaning in any hierarchy, and therefore cannot be used reliably at all.

Drilling Up and Drilling Down in Dimensional Reports

When working with dimensional or dimensionally-modeled relational (DMR) data sources, you can create reports that allow the reader to view more general or more detailed information on your data within a predefined dimensional hierarchy (such as Years - Year - Quarter - Month) without having to create different reports.

You can link groups of data items from different queries so that when you drill up or drill down in one query, the data item also drills up or drills down in the linked queries. Linking data items is useful if your report includes more than one query with the same data item. For example, if your report shows a list and a crosstab that each include the Product Line data item, you can link the Product Line data item from the crosstab query to the Product Line data item from the list query so that when you drill up in the crosstab Product Line data item, the list Product Line data item also drills up.

Member Sets

Member sets are used to group data items that are logically related for various actions, such as drill actions, zero suppression, and ranking. They can be defined as a flat list or as a tree structure in which member sets in the same parent chain are considered related.

For example, for drill operations, a member set defines the set of items that can potentially change when a given item in the set is drilled on. The values of other items in the query or even those in the same hierarchy are preserved when any item in this set is drilled on. Usually, a member set references items that have logical roles in a drill action, such as a detail, a summary of the detail, or a parent of the detail. A single data item can belong to only one member set.

If you do not define member sets for items, the IBM Cognos Business Intelligence server associates items into default member sets and behaviors using simple dimension rules on item expressions. You can override the behavior for a particular item while other items continue to use the default.



When you define a member set, you must explicitly define behaviors for each item in the set. Items in the set that have no behaviors have their values preserved.

Drill behaviors always act from a root member set. This means that when an item is drilled on, the root member of its member set is found and all items from the root down are processed. Although calculations and aggregates are not directly related by hierarchy, they respond because of their dependence on the items upon which they are based.

Create Member Sets

Create a member set when you want to define a non-default drill behavior. You specify what items respond to a drill action by adding them to the member set.

Procedure

1. Pause the pointer over the query explorer button  and click the query in which to create a member set.
2. In the **Properties** pane, set the **Define Member Sets** property to **Yes**.
3. Double-click the query and click the **Member Sets** tab.
4. From the **Source** tab , drag items to the work area.

To define a member set as a tree structure, drag the item that will serve as the root item of the set to the work area, and then drag other items over the root item to create the tree structure.

Note: You can also nest member sets.

Create a Drill-up and Drill-down Report

You can link groups of data items from different queries so that when you drill up or drill down in one query, the data item also drills up or drills down in the linked queries.

When you drill down or up, you can specify whether the column title shows the member caption value or the level label value. By default, titles use member captions. Using level labels may be more meaningful. For example, within the Country or Region column, you drill down on Australia. By default, the column title becomes Australia, the member caption. It may be more meaningful to use Country or Region, the level label, as the column title.

Tip: The Returned Items sample report in the GO Data Warehouse (analysis) package includes drilling. For more information about The Sample Outdoors Company samples, see Appendix C, "Sample Reports and Packages," on page 525.

Before you begin

Before you begin, ensure that you are using a dimensional data source.

Procedure

1. From the **Data** menu, click **Drill Behavior**.
2. On the **Basic** tab, in the **Report output drill capabilities** box, select the **Allow drill-up and drill-down** check box.



By default, IBM Cognos Report Studio determines which items can be drilled on based on the dimensional structure.

Tip: To enable the report to be used as the source during a package drill-through, select the **Allow this report to be a package-based drill-through source** check box and click **OK**. For more information about package drill-through, see the *Administration and Security Guide*.

3. To disable drill-up or drill-down for a data item, select the data item in either the **Disable drill-up for** box or the **Disable drill-down for** box.
4. From the **Advanced** tab, you can change the drill-up or drill-down behavior for any data item by selecting the data item and then choosing one of the following behaviors.

Behavior name	Drill-up behavior	Drill-down behavior
Preserve	The data item's value will remain unchanged.	The data item's value will remain unchanged.
Empty Set	The set of values associated with this data item is set to be the empty set (novalues). For crosstabs, the data item will effectively be removed from the report.	The data item will be removed from the report.
Replace Item	The data item's value will change to become the parent (if a lowest-level summary was drilled up on) or the grandparent (if a lowest-level detail of a dimension was drilled up on) of the item that was drilled on.	The data item's value will change to become the item that was drilled on.

Behavior name	Drill-up behavior	Drill-down behavior
Replace Expression	The data item's value will change to become the children of the parent (if a lowest-level summary was drilled up on) or the children of the grandparent (if a lowest-level detail of a dimension was drilled up on) of the item that was drilled on.	The data item's value will change to become the children of the item that was drilled on.
Change Expression	The data item's value will change to become the value of some other data item in the query.	The data item's value will change to become the value of some other data item in the query.
Depth Based Expression	The data item's value will change to become all data items n generations higher in the dimensional hierarchy than the item that was drilled on. The number of generations or levels is determined by the Depth value.	The data item's value will change to become all data items n generations higher in the dimensional hierarchy than the item that was drilled on. The number of generations or levels is determined by the Depth value.
Ancestor	The data item's value will change to become the data value of the ancestor n generations higher in the dimensional hierarchy than the item that was drilled on. The number of generations or levels is determined by the Depth value.	The data item's value will change to become the data value of the ancestor n generations higher in the dimensional hierarchy than the item that was drilled on. The number of generations or levels is determined by the Depth value.

5. In the **Column title drill behavior** box, specify whether to use member captions or level labels as the columns titles for each data item.
6. From the **Data Items Linking** tab, you can link groups of data items:
 - Click the new button .
 - Type a name for this group of linked data items and click **OK**.
To rename a group of linked data items, click the group, click the **Rename Group of Linked Data Items** icon , type a name, and click **OK**.
 - Use the arrows to move data items from the queries on the left to the groups on the right.

Note: You can only add a data item to one group.

Results

The report will generate links for any item that can be drilled up or down on.

When you run a report, you can drill down or drill up by right-clicking the data item and choosing the action from the context menu. The menu items will be disabled if an item cannot be drilled up or down on.

Related tasks:

“Create a Drill-up and Drill-down Chart” on page 157

If you use a dimensionally-modeled data source, you can create a chart that allows you to drill down to lower-level data or drill up to higher-level data.

Recommendation - Drilling Down in Very Large Data Sources

When you drill down in a report that uses a very large data source query results can be much larger than what can be held in memory. For example, if you insert the lowest level of four hierarchies that each contain 1000 members, the report can contain 1,000,000,000,000 cells. At best, this query will take a very long time to run. While this large query executes, all other queries for the same server process will likely be blocked. For most data sources, the query will likely fail due to insufficient memory or timing out. Then the memory is released and normal services resume.

However, when using a Microsoft SQL Server 2005 Analysis Services (SSAS) cube, the memory consumed by the SSAS client is not always released in a way that other queries can effectively re-use. The server continues to run with insufficient memory, causing new queries to either run very slowly or fail completely. You may encounter an error, and, to continue, the system administrator must manually stop and restart the IBM Cognos BI service.

To avoid these problems, consider the size of hierarchy levels and sets when creating reports and avoid combining them in ways that create large queries. To determine the size of a set, create and run a very small report that includes only a count of the members within that set. You can also use filtering techniques to focus your data.

Example - Create a Dashboard Report

Create a dashboard report to show a high-level graphical view of company performance indicators.


By using dashboard reports, users can

- drill up and drill down to see higher and lower levels of detail
- navigate to other targets, including IBM Cognos Report Studio reports, IBM Cognos Query Studio reports, and IBM Cognos Analysis Studio analyses
- include multiple charts derived from different data sources in a single report

Dashboard reports are not the same as workspaces or dashboards created in IBM Cognos Workspace. Dashboard reports display several different report objects in one report, but the information in the report is static. Workspaces created in Cognos Workspace are a collection of IBM Cognos content that you assemble into an interactive workspace. Content is displayed in widgets. For information about creating interactive and sophisticated workspaces, see the IBM Cognos Workspace *User Guide*. You can also create dashboards within IBM Cognos Connection. In these dashboards, content is displayed in portlets within pages. For more information, see the IBM Cognos Connection *User Guide*.


In this topic, you learn how to create a dashboard report so that users can examine important sales data in a single view.

It should take 15 to 20 minutes to complete this topic, and your dashboard report will look like this.



Procedure

1. Create a blank report with the **GO Data Warehouse (analysis)** sample package.
2. Add a column chart, a bullet chart, and a crosstab.
3. Drag the following items to the bullet chart:
 - **Revenue** (in **Sales and Marketing (analysis)**, **Sales**, **Sales fact**) to the **Bullet Measure** drop zone
 - **Planned Revenue** to the **Target Measure** drop zone
 - **Product line level** (in **Products**) to the **Series (matrix rows)** drop zone
 - **Region level** (in **Retailers**) to the **Categories (matrix columns)** drop zone
4. Drag the following items to the column chart:
 - **Revenue** (in **Sales fact**) to the **Default measure (y-axis)** drop zone
 - **Product line level** (in **Product**) to the **Categories (x-axis)** drop zone
 - **Retailers level** (in **Retailers**) to the **Series (primary axis)** drop zone
5. Drag the following items to the crosstab:
 - **Gross margin** (in **Sales fact**) to the **Measures** drop zone
 - **Product line level** (in **Product**) to the **Rows** drop zone
 - **Region level** (in **Retailer site**) to the **Columns** drop zone
6. Click the bullet chart.
7. Set the **Size & Overflow** property width to **300 px** and height to **300 px**.

8. Set the **Title** property to **Show**.
9. Double-click the chart title and type the following text:
Gross Profit for Product Lines by Region
10. Set the **Font** property for the chart title to **Arial, 12pt, Bold**.
11. Set the **Padding** property for the left and bottom padding to **20 px**.
12. In the **Bullet Indicators** property, set the bar width to 30%.
13. Click the chart, click the **Chart Palette Presets** icon , and click **Contemporary** from the available palettes.
14. Set the **Size & Overflow** property width to **300 px**.
15. Set the **Title** property to **Show**.
16. Double-click the chart title and type the following text:
Product Lines: Revenue by Retailer
17. Set the **Font** property for the chart title to **Arial, 12pt, Bold**.
18. From the **Data** menu, click **Drill Behavior**.
19. Select the **Allow drill-up and drill-down** check box.
20. Run the dashboard report to view what it will look like for your users.

Results

Users can drill up or drill down on values in the report to view related information.

For more information, see the following references:

- Creating Report Templates
- Add Relational Data to a Report or Add Dimensional Data to a Report
- “Customize a Current Default Gauge Chart” on page 147
- Customize a Legacy Gauge Chart
- Specify the Height and Width
- Specify the Font
- Create a Drill-up and Drill-down Report

Chapter 12. Adding Prompts to Filter Data

You can add prompts to a report to add interactivity for users. Prompts act as questions that help users to customize the information in a report to suit their own needs. For example, you create a prompt so that users can select a product type. Only products belonging to the selected product type are retrieved and shown in the report.

Prompts are composed of three interrelated components: parameters, prompt controls, and parameter values. Parameters are based on parameterized filters and form the questions to ask users. Prompt controls provide the user interface in which the questions are asked. Parameter values provide the answers to the questions.

IBM Cognos Report Studio provides several ways to create prompts. You can

- use the Build Prompt Page tool
- build your own prompt and prompt page
- create a parameter to produce a prompt
- insert prompts directly into the report page
- in dimensional reporting, you can also define prompts using context filters

If you include reports from different packages in an interactive dashboard that uses global filters, ensure that you use the same parameter name for the prompt in all the reports. For more information about creating interactive dashboards in IBM Cognos Connection, see the IBM Cognos Business Intelligence *Administration and Security Guide*.

You can also create prompts in the package. For more information, see the IBM Cognos Framework Manager *User Guide*.

You can also use context filters, also known as slicer filters, to focus the data in your report.

Syntax of Prompt Expressions

Prompt expressions use the following syntax, where p represents the parameter name.

You can also use these expressions to create parameterized data items that you can then use in master detail relationships.

The type of expression you use depends on whether you have chosen relational or dimensional reporting style. For more information about reporting styles, see “Relational and dimensional reporting styles” on page 26.

Relational: Detail Filter Expressions	Dimensional: Context (Slicer) or Edge Expressions
[data item] = ?p?	[level or hierarchy]->?p?
for single-select prompts and master detail relationships	For single-select member prompts and master detail relationships

Relational: Detail Filter Expressions	Dimensional: Context (Slicer) or Edge Expressions
<p>[data item] in ?p?</p> <p>for multi-select prompts</p>	<p>set([level or hierarchy]->?p?)</p> <p>For multi-select member prompts</p> <p>filter ([set], [property expression] = ?p?)</p> <p>For single-select value prompts and master detail relationships</p> <p>A property expression is an expression that is assigned to a property to enable dynamic update of the property when the report runs.</p> <p>filter ([set], [property expression] IN ?p?)</p> <p>For multi-select value prompts</p> <p>A property expression is an expression that is assigned to a property to enable dynamic update of the property when the report runs.</p>

Related concepts:

“Prompt control labels” on page 490

You can associate labels to prompt controls to make the prompts accessible.

Related reference:

Appendix H, “Prompt API for IBM Cognos BI,” on page 1005

The JavaScript Prompt API provides report authors with a method of customizing prompt interaction in the reports they author.

Use the Build Prompt Page Tool

Use the **Build Prompt Page** tool to quickly add filters and prompts to a report. This tool creates filters in the query using the prompt information properties that are set in the IBM Cognos Framework Manager model. For more information about the prompt information properties, see the Framework Manager *User Guide*.

Note: The Promotion Success sample report in the GO Data Warehouse (analysis) package includes a prompt page. The Historical Revenue sample report in the Sales and Marketing (cube) package and the Eyewear Revenue by Brand and Size sample report in the GO Data Warehouse (analysis) package include multiple prompts. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Before you begin

Note: The **Build Prompt Page** tool creates a static report specification, so if the prompt information properties are updated in the Framework Manager model, those updates will not be reflected in your report.

Procedure

1. Click the column or row on which users will be prompted.
To create multiple prompts or a cascading prompt, click more than one column or row.

- From the **Tools** menu, click **Build Prompt Page**.

A prompt page is created that has



- a page header
- a prompt control for each selected column
- a page footer containing **Cancel**, **Back**, **Next**, and **Finish** buttons

Build Your Own Prompt and Prompt Page

Create your own prompt and prompt page to control how they appear in a report.

Note: The Promotion Success sample report in the GO Data Warehouse (analysis) package includes a prompt page. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure

- Pause the pointer over the page explorer button  and click **Prompt Pages**.
- From the **Toolbox** tab , drag **Page** to the **Prompt Pages** box.
- Double-click the page you just created.
- From the **Toolbox** tab, drag one of the following prompt controls to the prompt page.

Prompt control	Description
Text Box Prompt	Retrieves data based on a value that users type. Use this control when users know exactly what value they want to enter, such as a name or account number.
Value Prompt	Retrieves data based on values that users select from a list. Use this control to show a list of possible values from which users can choose. Note: The maximum number of items that can appear in a list is 5000.
Select & Search Prompt	Retrieves values based on search criteria that users specify. Data is then retrieved based on values users select from the search results. Use this control instead of a value prompt if the list of values is very long, which can slow down performance. Tip: Users have the option of performing a case sensitive or case insensitive search. A case sensitive search is faster, while a case insensitive search usually returns more values. You cannot use this control if you are working with SAP BW data sources.

Prompt control	Description
<p>Date Prompt</p>	<p>Retrieves data based on a date that users select.</p> <p>Use this control to filter a date column. Users can retrieve data for a specific day, a set of days, or a range of days.</p>
<p>Time Prompt</p>	<p>Retrieves data based on a time that users select.</p> <p>Use this control to restrict a report to a particular time or time range. For example, users can see how many orders are received after business hours. Users can then use this information to determine the number of staff needed to work after hours.</p>
<p>Date & Time Prompt</p>	<p>Retrieves data based on a date and time that users select.</p> <p>Use this control to filter a datetime or timestamp column. This control is useful for specifying ranges. For example, users can retrieve all orders received from Monday at 12:00 a.m. to Friday at 5:00 p.m.</p>
<p>Interval Prompt</p>	<p>Retrieves data based on a time interval that users specify.</p> <p>Use this control to retrieve data that is related to the passage of time. For example, users can retrieve a list of products that were returned 30 or more days after they were purchased.</p>
<p>Tree Prompt</p>	<p>Retrieves data based on values that users select from a list. Values are organized hierarchically.</p> <p>This control is useful when you are working with dimensional data sources. Data is shown from the top of a dimension hierarchy to the most detailed member, and users can choose the level of detail they want to view in the report. For more information about tree prompts, see “Control the Data That Appears in a Tree Prompt” on page 339.</p> <p>Tree prompts let you page through large numbers of prompt values with a More link at the bottom of the tree.</p>
<p>Generated Prompt</p>	<p>Selects a prompt control based on the data type of the data item.</p> <p>This control acts like a placeholder. When users run the report, the control is replaced by the appropriate prompt control. For example, if users are prompted for date values, the control is replaced by a date & time prompt.</p>

The **Prompt Wizard** dialog box appears.

5. If you are creating a text box, date, time, date and time, interval, or generated prompt, do the following:
 - Create a new parameter for the prompt or use an existing parameter.
 - Click **Next**.
 - If you created a new parameter, define the expression by selecting a data item from the package and the operator to use.

Tip: Make the prompt optional by selecting the **Make the filter optional** check box.

- Go to step 7.
6. If you are creating a value, select & search, or tree prompt, do the following:
 - Create a new parameter for the prompt or use an existing parameter.
 - Click **Next**.
 - If you created a new parameter and you want to use the parameter to filter data, select the **Create a parameterized filter** check box and define the expression by selecting a data item from the package and the operator to use. If you are creating a tree prompt, you must choose **in** in the **Operator** box. You can also use a parameter to provide a value for a layout calculation, such as showing a user's name in the report. When the report is run, you can use a parameter to prompt the user to type his name and have it appear in the report.

Tip: Make the prompt optional by selecting the **Make the filter optional** check box.

- Click **Next**.
- If you created a parameterized filter and you have more than one query defined in the report, select the check box for the query on which to filter and click **Next**.
- Select the **Create new query** check box to create the query that will be used to build the list of data values shown when the report is run.

Tip: Do not create a new query if you want to link the prompt to an existing query or if you intend to create the query at a later time.

- Click the ellipsis button beside **Values to use** and click the data item on which to prompt.
 - To choose a data item that is different than what users will see when they are prompted, click the ellipsis button beside **Values to display** and click the data item.
 - To create a cascading prompt, in the **Cascading source** box, click the parameter that represents the cascade source.
7. Click **Finish**.

Results






The prompt control is added to the prompt page. A prompt page is like a report page. You can insert graphics and text and apply formatting.


You can also modify the properties of the prompt control by clicking it and making changes in the **Properties** pane.

Example - Create a Report Showing Products Shipped for a Specific Time Interval

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a report that shows the time interval between closing and shipping dates.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **List** and click **OK**.
4. From the **Source** tab , expand **Sales and Marketing (query)** and **Sales (query)**.
5. Expand **Sales fact** and double-click **Quantity**.
6. Expand **Products** and double-click **Product type**.
7. Expand **Sales order** and double-click **Order number**.
8. Create a time interval calculation:
 - From the **Toolbox** tab , drag **Query Calculation** to the right of **Quantity** in the list.
 - In the **Name** box, type the following and click **OK**:
Time Interval
 - In the **Expression Definition** box, type the following and click **OK**:
[Sales (query)].[Time (close date)].[Date (close date)]-[Sales (query)].[Time (ship date)].[Date (ship date)]
9. Create a filter:
 - From the **Data** menu, click **Filters** .
 - Click the add button .
 - In the **Expression Definition** box, from the **Data Items** tab , double-click **Time Interval** calculation you created.
 - Add **> ?p1?** after **Time Interval** to create the following expression:
[Time Interval] > ?p1?
 - Click **OK** twice.

A parameterized filter is created that will return data when the difference between the return date and the order date is greater than the value specified by the user.
10. Create a prompt page:
 - Pause the pointer over the page explorer button  and click **Prompt Pages**.
 - From the **Toolbox** tab, drag **Page** to the **Prompt Pages** pane, and then double-click it.
 - From the **Toolbox** tab, drag **Interval Prompt** to the work area.
The **Prompt Wizard** dialog box appears.
 - Click **Use existing parameter**, and then click **p1**.

- Click **Finish**.
11. Run the report.
An interval prompt appears.
 12. In the **Days** box, type a value and click **Finish**.

Tip: You can also type values for the **Hrs** and **Mins** boxes.

Results

A list report appears showing all products that were shipped after the time interval you specified. For example, if you typed 5, the list will show products that were shipped more than 5 days after the order date.

Order number	Product type	Quantity	Time Interval
100001	Lanterns	256	29 days
100005	Binoculars	65	9 days
100005	Knives	502	9 days
100005	Watches	24	9 days
100005	Woods	26	9 days
100011	Cooking Gear	2,172	10 days
100011	First Aid	312	10 days
100011	Insect Repellents	1,792	10 days
100011	Knives	2,490	10 days
100011	Navigation	98	10 days
100011	Sleeping Bags	242	10 days
100011	Sunscreen	1,164	10 days

Figure 56. List showing order number, product name, quantity, date, and time interval



Create a Parameter to Produce a Prompt




IBM Cognos Report Studio can automatically generate prompted reports based on parameters you create. When you run the report, Report Studio can generate a prompt page for each parameter not associated to an existing prompt page depending on whether the prompt run option is selected or not.

Note: When Report Studio automatically generates a prompt, it creates filters in the query using the prompt information properties that are set in the IBM Cognos Framework Manager model. For more information about the prompt information properties, see the Framework Manager *User Guide*.

You can also define parameters when you want to create a drill-through report or define master detail relationships.

Procedure

1. From the **Data** menu, click **Filters** .
 2. On the **Detail Filters** tab, click the add button .
- The **Detail Filter** dialog box appears.

3. In the **Available Components** box, click the **Source** tab  or the **Data Items** tab  to select the data item to use for the prompt:
 - To filter data based on data items not shown in the report, double-click a data item on the **Source** tab.
 - To filter data that appears in the report but not necessarily in the model, such as calculations, double-click a data item on the **Data Items** tab.
 The data item appears in the **Expression Definition** box.
4. In the **Expression Definition** box, type an operator after the data item or select an operator from the **Functions** tab .

The operator sets some of the default properties of the prompt. For example, if the operator is equals (=), users will be able to select only a single prompt value and the prompt's **Multi-Select** property is set to **No**.

For more information about creating expressions, see “Using Relational Calculations” on page 262 or “Using Dimensional Calculations” on page 316.
5. Type a name after the operator to define the prompt parameter. A question mark must precede and follow the name.
6. To specify whether the prompt is mandatory, in the **Usage** box, click **Required**, **Optional**, or **Disabled**.

Create a Prompt Directly in a Report Page

You can add prompt controls directly in a report page instead of creating a prompt page.

Prompt controls that are added to report pages will not appear in the following:

- saved reports
- PDF reports
- reports that are sent to users by email
- scheduled reports


Prompt controls are interactive. They are used to satisfy parameter values before running a report. As a result, prompt controls added to a report page only appear when you run the report in HTML format. When you run a report in HTML format, users select which values they want to see, and the report is refreshed, producing a new report.

For the previously listed non-interactive reports, prompt parameter values must be collected and satisfied before the report is run. You provide the parameter values using the **Run options** tab in IBM Cognos Connection. If you do not provide all the required values, the report will fail to run. You can access the Run options tab

by clicking the set properties button  for the report.

Tip: The Revenue by Product Brand (2011) sample report in the Sales and Marketing (cube) package and the Rolling and Moving Averages interactive sample report include value prompts. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure

1. From the **Toolbox** tab , drag a prompt control to the report.
The **Prompt Wizard** dialog box appears.
2. Provide the information necessary to create the prompt.

Tip: Make the prompt optional by selecting the **Make the filter optional** check box. Otherwise, when you run the report for the first time, the prompt appears in a generated prompt page rather than in the report page. Alternatively, you can specify a default selection for the prompt.

3. In the work area, click the prompt.
4. In the **Properties** pane, set the **Auto-Submit** property to **Yes**.
If you do not set the **Auto-Submit** property to **Yes**, the report will not refresh when users select a different prompt value.

Tip: An alternative to setting the prompt to auto-submit is to add a prompt button from the **Toolbox** tab and set its **Type** property to **Finish**.

Results

The prompt control is added to the report page. You can modify its properties by clicking it and making changes in the **Properties** pane.

Modifying Prompts

For each prompt you create, you can modify its properties by specifying values in the **Properties** pane.

For example, you can

- change the prompt control interface
- require user input
- enable multiple selections
- show or hide prompt statuses
- specify default selections
- specify prompt values
- add prompt buttons
- create cascading prompts

Some properties you set for a prompt may be overridden under some conditions. For example, some properties set for the filter associated with a prompt may override the corresponding prompt property.

Change the Prompt Control Interface

By default, when you create a prompt, IBM Cognos Report Studio selects the prompt control interface. You can change the prompt control interface depending on the type of prompt you created. For example, for a value prompt, you can choose a drop-down list, a list box, or a radio button group.



Procedure

1. Click the prompt control.
2. In the **Properties** pane, set the **Select UI** property to the interface.

Specify That a Prompt Requires User Input

You can specify that a prompt requires user input before the report can run.

Procedure

1. Click the prompt control.
2. In the **Properties** pane, set the **Required** property to **Yes**.
3. Pause the pointer over the page explorer button  and click a report page.
4. From the **Data** menu, click **Filters** .
5. Click the filter associated with the prompt.
6. In the **Usage** box, click **Required**.

Results

When you run the report, a star appears next to the prompt indicating that the user must select or type a value.



If you have a cascading prompt and the parent prompt control is required, the child prompt control is disabled. This ensures that users choose at least one value in the parent prompt before they can choose a value in the child prompt. Conversely, if the parent control is optional, then the child control is populated. This gives users the ability to choose values in the child prompt without having to choose a value in the parent prompt.

Allow Users to Select Multiple Values in a Prompt

You can allow users to select more than one value in a prompt. For example, you have a prompt for which users must select a product line. You can modify the prompt so that users can select more than one product line.

If you enable multiple selections, the **Auto-Submit** property is always set to no.

Procedure

1. Click the prompt control.
2. In the **Properties** pane, choose whether to allow users to specify more than one value or a range of values:
 - To allow users to specify more than one value, set the **Multi-Select** property to **Yes**.
 - To allow users to specify a range of values, set the **Range** property to **Yes**.
3. Pause the pointer over the page explorer button  and click a report page.
4. From the **Data** menu, click **Filters** .

If you have more than one query defined in the report, you must first click an object linked to a query.
5. Double-click the filter associated with the prompt.
6. Change the operator to one of the following:
 - If you are creating a multi-select prompt, change the operator to **in**.
For example, [Product_line] in ?Product line? where [Product_Line] is the name of the data item allows users to select multiple product lines.
 - If you are creating a range prompt, change the operator to **in_range**.

For example, [Margin] in_range ?Margin? where [Margin] is the name of the data item allows users to specify a margin range.

Show or Hide Prompt Status

Each prompt you create in a report provides dynamic validation when the report is run. Validity checks are performed to ensure that the data is correct and that required values are supplied. For example, a star appears next to each required prompt. An arrow appears next to a prompt if you must select or type a value. If you type an incorrect value, a dotted line appears. You can choose whether to show the star and arrow for each prompt.


Procedure

1. Click the prompt control.
2. In the **Properties** pane, set the **Hide Adornments** property to **Yes** to hide the prompt characters or **No** to show them.

Specify a Default Selection for a Prompt

You can specify a default selection for a prompt so that users do not have to select or type a value when they run the report.

Procedure

1. Click the prompt control.
2. To define a range of values, in the **Properties** pane, set the **Range** property to **Yes**.
3. To specify more than one default selection, in the **Properties** pane, set the **Multi-Select** property to **Yes**.
4. In the **Properties** pane, double-click the **Default Selections** property.
5. Click the add button  and do one of the following:
 - If you chose to define a single value, type the value as the default selection.
 - If you chose to define a range of values, type the minimum and maximum values of the range in the **Minimum value** and **Maximum value** boxes, respectively.
6. Repeat step 4 to specify other default selections.

Customize Prompt Text

You can customize the instructional text that appears around prompts. For example, a value prompt with multiple selections includes a **Select all** link below the choices that you can customize to text other than **Select all**. You can also specify translated text in many languages for international report users.

Procedure

1. Click the prompt control.
2. To change the default prompt text, in the **Properties** pane, double-click any of the properties under **Prompt Text**.

Note: When you select a property in the **Properties** pane, its description appears in the information pane below the **Properties** pane.

3. Click **Specified text**, and then click the ellipsis button.
4. In the **Localized Text** dialog box, type the text that you want to appear.
5. To add customized text for other languages:

- Click **Add**.
- Select the countries and regions for which you want to specify localized text and click **OK**.
- To specify text for a country and region, select the country and region and click **Edit**, and then type the localized text in the text box.

Specify Prompt Values

You can provide your own values in a prompt instead of the default values that come from the database.



You can specify your own prompt values to

- show something different from what is in the database
- improve performance by not accessing the database
- provide text for optional prompts, such as Select a value
- restrict the number of values available

For example, you have a prompt in which users choose a country or region. For the database value United States, you want USA to appear in the prompt.

Tip: The Rolling and Moving Averages interactive sample report includes a value prompt. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure




1. Click the prompt control.
2. In the **Properties** pane, double-click the **Static Choices** property.
3. Click the add button .
4. In the **Use** box, type the prompt value to add.
5. In the **Display** box, type the value that will appear in the prompt.
6. Repeat steps 3 to 5 to add other prompt values.
7. To link a prompt value to a condition, do the following:
 - In the **Variable** box, choose the variable to use or create your own. For information about creating variables, see “Add a Variable from the Condition Explorer” on page 386.
 - In the **Value** box, click one of the possible values for the variable.
 - Click the static value to link to the variable and click the edit button .
 - In the **Display** box, type the value to appear in the prompt.
 - Repeat this procedure for each additional value.

Add a Prompt Button

Add prompt buttons so that users can submit selected items, cancel reports, or navigate between pages.

When you are building prompts and prompt pages, you may have to add prompt buttons to submit selections. Some prompt controls, such as the value prompt, can be set to submit selections automatically. Other prompt controls, such as the date prompt, require a prompt button.

Procedure

1. Pause the pointer over the page explorer button  and click the page to which to add a prompt button.
2. From the **Toolbox** tab , drag **Prompt Button**  to the work area.
3. Click the prompt button and, in the **Properties** pane, set the **Type** property to one of the following actions.




Goal	Action
Cancel the report	Cancel
Go to the previous prompt page	Back
Go to the next prompt page	Next
Run the report	Finish
Reprompt the user Tip: Reprompting users is useful when you have cascading prompts.	Reprompt

Create a Cascading Prompt

Create a cascading prompt to use values from one prompt to filter values in another prompt. For example, a report contains the columns Product line and Product type. You create prompts for these columns, and you specify that the Product type prompt is a cascading prompt that uses Product line as the source. When users select a product line, they see only the product types related to the selected product line.

Tip: The Employee Training by Year sample report in the GO Data Warehouse (analysis) package includes cascading prompts. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure


1. To make the cascading source a required prompt, select it and, in the **Properties** pane, set the **Required** property to **Yes**.
2. Click the prompt control to use as a cascading prompt.
3. In the **Properties** pane, double-click the **Cascade Source** property.
4. Click the parameter that represents the cascade source.
5. If the prompt allows users to select multiple values, add a prompt button to the cascade source to provide the cascading prompt with the appropriate values:
 - From the **Toolbox** tab , drag **Prompt Button**  to the report.
 - Click the prompt button and, in the **Properties** pane, set the **Type** property to **Reprompt**.
 - To change the text in the prompt button, on the **Toolbox** tab, drag **Text Item**  to the prompt button and type the text.

Control the Data That Appears in a Tree Prompt

You can control what data appears in a tree prompt and how the data is structured to get the results that you want. To do this, you add various functions to the filter expression.

In addition, the operator that you chose in the **Prompt Wizard** dialog box controls what appears next to each prompt value. If the operator is in or not in, check boxes appear next to each prompt value. If the operator is equals (=), no check boxes appear.

Procedure

1. Pause the pointer over the query explorer button  and click the query that is associated with the prompt.
2. In the **Data Items** pane, double-click the data item on which you are prompting.
3. In the **Expression Definition** box, type one of the following functions.

Goal	Function
Show the hierarchical structure of all members in the hierarchy. If this function is not used, all members are shown in a flat list.	rootmembers (<i>data_item</i>)
Show the descendants of the data item in a hierarchical structure where x represents the level. For example, if you are prompting on the Year hierarchy and x=1, you will see 2010, 2011, and 2012 in the tree. If x=2, you will see 2010 Q1, 2010 Q2, and so on.	descendants (rootmembers (<i>data_item</i>), x)
Show the children of a member. For example, 2012 Q1, 2012 Q2, 2012 Q3, and 2012 Q4 appear for the member 2012.	children (<i>member</i>)

Using in_range Filters with Character Data


If you use an in_range filter with character data, and the **From** value is greater than the **To** value, the filter returns no results. For example, if the **From** value is "Zone" and the **To** value is "Aloe Relief", the report returns no data.

To allow results within a range regardless of whether the **From** value is greater than the **To** value, your IBM Cognos administrator can enable a prompting setting. For more information, see the IBM Cognos Business Intelligence *Administration and Security Guide*.

Showing prompt values in generated SQL or MDX

You can show prompt values when viewing the generated SQL or MDX of a query or report.

Procedure

1. Pause the pointer over the query explorer button  and click the query for which you want to view the generated SQL or MDX.
2. In the **Properties** pane, set the **Use SQL Parameters** property to **Literal**.

Related tasks:

"View the SQL for an Entire Report or a Query" on page 260

View the SQL to see what is passed to the database when you run a report.

“View the SQL or MDX for an Entire Report or a Query” on page 309
View the SQL or MDX to see what is passed to the database when you run a report.

Chapter 13. Laying Out a Report

When creating a report, a good layout is essential to ensure that the information in the report is presented in a clear and effective manner.

Report Layout Recommendations

Consider the following recommendations when creating the layout of a report.

- Define the page structure.

Determine what goes into the page header, body, and footer. The page header contains information that appears at the top of each page. The page body contains information that starts on the first instance of the page. If there is too much data to fit on a single page, it continues across all instances of the page. The page footer contains information that appears at the bottom of each page.

- Identify horizontal bands of information.

Look for natural bands of information running across the page. Each of these bands typically translates into a block.

- Identify vertical bands of information.


In each horizontal band of information, look for bands that run up and down the page. Each of these bands typically translates into table cells.

- Decide which data frames to use to lay out the data.

Choose a list, crosstab, chart, repeater, or text frame.

- Set properties at the highest level item possible.

By setting properties at the highest level, you set them once instead of setting them for each child object. For example, if you want all text items in a report to appear in a specific font, set the font for the page.

Tip: When setting properties for an object, click the select ancestor button  in the **Properties** pane title bar to see the different levels available.

- Use padding and margins to create white space.

Do not use fixed object sizing unless it is absolutely necessary. When you specify that an object has a fixed size, your layout becomes less flexible.

The Page Structure View

When you add objects to a report, you usually work in the layout. An alternative view of the report is available.

From the **View** menu, click **Page Structure** to view the report in a different way.




Figure 57. Example of the page structure view

Use the page structure view

- to view the entire contents of a report page in a tree structure
Using a tree structure is useful for locating the objects in a page and troubleshooting problems with nested objects.
- to quickly move objects from one area of a page to another
If you have a complex layout, it may be difficult to select, cut, and paste objects in the layout view. Objects are easier to locate in the page structure view.
- to modify object properties
You can modify object properties in the layout or in the page structure view.

Tip: To switch back to the report layout, from the **View** menu, click **Page Design**.

Related concepts:



“Work in design, structure, or Active Report preview view” on page 33

IBM Cognos Report Studio has three views in which you can author reports: Page Design view, Page Structure view, and Active Report Preview view. Active Report Preview view is available only when you are authoring an IBM Cognos Active Report. You can choose a report authoring view on the **View** menu or by clicking the view icons in the Explorer bar.

Copy Object Formatting

You can quickly copy the formatting of items in your report, such as fonts, colors, borders, and number formats, and apply that formatting to other items.

Procedure

1. Click an item that has the formatting to copy.
2. Do one of the following:
 - To copy all the formatting applied to the item, click the pick up style button , click the item to format, and then click the apply style button .
 - To copy only one of the formatting styles, click the down arrow to the right of the pick up style button and click the style to copy. Then click the item to format and click the apply style button.

3. If you want to make changes to a style that you copied, click the down arrow to the right of the pick up style button and click **Edit Dropper Style**.
4. In the **Style** dialog box, specify basic and advanced style characteristics.

Add a Header or Footer to a Report or List

Add a header or footer to make a report easier to read. Headers and footers are containers in which you can add objects like text, images, and report expressions such as the current date and page numbers. You can add headers and footers to pages and lists.

Tip: The Revenue by Product Brand (2011) sample report in the Sales and Marketing (cube) package includes a customized header and footer. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Add a page header or footer when you want information to appear on every page in the report, such as a title or page numbers. You can use combinations of text, data items, and report expressions in titles.

You can add the following headers and footers to lists to organize data into logical sections or to identify every change in value of a column.

Type	Description
List page header	Adds a header that appears at the top of the list on every page in which list data appears.
Overall header	Adds a header that appears once at the top of the list.
Group or section header	Adds a header that appears for each group of a grouped column or each section.
Group or section footer	Adds a footer that appears for each group of a grouped column or each section.
Overall footer	Adds a footer that appears once at the bottom of the list.
List page footer	Adds a footer that appears at the bottom of the list on every page in which list data appears. Note that summary calculations in list page footers only summarize the data that is visible on that page of the list report.


You can also add section footers by adding a summary.

Before you begin


To see the headers and footers, ensure that the visual aids are turned on.


Procedure

1. If you want to add a page header or footer, from the **Structure** menu, click **Headers & Footers, Page Header & Footer**, select the appropriate check boxes, and click **OK**.

Tip: You can also click the headers & footers button  on the toolbar.

2. If you want to add a list header or footer, from the **Structure** menu, click **Headers & Footers, List Headers & Footers**, select the appropriate check boxes, and click **OK**.

Tip: You can also click the headers & footers button on the toolbar and then click the list headers & footers button .

3. If you want to add objects to a header or footer, drag the objects from the **Toolbox** tab  to the appropriate location.

To add objects to a list header or footer, you must first unlock the report. From the **Structure** menu, click **Lock Page Objects**.

Tip: To add data items to the page header or footer, you must associate a query to the page.

4. To split a header or footer into multiple cells that span the list, from the **Structure** menu, click **Headers & Footers** and click **Split List Row Cell**.
5. To merge multiple cells in a header or footer, from the **Structure** menu, click **Headers & Footers** and click **Merge List Row Cells**.
6. To add rows to a header or footer, from the **Structure** menu, click **Headers & Footers** and click **Insert List Row Cells Above** or **Insert List Row Cells Below**.


Add Borders to an Object

You can add borders to objects in a report such as a column, a header, or a footer or to the whole report.

Tip: You can also add borders using the IBM Cognos Report Studio toolbar.

Procedure

1. Click the object to which to add a border.

Tip: To quickly select the parent of an object, click the object, and then click the select ancestor button  in the title bar of the **Properties** pane.

2. In the **Properties** pane, double-click the **Border** property and select values in the **Color**, **Style**, and **Width** boxes.

Note: Specifying a width using % as the unit of measure is not supported when producing reports in PDF.

3. Apply the selected values to the top, bottom, left side, right side, or all sides of the object by clicking the appropriate button in the **Preview** section.

Tip: To clear the border applied, click the clear borders button .



Add a Text Item to a Report

You can add text to a report. You can insert text in other objects, such as a block or table cell, or directly in the report page.

You can also add multilingual text to a report.

You can now format the text by changing the font, color, size, and so on. Select the text and make the appropriate changes in the **Properties** pane.

Procedure

1. From the **Toolbox** tab , drag the **Text Item** object  to the report.
The **Text** dialog box appears.
2. Type the text and click **OK**.

Tip: You can also paste text from another part of the report.

Specify the Font for a Report

You can specify the font for text in a report.

Procedure

1. Click the object.

Tip: To specify the default font for the report, click the page.

2. Do one of the following:
 - From the toolbar, specify the font properties.
 - In the **Properties** pane, double-click the **Font** property and specify the font properties.

To specify the color of the text, click **Foreground Color**. Alternatively, you can specify the color of the text by clicking the **Foreground Color** property for the object.

Tip: Type a list of fonts in the **Family** box if you are not sure whether a specific font is installed on a user's computer. For example, if you type Times New Roman, Arial, monospace, IBM Cognos Report Studio checks to see if Times New Roman is installed. If it is not, Report Studio checks for Arial. If Arial is not installed, the monospace font used by the computer is used.

Results

If you clicked **(Default)** for any of the font properties, the default value for the property is used. Default values are stored in a style sheet that is used across all IBM Cognos Business Intelligence tools. You can modify default values by modifying classes.



Insert an Image in a Report

You can insert an image in a report. You can insert images in other objects, such as blocks or table cells, directly in the report page or as the background image of another object.

Before you begin

The images that you insert must first be uploaded to the IBM Cognos Business Intelligence server or another Web server and must be .gif or .jpg format.

Procedure

1. From the **Toolbox** tab , drag the **Image** object  to the report and then double-click it.
2. In the **Image URL** dialog box, type the URL of the image to insert or click **Browse** to go to the location containing the image.

To browse images on a Web server, you must enable Web-based Distributed Authoring and Versioning (WebDAV) on your Web server. For more information about configuring Web servers, see the IBM Cognos Business Intelligence *Installation and Configuration Guide*.

Insert a Background Image in an Object

You can insert a background image for objects in a report. For example, use a background image to add a watermark to a page.

You can also create your own background visual effects, such as drop shadows and gradient fills. For more information, see “Add Background Effects.”

Before you begin

The images that you insert must first be uploaded to the IBM Cognos Business Intelligence server or another Web server and must be .gif or .jpg format.

Procedure

1. Select the object.
2. In the **Properties** pane, under **Color & Background**, double-click the **Background Image** property.
3. To use the background from the default style for the object (Cascading Style Sheet (CSS) class), click **Default**.
4. To explicitly not insert a background image, click **None**.
This option overrides any default background images including background gradients on objects that appear in the 10.x report styles.
5. To insert a specific image, click **Specified** and in the **Image URL** box, type the URL of the image to insert or click **Browse** to go to the location containing the image.
To browse images on a Web server, you must enable Web-based Distributed Authoring and Versioning (WebDAV) on your Web server. For more information about configuring Web servers, see the IBM Cognos Business Intelligence *Installation and Configuration Guide*.
6. In the **Position** box, choose how to align the image in the object.
7. In the **Tiling** box, click a tiling option.

Related tasks:

“Change a Chart Background in a Legacy Chart” on page 119

You can use a solid color, a pattern, or a gradient fill effect to customize the chart background.

Add Background Effects

You can add background effects to enhance the appearance of your report. You can enhance objects, such as data containers (lists, crosstabs, and charts), headers, footers, page bodies, and so on with borders, gradient fill effects, drop shadows, and background images. You can also apply background effects as a class style.

The background effect is rendered within the rectangle area that bounds the object. To use a generated background in a chart, the chart must have a fixed size.

If the background image is complex and large, the size of the report output may be affected proportionately.


Background effects are rendered only if the data container has a fixed height and width; if a percentage size is used, the effects are ignored.

Resizing or overflow behavior is ignored for generated images in HTML reports.

Add background effects to a chart

Background effects include borders, fills, drop shadows, and images.

Procedure


1. Click the chart object.
2. To choose a preset background effect, click the background effects presets button  on the style toolbar, and then click a background.
3. In the **Properties** pane, under **Color & Background**, double-click the **Background Effects** property.
4. Select one or more of the following:
 - To apply a border, click **Border** and specify settings for border style, width, color, corner radius for rounded rectangles, and transparency. If the element also includes a fill with a transparency setting, select the **Allow transparent bleed** check box to apply the same transparency to the border.
 - To apply a fill effect, click **Fill** and specify the settings. The fill effect can either be a solid color, a gradient, or a pattern. You can define a gradient fill effect as a linear, radial line, or radial rectangle gradient.
 - To apply a drop shadow effect, click **Drop Shadow** and specify the shadow color, transparency value, color, and offset settings. The default horizontal and vertical offset is 5 pixels.
 - To specify one or more images as a background, click **Images**. You can specify the transparency value and the position for each defined image. You can also specify a custom position for each image.

Tip: To remove the effect, clear its check box.

Add a background gradient to a page

A background gradient is a shading that goes from one color to another either horizontally or vertically across your page.

Procedure

1. Click anywhere in the report page.
2. In the **Properties** pane title bar, click the select ancestor button  and click **Page**.
3. Under **Color & Background**, double-click the **Gradient** property.
4. Select the **Gradient** check box and then select the colors and direction for the gradient.


Background gradients and drop shadows do not appear in Microsoft Excel spreadsheet software output. They are also supported only for report outputs run in the Microsoft Internet Explorer Web browser.

Tip: To remove the effect, clear the **Gradient** check box.

Add a drop shadow to a container

A drop shadow is a border on the bottom and right of an object. You can specify the color and transparency of this shadow.

Procedure

1. Click the crosstab, list, repeater table, or table in the report.
2. In the **Properties** pane title bar, click the select ancestor button  and click **Crosstab, List, Repeater Table, or Table**.

Tip: You can also click the container selector (three orange dots) of the container to select it.

3. Under **Color & Background**, double-click the **Drop Shadow** property.
4. Select the **Drop shadow** check box and then select the color, offset, and transparency values.

Background gradients and drop shadows do not appear in Excel output. They are also supported only for report outputs run in the Internet Explorer Web browsers.

If you add a drop shadow, ensure that you also specify a background color for the object. Otherwise, if you keep the default transparent background, data values also have a drop shadow and are difficult to read.

Tip: To remove the effect, clear the **Drop shadow** check box.

Insert a Formatting Object in a Report

In addition to text and images, the **Toolbox** tab  contains other objects that you can add to the report layout.

Object	Description
Block	Adds an empty block, which is a container in which you can insert other objects. This is useful for controlling where objects appear. Tip: You can use blocks to add space between objects. However, empty blocks are not rendered. You must insert an object or specify the height and width. Tip: The Revenue by GO Subsidiary 2011 sample report in the GO Data Warehouse (analysis) package includes an empty block. For more information about The Sample Outdoors Company samples, see Appendix C, "Sample Reports and Packages," on page 525.
Table	Adds a table, which is a container in which you can insert other objects. This is useful for controlling where objects appear.
Field Set	Adds an empty block that has a caption. This is similar to the Block object, but with a caption.
Intersection (Tuple)	Adds an intersection (tuple). For more information, see "Create an Intersection (Tuple)" on page 320.
Query Calculation	Adds a calculated column. For more information, see "Using Relational Calculations" on page 262 or "Using Dimensional Calculations" on page 316.

Object	Description
Crosstab Space	<p>Inserts an empty cell on a crosstab edge. Allows for the insertion of non-data cells on an edge. Blank cells appear for the edge when the report is run.</p> <p>Insert this object when a crosstab edge does not produce useful data and you want blanks to appear in the cells instead.</p>
Crosstab Space (with fact cells)	<p>Inserts an empty cell on a crosstab edge. Allows for the insertion of non-data cells on an edge. The contents of the fact cells for the edge are rendered when a measure is added or the default measure is specified.</p> <ul style="list-style-type: none"> • If the crosstab space is nested, the scope of the fact cells is the scope of the item that is at the level before the space. • If the crosstab space is not nested and there are no items nested below it, the scope of the fact cells is the default measure.
Singleton	Inserts a single data item.
Conditional Blocks	Adds an empty block that you can use for conditional formatting.
HTML Item	<p>Adds a container in which you can insert HTML code. HTML items can be anything that your browser will execute, including links, images, multimedia, tooltips, or JavaScript.</p> <p>HTML items appear only when you run the report in HTML format.</p> <p>Note: You cannot include <form> tags in HTML items.</p> <p>Tip: The Table of Contents sample report in the GO Sales (analysis) package includes an HTML item. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.</p> <p>Note: When you upgrade to the next version of IBM Cognos Business Intelligence, the report upgrade processes do not account for the use of undocumented and unsupported mechanisms or features, such as JavaScript, that refers to IBM Cognos HTML objects.</p>
Rich Text Item	<p>Inserts an object that is used to render HTML in the layout. This object is similar to the HTML Item, except that rich text items also render in PDF output. Using rich text items is useful when you want to add annotations defined in a data source to a report.</p> <p>Note: Rich text items support only a restricted set of well-formed XHTML.</p>
Hyperlink	Adds a hyperlink so that users can jump to another place, such as a Web site.
Hyperlink Button	Adds a hyperlink in the form of a button.
As of Time Expression	Adds an As of Time expression so that you can show data for a specific time period.
Page Number	Inserts page numbers that you can customize.

Object	Description
Row Number	Numbers each row of data returned when the report is run. Note: You can add row numbers only to lists and repeaters.
Layout Component Reference	Adds a reference to another object. Useful when you want to reuse an object.
Table of Contents	Creates a table of contents that is rendered in the output of a report.
Table of Contents Entry	Adds a table of contents marker.
Bookmark	Inserts a bookmark so that users can move from one part of a report to another.

For information about each prompt control and prompt buttons, see Chapter 12, “Adding Prompts to Filter Data,” on page 327. The **Toolbox** tab contains other objects when you work in other areas such as Query Explorer and Condition Explorer.

Before you begin

Before you can add a hyperlink, HTML item, or hyperlink button, you must have the **HTML Items in Report** capability. For more information, see the IBM Cognos Business Intelligence *Administration and Security Guide*.

Procedure

To add an object, drag or double-click it from the **Toolbox** tab.

Elements Supported in Rich Text Items

Rich text items support all XHTML character entities, such as (non-breaking space), and the following elements: div, span, ul, ol, and li.

Each element only supports the style attribute, which must contain a valid CSS style. In addition, ul and ol elements support list-style attributes. Specifically, the ol element supports decimal, and the ul element supports circle, disc, and square, as well as list-style-image.

For example, the following code produces an unordered list entitled List: with three items. Each list item is in a different color, and the list-style attribute used is circle.



```
<div style="font-size:14pt; text-decoration:underline">List:</div>
<ul style="list-style-type:circle">
<li style="color:green">Item <span style="font-weight:bold">A</span></li>
<li style="color:red">Item B</li>
<li style="color:blue">Item C</li>
</ul>
```

Example - Add a Multimedia File to a Report

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You want to insert a Microsoft Windows Media Audio/Video file named GO.wmv in a template that serves as a cover page for all reports.

You must have Windows Media Player installed on your computer.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template** and in the **New** dialog box, click **Blank**.
3. From the **Toolbox** tab , drag the **HTML Item** object  to the report.
4. Select the **HTML Item**.
5. In the **Properties** pane, double-click the **HTML** property.
6. In the **HTML** dialog box, type the following:

```
<OBJECT classid="CLSID:6BF52A52-394A-11D3-B153-00C04F79FAA6">
<PARAM NAME="URL" VALUE="/c10/webcontent/samples/images/
GO.wmv"/> </OBJECT>
```

Results

When you run the report in HTML format, the multimedia file plays in Windows Media Player.

Align an Object in a Report

You can specify a horizontal and vertical alignment for an object in a report to determine where they appear.

Tables can also be used to determine where objects appear in a report.

Note: The **Justify** horizontal alignment works with HTML output but does not apply to PDF output.

Procedure

1. Select the object to align.
2. From the toolbar, click one of the available horizontal or vertical alignment buttons.

Using a table to control where objects appear




You can use tables in your report to control where objects appear. Tables can be inserted anywhere in a report, such as a header, a footer, or the page body. After you create a table, insert the objects you want in the cells.

You can also apply a predefined table style to tables. Other table properties are described in Appendix G, "Report Studio Object and Property Reference," on page 799.

The alignment buttons can also be used to determine where objects appear in a report.

Tip: The Singletons on Page Body sample report in the GO Sales (analysis) package includes a table to control the report layout. For more information about The Sample Outdoors Company samples, see Appendix C, "Sample Reports and Packages," on page 525.

Procedure

1. From the **Toolbox** tab , drag **Table**  to the report.
The **Insert Table** dialog box appears.
2. In the **Number of columns** and **Number of rows** boxes, type the number of columns and rows for the table.
3. If you want to have the table span the width of the report page, select the **Maximize width** check box.
4. If you want to add borders to the table, select the **Show borders** check box.
5. If you want to merge cells in the table, select the cells and click the merge cells  button.
6. Select the table object.
7. In the **Properties** pane, under **Positioning**, double-click the **Table Properties** property.
8. To display both the inside and outside borders, do the following:
 - Clear the **Collapse borders** check box.
 - Type a number in the **Cell spacing** text box to define how much space to add between the table cells.
 - Select the **Show empty cell borders** check box to display the borders even for empty cells.
9. To fix the size of the columns in the table, check the **Fixed size** check box.
When this check box is cleared, the table columns expand to fit the text.

Apply a Table Style

Apply a table style to quickly format tables. You can also apply a table style to lists, crosstabs, and repeater tables.

About this task

By default, when a new object is inserted in a list or crosstab, the object inherits the style from an object of the same type in the data container. For example, if you insert a measure in a list, the measure inherits the style of a measure that is already in the list, if there is one. If you do not want objects to inherit styles, clear the **Table Style inheritance** option in the **Tools** menu (**Tools, Options, Report** tab).

The following rules explain how style inheritance is applied to lists and crosstabs.

- Styles are inherited in the following order: custom, client default, and server default.
A custom style is a style that you manually apply. A client default style is one of the styles available in the **Apply Table Style** dialog box. The server default style is the style applied when **Default** is selected in the **Apply Table Style** window.
- When a new column or row is inserted, it inherits the style from the sibling of the same type that is on its right or below it.
- If there is no sibling of the same type, then the style of the nearest sibling that is on its left or above it is applied.
- If there is no sibling of the same type in the container, then the client or server default table style is applied.
- If a custom style is applied to a column or row and the object is then moved to another location, the object retains the custom style.

Custom styles applied to part of an object, such as the header, body, or footer, may be lost. For example, if a container has a footer, the footer is recreated when a column is moved. The recreated footer is rendered using the style that was applied to the footer before you customized its style.

- Deleting a column or row has no impact on the styles of the other objects in the container.
- Styles are preserved if a column is grouped or ungrouped. The same applies when creating or removing sections.
- When drilling up or down, the style of the parent item is applied.

Procedure

1. Click the table, list, crosstab, or repeater table.
2. From the **Table** menu, click **Apply Table Style**.
3. In the **Table styles** box, click a table style.

Tip: Some styles are unique to tables, lists, or crosstabs.

4. If you are applying a table style to a table or list, in the **Apply special styles to** section, select or clear the various column and row check boxes based on how you want to treat the first and last columns and rows.

Some check boxes may not be available for particular table styles, or to particular columns or rows.


5. If you are applying a table style to a list or crosstab and you want the style to be applied to all lists or crosstabs in the report, select the **Set this style as the default for this object type** check box.

For a list, you may need to clear the **First column** and **Last column** check boxes in the **Apply special styles to** section before you can select this check box. In addition, some table styles cannot be set as the default.

Apply Padding to an Object

Apply padding to an object to add white space between the object and its margin or, if there is a border, between the object and its border.

Tip: You can quickly apply left or right padding by either pressing Tab and

Shift+Tab or by clicking the increase indent  and the decrease indent buttons in the toolbar. When using the toolbar buttons, you can indent an object by up to nine times the indentation length. You can specify the indentation length to use by clicking the arrow beside either button and clicking **Set Default Indent Length**.

Tip: The GO Balance Sheet as at Dec 31 2012 sample report in the GO Data Warehouse (analysis) package includes padding. For more information about The Sample Outdoors Company samples, see Appendix C, "Sample Reports and Packages," on page 525.

Procedure

1. Select the object to which to apply padding.
2. In the **Properties** pane, double-click the **Padding** property.
3. Specify top, bottom, left, and right padding by typing values in the corresponding boxes and choosing the unit of measure.

Note: Specifying padding using % as the unit of measure is not supported when producing reports in PDF.

Set Margins for an Object

Set the margins for objects in a report to add white space around them.

For Date, Time, Row Number, and Page Number objects, you can only set the left and right margins. If you want to set the top or bottom margins for these objects, place them in a table or a block. Then set the margin or padding properties on the table or block object.

Procedure

1. Select the object.
2. In the **Properties** pane, double-click the **Margin** property.
3. Specify the top, bottom, left, and right margins by typing values in the corresponding boxes and choosing the unit of measure.



Note: Specifying margins using % as the unit of measure is not supported when producing reports in PDF.

Add Multiple Items to a Single Column

You can add multiple items to a single column to condense a report. For example, you have a list report that contains many columns. You can reduce the number of columns in the list by putting related information in a single column.

Procedure


1. From the **Structure** menu, click **Lock Page Objects** to unlock the report.
2. From the content pane, drag the items to the column.




For example, you can add data items from the **Source** tab  or text items from the **Toolbox** tab .

Example - Create a Report with Multiple Items in One Column

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a list report showing the name, position, email address, phone number, extension, and fax number for each sales representative in each city organized by country or region. To reduce the number of columns in the list, you show email addresses, phone numbers, extensions, and fax numbers in a single column.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **List** and click **OK**.
4. From the **Source** tab , expand **HR (query)**, **Employee summary (query)**, and **Employee by region**. Add the following data items to the list by double-clicking them:
 - **Country or Region**
 - **City**
 - **Employee name**

- **Position name**
 - **Email**
 - **Work phone**
 - **Extension**
 - **Fax**
5. Click the **Country or Region** column and, from the **Structure** menu, click **Section** .
 6. From the **Structure** menu, ensure that the report is unlocked
 7. Click **Country or Region** and, in the **Properties** pane, double-click the **Font** property.
 8. Change the font to **Arial Black, 11 pt, and Bold**, and then click **OK**.
 9. From the **Toolbox** tab , drag **Table** to the right of the **Work phone** text item in the first row of **Work phone** column and create a table that has one column and three rows.
 10. Drag the following data items to the table:
 - **Email** to the first row
 - **Work phone** to the second row
 - **Fax** to the third row
 11. Drag **Extension** to the right of **Work phone** in the table.
 12. From the **Toolbox** tab, drag **Text Item** to the left of each item in the table and type the following for each item, putting a blank space before and after the text:
 - **Email:**
 - **Work phone:**
 - **ext:**
 - **Fax:**
 13. Ctrl+click the **Extension**, **Email**, and **Fax** column titles and click the delete button .
 14. Click the **Work phone** column title.
 15. In the **Properties** pane, click the **Source Type** property and click **Text**.
 16. Double-click the **Text** property.
 17. Type the following and click **OK**:

Contact Information
 18. Select the **Work phone** data item in the first row of the list above the table and click the delete button.
 19. Double-click the text item in the page header, type the following, and click **OK**:

Sales Representatives Contact List
 20. From the **Structure** menu, click **Lock Page Objects**.
The report is locked.
 21. Run the report.

Results

Contact information for each sales representative appears in a single column.

Sales Representatives Contact List

Australia

City	Employee name	Position name	Contact Information
Melbourne	Alice Walter	Branch Sales Manager	Email: AWalter@grtd123.com Work phone: +(61) 03 2982 4242 ext: 8910 Fax: +(61) 03 2982 4243
Melbourne	Alice Walter	Level 3 Sales Representative	Email: AWalter@grtd123.com Work phone: +(61) 03 2982 4242 ext: 8910 Fax: +(61) 03 2982 4243
Melbourne	Andrea Samuel	Payroll Clerk	Email: ASamuel@grtd123.com Work phone: +(61) 03 2982 4242 ext: 8224 Fax: +(61) 03 2982 4243
Melbourne	Catherine Fowle	Warehouse Worker	Email: CFowle@grtd123.com Work phone: +(61) 03 2982 4242 ext: 8465 Fax: +(61) 03 2982 4243
Melbourne	Cindy Sandles	Product Technician	Email: CSandles@grtd123.com Work phone: +(61) 03 2982 4242 ext: 8225 Fax: +(61) 03 2982 4243
Melbourne	Dan Michaels	Budget Analyst	Email: DMichaels@grtd123.com Work phone: +(61) 03 2982 4242 ext: 8480 Fax: +(61) 03 2982 4243
Melbourne	Dave Smythe	Level 1 Sales Representative	Email: DSmythe@grtd123.com Work phone: +(61) 03 2982 4242 ext: 8909 Fax: +(61) 03 2982 4243
Melbourne	David Dolby	District Sales Manager	Email: DDolby@grtd123.com Work phone: +(61) 03 2982 4242 ext: 8288 Fax: +(61) 03 2982 4243


Figure 58. List showing the city, employee name, position, and contact information for Australia

Reuse a Layout Object

You can save time by reusing layout objects that you add to a report instead of re-creating them. For example, you have a multiple-page report and you want to show the company logo in the page header of each page. Insert the logo once and reuse it on all other pages.

Procedure


1. Click the object to reuse.

Tip: To quickly select the parent of an object, click the object, and then click the select ancestor button  in the title bar of the **Properties** pane.

2. In the **Properties** pane, set the **Name** property to a value beginning with a letter to uniquely identify the object and press the Enter key.

IBM Cognos Report Studio may have already specified a name for the object.

3. To reuse the object in another report, open that report.

4. From the **Toolbox** tab , drag the **Layout Component Reference** object to the location in which it will be reused.

5. In the **Component Location** box, do one of the following:
 - To reference an object in the current report, click **This report**.
 - To reference an object in another report, click **Another report**, click the ellipsis button, and open the report.

Note: In active reports, you cannot reference objects from another active report.

6. In the **Available components to reference** box, click the object and click **OK**.
7. If the referenced object is in another report, click the **Layout Component Reference** object and in the **Properties** pane, set the **Embed** property to specify how to store the referenced object in the report:

- Click **Copy** to store a copy of the object.

The copy is not automatically updated if the source object is modified.

Note: In active reports, you can store referenced objects only by copying them to the report.

- Click **Reference** to store a reference, or pointer, of the object.

The reference of the object is automatically updated if the source object is modified. For example, if you open or run the report, you see the modified object.

Results

A copy or reference of the object appears where you placed the **Layout Component Reference** object. If a source object is changed, you can update reused objects.

Tip: You can also create a new report or template and add all the objects to share. All your shared objects then reside in a single location, like a library.

Change a Reused Object

If you reuse an object that contains other objects, you can change the child objects to something different. For example, you have a block object containing a text item in the page header and you decide to reuse the block in the page footer. However, you want the text item in the page footer block to show different text from that in the page header.

About this task

If you reuse a visualization, you cannot change the data container of the visualization.

Procedure

1. In the parent object to reuse, click the child object to change.
2. In the **Properties** pane, set the **Name** property to a value beginning with a letter to uniquely identify the object.

IBM Cognos Report Studio may have already specified a name for the object.
3. Select the copy of the parent object you created with the **Layout Component Reference** object.
4. In the **Properties** pane, double-click the **Overrides** property.
5. In the **Overrides** dialog box, select the child object to change and click **OK**.

The child object in the copy of the parent object is replaced by the following text:

Drop item to override component child.

6. Drag an object to replace the child object.

You can replace the child object with any other object, not just an object of the same type. For example, if the child object is a text item, you can replace it with an image.

Update Reused Objects

If a report contains objects referenced in another report, you can quickly update the referenced objects if the source objects have changed. Shared objects are stored in the layout component cache.

Procedure

1. Open the report to update.

2. From the **Tools** menu, click **Layout Component Cache**.

The **Layout Component Cache** dialog box appears, showing all reports that contain referenced objects and the source reports where the objects exist.

3. To view which components are reused, click a source report.

The components that are reused appear in the **Components used** pane.

4. Click **Reload Components** to refresh all referenced objects.


Although referenced objects are automatically refreshed when you open or run a report, clicking this button updates components that were changed while the report is open.

5. Click **Update All Component Copies** to refresh all copied objects.

6. Click **Close**.

Specify text and container direction

You can specify text and container direction by choosing any of these options.

Option	Description
Direction	<p>Sets the reading order of an object, such as right-to-left. If Inherit is selected, the direction is inherited from the parent object. The default is left-to-right.</p> <p>For text objects, an additional choice named Contextual exists. This choice sets the text direction based on the first letter in the text. If the letter belongs to a right-to-left script, the text direction is right-to-left. Otherwise, the text direction is left-to-right. Numbers and special characters do not influence the text direction. For example, if the text starts with a number followed by an Arabic letter, the direction is right-to-left. If the text starts with a number followed by a Latin letter, the direction is left-to-right.</p> <p>Tip: You can also set the direction of text objects by clicking the Text direction icon  in the toolbar. This icon is visible only when the IBM Cognos Connection user preference Enable bidirectional support is selected.</p>
Writing mode	Sets the direction and flow of content in an object.

Option	Description
Bidirectional	Sets the level of embedding in an object. For text objects, if the Direction option is set to a value other than (Default) and no value is selected for this option, this option is set to Embed . Setting this option to Embed ensures that the base text direction specified for the text is applied.
Justification	Sets the type of alignment used to justify text in an object.
Kashida space	Sets the ratio of kashida expansion to white space expansion when justifying lines of text in the object. This property is used in languages that use the Arabic writing script.

About this task

Specifying text direction and container direction depends on the object selected in the report. The following list describes the types of objects in Report Studio that you can specify text or container direction.

- **Compound objects**
Compound objects are container objects that contain text. Examples include charts, maps, active reports, and prompts. You cannot set text direction for specific text objects in a compound object.
To specify container direction for compound objects, click the **Direction & Justification** property for the object. To specify text direction for text in compound objects, click the **Contained Text Direction** property for the object.
- **Container objects**
You can specify only container direction for container objects, such as a report page. Click the **Direction & Justification** property for the object to specify container direction.
By default, the text direction of text in a container object is inherited from the container.
- **Text objects**
For all text objects, the **Direction & Justification** property specifies the text direction.

In charts, container direction impacts all aspects of a chart. The following list describes the parts of a chart that are affected by container direction.


- The chart itself.
- The location of the Y-axis and the horizontal run direction of the X-axis.
- The labeling, including the orientation of angled labels on axes.
- The location of the legend as well as the legend content.

Container direction has no impact on rotary axes. For example, the slices in a pie always progress in the same direction around the pie. However, container direction does affect labelling as well as position and direction of the legend.

Note: You cannot specify base text direction and container direction for legacy charts.

Procedure

1. Click an object.

Tip: To specify the base text direction of a text object that is inside another object, such as a list column, you must first unlock  the report.

2. In the **Properties** pane, click one of the following properties:

- **Direction & Justification**
- **Contained Text Direction**

This property applies only to compound objects.

3. Specify the text direction and container direction options that you want.

Related concepts:

“Support for bidirectional languages” on page 60

You can author reports that support bidirectional languages. You can specify base text direction, digit shaping, and container direction.

Specify Line Spacing and Breaking

You can specify text properties by choosing any of these options.

Option	Description
Line Height	Sets the distance between lines of text in an object.
Letter Spacing	Sets the amount of additional space between letters in an object.
Text Indent	Sets the indentation of the first line of text in an object. Note: This property works with HTML output but does not apply to PDF output.
Word Break	Sets line-breaking behavior within words.
Break words when necessary	Sets whether to break words when the content exceeds the boundaries of an object.
Enforce stricter line-breaking rules for Japanese Text	Sets line-breaking rules for Japanese text.

Procedure

1. Click an object.
2. In the **Properties** pane, double-click the **Spacing & Breaking** property.
3. Specify the text properties.

Specify the Height and Width of an Object

You can specify the height and width of objects using various units of measurement. In addition, if the object is a field set, text box prompt, prompt button, hyperlink button, block, or a conditional block, you can specify how to handle content overflow. Specify the height and width by choosing any of these options.

Option	Description
Height	Sets the height of the object.

Option	Description
Width	Sets the width of the object.
Content is not clipped	If the contents of the block exceed the height or width of the block, the block automatically resizes to fit the contents.
Content is clipped	If the contents of the block exceed the height or width of the block, the content is clipped. Note: The clipped content still exists. It is just not visible in the block.
Use scrollbars only when necessary	If the contents of the block exceed the height or width of the block, scrollbars are added to the block.
Always use scrollbars	Scrollbars are added to the block.

Do not use percentages to resize charts and maps that contain interactive elements that are activated when you pause the pointer over them, such as tooltips or drill-through links, because the browser is unable to realign the hard-coded hot spots after an image is resized.

When you use a percentage to specify the size of an object, the percentage is relative to the object's parent. In some cases, setting the size of an object using percentages will not give you the results that you want unless you also specify the size of the parent container.

Procedure

1. Click an object.
2. In the **Properties** pane, double-click the **Size & Overflow** property and specify the height and width.

Control How Other Objects Flow Around an Object

You can control how objects flow around other objects by choosing any of the following options.

Option	Description
Float	Sets how other objects flow around the object.
Allow floating objects on both sides	Allows other objects to flow on both sides. The Float property must be set.
Move below any floating object on the left side	If there are other objects to the left of the object, the object moves below those objects. The Float property must be set.
Move below any floating object on the right side	If there are other objects to the right of the object, the object moves under those objects. The Float property must be set.
Move below any floating object	Moves the object under any other object in which the Float property was set.

Procedure

1. Click an object.
2. In the **Properties** pane, double-click the **Floating** property.

3. Specify how other objects flow around the object by specifying the floating options.

Specify Report Properties

You can change the default report property settings.

Procedure

1. From the **File** menu, click **Report Properties**.
2. To specify the classes that IBM Cognos Report Studio uses to format objects, click **Report styles** and choose one of the available options.
3. For reports with multiple data containers, to render the default number of rows of each data container on each HTML page, you must set the **Page break by data container for interactive HTML** option to **Yes**. The default value is **No**.
4. To show each report page in its own tab in HTML output, click the **View pages as tabs** menu and select the location where you want the tabs to appear in browsers.
5. To automatically create extended data items every time a data item is inserted, select the **Always create extended data items** check box.

IBM Cognos Report Studio creates extended data items by default.

6. To create a single, scrollable HTML page when you run and save this report as HTML from IBM Cognos Connection, clear the **Paginate saved HTML output** check box.

The default is to paginate HTML reports with the same page breaks as PDF reports. The single, scrollable HTML page will be available from IBM Cognos

Connection when you click the view report output versions action .

7. For reports in Excel 2007 format, if you do not want to group repeating cells in lists and crosstabs, clear the **Group repeating cells when exporting to Excel** check box.

When this check box is selected, grouped cells in crosstab rows and columns and grouped columns in lists are merged into a cell area in the Excel output. When the check box is cleared, merged cells are split.

8. If you work with reports that are created in IBM Cognos ReportNet and you want to create CSV report output, click **Use 1.x CSV export**.

This option ensures that all the query columns are exported. In IBM Cognos ReportNet, if a data item was referenced by using the **Properties** property of a list, it was included in the CSV output. In IBM Cognos Business Intelligence, the default is to export only the columns in the list.

Related concepts:

“Create and Modify Report and Object Styles” on page 365

Create your own classes or modify existing classes in a report to format objects across a report according to your particular needs. In IBM Cognos Report Studio, objects in reports are assigned a Cascading Style Sheet (CSS) class that provides a default style for the object. For example, when you create a new report, the report title has the class property **Report title text** assigned to it. In addition, objects inherit the classes set on their parent objects.

“Controlling the Rows Per Page for Multiple Containers in HTML and PDF” on page 52

If you have more than one data container in a report, such as a list and a crosstab, you can control how the report is rendered in HTML and PDF by setting the **Rows Per Page** property for each container.

“Extended Data Items” on page 277

Extended data items differ from the traditional, expression-based text strings by enabling you to add children, view details, select sets, sort sets, and apply contextual calculations.

“Option to group repeating cells in reports produced in Excel 2007 format” on page 54

When you produce reports in Excel 2007 format, you can specify whether repeating cells are grouped, or merged, into a single cell.

Related tasks:

“Producing tabbed reports” on page 468

When you produce reports in HTML format, you can show each report page as a tab.

Create and Modify Report and Object Styles

Create your own classes or modify existing classes in a report to format objects across a report according to your particular needs. In IBM Cognos Report Studio, objects in reports are assigned a Cascading Style Sheet (CSS) class that provides a default style for the object. For example, when you create a new report, the report title has the class property **Report title text** assigned to it. In addition, objects inherit the classes set on their parent objects.

You can use classes to highlight data using conditional styles.

Classes you create or modify can be applied only to the current report. To create or modify classes for all reports, you must modify a layout style sheet. In addition, some classes can be used to format Query Studio reports.

If you use the Microsoft Internet Explorer Web browser, version 6, some color gradients used in the 10.x default report styles are not supported.

Modify the report style

You can define whether your report uses the default styles for this version or the styles from a previous version.

Procedure



1. From the **File** menu, click **Report Properties**.
2. Click **Report styles** and select one of the following options:
 - To work with classes in the default style sheet, click **10.x styles**.
 - To work with classes that were used in IBM Cognos 8, click **8.x styles**.
Use 8.x report styles when you are working with reports created in IBM Cognos 8 and you want to preserve their original appearance.
 - To work with classes that were used in IBM Cognos ReportNet, click **1.x styles**.
Use 1.x report styles when you are working with reports created in ReportNet and you want to preserve their original appearance.
 - To work with classes that have minimal styling defined, click **Simplified styles**.

This option is useful when creating financial reports.

Modify object styles

You can change global classes to modify the style of all objects in a report or you can modify local classes and apply them to specific objects.

Procedure

1. Pause the pointer over the page explorer button  and click **Classes**.
2. To create a new class, from the **Toolbox** tab , drag **Class** to the **Local Classes** pane.
3. To modify an existing class, in the **Local Classes** or **Global Class Extensions** pane, click the class.


Modify a global class to apply a change to all objects that use that class. For example, if you modified the style **List column title cell**, all column titles in lists will reflect your modifications.

Tip: Ctrl+click classes to make the same change to more than one class.

4. In the **Properties** pane, modify the properties to specify your desired formatting.

Tip: Look at the **Preview** pane to preview your changes for different report objects, such as blocks, table cells, and text items.

If you modify a global class, a pencil symbol appears beside the global class icon to indicate that the class was modified.

5. Apply the class to objects:
 - Pause the pointer over the page explorer button and click a report page.
 - Click an object to which to apply a class.
 - In the **Properties** pane, double-click the **Class** property.
 - Click the classes to apply from the **Local classes** and **Global classes** panes and click the right arrow button .
 - If you applied more than one class, in the **Selected classes** pane, specify the order in which the classes are applied using the up and down arrow buttons.

Classes in the **Selected classes** pane are applied from top to bottom. The style properties from all classes are merged together when they are applied. However, if the classes have style properties in common, the properties from the last class applied override those from previous classes.

Reusing styles from another report

You can apply local and global styles from one report in another report.

About this task

Local styling is kept when you reference styles from another report. However, you can remove some or all local styling from the target report.



If the referenced report is renamed or moved, IBM Cognos Business Intelligence automatically updates the reference information in the target report.

You can reference local classes only if local classes with the same name exist in the target report. You can reference styles from a report only if you have the permissions to access the report. If you referenced styles from a report and the

permissions for the report are changed so that you can no longer access it, the referenced styles are still applied when the target report is run.

You cannot use a report that contains referenced styles as the source report for style references for other reports.

If the target report contains more than one page, the **Preview** pane in the Report Style References window shows how the referenced styles are applied in the report page that you are currently viewing.

Tip: You can see which global classes contain inherited styles when you click **View > Classes**. Global classes that reference styles from another report are identified by the referenced styles icon . You can also modify classes that contain referenced styles. Such classes are identified by the modified referenced styles icon .

Procedure

1. From the **Tools** menu, click **Style References**.
2. Select the **Apply style from report** check box.
3. Click the ellipsis icon and open the report that contains the styles that you want to reuse.
4. To remove local styles in the report, in the **Remove custom styles from the current report** section, select the check boxes of the styles that you want to remove.
5. To specify when to refresh styles when styles in the referenced report are modified, in the **Refresh report styles** section, select one of the following options.
 - To refresh styles automatically, click the **Run time** radio button.
 - To control when styles are refreshed, click the **Manually** radio button.
When this choice is selected, styles are refreshed only when you click the **Refresh now** icon.

(Don't Print) Class

The **(Don't Print)** class allows HTML items to display in the Web browser but not to print.

The **(Don't Print)** class behaves as follows in the various report output formats:

- **HTML**
The Web browser defines the behavior. The HTML standard is that the item appears on the screen in the Web browser but is excluded by the print operation of the Web browser.
- **PDF**
The item is excluded from the output.
- **Microsoft Excel 2002 spreadsheet software**
The class is specified in the HTML that IBM Cognos uses to render Microsoft Excel 2002 output. However, Microsoft Excel 2002 does not appear to honor it and displays the item as missing some or all other style definitions.
- **Microsoft Excel 2007 spreadsheet software**
The item is excluded from the output.
- **CSV**
The item is included in the output.

- XML
The item is included in the output.

An alternative way to consistently exclude a report object from HTML, PDF and Microsoft Excel output is to set the **Box Type** property for the object to **None**. CSV and XML report outputs will still contain the object.

Modify Classes to Format Query Studio Reports

Some global classes are specific to IBM Cognos Query Studio or can be applied to Query Studio reports. You can modify the following classes to format Query Studio reports.

To format a Query Studio report using the modified classes, the template must be applied to the report. For more information about applying a template to a Query Studio report, see the *Query Studio User Guide*.

Class	Description
List column body cell	Style used to format list data.
List column title cell	Style used to format list column titles.

To modify classes, you must

1. Create a Query Studio template.
2. Modify the global classes.
3. Save the template.

Modifying the Default Layout Style Sheet

In addition to creating or modifying classes in a report, you can create and modify classes that will apply to all reports. Default styles are stored in a style sheet named `GlobalReportStyles.css`.

For information about modifying the style sheet, see the *IBM Cognos Business Intelligence Administration and Security Guide*.

Add Color to an Object

You can add background and foreground color to objects in the report. The foreground color applies to the text within objects.

Tip: The TOC Report sample report in the GO Data Warehouse (query) package includes objects with color. For more information about The Sample Outdoors Company samples, see Appendix C, "Sample Reports and Packages," on page 525.


About this task

When you open one of the color windows, such as the Foreground Color window, you can save up to eight colors as favorites. Saving colors as favorites is useful when you define a custom color. When you save a custom color as a favorite, you do not need to reenter the RGB color values when you want to use the color elsewhere in the report.



Favorite colors are stored in cookies. As a result, favorite colors are shared across all Report Studio users.

Procedure

1. Select the object.

Tip: To quickly select the parent of an object, click the object, and then click the select ancestor button  in the title bar of the **Properties** pane.

2. Do one of the following:

- Click the background color button  or the foreground color button .
- In the **Properties** pane, double-click the **Background Color** or **Foreground Color** property.

3. To apply an existing color, click the **Basic Colors** tab or **Color Swatch** tab and choose one of the available colors.

Use a basic color to select a color from a small set of colors. Use the color swatch to select from 216 available colors.

4. To apply a custom color, click the **Custom Color** tab and type values in the **Red**, **Green**, and **Blue** boxes.

The values must be hexadecimal.

5. If the object is an extensible visualization and you want to specify the transparency, under **Transparency (%)**, type a percentage value or use the slider to set the transparency to the value that you want.

6. To save a color as a favorite, click **Set as favorite**.

If you save a color with a transparency value as a favorite, the transparency is applied only when you add the favorite color to an extensible visualization.

Tip: You can modify or replace a color that was saved as a favorite. Click the favorite color, make the changes that you want, and click **Set as favorite**.

Related tasks:

“Add Background Effects to a Chart Object in a Legacy Chart” on page 120
You can change the look of certain charts and chart objects by applying visual effects such as drop shadows, borders, fills, texture effects, and bevel effects.

Chapter 14. Working with your external data

You can supplement your enterprise data with your own external or personal data file.

You can create a report that uses an external file that contains data that is not part of your IBM Cognos Business Intelligence enterprise data. For example, you are an analyst and you receive a spreadsheet that contains what-if data about opening new branches of your retail store. You are asked to analyze the impact of these possible new branches on existing sales volumes. You link this scenario data with your enterprise data and create a professional report in IBM Cognos BI.

You import your own data file and start reporting on it right away. After you import the file, it is protected by the same IBM Cognos security as your enterprise data. As a result, you can report on your data in a secure and private environment.

You can import your external data in different tools.

My Data Sets tool

You can import the following types of files:

- Microsoft Excel (.xls and .xlsx) spreadsheet software files
- Delimited text files, such as .csv files

After you import your data, it is saved in a database. You then publish a package that contains your data and you can then report on your data. You can grant other users access to your personal data by sharing the corresponding packages.

Manage External Data tool

You can import the following types of files:

- Microsoft Excel (.xls and .xlsx) spreadsheet software files
- Tab-delimited text (.txt) files
- Comma-separated (.csv) files
- XML (*.xml) files

After you import your data, you then publish a package that contains your data in addition to the data contained in an existing package. You can then report on your data.

To review an up-to-date list of the environments that are supported by IBM Cognos products, including information about operating systems, patches, browsers, web servers, directory servers, database servers, and application servers, see Supported Software Environments (www.ibm.com/support/docview.wss?uid=swg27042164).

My Data Sets

Use the **My Data Sets** tool to create reports that are based on your personal data that is contained in delimited text files and Microsoft Excel (.xls and .xlsx) spreadsheet software files.

You can access the **My Data Sets** tool from the IBM Cognos Welcome page and from the **My Area Options** menu  in IBM Cognos Connection.

First, you import your Microsoft Excel (.xls and .xlsx) spreadsheet software files and delimited text files, such as .csv files, into **My Data Sets**. Your data is then saved in a database and is protected by the same IBM Cognos security as your enterprise data. You then publish a stand-alone package to any location in IBM Cognos Connection for which you have write permissions. As a result, you can report on your data in a secure environment. You can see only your personal data sets and can delete any packages or data sets that you created. You can grant other users access to your personal data by sharing the corresponding packages.

The My Data Sets feature must be enabled by your Cognos Business Intelligence administrator before you can use it.

For more information, see the following documents.

- *IBM Cognos Connection User Guide*
- *IBM Cognos Business Intelligence Administration and Security Guide*

Manage external data

You can supplement your enterprise data with your own external or personal data file by using the **Manage External Data** tool in IBM Cognos Report Studio and IBM Cognos Workspace Advanced.

You import your own data file and start reporting on it right away. After you import the file, it is protected by the same IBM Cognos security as your enterprise data. As a result, you can report on your data in a secure and private environment.

You can use the following types of files:

- Microsoft Excel (.xls) spreadsheet software files

The **Manage External Data** tool supports external data sources from Microsoft Excel up to version Microsoft Excel 2007.

To review an up-to-date list of the environments that are supported by IBM Cognos products, including information about operating systems, patches, browsers, web servers, directory servers, database servers, and application servers, see Supported Software Environments (www.ibm.com/support/docview.wss?uid=swg27042164).

- Tab-delimited text (.txt) files
- Comma-separated (.csv) files
- XML (*.xml) files

Your XML files must adhere to the IBM Cognos schema specified at `c10_location/bin/xmldata.xsd`. For more information, contact your IBM Cognos administrator.

This schema consists of a dataset element, which contains a metadata element and a data element. The metadata element contains the data item information in item elements. The data element contains all the row and value elements.

For example, the following simple XML code produces a table with two columns (Product Number and Color) and two rows of data.

```
<?xml version="1.0" ?> <dataset xmlns="http://developer.cognos.com/schemas/xmldata/1/" xmlns:xs="http://www.w3.org/2001/XMLSchema-instance">
<metadata> <item name="Product Number" type="xs:string" length="6"
```

```
scale="0" precision="2" /> <item name="Color" type="xs:string"
length="18" scale="0" precision="8" /> </metadata> <data> <row>
<value>1</value> <value>Red</value> </row> <row> <value>2</value>
<value>Blue</value> </row> </data> </dataset>
```

To work with your external data by using the **Manage External Data** tool, you start with an existing IBM Cognos package. You import data from your external file into the package and create links between data items in your file and data items in your enterprise data source. You then publish a new package that you can use to create reports that use your data and your enterprise data, or reports that use only your data. You can link your external data with both dimensional and relational data sources.

Before you can import your own external data file, your IBM Cognos administrator must grant you permission for the **Allow External Data** capability that is found within the **Report Studio** capability. You must also have permissions to use IBM Cognos Report Studio or IBM Cognos Workspace Advanced. For more information, see the *IBM Cognos Business Intelligence Administration and Security Guide*.

Packages that contain external data

When you import external data into a package with the **Manage External Data** tool, you do not overwrite the original package. You create a new package that includes the original package, the new external data, and any links or relationships that you defined between the two. By default, the new package is saved in the **My Folders** area of IBM Cognos Connection, with **External Data** appended to the original package name. You can change where your package is published.

Note: The current content language is used to create the new package, and users cannot select the language for the package. For example, the content language in Cognos Connection is set to English. External data is imported into the GO Sales (query) package, and a new package called GO Sales (query) External Data is created. If the content language is changed to a different language, the package name is not translated, even though GO Sales (query) is a multilingual package.

IBM Cognos samples

Sample external data sources in Microsoft Excel (.xls) format are provided with IBM Cognos BI. You can import these sample files into the Sample Outdoors Company sample reports that are found within the **Cognos Workspace Advanced** folder of the **GO Data Warehouse (analysis)** or **GO Data Warehouse (query)** package.

You can find sample external data source files on the server where IBM Cognos BI is installed in the `c10_location/webcontent/samples/datasources/other` directory.

To obtain these files, contact your IBM Cognos administrator.

Preparing to Work with your External Data

To work with your external data, follow the process in this section.

There are four steps to preparing to work with your external data. The following diagram details these steps.




Figure 59. Process to prepare to work with external data

1. Prepare your external data file for import.


Ensure that your external data file matches your enterprise data for your reporting needs. For example, if your external data file contains sales values by month, ensure that the formatting of months in your file matches the formatting used in your enterprise data source. Ensure that you can uniquely link at least one column from your external data file, such as product codes or years, with your enterprise data source.

The maximum file size that you can import is 2.5 MB, with a maximum of 20000 rows. You can import a maximum of one external data file per package. Your IBM Cognos modeler can override these governors in IBM Cognos Framework Manager.
2. Import your external data.

You import your external data file from your own computer or from a location on your network into an existing IBM Cognos package.

A step-by-step wizard guides you through importing your data. If you want to create reports that contain data from both your external data file and your enterprise data source, you must link data items from the two data sources. You can import all or a subset of data columns from your external file.

By adding external data, you extend an existing IBM Cognos package definition with the new data items from your file and you create a new package.
3. Create reports with your external data file.

After you import and link your external data, it appears as a new namespace in the data tree of the **Source** tab  and is integrated with the IBM Cognos content.

You can then create reports with your data and perform any operation, such as filtering, sorting, grouping, or adding calculations. When you run the report, it uses data items from your external data file.

You can save reports that contain your external data within the **My Folders** area of the IBM Cognos portal.
4. Determine whether you want to share your reports that use external data with other people in your organization. If you decide to share, take into account these considerations.

Working with Date Data

If the data that you import contains dates, ensure that the dates use the format yyyy-mm-dd.

Working with Dimensional Data Sources

If your enterprise data source is dimensional, such as OLAP or dimensionally-modeled relational, and you want to link your external data with your enterprise data, you must first create a tabular or list report. Create and save a list report with your enterprise data that contains the data items that you want to use to link with your external data. Ensure that you remove the aggregate rows that are automatically added in the footer of the list. This list is a projection of your dimensional data source.

When you import your external data, use the list report that you created to link your external data with the query subject from your enterprise data.

Data in your external file is relational by nature because it consists of tables and rows. If your enterprise data source is dimensional, you can still import and work with your external data. However, you cannot mix relational data from your external data files, and dimensional data from your enterprise data source within the same query. For example, a data container, such as a list, crosstab, or chart, uses one query and you cannot mix relational and dimensional data within the same list, crosstab, or chart. Doing so will cause an error.

If you want to use data from both the external data file and the original package within the same query, you must link the external data to a query subject within the current package instead of another report.

Working with External Data in an Unsecured IBM Cognos Application

If your IBM Cognos application is not secured, and users can log on anonymously, you may encounter issues if multiple people import external data in the same package.

For example, Robert imports his external data into package A and saves the package and reports he created in **My Folders**. Then, Valerie also imports her external data into the same package A and saves the package in **My Folders**. Valerie has therefore overwritten Robert's external data in package A. Now, if Robert tries to run one of his reports, he encounters errors because his external data is no longer in package A.

To avoid this problem,


- save packages that contain external data with a unique name.
- apply security to your IBM Cognos applications so that users do not share the same **My Folders** area.

Import Data

You select the file to import from your own computer, or from your local area network.

You select which columns to import.



You then specify a namespace to use. The namespace provides a unique name to associate with the data items that you import. The namespace appears in the data

tree in the **Source** tab  and is used to organize the data items. By default, the namespace is the imported file name without the extension.

If you change the default name for the namespace, you are prompted to select the external data file each time that you run the report. To avoid this prompt, select the **Allow server to automatically load file** check box.

Procedure

1. From the **Tools** menu, click **Manage External Data**.

Tip: You can also click the **Manage External Data** icon  at the top of the **Source** tab .

2. On the **Select Data** page of the wizard, under **External data file**, click **Browse** and select your external data file to import.
If you want the server to load the file without prompting users when they run the report, select the **Allow the server to automatically load the file** check box. If selected, you must use the Universal Naming Convention (UNC) path, such as `\\servername\filename`, and you must ensure that the IBM Cognos server has access to the file.
3. Under **Data items**, select the check box for the data items that you want to import.
4. Type a name for the namespace and click **Next**.
The namespace appears in the **Source** tree, and identifies the external data within the package. By default, the name is the name of your imported external data file.
5. If you do not want to link your data or change the data attributes, click **Finish** now.

Related tasks:

“MSR-PD-0012 error when importing external data” on page 501

When you try to import an external data file, you receive an MSR-PD-0012 error.

“MSR-PD-0013 error when importing external data” on page 501

When you try to import an external data file, you receive an MSR-PD-0013 error.

Map Data

If you want to create reports that contain data from both your external file and from your enterprise data, you must link at least one query subject from your package or from an existing report to a data item in your external data. This mapping creates a relationship between your external data and your enterprise data. For example, your external data contains information about employees, including an employee number. You map the employee number from your external data file to the employee number in your enterprise data. This ensures that your data is integrated smoothly.

About this task

Mapping a data item in your external data to a query subject that references other query subjects is not supported. For example, the query subject cannot contain a calculation that references a query item from another query subject. Such a mapping produces the following error message:

MSR-PD-0001 Failed to relate external data to objects in the underlying package. The item [query item] does not lead to a query subject.

Procedure

1. On the **Data Mapping** page, link existing query subjects in your enterprise data to data items in your external data file.
2. Under **Existing query subject / report**, click the ellipsis button and do one of the following:
 - If you want to select a query subject from the data tree, click **Choose Query Subject** and select a query subject.

Note: This option is not available when working with dimensional packages.

- If you want to select from the query subjects included in a report, click **Choose a Report** and select a report.
3. Click the two data items that you want to link and click the **New link** button. You cannot link a data item in your external data to a calculation in a query subject.

A link appears linking two data items.

Tip: You can create multiple links for multiple data items. To delete a link, select the link and click **Delete Link**.

4. If your report is using the dynamic query mode, specify the type of filter to generate for the join relationship by clicking the **Join filter type (DQM only)** menu and choosing one of the available values.

A join relationship is created when you link data items. The filter type is used to optimize the join relationship. In generates an IN predicate of constant values. Between generates a BETWEEN predicate using the minimum and maximum values of the join keys. Table generates a table row constructor form of the IN predicate. The default value is In.


5. Click **Next**.

Finish Importing Data

You can change how query items from your external data file appear after they are imported into IBM Cognos Business Intelligence. For example, you can change the number of decimal places or the default summary.

If you want to use numeric data from your external data source as a measure in a crosstab, you must assign that data item a default summary other than

Unsupported. A specified default summary makes the data item appear as a

measure in the data tree in the **Source** tab . Otherwise, if you add the data item with an **Unsupported** default summary as the measure in a crosstab, no values appear.

Attribute	Description
Data type	Identifies whether data in the file is one of the following types: Integer , which represents numeric values. Decimal , which represents integer values that are scaled by a variable power of 10. Text , which represents values that contain letters and symbols. Date or Date Time , which represent dates and times.

Attribute	Description
Default summary	Identifies Sum, Average, Max, Min, Count or Unsupported as the default type of summary for the data item. Applies only to Integer and Decimal data types.
Decimal places	Specifies the number of decimal places for the data item. Applies only to the Decimal data type.

If you mapped links between data items in your external data and data items in your enterprise data, specify the options that define the relationships between the data items.

For each data item that you import and link, specify whether values are unique or exist more than once in both your external data and in your enterprise data. You can also specify how to handle rows that contain missing values in the report results.

Procedure

1. On the **Data Attributes** page, specify the attributes for each data item after it is imported and click **Next**.
For example, if you import numeric data items, you can change the default summary and number of decimal places.
2. On the **Mapping Options** page, specify the relationships between the linked data items and how to process the results in the report output.
3. Click **Finish**.

Publish the Package


You can change the name and location of the package with your external data to help you differentiate between data packages.

Procedure

1. If you want to rename the package that will be published or change the location where it is published, do the following:
 - In the **Manage External Data** dialog, under **Package name**, click the ellipsis button.
 - Type a new name for the package and select the location where to save it.
 - Click **Save**.
2. Click **Publish**.

Results

IBM Cognos Business Intelligence imports your external data into a new package. A namespace with the data items from your external file appears in the data tree in


the **Source** tab .

You can now create reports with your external data.

Edit Your External Data



After you import your data, you can change the data mappings and options that you originally specified and republish the package.

You can


- Rename the namespace, which renames the organizational folder that appears in the data tree in the **Source** tab . If you change the namespace, you are prompted for the external data file when you run the report.
- Change which columns to import.
- Change the data mapping links.
- Change the data attributes.
- Change the mapping options.

You can also import multiple external data files into the same package. To do this, your data modeler must modify governors in the model and republish the package that contains your enterprise data. For more information, see the *IBM Cognos Framework Manager User Guide*.

Procedure

1. From the **Tools** menu, click **Manage External Data** .
2. In the **Manage External Data** dialog box, select the external data to edit and click the **Edit** icon .
3. In the left pane, select the options that you want to change.
4. Click **OK** and then republish the package.

Results



IBM Cognos Business Intelligence reimports your external data and updates the data items that appears in the data tree in the **Source** tab .

You can now create and update reports with your external data.

Delete Your External Data

You can delete your external data from within the package that you created if you no longer need it.

Procedure

1. From the **Tools** menu, click **Manage External Data** .
2. In the **Manage External Data** dialog box, select the external data package to delete and click the delete button .
3. Click **Publish**.

Results

The external data namespace is removed from the package.

If you also no longer require the external data package or any reports created with the package, you can delete it from within IBM Cognos Connection.

Running a Report That Contains External Data

Reports that contain external data run the same way as reports that contain only enterprise data. If you have access to the report, you will also have access to the external data included within the report.

You may be prompted to select the location of the external data file when you run the report if either

- the report author did not specify to automatically load the file.
- the IBM Cognos Business Intelligence server cannot locate the file.

However, you are not re-prompted within the same Web browser session.

You can determine whether data in a report uses external data by tracing its lineage. For more information, see “View Lineage Information for a Data Item” on page 58.

Making your Reports Public

After you create a report that uses your external data, you may want to make it public to share it with coworkers. They can run your report using your external data file that you made available on a public network drive that the IBM Cognos server can access. They can also use their own version of the file. If they use their own version, the file must contain the same columns as your original external data file that you used to import the data and create the report. In addition, you must clear the **Allow server to automatically load file** check box in the **Select Data** page of the **Manage External Data** wizard.

To make reports public, you must save them in the **Public Folders** area of the IBM Cognos portal. To save content in **Public Folders**, you must have the appropriate permissions. Contact your IBM Cognos administrator to obtain permissions and to inform him or her that you are sharing a package or files.

If you share your reports, ensure that you maintain the reports.

Chapter 15. Using Conditions

You can define conditions to control what users see when they run a report. Conditions can apply to specific items in a report. For example, you can define a conditional style to highlight exceptional data, such as product revenue that exceeds your target.

Conditions can also apply at the report layout level. Conditional layouts are useful for delivering reports to a multilingual audience. For example, you can have text items, such as titles and cover pages, appear in the same language as the data in the report.

Related concepts:

“Creating a Conditional Color Palette in a Chart” on page 115

You can create a conditional palette to color data items in your chart in different ways depending on a condition. For example, in a column chart that shows revenue per month, you want to make the columns for the months that have a revenue greater than \$1000000 green.

Highlight Data Using a Conditional Style

Add conditional styles to your report to better identify exceptional or unexpected results. A conditional style is a format, such as cell shading or font color, that is applied to objects if a specified condition is true.

For example, you want to automatically highlight in green the departments in your organization that meet their budget quotas and highlight in red the departments that go over budget. Creating conditional styles color-codes information in your reports so that you can find areas that need attention.

You can apply multiple conditional styles to objects. For example, you can apply one style in specific cells and another style for the overall report. If multiple styles set the same property, such as font color, the last style in the list is applied.

You can apply conditional styles based on any data item in your report.

You can create the following types of conditional styles.

Type	Description
Numeric Range	Highlights straight numerical data, such as revenues and losses.
Date/Time Range	Highlights data from specific dates and times.
Date Range	Highlights data from specific dates.
Time Range	Highlights data from specific times.
Interval	Highlights data falling between set intervals.

Type	Description
String	Highlights specific alphanumeric items in a report. For example, you can highlight all instances of a specific word or phrase, such as Equipment. String criteria are case-sensitive. If multiple string conditions are met, only the first conditional style is applied.
Advanced	Creates conditional styles that use calculations or expressions. If multiple advanced conditions are met, only the first conditional style is applied.

You can also apply a conditional color palette to a chart.

Note: Conditional styles and conditional data formatting do not work on chart axis labels. If you apply a conditional style or conditional data formatting to a chart axis, only the first style defined is applied.

You can perform a search to find objects in your report that use conditional styles. You can also view all the conditional styles used in your report to delete or modify them.


You can also use variables to highlight data. If a report contains both conditional styles and style variables, the style variables are applied first and then the conditional styles are applied.

Tip: The Return Quantity by Order Method sample report in the GO Data Warehouse (analysis) package includes conditional highlighting. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.



Create a New Conditional Style

You can apply conditional styles based on any data item in your report.


Procedure

1. Click the object for which you want to define a conditional style and click the conditional styles button .

Tip: You can also right-click the object and click **Style, Conditional Styles** or click the object, and then, in the **Properties** pane, set the **Conditional Styles** property.


2. Click the add button  and click **New Conditional Style**.
3. Select the data item to determine the condition and click **OK**.
The type of conditional style that you can use depends on the type of data item you select.
4. In the **Name** box, type a name for the conditional style.
5. To define a numeric value, date/time, date, time, or interval condition:
 - Click the new button  and select a value to define a threshold.


The value appears in the **Range** column, and two ranges are created.

- For each range, under **Style**, click one of the predefined styles to apply to the range or click the edit button  and create a new style.

Tip: You can also define a style for the cells in your report that have missing values.

- Repeat these steps to add other conditions.

Tip: Under **Style**, pause the pointer over each range  to see the condition produced for that range.

- To move a value above or below a threshold, click the arrow button  next to the value.

For example, you insert a threshold value of five million. By default, the ranges are less than or equal to five million and greater than five million. Moving the five million value above the threshold changes the ranges to less than five million and greater than or equal to five million.

6. To define a string condition:


- Click the new button and select how to define the condition.
- To select more than one individual value, click **Select Multiple Values** and click the values.
- To type specific values, click **Enter Values** and type the values.
- To specify your own criteria, such as values that begin with the letter A, click **Enter String Criteria** and specify the condition.
- For each condition, under **Style**, click one of the predefined styles to apply or click the edit style button and create a new style. Specify the style to apply to remaining values by clicking one of the predefined styles beside **Remaining values (including future values)**.
- Specify the order in which to evaluate the conditions.

Conditions are evaluated from top to bottom, and the first condition that is met is applied.

Reuse an Existing Conditional Style

You can create a conditional style once and reuse it on multiple objects in your report. You can specify the order in which conditional styles are applied. You can also use existing local classes as your conditional styles.

Procedure

1. Click the data item for which you want to define a conditional style, and then click the conditional styles button .

Tip: You can also right-click the data item and click **Style, Conditional Styles** or click the data item, and then, in the **Properties** pane, set the **Conditional Styles** property.


2. Click the add button , click **Use Existing Conditional Style**, and select the style.

Create an Advanced Conditional Style



You can create advanced conditional styles that use calculations or expressions.

If multiple advanced conditions are met, only the first conditional style is applied.

Procedure

1. Click the data item for which you want to define a conditional style, and then click the conditional styles button .

Tip: You can also right-click the data item and click **Style, Conditional Styles** or click the data item, and then, in the **Properties** pane, set the **Conditional Styles** property.

2. Click the add button  and click **Advanced Conditional Style**.
3. Type a name for the conditional style.
4. Click the add button and specify the expression that defines the condition.
5. For each condition, under **Style**, click one of the predefined styles to apply or click the edit button  and create a new style. Specify the style to apply to remaining values by clicking one of the predefined styles beside **Remaining values (including future values)**.
6. Specify the order in which to evaluate the conditions by clicking a condition and then clicking the move up or move down arrow.
Conditions are evaluated from top to bottom, and the first condition that is met is applied.

Manage Conditional Styles

You can view, modify, or delete the conditional styles that are applied to your report. You can also define a new conditional style.

In the IBM Cognos Report Studio options, you can specify whether to automatically delete conditional styles that are no longer used in a report.


Procedure

From the **Tools** menu, click **Manage Conditional Styles**.

Example - Add a Conditional Style to an Existing Report

You are a report writer at The Sample Outdoors Company, which sells sporting equipment. You have a report that compares current year data to previous year data and highlights negative percentage variances in red (Poor) and positive percentage variances in green (Excellent). You want to add a third conditional style to indicate percentage variances above 0 but less than 10. You create a conditional style that highlights percentage variances between 0 and 10% in yellow (Average).

Procedure

1. Open the **GO Balance Sheet as at Dec 31 2012** report from the **GO Data Warehouse (analysis)** package.
2. Right-click any cell in the **% Variance** column and click **Style, Conditional Styles**.
3. Select **Conditional Style 1** and click the edit button .

4. Select the first advanced condition listed and click the edit button.
5. Delete =0 from the expression definition.
6. Click the **Functions** tab, and then expand the **Operators** folder.
7. Double-click **between**, and then click after **between** in the expression, add a space, and type 0.
8. Double-click **and**, and then click after **and** in the expression, add a space, type .1, and click **OK**.
9. From the **Style** box associated with this condition, click **Average**.
10. Select the second advanced condition listed and click the edit button.
11. Replace >0 in the expression with >.1 and click **OK**.
12. Leave the style associated with this condition as is.
13. Run the report.

The new conditional style appears in the % **Variance** column.

Year to date (USD \$000's)	Current Year (2012)		Previous Year (2011)	
	December	December	Variance	% Variance
Assets (total)	9,459,048	10,717,093	-1,258,045	-11.74%
Current assets (total)	5,709,903	5,960,900	-250,996	-4.21%
Operating assets (total)	3,319,279	4,301,658	-982,378	-22.84%
Other assets (total)	429,865	454,536	-24,671	-5.43%
Liabilities (total)	-4,255,662	-3,856,126	-399,536	10.36%
Current liabilities (total)	-3,364,742	-3,059,376	-305,366	9.98%
Long-term and other liabilities (total)	-890,920	-796,749	-94,171	11.82%
Equity (total)	-5,203,386	-6,860,968	1,657,582	-24.16%
Common stock	-1,871,226	-1,780,558	-90,668	5.09%
Other capital	-991,916	-615,202	-376,714	61.23%
Retained earnings - net	-2,327,374	-4,450,170	2,122,797	-47.70%
Currency translation gain (or loss)	-12,870	-15,038	2,168	-14.41%
Declared dividends	0	0	0	-
BALANCE	0	0	0	-

Figure 60. Conditional styles that are applied to a report

Highlight Data Using a Style Variable

Highlight data in your report to better identify exceptional results. For example, you want to identify sales representatives who have exceeded their quota. You create a condition that checks whether each representative's sales for the year is greater than their quota for the year.

Style variables are useful if you are working with reports that were created in a previous version of IBM Cognos Business Intelligence or if you want to use language variables to specify conditional styles.

You can also use conditional styles to highlight data. If a report contains both conditional styles and style variables, the style variables are applied before the conditional styles.

Procedure

1. Create a variable and define the condition that determines if the data will be highlighted.
2. In the work area, click the column to highlight based on the condition.


3. In the **Properties** pane, double-click the **Style Variable** property.
4. Click **Variable**, click the variable to assign to the object, and click **OK**.
5. If you assigned a string variable, in the **Values** box, select the values for the condition to support.

Tip: A default value exists for the variable, and it is always selected.

6. If you assigned a language variable, in the **Values** box, select the languages for the condition to support.

Tip: A default value exists for the variable, and it is always selected.

7. Click **OK**.

8. Pause the pointer over the condition explorer button  and click a value other than the default value.

Tip: When you select a value in the condition explorer, the Explorer bar becomes green to indicate that conditional formatting is turned on and that any changes you make to the report apply only to the variable value.

For example, if you created a Boolean variable, click **Yes**.

9. In the **Properties** pane, specify the formatting with which to highlight the column when the condition is satisfied.

For example, click the **Border** property to create a thicker border around the column.

10. Repeat steps 8 to 9 for other possible values defined for the variable.

Tip: To view the report with no variables applied, pause the pointer over the condition explorer button and click **(No variable)** or triple-click the Explorer bar.

Results

When you run the report, the report objects to which you applied the variable are highlighted when the condition is satisfied. For example, if you created a Boolean variable, the objects are highlighted when the condition is met. If the condition is not satisfied for any object, no conditional formatting is applied.

Adding Conditional Rendering to a Report


You can specify which objects are rendered when a report is run.


Before you can add conditional formatting or conditional rendering to your report, you must add a variable. You can create a variable in the condition explorer or in the **Properties** pane.

Add a Variable from the Condition Explorer

Before you can add conditional formatting or conditional rendering to your report, you must add a variable. You can create a variable in the condition explorer or in the **Properties** pane.

Procedure


1. Pause the pointer over the condition explorer button  and click **Variables**.


2. From the **Toolbox** tab , drag one of the following variables to the **Variables** pane:
 - To create a variable that has only two possible values, **Yes** and **No**, drag **Boolean Variable**.
 - To create a variable whose values are string-based, drag **String Variable**.
 - To create a variable whose values are different languages, drag **Report Language Variable**.
3. If you created a Boolean variable, in the **Expression Definition** box, define the condition and click **OK**.
 For example, the following expression returns the value **Yes** if revenue is less than one million and the value **No** if revenue is greater than or equal to one million:

```
[Revenue]<1000000
```

 For information about creating expressions, see “Using Relational Calculations” on page 262 or “Using Dimensional Calculations” on page 316 and Appendix F, “Using the expression editor,” on page 575.
4. If you created a string variable, do the following:
 - In the **Expression Definition** box, define the condition and click **OK**.
 For example, the following expression returns the value **high** if revenue is greater than one million and the value **low** if revenue is less than or equal to one million:

```
if ([Revenue]>1000000) then ('high') else ('low')
```

 For information about creating expressions, see “Using Relational Calculations” on page 262 or “Using Dimensional Calculations” on page 316 and Appendix F, “Using the expression editor,” on page 575.
 - Click the add button  in the **Values** pane.
 - For each value that the variable can assume, type the name of the value that corresponds with the possible outcomes defined in the expression.
 For example, in the previous expression, you must create two values for the variable, high and low.

Tip: You can create a group by clicking two or more values and then clicking the group values button . For example, you can create a group that includes the available French languages.
5. If you created a language-specific variable, in the **Languages** dialog box, select the languages to support.

Add a Variable from the Properties Pane


Before you can add conditional formatting or conditional rendering to your report, you must add a variable. You can create a variable in the condition explorer or in the **Properties** pane.

Procedure

1. Select the report object.
2. In the **Properties** pane, under **Conditional**, double-click the conditional property to which to assign the variable.

The following conditional properties are available:

Goal	Conditional Property
Specify a variable based on which text can be conditionally shown. For example, you want different text to appear when a report is run in a different language.	Text Source Variable
Specify a variable based on which object can be conditionally rendered. For example, you want to make a revenue report smaller by not rendering rows that are below a threshold.	Render Variable
Specify a variable based on which object can be conditionally styled. For example, you want data that meets some criterion to appear in a different color.	Style Variable
Specify a variable based on which objects in a block can be conditionally rendered. Applies only to conditional block objects that you insert in a report.	Block Variable

3. In the **Variable** box, click an existing variable or one of the following variable types:
 - <New language variable>
 - <New string variable>
 - <New boolean variable>
4. In the **New Variable** dialog box, in the **Name** box, type the name of the variable.
5. If you created a string variable, click the add button , type the string values to define, and click **OK**.
6. If you created a language variable, select the languages to support and click **OK**.
7. In the **Expression Definition** box, define the condition.

Hide or Show an Object

You can hide and show objects in a report based on a condition you define.


You can also specify that an object should not be rendered based on a condition.

Tip: The Global Bonus Report sample report in the GO Data Warehouse (analysis) package includes hidden objects. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure

1. Create a variable, and define the condition that determines if the object is shown or hidden.

Tip: Create a Boolean variable to show and hide objects, as this type of variable has only two possible values.

2. From the **Toolbox** tab , drag a **Conditional Blocks** object to the work area.
3. Select the conditional block.
4. In the **Properties** pane, double-click the **Block Variable** property.
5. In the **Variable** box, click the variable you created and click **OK**.
6. Set the **Current Block** property to **Yes**.
7. From the content pane, drag the object to show or hide to the conditional block.
For example, drag a data item from the **Source** tab or from the **Data Items** tab.
You may need to link the report page to a query before you can add a data item to the block.

Results

When you run the report, the report objects to which you applied the variable are visible when the condition is satisfied and invisible when it is not.

Add Conditional Rendering


Add conditional rendering to specify which objects are rendered when a report is run. This is useful when your report contains sensitive data.

Conditional rendering is not the same as hiding objects. When you hide an object, the object exists but is transparent. If an object is not rendered, it is not in the report.

For a list of objects that can be rendered conditionally, see the Render Variable property in Appendix G, “Report Studio Object and Property Reference,” on page 799.

Procedure

1. Select the list column to be rendered conditionally.

Tip: You must select the list column, not the list column body or the list column title. If the body or title is selected, as indicated in the **Properties** pane, click the select ancestor button  and click the list column.

2. In the **Properties** pane, double-click the **Render Variable** property.
3. Click **Variable** and click the variable that will determine if the column will be rendered.
4. In the **Render for** box, select the values that the condition will support.









Tip: A default value exists for the variable, and it is always selected.



Example - Create a Conditional Report

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a report that shows orders after a date specified by the user. The report will prompt the user for a date and ask whether the user wants to see a description for each order.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.

3. In the **New** dialog box, click **List** and click **OK**.
4. From the **Source** tab , expand **Sales and Marketing (query)**, and **Sales (query)** and add data items to the list:
 - Expand **Time dimension** and add **Date**.
 - Expand **Sales order** and add **Order number**.
 - Expand **Product** and add **Product name** and **Product description**.
 - Expand **Sales fact** and add **Quantity**, **Unit price**, and **Revenue**.
5. Click **Date**, and then click the section button .
6. Select the **Order Number** column and click the group button .
7. Click **Revenue**, and then click the summarize button  and click **Total**.
8. Change the title of the report to **New Orders**.
9. Pause the pointer over the page explorer button  and click **Prompt Pages**.
10. Create a new prompt page by double-clicking **Page** in the **Toolbox** tab .
11. Double-click the new prompt page.
12. From the **Toolbox** tab, double-click **Text Item** and type the following text:
Enter the start date, and select if descriptions will be shown.
13. Insert a 2 by 2 table into the prompt page by clicking the insert table button  and moving the pointer until four squares are highlighted in a 2 by 2 pattern.
14. From the **Toolbox** tab, drag a **Text Item** into the upper-left cell and type the following text:
Starting Date
15. From the **Toolbox** tab, drag a **Text Item** into the lower-left cell and type the following text:
Show Descriptions
16. From the **Toolbox** tab, drag a **Date Prompt** into the upper-right cell.
17. In the **Prompt Wizard** window, select **Create a new parameter**, type **p_Date** in the space provided, and then click **Next**.
18. In the **Create Filter** window, select **Create a parameterized filter** with the following entries:
 - For **Package item**, click the ellipsis button and open **Sales (query)** and **Time dimension**, and then click **Date**.
 - For **Operator**, click **>**.
19. Click **Finish**.
20. From the **Toolbox** tab, drag a **Value Prompt** into the lower-right cell.
21. In the **Prompt Wizard**, in the **Choose Parameter** window, select **Create a new parameter**, type **p_ShowDesc** in the space provided, and then click **Finish**.
22. Select the **Value Prompt** and, in the **Properties** pane, double-click **Static Choices**.
23. Click the add button .
24. In the **Edit** dialog box, type **Yes** in both the **Use** and **Display** boxes.
25. Click the add button.

26. In the **Edit** dialog box, type **No** in both the **Use** and **Display** boxes.
27. Click **OK**.
28. Pause the pointer over the condition explorer button  and click **Variables**.
29. From the **Toolbox** tab, create a new Boolean variable by double-clicking **Boolean Variable**.
30. In the **Report Expression** dialog box, type the following in the **Expression Definition** window and click **OK**:
`ParamDisplayValue("p_ShowDesc") = 'Yes'`
31. In the **Properties** pane, set the **Name** property to **showDesc**.
32. Pause the pointer over the page explorer button and click the report page.
33. Click the **Product descriptions** column.
34. In the **Properties** pane, click the select ancestor button  and click **List Column**.
35. In the **Properties** pane, set the **Render Variable** property to the **showDesc** Boolean variable you created.
36. Run the report.

Results

The report prompts you for a date. Orders that occur after the date you entered are shown. The report also asks whether to show the **Descriptions** column, and the column is rendered only if you choose **Yes**.

Add Multiple Layouts

Add multiple layouts to show a report in different ways. For example, you can define a different layout for each language in a multilingual report. This allows you to create a single report that can be viewed by report consumers that use different regional settings.

Procedure

1. Create a variable and define the condition that will be used for each layout.
 For example, create a report language variable that includes each language that requires a conditional layout.
Note: Expressions used in a conditional layout cannot reference a query.
2. From the **File** menu, click **Conditional Layouts**.
3. Select a variable, and then select the values that require a separate layout.

Results

A layout is created for each value you selected. Use the page explorer to navigate the different layouts. For each layout, click **Report Pages** to create a report page or **Prompt Pages** to create a prompt page and add objects.

Tip: You can create new variables from the **Conditional Layouts** dialog. The variables are added to the condition explorer. For more information, see “Add a Variable from the Condition Explorer” on page 386.

Setting up a Multilingual Reporting Environment

You can create reports that show data in more than one language and use different regional settings. This means that you can create a single report that can be used by report consumers anywhere in the world.

The samples databases provided with IBM Cognos store a selection of text fields, such as names and descriptions, in more than 25 languages to demonstrate a multilingual reporting environment. For information about how data is stored in the samples databases and how the samples databases are set up to use multilingual data, see the *Administration and Security Guide*.

Here is the process for creating a multilingual reporting environment:

- Use multilingual metadata.

The data source administrator can store multilingual data in either individual tables, rows, or columns.

For more information about configuring your database for multilingual reporting, see the *Administration and Security Guide*.

- Create a multilingual model.

Modelers use IBM Cognos Framework Manager to add multilingual metadata to the model from any data source type except OLAP. They add multilingual metadata by defining which languages the model supports, translating text strings in the model for things such as object names and descriptions, and defining which languages are exported in each package. If the data source contains multilingual data, modelers can define queries that retrieve data in the default language for the report user.

For more information, see the Framework Manager *User Guide*.

- Create multilingual maps.

Administrators and modelers use a Microsoft Windows operating system utility named Map Manager to import maps and update labels for maps in IBM Cognos Report Studio. For map features such as country or region and city names, administrators and modelers can define alternative names to provide multilingual versions of text that appears on the map.

For more information, see the Map Manager *Installation and User Guide*.

- Create a multilingual report.

The report author uses Report Studio to create a report that can be viewed in different languages. For example, you can specify that text, such as the title, appears in German when the report is opened by a German user. You can also add translations for text objects, and create other language-dependent objects.

- Specify the language in which a report is viewed.

You can use IBM Cognos Connection to do the following:

- Define multilingual properties, such as a name, screen tip, and description, for each entry in the portal.
- Specify the default language to be used when a report is run.

Tip: You can specify the default language on the run options page, in the report properties, or in your preferences.

- Specify a language, other than the default, to be used when a report is run.

For more information, see the IBM Cognos Connection *User Guide*.

The data then appears in the language and with the regional settings specified in

- the user's Web browser options

- the run options
- the IBM Cognos Connection preferences

Any text that users or authors add appears in the language in which they typed it.

Create a Multilingual Report in Report Studio

You can create a report in IBM Cognos Report Studio that can be viewed in different languages. For example, you can specify that text such as the title appears in German when the report is opened by a German user. You can also add translations for text objects and create other language-dependent objects.


Before you begin

If you want the report to show data in different languages, the model must also be multilingual.

Procedure

1. Create a report language variable.
2. In the work area, select the object to modify based on a language.
3. In the **Properties** pane, double-click the **Style Variable** property.
If you are changing the language of a text string, click **Text Source Variable** instead.
4. Click **Variable** and click the language variable you created.
5. In the **Values** box, select the languages for the condition to support and click **OK**.

Tip: A default value exists for the variable, and it is always selected.

6. Pause the pointer over the condition explorer button  and a language for the variable.

Tip: When you select a value in the condition explorer, the Explorer bar becomes green to indicate that conditional formatting is turned on and that any changes you make to the report apply only to the variable value.

7. In the **Properties** pane, specify the formatting for the language.
For example, to change the language of a text string, double-click the **Text** property and select the new string.
8. Press Enter when you are done.
9. Repeat steps 6 to 8 for all other languages specified for the variable.

Tip: To view the report with no variables applied, pause the pointer over the condition explorer button and click **(No variable)** or triple-click the Explorer bar.

Results

When you run the report, the report objects to which you applied the variable are formatted according to the browser's language.

Chapter 16. Bursting Reports

Burst a report to distribute its contents to various recipients. Bursting is the process of running a report once and then dividing the results for recipients who each view a subset of the data. For example, salespeople in different regions each need a report showing the sales target for their country or region. You use burst reports to send each salesperson only the information they need. Burst reports can be distributed by email or saved to a folder for viewing in IBM Cognos Connection.

Tip: The Bursted Sales Performance Report sample report in the GO Data Warehouse (analysis) package includes bursting. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

To burst a report against a dimensional data source, see “Creating Burst Reports Using Dimensional Data Sources” on page 399.

You cannot burst crosstab or chart reports. However you can burst a report where a container includes a crosstab or chart that is part of a master detail relationship. In this situation, you can burst only HTML, PDF, and XLS output formats; you cannot burst CSV or XML output formats.

For information about avoiding disk space exhaustion when bursting charts or crosstabs, see “Master Detail or Burst Reports with Charts or Crosstabs May Result in Denial of Service” on page 517.

Procedure

1. define burst recipients
2. specify burst groups
3. set burst options
4. enable bursting

Defining Burst Recipients



Define the recipients who will receive data when the report is run. You can distribute burst reports to individual users, groups, roles, distribution lists, and contacts.

To define the recipients, you create a calculated field, create the burst table in the source database, and then import the table into a package.

Create a Calculated Field

You can use a calculated field to dynamically create burst report recipients.

Procedure

1. Pause the pointer over the query explorer button  and click the query that will produce the data to distribute.
2. From the **Toolbox** tab , drag **Data Item** to the **Data Items** pane.

3. In the **Expression Definition** box, type the expression that will generate the list of recipients and click **OK**.

For example, typing the following expression builds the list of the employees of The Samples Outdoors Company. The expression concatenates the first letter of each employee's first name with their last name.

lower(substring([Employee summary (query)].[Employee by organization].[First name],1,1) + [Employee summary (query)].[Employee by organization].[Last name])

4. To give the data item a more meaningful name, in the **Properties** pane, set the **Name** property to a different name and press the Enter key.

Creating the Burst Table in the Source Database

You can create a burst table in the source database for the list of recipients. The steps you must follow depend on the database system you are using. The burst table must contain the following columns:

- A unique identifier

Tip: Some database systems do not require a unique identifier for each table.

- A recipient column
- The data item on which to burst

You can also include other columns that provide additional information. For example, if you plan to distribute reports by email, you can add a column for the email address of each recipient.

After you create the table, add the recipients who will receive the report. You can create a mixed recipients list that includes individual users, groups, roles, contacts, distribution lists, or email addresses. For example, a burst table may contain the following recipients.

Recipient example	Recipient type
CAMID("":Canada")	Group
CAMID(":""/contact[@name='Silvano Allessori']	Contact
CAMID(":""/distributionList[@name='European Partners']	Distribution list
CAMID("LDAP_Local_ID :u:uid=gbeliding,ou=people")	Authentication provider user or group, where LDAP_Local_ID is the name of an LDAP namespace ID, and people is the name of an organizational unit
c10@ibmcognos99.com	Email address

CAMID stands for Cognos Access Manager ID, and it represents an internal search path to the recipients. Specify search paths when you want to save burst reports in a folder. You can obtain the search path in IBM Cognos Connection by opening the **Set properties** page for each recipient and clicking **View the search path**. Ensure that you use the proper syntax when adding recipients to the burst table.

In the case of NTLM namespaces, user IDs in the search path use alphanumeric or numeric characters that make them difficult to read. You can use the following alternate search path syntax:

```
directory/namespace[@name="Local NT"]//account[@userName="gbeliding"]
```

where Local NT is the name of a namespace and gbelding is the name of a user. The double slash before the account element indicates that you are searching all accounts under the specified namespace.

Note: If you have a mixed recipients list, do not mix email address recipients and alternate path recipients. Because the alternate path syntax contains the @ symbol, it will be mistaken for an email address.

For more information about users, groups, roles, contacts, and distribution lists, see the IBM Cognos Business Intelligence *Administration and Security Guide*.

Importing the Table into a Package

After you create the burst table in the source database, you must add it to the package that you will use to create the report.

For more information about importing tables and creating relationships, see the Framework Manager *User Guide*.

Procedure

1. Open the package.
2. Import the table.
3. Define the relationship between the burst table and the table containing the data item on which to burst.


For example, you are bursting on country or region code. You define a relationship between country or region code in the burst table and country or region code in the Country or Region table.


4. Save and publish the package.

Specify a Burst Group

Specify burst groups to set how the report will be distributed. Burst groups are defined by a data item that you create in the report or that you add from the burst table.

Procedure

1. Pause the pointer over the query explorer button  and click the query that will produce the data to distribute.
2. If you are creating a data item, do the following:


- From the **Toolbox** tab , drag **Data Item** to the **Data Items** pane.
- In the **Expression Definition** box, type the expression that defines the burst key.

For example, the following expression builds an email address for each sales representative in The Sample Outdoors Company. The expression incorporates the calculated field that was previously created, which is named `userID` in the following expression, with `ibmcognos99.com` as the domain name.

```
[userID]+'@ibmcognos99.com'
```

Tip: To give the data item a more meaningful name, in the **Properties** pane, set the **Name** property to a different name and press Enter.

3. To specify a burst table column as the data item, do the following:

- From the **Source** tab , expand the burst table.
- Drag the data item to the **Data Items** pane.
For example, if you are bursting reports by email, drag the data item containing email addresses.

Set Burst Options

Set burst options for the report to indicate the data item on which to burst and the recipients.


Before you begin


Before you set burst options, ensure that the data item on which you intend to burst is in the report and is grouped. The grouped column will create the appropriate subsets of data. In addition, you must associate the burst key with this level of grouping.

Procedure

1. From the **File** menu, click **Burst Options**.
2. Select the **Make report available for bursting** check box.
3. Under **Burst Groups**, in the **Query** box, click the query that contains the data item on which to burst.

Tip: You can choose a query that does not appear in the layout. This is useful to distribute the same report to all burst recipients.

4. In the **Label** box, click the data item with which to label each burst report.
5. Click the edit button .
6. In the **Data Items** box, drag the data item on which to burst to the **Groups** folder and click **OK**.

Tip: You can specify the sort order of data within each group by dragging data items to the **Sort List** folder and then clicking the sort order button .

7. Under **Burst Recipient**, in the **Query** box, click the query that contains the data item to be used as the distribution list.
8. In the **Data Item** box, click the data item that contains the recipients.
9. In the **Type** box, choose the method to burst the report:
 - Click **Automatic** to let IBM Cognos Business Intelligence determine from the data item whether to email reports or send them to folders in IBM Cognos Connection.
 - Click **Email addresses** to distribute reports by email.
 - Click **Directory entries** to distribute reports to folders that recipients can access in IBM Cognos Connection.

Note: To burst reports to multiple mobile device users, you must choose to distribute reports to folders. You can choose **Directory entries**, or you can choose **Automatic** if the data item returns directory entries instead of email addresses. To view the reports, the recipients must have IBM Cognos Mobile installed on their mobile devices. For more information about IBM Cognos Mobile, see the IBM Cognos Business Intelligence *Administration and Security Guide*.

When recipients log into IBM Cognos BI, they will see only the report that is specific to them.


10. If the report contains two nested data containers, such as a list and a chart, click the ellipsis button beside **Master detail relationships** and define the relationship between the data containers.

For information about master detail relationships, see “Create a Master Detail Relationship” on page 307.

Enable Bursting

When the report is ready to be distributed, enable bursting for the report in IBM Cognos Connection.

Procedure

1. Locate the report in IBM Cognos Connection.
2. Under **Actions**, click the run with options button .
3. Click **advanced options** on the right of the screen.
4. Under **Time and mode**, click **Run in the background**.
5. Select the **Burst the report** check box.
6. If you are distributing reports by email, select the **Send the report by email** check box.

Tip: If you are bursting the report to a folder, you can also send the report by email if the **Send the report by email** check box is selected. Reports will be emailed if the recipient's email address is stored in the authentication source you are using or if they are entered in the recipient's personal information in IBM Cognos Connection.

7. If the burst report contains a drill-through link to another report and you are distributing the burst report by email, do the following:
 - Click **Edit the options**.
 - Select the **Include a link to the report** check box.If you do not select the check box, the drill-through links in the burst report will not work.
8. Run the report.

Results

Allow a few moments for the report to run. If you are an administrator, you can view all outputs for the report. Under **Actions**, click **View the output versions for this report**. When burst recipients log into IBM Cognos Connection or access their email accounts, they will see only the data that is meant for them.

Creating Burst Reports Using Dimensional Data Sources

You can burst a report using a dimensional data source by using burst information that is stored in the data source. Because you do not want to append bursting information to existing dimensional data sources, you can create a relational data source that contains the burst information.

Report bursting is limited when the underlying data source is a cube (MOLAP data source such as IBM Cognos PowerCube, Microsoft Analysis Services, Oracle Essbase, or IBM DB2/OLAP). The burst report must be a grouped report, and the

burst is restricted to the outermost grouping in the report. For example, if you have a report grouped on Country or Region and State, then you can burst the report only on Country or Region.

Procedure

1. In IBM Cognos Framework Manager, include both the dimensional data source that is the basis for reporting and the relational burst table in the model.
For more information about models, see the Framework Manager *User Guide*.
2. In IBM Cognos Report Studio, create a master detail report in which the master query drives the report and the detail query contains the burst information.
You must group the master query on the data item on which you are bursting. This data item must have a corresponding data item in the relational burst table.
Author the detail query against the relational burst table. The burst table must contain two columns: the data item corresponding to the data item used in the master report for bursting and the data item that contains the recipient information. The recipient can be an email address or an expression that results in a search path to an object in IBM Content Manager, such as an account, group, role, contact, or distribution list.
For more information about master detail queries, see “Create a Master Detail Relationship” on page 307.
3. Ensure that the detail query, which must be evaluated by IBM Cognos Business Intelligence when the report is executed, is not visible:
 - Place a list that is based on the detail query in a conditional block with a box type of **None**.
 - Link the master and detail queries using the following expression:
[Master Burst Key] = [Detail Burst Key]


Results







When you set the burst options for the report, the master query provides the data items for the burst key and the detail report provides the data items for the burst recipients.

Example - Burst a Report

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a report that lists product sales for each sales representative. The report is to be emailed to each sales representative, but they only need to see the data that pertains to them. You create a list report that you burst to each sales representative.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **List** and click **OK**.
4. From the **Source** tab , expand **Sales and marketing (query)** and **Sales (query)**. Add the following data items:
 - Expand **Employee by region** and add **Employee name**.
 - Expand **Products** and add **Product line**, **Product type**, and **Product**.

- Expand **Sales fact** and add **Quantity** and **Revenue**.
5. Group the **Employee name**, **Product line**, and **Product type** columns.
 6. Click the **Employee name** column, click the headers and footers button , and then click **Create Header**.
Employee name appears as a header in the list. You no longer need to keep the data item as a list column.
 7. In the list, click the **Employee name** column and click the delete button .
 8. Click **Revenue**, and then click the summarize button  and click **Total**.
 9. Pause the pointer over the query explorer button  and click **Query1**.
 10. From the **Source** tab, drag **Email** from the **Employee by region** folder to the **Data Items** pane.
 11. From the **File** menu, click **Burst Options**.
 12. Select the **Make report available for bursting** check box.
 13. Under **Burst Groups**, in the **Query** box, click **Query1**.
 14. In the **Label** box, click **Employee name**.
 15. Click the edit button .
 16. In the **Data items** box, drag **Employee name** to the **Groups** folder and click **OK**.
 17. Under **Burst Recipient**, in the **Query** box, click **Query1**.
 18. In the **Data Item** box, click **Email**.
 19. In the **Type** box, click **Email addresses**.
 20. Save the report.
 21. Locate the report in IBM Cognos Connection.
 22. Under **Actions**, click **Run with options** .
 23. Click **advanced options** on the right of the screen.
 24. Under **Time and mode**, click **Run in the background**.
 25. Select the **Burst the report** check box.
 26. Select the **Send the report by email** check box.
 27. Run the report.

Results

When sales representatives access their email accounts, they will see reports with only the data that is meant for them.

Chapter 17. Format Data

Format data in a report to improve readability. For example, you can show all date values in the order year, month, and day. If you do not set **Data Format** properties here, data is formatted according to the properties set in the model. If the properties were not set in the model, data is formatted according to the International Components for Unicode (ICU) formats.

Special cells, such as overflow or underflow, errors, or not applicable values, appear with two dash (--) characters unless you override them.

You can also format data based on a condition or specify the format for a particular object.

When you create a calculation that uses mixed currency values or other mixed units of measure, an asterisk character (*) might appear as the unit of measure. To avoid this problem, change the format of the column or row that contains the result of the calculation so that the wanted unit of measure appears.


Set the Default Data Formats

Set the default data properties for each type of data, including text, number, currency, percent, date, time, date/time, and time interval.

Procedure

1. From the **Data** menu, click **Default Data Formats**.
2. In the **Format type** box, click a format type.

The properties that you can set for the selected format type appear in the **Properties** box.

3. If you clicked the **Currency** format type and require different currencies in the report, click the add button  and select currency check boxes.

For example, you may have one column with values are in euros and another column whose values are in US dollars.

4. Set the properties.

If you added currencies in step 3, click each one and set the properties. If you did not add any currencies, any properties you set will apply to all currencies.

For properties in which you type meta-characters that represent certain types of information, such as YYYY-MM-DD for dates, the meta-characters that are required depend on the authoring language specified for the report. For more information, see "Using Patterns to Format Data" on page 409.

If you set a value for the **Pattern** property, all other formatting properties are ignored with the following exceptions:

- **Missing Value Characters**
- **Zero Value Characters**
- **Negative Pattern**

Some properties are language-sensitive and should be changed only with caution.

Results

The data formatting properties you set are applied to objects only in the current layout. If a data item contains values in multiple currencies but only a subset of those currencies have defined formats, the default format for the locale in which you are working is applied to values with no specified format.

Specify the Data Format for an Object

Specify the format for a particular object if you are not getting the results you want.

For example, you add a measure to a report and you want to see two decimals when you run the report. You set the number of decimals to two for the **Number** format type for the current layout. However, when you run the report, you see more than two decimals for the measure. To get the results you want, you must map the measure to the **Number** format type.

About this task

Data formats are not applied in delimited text (CSV) and XML report outputs.

The time interval data format assumes that input values are in milliseconds. As a result, when the time interval format is applied to an object, the values that appear in the report output are in milliseconds. You can apply the cast function to return the interval type that you want.

Procedure

1. Click the object.
2. In the **Properties** pane, double-click the **Data Format** property.
3. Under **Format type**, click the format type to apply to the object.
4. To override any of the properties of the format type that were defined for the current layout, in the **Properties** box, click the property and specify its value.

Specifying the Number of Decimals in Numbers

When specifying the number of decimals, IBM Cognos Business Intelligence uses the IEEE 754 default rounding mode known as half even. With half even rounding, numbers are rounded toward the nearest truncated value, unless both truncated values are equidistant, in which case the value ending in an even digit is chosen, as follows:

- If the digit immediately after the precision to be shown is greater than 5, the number is rounded up.
- If the digit immediately after the precision to be shown is less than 5, the number is rounded down.
- If the digit immediately after the precision is a 5, the number is rounded down when the preceding digit is even and rounded up when the preceding digit is odd.

For example, the number 78.5 is rounded to 78, while the number 73.5 is rounded to 74.

In addition, if the maximum number of decimals is lower than the actual number of decimals in the number, the number is rounded to the maximum number of decimals.

Digit shaping in charts and maps

When working with bidirectional content, you cannot specify digit shaping at the chart or map level. You can specify digit shaping for the objects in charts and maps.

To understand how digit shaping is applied to charts and maps, you must know which chart and map objects are considered text and which objects are considered numeric values.

The following table describes the chart and map objects that are considered text.

Table 6. Chart and map objects that are considered text

Container	Object
Chart	chart title, subtitle, footer, notes, legend item, legend title, regression label, marker label, background image label, axis titles, discrete axis label (for example, category axis label, x-axis), baseline labels
Map	map title, subtitle, footer, legend title, notes, axis labels

The following table describes the chart and map objects that are considered numeric values.

Table 7. Chart and map objects that are considered numeric values

Container	Object
Chart	numeric axis label (for example, measure axis label, y-axis), numeric values that appear in the legend (you can select to show the first, last, maximum, minimum value for each item in legends), numeric values that appear in the chart
Map	legend items

The following list describes the different digit shaping options and how digit shaping is applied to charts and maps.

- The digit shape options for text objects, which include titles, footers, and labels, are Default, None, National, and Contextual. Digit shape options for numeric values are Default, None, and National. There is no Contextual option for numeric values.
- By default, digit shaping is not applied to numbers that appear on an object that is considered text. For example, if a chart shows year data on the x-axis and the content language specified in IBM Cognos Connection is Arabic (Egypt), no digit shaping is applied because the x-axis label is considered a string.

The following list describes the default digit shaping behavior for charts and maps when the content language implies non-European digits, such as Arabic (Egypt).

- Numeric values that have a specific format, such as decimal or currency, are displayed as Arabic-Indic.
- Except for matrix charts, numeric axis labels for charts and maps are displayed in European digits.

This is due to the way that charts and maps are rendered. The engine used to render charts and maps does not perform any formatting for numeric axis labels. No locale information is passed, and consequently the labels are displayed as European digits. To display the labels as Arabic-Indic, select the digit shaping option National.

Matrix charts are rendered using International Components for Unicode (ICU) to format numbers. Locale information is passed and the numbers are shaped accordingly. For example, when the content language is Arabic (Egypt), ICU displays numbers as Arabic-Indic.

- Numbers within text labels are displayed as is. That is, no digit shaping is applied.

The following list describes the default digit shaping behavior for charts and maps when the content language is Thai.

- Numeric values that have a specific format, such as decimal or currency, are displayed as European digits.
- Numbers within text labels are displayed as is. That is, no digit shaping is applied.

Related concepts:

“Support for bidirectional languages” on page 60

You can author reports that support bidirectional languages. You can specify base text direction, digit shaping, and container direction.

Related information:

“Digit Shaping” on page 1000

Specifies the digit shaping option to apply. When National is selected, digit shapes are determined from the user’s content language. When Contextual is selected, digit shapes are determined from adjoining characters in the value. For example, if the most recent strongly directional character before the numerical character is left-to-right, the number is displayed as a European number. If the most recent strongly directional character before the numerical character is right-to-left, the number is displayed in Arabic-Indic format. If there are no strongly directional characters before the numerical character, the number is displayed according to the base text direction of the field. When None is selected, no shaping is performed, and the value as it appears in the data source is shown. The default depends on the type of value. When the value is a string, the default is None.

Locale-sensitive Properties

IBM Cognos Report Studio contains an extensive library of customized properties adapted to users from different regions who speak different languages. For example, if a modeler specifies that a given data item is a currency, only the proper currency symbol must be specified. When reports are created, Report Studio automatically adapts the format of the currency numbers to each user according to the content language specified in IBM Cognos Connection.

When modelers or report authors specify properties, these properties override user preferences and risk creating inconsistent formatting for users of other cultures. It is usually much easier and safer to let Report Studio take care of formatting. For example, for the date format type, different regions use different characters to represent the date separator. If you specify a date separator, you may confuse users in other regions.

The following data formatting properties are locale-sensitive:

- **Currency Symbol Position**
- **Date Separator**
- **Date Ordering**
- **Calendar Type**
- **Time Separator**

- **Display AM/PM Symbols**
- **Clock**
- **Decimal Symbol**
- **Negative Sign Position**
- **Thousands Separator**
- **Group Size (digits)**
- **Secondary Group Size (digits)**
- **Missing Value Characters**
- **Zero Value Characters**
- **Pattern**
- **Negative Pattern**

Suppress Empty Cells

Sparse data may result in crosstabs showing empty cells. For example, a crosstab that matches employees with products results in many rows of empty values for the revenue measure if the employee does not sell those products.

You can suppress rows, columns, or rows and columns based on divide by zero, missing, and overflow values. Suppressing rows or columns without data gives you a more concise view of your report.


Calculations are performed before suppression is applied. If you have multiple crosstabs or charts, you must select one in order to access suppression options.

Within a list report, suppression applies only to rows and is based on non-grouped data items. If details of a group are null, then the header and footer are also suppressed.

Suppression can also be applied to charts, repeaters, and repeater tables.

Access to the suppression feature depends on the settings in your modeling component, IBM Cognos Transformer, IBM Cognos Framework Manager, and IBM Cognos Administration.

Procedure

1. From the **Data** menu, click **Suppress**  and click **Suppression Options**.
2. Under **Suppress**, choose what sections to suppress.
3. Under **Suppress the following**, choose which values to suppress.

Related concepts:

“Limitations When Formatting Empty Cells in SAP BW Data Sources” on page 566
 When working with SAP BW data sources, if the SAP BW server administrator configured custom formatting for empty cells on the SAP BW server, this custom format does not appear in IBM Cognos Business Intelligence reports. Ask your administrator to configure the formatting of empty cells in IBM Cognos BI.

Suppress Null Cells Using Filters

You can also use filters to suppress null cells in your reports. Using filters ensures that calculations take suppression into account. You may also obtain better report performance because the filtering is done at the data source.

If your report includes more than one measure or fact expression, it is best to base the filter on only one underlying fact or measure.

Relational-style Reports

In relational-style reports, you can use detail and summary filters.

Dimensional-style Reports

In dimensional-style reports, you can use the filter function.


For example, insert a set expression in your crosstab and use the expression filter (descendants ([Set]) is not null). If your crosstab includes three or more levels within the same dimension on an edge, use the expression filter (descendants (currentMember([Hierarchy]) is not null).

If your crosstab includes nested sets, filter the sets using a cascading approach to improve performance. For example, first filter the outermost (or highest nested level) set, and then filter the remaining sets proceeding inward.

Example - Suppress Zeros in Rows and Columns in an Existing Report

You are a report writer at The Sample Outdoors Company, which sells sporting equipment. You have a report that compares current year data to previous year data. You want to suppress zeros in the report to make the report more concise. You use the zero suppression tool to set the level of suppression.

Procedure

1. Open the GO Balance Sheet as at Dec. 31, 2012 report.
 2. From the **Data** menu, click **Suppress**  and click **Suppression Options**.
 3. Under **Suppress the following**, click **Rows and columns**.
 4. Under **Suppress the following type of values**, select the **Zero values** check box.
 5. Run the report.
- Rows and columns containing zeros are hidden.

Great Outdoors Company			
balance sheet as at Dec 31, 2012 (with prior year comparative data)			
Year to date (USD \$ 000's)	2012 Actual results in USD		2011 Actual results in USD
	December 2012		December 2011
Assets (total)	\$4,353,363,798		\$3,804,483,176
Current assets (total)	\$2,336,392,807		\$2,139,066,575
Operating assets (total)	\$1,778,012,688		\$1,484,257,572
Other assets (total)	\$238,958,303		\$181,159,029
Liabilities (total)	(\$1,602,289,213)		(\$1,754,874,006)
Current liabilities (total)	(\$1,144,967,294)		(\$1,206,574,775)
Long-term and other liabilities (total)	(\$457,321,919)		(\$548,299,231)
Equity (total)	(\$2,751,074,586)		(\$2,049,609,170)
Common stock	(\$719,183,000)		(\$749,178,000)
Other capital	(\$69,921,200)		(\$183,898,457)
Retained earnings - net	(\$1,961,541,522)		(\$1,116,128,225)
Currency translation gain (or loss)	(\$428,864)		(\$404,488)

Figure 61. Balance sheet with zero suppression applied in rows and columns

Specify what appears for data containers that contain no data

You can specify what appears in a data container when no data is available from the database.

When no data is available, you can show one of the following options:



- An empty data container, such as a blank list.
- Alternate content, such as another data container or an image. You can insert any object from the **Toolbox** tab.
- Text, such as *There is no data available for this month*. If you show text, you can format it. By default, the text **No Data Available** appears.


You can specify what appears when no data is available for the following data containers: lists, crosstabs, charts, maps, repeaters, repeater tables, and tables of contents.

If your report includes multiple data containers, you can specify different no data contents for each container.

Tip: The No Data sample report in the GO Sales (query) package includes data containers that have no data. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure

1. Select a data container.
2. In the **Properties** pane, click the select ancestor icon  and click the data container type.
3. Click the ellipsis button next to the **No Data Contents** property and select what should appear for data containers that contain no data:
 - To show an empty data container, click **No Contents**.
 - To show alternate content, click **Content specified in the No data tab**.
Two tabs appear at the top of the data container and the **No Data Contents** tab  is selected automatically.

From the **Toolbox** tab , insert the objects to appear when there is no data available into the **No Data Contents** tab.
- To show text, click **Specified text** and type the text that you want to appear.

Using Patterns to Format Data

You can format data so that it matches any pattern of text and numbers when default formats are not appropriate. For example, you can format dates to use full text including the era, or you can format them to only use numbers and show the last two digits of years to save space.

Using symbols and patterns can provide similar results as basic data formatting tasks. For example, you can set how many digits appear after the decimal point. You can achieve these types of results with a pattern, or you can set the **No. of Decimal Places** property. Patterns allow flexibility for more complex requirements.

Each supported content language code requires a specific set of symbols to be used in patterns. For each language code, there are two tables you will need; one for

date and time symbols, and one for decimal symbols. The decimal symbols are the same for all locales, however, date and time symbols are grouped into six locale groups. Check the Date and Time Symbol section to see which locale group is used for your locale.

To define patterns, open the **Data Format** dialog box, and edit the **Pattern** property for each format type. Use the symbols that are defined in the language code tables, and follow these guidelines.

Pattern Guidelines

When you define a pattern, the number of symbols you use affects how the data will be shown. There are different rules for text, numbers, and values that can take the form of text or numbers.

Text

You can specify whether text is produced in full or abbreviated form.

Number of symbols	Meaning	Example
4 or more	Full text form	EEEE produces Monday
Less than 4	Abbreviated form	EEE produces Mon

Numbers

The number of symbols you use in a pattern sets the minimum number of digits that are produced in a report. Numbers that have fewer digits than specified are zero-padded. For example, if you specify mm for minutes, and the database value is 6, the report will show 06.

Note: The year value is handled differently. If you specify two symbols for year, the last two digits of the year value is produced. For example, yyyy produces 2013, and yy produces 13.

Text and Numbers

For values that can produce text or numbers, such as months, you can specify whether text or numbers are produced, and whether words are abbreviated.

Number of symbols	Meaning	Example
3 or more	Text	MMMM produces January MMM produces Jan
Less than 3	Numbers	MM produces 01 M produces 1

Date and Time Symbols

Date and time symbols are divided into locales, each of which is detailed in the following sections.

Locale Group A

Locales: af-za, en, en-au, en-be, en-bw, en-ca, en-gb, en-hk, en-ie, en-in, en-mt, en-nz, en-ph, en-sg, en-us, en-vi, en-za, fo-fo, gl-es, id, id-id, is, is-is, it, it-ch, it-it, kk-kz, ms, ms-bn, ms-my, nb-no, nl, nl-be, nl-nl, no, no-no, om-et, om-so, pl, pl-pl, pt, pt-br, pt-pt, so-dj, so-et, so-ke, so-so, sv, sv-fi, sv-se, sw-ke, sw-tz

Meaning	Symbol	Presentation	Example
Era	G	Text	AD
Year	y	Number	2013
Year (of 'Week of Year')	Y	Number	2013
Month in year	M	Text and number	July and 07
Week in year	w	Number	27
Week in month	W	Number	2
Day in year	D	Number	189
Day in month	d	Number	10
Day of week in month	F	Number	2 (2nd Wed in July)
Day of Week (1=first day)	e	Number	2
Day in week	E	Text	Tuesday
a.m. or p.m. marker	a	Text	pm
Hour in day (1 to 24)	k	Number	24
Hour in a.m. or p.m. (0 to 11)	K	Number	0
Hour in a.m. or p.m. (1 to 12)	h	Number	12
Hour in day (0 to 23)	H	Number	0
Minute in hour	m	Number	30
Second in minute	s	Number	55

Meaning	Symbol	Presentation	Example
Millisecond	S	Number	978
Time zone	z	Text	Pacific Standard Time
Escape used in text	'	n/a	n/a
Single quote	"	n/a	'

Locale Group B

Locales: be-by, bg-bg, el, el-gr, fi, fi-fi, hr, hr-hr, hu, hu-hu, ja, ja-jp, ko, ko-kr, ro, ro-ro, ru, ru-ua, ru-ru, sh-yu, sk, sk-sk, sl-si, sq-al, sr-sp, th, tr, tr-tr, uk-ua, zh, zh-cn, zh-hk, zh-mo, zh-sg, zh-tw

Meaning	Symbol	Presentation	Example
Era	G	Text	AD
Year	a	Number	2013
Year (of 'Week of Year')	A	Number	2013
Month in year	n	Text and number	July and 07
Week in year	w	Number	27
Week in month	W	Number	2
Day in year	D	Number	189
Day in month	j	Number	10
Day of week in month	F	Number	2 (2nd Wed in July)
Day of Week (1=first day)	e	Number	2
Day in week	E	Text	Tuesday
a.m. or p.m. marker	x	Text	pm
Hour in day (1 to 24)	h	Number	24
Hour in a.m. or p.m. (0 to 11)	K	Number	0
Hour in a.m. or p.m. (1 to 12)	k	Number	12

Meaning	Symbol	Presentation	Example
Hour in day (0 to 23)	H	Number	0
Minute in hour	m	Number	30
Second in minute	s	Number	55
Millisecond	S	Number	978
Time zone	z	Text	Pacific Standard Time
Escape used in text	'	n/a	n/a
Single quote	"	n/a	'

Locale Group C

Locales: ca-es, cs, cs-cz, da, da-dk, es, es-ar, es-bo, es-cl, es-co, es-cr, es-do, es-ec, es-es, es-gt, es-hn, es-mx, es-ni, es-pa, es-pe, es-pr, es-py, es-sv, es-us, es-uy, es-ve, eu-es, mk-mk

Meaning	Symbol	Presentation	Example
Era	G	Text	AD
Year	u	Number	2013
Year (of 'Week of Year')	U	Number	2013
Month in year	M	Text and number	July and 07
Week in year	w	Number	27
Week in month	W	Number	2
Day in year	D	Number	189
Day in month	t	Number	10
Day of week in month	F	Number	2 (2nd Wed in July)
Day of Week (1=first day)	e	Number	2
Day in week	E	Text	Tuesday
a.m. or p.m. marker	a	Text	pm
Hour in day (1 to 24)	h	Number	24

Meaning	Symbol	Presentation	Example
Hour in a.m. or p.m. (0 to 11)	K	Number	0
Hour in a.m. or p.m. (1 to 12)	k	Number	12
Hour in day (0 to 23)	H	Number	0
Minute in hour	m	Number	30
Second in minute	s	Number	55
Millisecond	S	Number	978
Time zone	z	Text	Pacific Standard Time
Escape used in text	'	n/a	n/a
Single quote	"	n/a	'

Locale Group D

Locales: de, de-at, de-be, de-ch, de-de, de-lu

Meaning	Symbol	Presentation	Example
Era	G	Text	AD
Year	j	Number	2013
Year (of 'Week of Year')	J	Number	2013
Month in year	M	Text and number	July and 07
Week in year	w	Number	27
Week in month	W	Number	2
Day in year	D	Number	189
Day in month	t	Number	10
Day of week in month	F	Number	2 (2nd Wed in July)
Day of Week (1=first day)	e	Number	2
Day in week	E	Text	Tuesday

Meaning	Symbol	Presentation	Example
a.m. or p.m. marker	a	Text	pm
Hour in day (1 to 24)	h	Number	24
Hour in a.m. or p.m. (0 to 11)	K	Number	0
Hour in a.m. or p.m. (1 to 12)	k	Number	12
Hour in day (0 to 23)	H	Number	0
Minute in hour	m	Number	30
Second in minute	s	Number	55
Millisecond	S	Number	978
Time zone	z	Text	Pacific Standard Time
Escape used in text	'	n/a	n/a
Single quote	"	n/a	'

Locale Group E

Locales: fr, fr-be, fr-ca, fr-ch, fr-fr, fr-lu

Meaning	Symbol	Presentation	Example
Era	G	Text	AD
Year	a	Number	2013
Year (of 'Week of Year')	A	Number	2013
Month in year	M	Text and number	July and 07
Week in year	w	Number	27
Week in month	W	Number	2
Day in year	D	Number	189
Day in month	j	Number	10
Day of week in month	F	Number	2 (2nd Wed in July)

Meaning	Symbol	Presentation	Example
Day of Week (1=first day)	e	Number	2
Day in week	E	Text	Tuesday
a.m. or p.m. marker	x	Text	pm
Hour in day (1 to 24)	h	Number	24
Hour in a.m. or p.m. (0 to 11)	K	Number	0
Hour in a.m. or p.m. (1 to 12)	k	Number	12
Hour in day (0 to 23)	H	Number	0
Minute in hour	m	Number	30
Second in minute	s	Number	55
Millisecond	S	Number	978
Time zone	z	Text	Pacific Standard Time
Escape used in text	'	n/a	n/a
Single quote	"	n/a	'

Locale Group F

Locales: ga-ie

Meaning	Symbol	Presentation	Example
Era	R	Text	AD
Year	b	Number	2013
Year (of 'Week of Year')	B	Number	2013
Month in year	M	Text and number	July and 07
Week in year	t	Number	27
Week in month	T	Number	2
Day in year	l	Number	189

Meaning	Symbol	Presentation	Example
Day in month	L	Number	10
Day of week in month	F	Number	2 (2nd Wed in July)
Day of Week (1=first day)	e	Number	2
Day in week	E	Text	Tuesday
a.m. or p.m. marker	a	Text	pm
Hour in day (1 to 24)	u	Number	24
Hour in a.m. or p.m. (0 to 11)	K	Number	0
Hour in a.m. or p.m. (1 to 12)	k	Number	12
Hour in day (0 to 23)	U	Number	0
Minute in hour	n	Number	30
Second in minute	s	Number	55
Millisecond	S	Number	978
Time zone	c	Text	Pacific Standard Time
Escape used in text	'	n/a	n/a
Single quote	"	n/a	'

Decimal Format Symbols

All locales

Symbol	Meaning
0	A digit that is shown even if the value is zero.
#	A digit that is suppressed if the value is zero.
.	A placeholder for decimal separator.
,	A placeholder for thousands grouping separator.
E	Separates mantissa and exponent for exponential formats.
;	Separates formats for positive numbers and formats for negative numbers.

Symbol	Meaning
-	The default negative prefix.
%	Multiplied by 100, as percentage.
‰	Multiplied by 1000, as per mille.
¤	The currency symbol. If this symbol is present in a pattern, the monetary decimal separator is used instead of the decimal separator.
¤¤	The international currency sign. It will be replaced by an international currency symbol. If it is present in a pattern, the monetary decimal separator is used instead of the decimal separator.
X	Other characters that can be used in the prefix or suffix.
'	Used to quote special characters in a prefix or suffix.
/u221E	Infinity symbol.
/uFFFD	Not a Number symbol.

Chapter 18. Using Query Macros

A macro is a fragment of code that you can insert in the Select statement of a query or in an expression. For example, add a macro to insert a new data item containing the user's name.

You can include references to session parameters, parameter maps, and parameter map entries in macros. Parameter values are set when you run the query. For example, you can use the language session parameter to show only the data that matches the language setting for the current user.

Macros can be used in these different ways:

- They can be inserted in the SQL.
An example is `Select * from Country where Country.Name = #myMap{$runLocale}#`
- They can supply an argument to a stored procedure query subject.
If a value is not hard-coded for the argument, the stored procedure query subject can be used to return different data.
- They can be inserted in expressions, such as calculations and filters.
An example is a filter `[gosales].[Sales staff].[Staff name] = #UserLookUpMap{$UserId}#`
- They can be used as a parameter wizard.
Parameters can reference other parameters. An example is `Map1, Key = en-us, Value = #myMap{$UserId}#`

You can also add query macros to the IBM Cognos Framework Manager model. For more information, see the Framework Manager *User Guide*.

Support for query macros in IBM Cognos Report Studio includes the same capabilities as macros used in Framework Manager. However, Report Studio query macros do not extend to the layout. Therefore, when making changes to the query using macros, you must bear in mind the side-effects on the layout. For example, if a macro removes a column from the query that the layout refers to, a run-time error will occur.

Syntax

Use the following syntax to reference session parameter and parameter values.

Object	Syntax	Example
Session key	<code>\$session_key</code>	<code>#my_account#</code>
Parameter map key	<code>\$map{<key>}</code>	<code>#map_one{'abc'}#</code>
Parameter map entry whose key is defined by a session parameter	<code>\$map{\$session_key}</code>	<code>#map_one{my_account}#</code>

You can add the following elements to further define the macro expression.

Symbol	Purpose
Single quotation marks ' '	<p>Delineates a literal string that has a single quotation mark as part of the string.</p> <p>If the single quotation mark displays in a string, such as a query item, the string must be enclosed in a single quotation mark on both sides of the string and the single quotation mark must be doubled. For example, ab'c is written as 'ab''c'</p> <p>If the single quotation mark displays in a macro, the string must be enclosed in square brackets. For example, ab'c is written as [ab'c]</p> <p>If the single quotation mark displays in a prompt, there is no need to enclose the string.</p> <p>To escape a single quotation mark in an expression, use &apos;</p>
Square brackets []	Encloses model objects, such as a namespace or query subject and macro names that contain restricted characters, such as a number sign, hyphen, or space.
Curly brackets, also known as braces { }	<p>Calls a function that is unknown to the parser, such as dateadd in DB2, and whose first argument is a keyword.</p> <p>Example:</p> <pre>dateadd ({month},2,<date expression>)</pre>
+ operator	Concatenates two strings, such as 'abc' + 'xyz'
Single quote function (sq)	<p>Surrounds the result of a string expression with single quotation marks. If the single quotation mark displays in a string, such as a query item, the string must be enclosed in a single quotation mark on both sides of the string and the single quotation mark must be doubled. You can use this function to build clauses to test against literal parameter-driven values.</p> <p>Here is an example:</p> <pre>#sq(\$my_sp)#</pre> <p>If a session parameter (my_sp) has the value ab'cc, the result is</p> <pre>'ab"cc'</pre>

Symbol	Purpose
Double quote function (dq)	<p>Surrounds the result of a string expression with double quotation marks. You can use this function to refer to table and column names with non-identifier characters, such as a blank space or a percent sign (%).</p> <p>Here is an example:</p> <pre>#dq ('Column' + \$runLocale)#</pre> <p>If runLocale=en-us, the result is "Column en-us"</p>
Square bracket function (sb)	<p>Inserts a set of square brackets into the argument to build object references in a model query and model expressions, such as filters and calculations.</p> <p>Here is an example:</p> <pre>#sb ('my item in ' + \$runLocale)#</pre> <p>If runLocale=en-us, the result is [my item in en-us]</p>

For information about functions, see Appendix F, “Using the expression editor,” on page 575.

Add a Query Macro

Add a query macro to allow run-time changes to be made to SQL queries.

About this task

When you reference a parameter, you must do the following:

- Use a number sign (#) at the beginning and end of each set of one or more parameters.
Everything between the number signs is treated as a macro expression, which is processed at runtime. Framework Manager removes anything that is outside the number signs.
- Precede each parameter map entry with a dollar sign (\$)
- Use a name that starts with an alpha character (a..z, A..Z)


Do not insert macros between existing quotation marks or square brackets because IBM Cognos Report Studio does not execute anything within these elements.

Tip: For a list of supported macro functions, see Appendix F, “Using the expression editor,” on page 575.

Procedure

1. To add a macro to an expression, in the Expression Editor, click the macros tab



2. Pause the pointer over the query explorer button  and click **Queries**.
3. If the query to which you are adding a macro was built by using your own SQL, do the following:
 - Click the **SQL** object that is linked to the query.
 - In the **Properties** pane, double-click the **SQL** property.
 - In the **SQL** dialog box, type the macro.
4. If the query to which you are adding a macro was not built by using your own SQL, do the following:
 - Click the query.
 - In the **Properties** pane, double-click the **Generated SQL/MDX** property.
 - In the **Generated SQL/MDX** dialog box, click **Convert**.
 - In the **SQL** dialog box, type the macro.

Creating Prompts Using Query Macros

You can create mandatory and optional prompts in reports using query macros.

Use the prompt macro functions `prompt` and `promptmany` to create single-value and multiple-value prompts. You can use prompt macro functions when working with a relational data source or a dimensionally-modeled relational (DMR) data source.

If you want to use a prompt macro in an expression such as a calculation, you must specify the data type when using an overloaded operator, such as a plus sign (+). You can use the plus sign to concatenate two items and to add two items.

If you want to define a filter on a dimension level and have the filter use the `prompt` or `promptmany` macro, you must provide the data type as `memberuniqueName` and a default value.

Here is an example:

```
members( [MS_gosales].[New Dimension].[PRODUCTLINE].[PRODUCTLINE])
  in ( set( #promptmany('what', 'memberuniqueName',
' [MS_gosales].[PROD1].[PRODUCTLINE].[PRODUCTLINE]
->[a11].[1]')# ) )
```

Here is an example of a mandatory prompt:

```
select
  COUNTRY_MULTILINGUAL.COUNTRY_CODE as COUNTRY_CODE,
  COUNTRY_MULTILINGUAL.COUNTRY as COUNTRY,
  COUNTRY_MULTILINGUAL."LANGUAGE" as LANGUAGE1,
  COUNTRY_MULTILINGUAL.CURRENCY_NAME as CURRENCY_NAME
from
  gosales.gosales.dbo.COUNTRY_MULTILINGUAL COUNTRY_MULTILINGUAL
where COUNTRY_MULTILINGUAL.COUNTRY = #prompt('CountryName')#
```

When default values are specified in the syntax of macro prompts, you may see an error. Use prompt syntax such as `where Country = ?Enter Country?`.

The `prompt` and `promptmany` functions have the following mandatory and optional parameters. All argument values must be specified as strings.

Name

This mandatory parameter is the name of the prompt. Name can also refer to the name of a parameter on a user-created prompt page, in which case the user-created prompt page appears when the report is run instead of the default prompt page that the macro would generate.

Datatype

This optional parameter is the prompt value data type. The default value is string. Prompt values are validated. In the case of strings, the provided value is enclosed in single quotation marks and embedded single quotation marks are doubled.

Values include the following:

- boolean
- date
- datetime
- decimal
- double
- float
- int
- integer
- interval
- long
- memberuniqueusername

Memberuniqueusername is not an actual data type. This value must be used when the data type of the parameter is member unique name (MUN).

- numeric
- real
- short
- string
- time
- timeinterval
- timestamp
- token

Token is not an actual data type. It is a way to pass SQL. A token does not pass values.

- xsddate
- xsddatetime
- xsddecimal
- xsddouble
- xsdduration
- xsdfloat
- xsdint
- xsdlong
- xsdshort
- xsdstring
- xsdtime

DefaultText

This optional parameter is the text to be used by default. If a value is specified, the prompt is optional.

If you use a space and no values are provided in the **Prompt Value** dialog box, a Where clause is usually not generated.

If you use text and no values are provided in the **Prompt Value** dialog box, a Where clause is usually generated using the default value.

Ensure that the text you provide results in a valid SQL statement.

Note: If the data type is memberuniquename, a value for the DefaultText parameter must be provided. For example:

```
(#prompt('WhichLevel', 'memberuniquename',  
'[goSalesAgain].[PRODUCT1].[PRODUCT].[PRODUCT(A11)]->[a11]')#)
```

Text

This optional parameter is text that precedes any user-provided values, such as 'and column1 = '.

QueryItem

This parameter is optional. The prompt engine can take advantage of the **Prompt Info** properties of the query item. Descriptive information can be shown, although the prompt value is a code.

TextFollowing

This optional parameter is the closing parenthesis that is used most often for the promptmany function. This parameter is also useful when the prompt is optional and is followed by hardcoded filters in the SQL statement.

Examples - selecting country or region prompts

When a report is run, you want your users to be prompted to choose the country or region for which they want to see data. The following code examples describe how you can use macros to create different prompts.

Mandatory prompt with no data type specified

Note the following:

- The Datatype argument is not specified. Therefore, it is a string, which is correct in this case.
- The DefaultText argument is not specified. Therefore, it is a mandatory prompt.

```
select  
  COUNTRY_MULTILINGUAL.COUNTRY_CODE as COUNTRY_CODE,  
  COUNTRY_MULTILINGUAL.COUNTRY as COUNTRY,  
  COUNTRY_MULTILINGUAL."LANGUAGE" as LANGUAGE1,  
  COUNTRY_MULTILINGUAL.CURRENCY_NAME as CURRENCY_NAME  
from  
  gosales.gosales.dbo.COUNTRY_MULTILINGUAL COUNTRY_MULTILINGUAL  
where COUNTRY_MULTILINGUAL.COUNTRY = #prompt('CountryName')#
```

Mandatory prompt with the data type specified

Note the following:

- This prompt requires a valid integer value as response.
- The `DefaultText` argument is not specified. Therefore, it is a mandatory prompt.

```
select
  COUNTRY_MULTILINGUAL.COUNTRY_CODE as COUNTRY_CODE,
  COUNTRY_MULTILINGUAL.COUNTRY as COUNTRY,
  COUNTRY_MULTILINGUAL."LANGUAGE" as LANGUAGE1,
  COUNTRY_MULTILINGUAL.CURRENCY_NAME as CURRENCY_NAME
from
  gosales.gosales.dbo.COUNTRY_MULTILINGUAL COUNTRY_MULTILINGUAL
where COUNTRY_MULTILINGUAL.COUNTRY_CODE >
  #prompt('Starting CountryCode',
    'integer',
    '',
    '',
    ''
  )#
  '[gosales].[COUNTRY_MULTILINGUAL].[COUNTRY_CODE]'
```

Optional prompt and mandatory filter with the data type and default value specified

Note the following:

- This prompt allows the user to supply a valid integer response.
- The `DefaultText` argument is specified. Therefore, the user may omit entering a value, in which case the value 10 is used. This makes it an optional prompt, but not an optional filter.

Example 1:

```
select
  COUNTRY_MULTILINGUAL.COUNTRY_CODE as COUNTRY_CODE,
  COUNTRY_MULTILINGUAL.COUNTRY as COUNTRY,
  COUNTRY_MULTILINGUAL."LANGUAGE" as LANGUAGE1,
  COUNTRY_MULTILINGUAL.CURRENCY_NAME as CURRENCY_NAME
from
  gosales.gosales.dbo.COUNTRY_MULTILINGUAL COUNTRY_MULTILINGUAL
where COUNTRY_MULTILINGUAL.COUNTRY_CODE >
  #prompt('Starting CountryCode',
    'integer',
    '10'
  )#
```

Example 2:

```
[gosales].[COUNTRY].[COUNTRY] = #prompt('countryPrompt','string','''Canada''')#
Result 2:
[gosales].[COUNTRY].[COUNTRY] = 'Canada'
```

Note the following:

- The `defaultText` parameter must be specified such that is literally valid in the context of the macro, because no formatting takes place on this value. See details below.
- The default string Canada in Example 2 is specified as a string using single quotes, in which the embedded single quotes are doubled up, thus 3 quotes. This results in the string being properly displayed within single quotes in the expression.
- As a general rule for the string datatype, the `defaultText` should always be specified as in the previous note, except in the context of a stored procedure parameter.

- For the defaultText of types date or datetime, a special format should be used in the context of SQL. Examples of these formats are 'DATE ''2012-12-25'' and 'DATETIME ''2012-12-25 12:00:00''. In all other contexts, you use the date/datetime without the keyword and escaped single quotes (e.g., '2012-12-25').

Prompt that appends text to the value

Note the following:

- The DefaultText argument is specified as a space character. In this case, the generated text is just the space character, which eliminates the Where clause from the query.
- The Text argument is specified, which is written into the generated SQL before the user-provided prompt value.

```
select
  COUNTRY_MULTILINGUAL.COUNTRY_CODE as COUNTRY_CODE,
  COUNTRY_MULTILINGUAL.COUNTRY as COUNTRY,
  COUNTRY_MULTILINGUAL."LANGUAGE" as LANGUAGE1,
  COUNTRY_MULTILINGUAL.CURRENCY_NAME as CURRENCY_NAME
from
  gosales.gosales.dbo.COUNTRY_MULTILINGUAL COUNTRY_MULTILINGUAL
#prompt('Starting CountryCode',
  'integer',
  ' ', // < = = this is a space
  'where COUNTRY_MULTILINGUAL.COUNTRY_CODE >'
)#
```

Syntax substitution

Note the following:

- The Datatype argument is set to token, which means that the user-provided value is entered without any checking on the provided value.
Because checking is not performed on the value, the expression editor may indicate that the expression is not valid. When a valid user-provided value is supplied or if you provide a valid default value, expression editor will interpret the expression as valid.
- Token should be used only if there is a list of pick-values for the user.
- The DefaultText argument is specified. Therefore, this is an optional prompt and group by COUNTRY is used in the generated SQL.

```
Select
  COUNTRY_MULTILINGUAL.COUNTRY_CODE as COUNTRY_CODE,
  COUNTRY_MULTILINGUAL.COUNTRY as COUNTRY,
  COUNTRY_MULTILINGUAL."LANGUAGE" as LANGUAGE1,
  COUNTRY_MULTILINGUAL.CURRENCY_NAME as CURRENCY_NAME
from
  gosales.gosales.dbo.COUNTRY_MULTILINGUAL COUNTRY_MULTILINGUAL
#prompt('Sort column',
  'token',
  'group by COUNTRY',
  'group by '
)#
```

Examples - creating prompts that use parameter maps

When a report is run, you want your users to select a language for the data in the report. The following examples describe several ways you can do this.

Prompt that uses session variables

Note the following:

- The name of the prompt is specified using a lookup in the parameter map named PromptLabels. The key value is the session variable \$language.
- The Where clause is using a parameterized column.

```
select
  ORDER_METHOD.ORDER_METHOD_CODE as ORDER_METHOD_CODE,
  ORDER_METHOD.ORDER_METHOD_#$language#
  as ORDER_METHOD_EN
from
  gosales.gosales.dbo.ORDER_METHOD ORDER_METHOD
#prompt($PromptLabels{$language},
  ' ',
  ' ',
  'where ORDER_METHOD.ORDER_METHOD_' + $language + '
>'
)#
```

A parameter map that nests prompts

Note the following:

- In the model, there is a parameter map DynPromptLabels with
#\$PromptLabels{\$language}#
- Part of the prompt information is run from a parameter map instead of being coded directly inside the SQL.
- The whole macro containing the prompt can be a value in a parameter map.

```
select
  ORDER_METHOD.ORDER_METHOD_CODE as ORDER_METHOD_CODE,
  ORDER_METHOD.ORDER_METHOD_#$language#
  as ORDER_METHOD_EN
from
  gosales.gosales.dbo.ORDER_METHOD ORDER_METHOD
#prompt($DynPromptLabels{'ex9'},
  ' ',
  ' ',
  'where ORDER_METHOD.ORDER_METHOD_' + $language + '
>'
)#
```

Examples - creating a multiple value prompt

When a report is run, you want your users to select one or more values. The following examples describe several ways you can do this.

Prompt with a required minimum

Note the following:

- The user must enter at least a single value.
- This resembles the first example on prompting for a country or region
“Mandatory prompt with no data type specified” on page 424.

```
select
  COUNTRY_MULTILINGUAL.COUNTRY_CODE as COUNTRY_CODE,
  COUNTRY_MULTILINGUAL.COUNTRY as COUNTRY,
  COUNTRY_MULTILINGUAL."LANGUAGE" as LANGUAGE1,
  COUNTRY_MULTILINGUAL.CURRENCY_NAME as CURRENCY_NAME
from
  gosales.gosales.dbo.COUNTRY_MULTILINGUAL COUNTRY_MULTILINGUAL
where COUNTRY_MULTILINGUAL.COUNTRY IN (#promptmany('CountryName')#)
```

Prompt with a required minimum with the data type specified

Note the following:

- This resembles the second example on prompting for a country or region “Mandatory prompt with the data type specified” on page 425.

```
select
  COUNTRY_MULTILINGUAL.COUNTRY_CODE as COUNTRY_CODE,
  COUNTRY_MULTILINGUAL.COUNTRY as COUNTRY,
  COUNTRY_MULTILINGUAL."LANGUAGE" as LANGUAGE1,
  COUNTRY_MULTILINGUAL.CURRENCY_NAME as CURRENCY_NAME
from
  gosales.gosales.dbo.COUNTRY_MULTILINGUAL COUNTRY_MULTILINGUAL
where COUNTRY_MULTILINGUAL.COUNTRY_CODE IN (
  #promptmany('Selected CountryCodes',
    'integer',
    ',',
    ',',
    ',')
  '[gosales].[COUNTRY_MULTILINGUAL].[COUNTRY_CODE]')#
)
```

Optional prompt with the data type and default value specified

The In clause and both parentheses are part of the SQL statement.

```
select
  COUNTRY_MULTILINGUAL.COUNTRY_CODE as COUNTRY_CODE,
  COUNTRY_MULTILINGUAL.COUNTRY as COUNTRY,
  COUNTRY_MULTILINGUAL."LANGUAGE" as LANGUAGE1,
  COUNTRY_MULTILINGUAL.CURRENCY_NAME as CURRENCY_NAME
from
  gosales.gosales.dbo.COUNTRY_MULTILINGUAL COUNTRY_MULTILINGUAL
where COUNTRY_MULTILINGUAL.COUNTRY_CODE IN (
  #promptmany('Selected CountryCodes',
    'integer',
    '10'
  )#
)
```

Prompt that adds text before the syntax

Note the following:

- This example uses the TextFollowing argument.

```
select
  COUNTRY_MULTILINGUAL.COUNTRY_CODE as COUNTRY_CODE,
  COUNTRY_MULTILINGUAL.COUNTRY as COUNTRY,
  COUNTRY_MULTILINGUAL."LANGUAGE" as LANGUAGE1,
  COUNTRY_MULTILINGUAL.CURRENCY_NAME as CURRENCY_NAME
from
  gosales.gosales.dbo.COUNTRY_MULTILINGUAL COUNTRY_MULTILINGUAL
#promptmany('Selected CountryCodes',
  'integer',
  ' ', // < = = this
  'where COUNTRY_MULTILINGUAL.COUNTRY_CODE IN
( ',
  ',',
  ' )'
)#
```

Optional prompt that adds text before the syntax

```
Select
  COUNTRY_MULTILINGUAL.COUNTRY_CODE as COUNTRY_CODE,
  COUNTRY_MULTILINGUAL.COUNTRY as COUNTRY,
  COUNTRY_MULTILINGUAL."LANGUAGE" as LANGUAGE1,
```

```

COUNTRY_MULTILINGUAL.CURRENCY_NAME as CURRENCY_NAME
from
gosales.gosales.dbo.COUNTRY_MULTILINGUAL COUNTRY_MULTILINGUAL,
gosales.gosales.dbo.COUNTRY_XX
where COUNTRY_MULTILINGUAL.COUNTRY_CODE = XX.COUNTRY_CODE
#promptmany('Selected CountryCodes',
            'integer',
            ', ',
            ' and COUNTRY_MULTILINGUAL.COUNTRY_CODE IN (',
            ' ',
            ')')
)#

```

Chapter 19. Using Drill-through Access

Using drill-through access, you can move from one report to another within a session while maintaining your focus on the same piece of data. For example, you select a product in a sales report and move to an inventory report about that product.

Drill-through access helps you to build business intelligence applications that are bigger than a single report. Drill-through applications are a network of linked reports that users can navigate, retaining their context and focus, to explore and analyze information.

Drill-through access works by defining the target report or object and then using information from the source report to filter the target. IBM Cognos BI can match data from the source to metadata in the target report, or you can define parameters in the target for greater control.

Note: In the dimensional reporting style, you can also enable drilling up and drilling down. For more information about drilling up and drilling down, see “Create a Drill-up and Drill-down Report” on page 322.

What You Should Know

For a drill-through link to work, it is necessary to know

- the source
- the target
- how the data in the packages that contain these objects is related

Depending on the underlying data, you may create a drill-through definition and have IBM Cognos BI match the data (dynamic drill-through) or create parameters in the target (parameterized drill-through).

- whether to run the target report or to open it

The target of drill-through access is usually a saved report definition. The report can be created in IBM Cognos Report Studio, IBM Cognos Query Studio, IBM Cognos PowerPlay Studio, or IBM Cognos Analysis Studio. The target of drill-through access can also be a package that contains an IBM Cognos PowerCube, in which case a default view of the PowerCube is created.

- whether the users of the drill-through link in the source report have the appropriate permissions to view or run the target report
- if the target is being run, in what format to run it, and what filters to use on the target

If you do not want to run the target report on demand, you may link to a bookmark in the saved output instead of running the report. For more information, see the IBM Cognos Business Intelligence *Administration and Security Guide*.

Sources and Targets

In IBM Cognos BI, there are many different examples of source and target. For example, you can drill through

- between reports created in different packages against different data source types, such as from an analysis against a package that contains a PowerCube to a detailed report against a package based on a relational data source
- from one existing report to another report using definitions created in Report Studio
- between IBM Cognos Viewer reports authored in Report Studio, Query Studio, and Analysis Studio
- to and from a package built on a PowerCube
- from IBM Cognos Series 7 to IBM Cognos BI reports
- from Metric Studio to other IBM Cognos BI reports by passing parameters using URLs

For more information, see the IBM Cognos Metric Studio *User Guide*.

Tip: In the GO Data Warehouse (analysis) package, the Positions to Fill sample report is a drill-through target report and the Recruitment Report sample report is a drill-through source report. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Understanding Drill-through Concepts

Before you set up drill-through access, you must understand the key concepts about drilling through. Knowing these concepts will help you to avoid errors so that report consumers drill through as efficiently as possible.

Drill-through Paths

You can create a drill-through path in a source report in IBM Cognos Report Studio, or using Drill-through Definitions in IBM Cognos Connection. A drill-through path is the definition of the path that is taken when moving from one report to another, including how the data values are passed between the reports.

Using **Drill-through Definitions**, you can create a drill-through path from any report in the source package to any target report in any other package in IBM Cognos Connection. This type of drill-through definition is stored in the source package. Users of any report in the package can use the drill-through definition to drill between any combination of IBM Cognos Analysis Studio, IBM Cognos Query Studio, IBM Cognos PowerPlay Studio, or IBM Cognos Viewer reports in any package.

For any target report that contains parameters, you should map the target parameters to the correct metadata in the drill-through path. This ensures that the values from the source report are passed to the correct parameter values, and that the target report is filtered correctly. If you do not map parameters, then the users may be prompted for values when the target report is run.

A report-based drill-through path refers to a path created and stored in a Report Studio source report. This type of drill-through path is also called authored drill through. The path is associated with a specific data column, chart, or cross tab in the source report, and is available only when users select that area of the report. If an authored drill-through definition is available, a hyperlink appears in the source report when it is run.

Report-based drill-through is limited to Report Studio source reports and any target reports. Use this type of drill-through access when you want to pass data

item values or parameter results from within a source report to the target report, pass the results of a report expression to a target report, or a use URL link as a part of the drill-through definition.

Selection Contexts

The selection context represents the structure of the values selected by the user in the source.

In IBM Cognos Analysis Studio, this includes the context area. When a package drill-through definition is used, the selection context is used to give values for mapped parameters (parameterized drill-through) or also to map the appropriate data items and values.

Drill-through links can also be defined to open the target object at a bookmark. The content of this bookmark may also specified by the selection context.

Drill-through access is possible between most combinations of the IBM Cognos Business Intelligence studios. Each studio is optimized for the goals and skills of the audience that uses it, and in some cases for the type of data source it is designed for. Therefore, you may need to consider how the various studios manage the selection context when you drill through between objects created in different studios, and how the data sources are conformed. During testing or debugging, you can see how source values are being mapped in different contexts using the drill-through assistant.

Drilling Through to Different Report Formats

The settings in the drill-through definition determine the format in which users see the report results.

For example, the users may see the reports in IBM Cognos Viewer as an HTML Web page, or the reports may open in IBM Cognos Query Studio, IBM Cognos PowerPlay Studio, or IBM Cognos Analysis Studio. If your users have PowerPlay Studio, then they may also see the default view of a PowerCube.

Reports can be opened as HTML pages, or as PDF, XML, CSV, or Microsoft Excel spreadsheet software formats. When you define a drill-through path, you can choose the output format. This can be useful if the expected use of the target report is something other than online viewing. If the report will be printed, output it as PDF; if it will be exported to Excel for further processing, output it as Excel or CSV, and so on.

To run reports, or drill to targets that run reports in the delimited text (CSV), PDF, Microsoft Excel spreadsheet (XLS), or XML output formats, users require the generate output capability for the specific format.

If you define a drill-through path to a report that is created in Analysis Studio, PowerPlay Studio, or Query Studio, consumers can open the report in its studio instead of in IBM Cognos Viewer. This can be useful if you expect a consumer to use the drill-through target report as the start of an analysis or query session to find more information.

For example, if an application contains a dashboard style report of high-level data, you can define a drill-through link to Analysis Studio to investigate items of interest. The Analysis Studio view can then be drilled through to a PDF report for printing.

Note: IBM Cognos Report Studio does not display data results.

Drilling Through Between Packages

You can set up drill-through access between packages.

The two packages can be based on different types of data source, but there are some limits. The following table shows the data source mappings that support drill-through access.

Table 8. Data source mappings that support drill-through access

Source data source	Target data source
OLAP	OLAP Note: OLAP to OLAP drill through is supported only if the data source type is the same, for example, SSAS to SSAS.
OLAP	Dimensionally modeled relational
OLAP	Relational data Note: For more information, see “Business Keys” on page 437.
Dimensionally modeled relational	Dimensionally modeled relational
Dimensionally modeled relational	Relational
Relational	Relational

Bookmark References

When you drill through, the values that you pass are usually, but not always, used to filter the report. IBM Cognos Business Intelligence supports bookmarks within saved PDF and HTML reports so that a user can scroll a report to view the relevant part based on a URL parameter.

For example, you have a large inventory report scheduled to run daily or weekly during off hours because of resource considerations. Your users may want to view this report as a target because it contains detailed information, but you want them to view the saved output rather than run this large report. Using this Action option and bookmark settings, users can drill through from another source location based on products to open the saved report to the page that shows the product they want to focus on.

When a bookmark in the source report is used in a drill-through definition, it provides the value for the URL parameter. When report consumers drill through using this definition, they see the relevant section of the target report.

Bookmark references are limited to previously run reports that are output as PDF or HTML and contain bookmark objects.

Members and Values

Dimensionally modeled data, whether stored in cubes or stored as dimensionally modeled relational (DMR) data, organizes data into dimensions. These dimensions contain hierarchies. The hierarchies contain levels. And the levels contain members.

An example of a dimension is Locations. A Locations dimension may contain two hierarchies: Locations by Organization Structure and Locations by Geography. Either of these hierarchies may contain levels like Country or Region and City.

Members are the instances in a level. For example, New York and London are members in the City level. A member may have multiple properties, such as Population, Latitude, and Longitude. Internally, a member is identified by a Member Unique Name (MUN). The method by which a MUN is derived depends on the cube vendor.

Relational data models are made up of data subjects, such as Employees, which are made up of data items, such as Name or Extension. These data items have values, such as Peter Smith.

In IBM Cognos Business Intelligence, the methods of drilling through available are

- Dimensional (member) to Dimensional (member)
- Dimensional (member) to Relational (data item value)
- Relational (data item value) to Relational (data item value)

If the target parameter is a member, the source must be a member. The source and target should usually be from a conformed dimension. However, if the data supports it, you may also choose to define a mapping using different properties of the source metadata item.

If the target parameter is a value, the source can be either a value or a member. If the source is a dimensional member, you must ensure that the level or dimension is mapped to the target data item correctly in the drill-through definition. The business key from which the member is sourced should usually match the relational target value, which is most often the business key. However, if the data supports it, you may also choose to define a mapping from the caption of the source metadata item.

Member Unique Names

The member unique name (MUN) is a unique identifier for a member in IBM Cognos reports. It is stored in the report specification when the member is referenced in the report directly.

The MUN is used in drill-through between OLAP data sources. The member keys in the MUN for the different OLAP data sources must match.

The MUN is used to find the member in the data source, which is similar to how business keys are used to find records in a table. For example, when you create OLAP dimension Products, you use the Product Line database column as a label for the members in your Product Line level. However, you use the Product Line Code business key from the database table to ensure that all the Product lines are unique in that level. The source value that you used to create the members is used in combination with the data source name, hierarchy, and level information in the member unique name.

If the MUN changes, members that are directly referenced in expressions, filters, or reports are no longer found. Changes to the MUN may be related to other changes. For example, changes to the hierarchy and level structures may change the level unique name, and changes to the business key values may change the member key path. Other factors that can affect the MUN are application changes during the design stage or over time, IBM Cognos PowerCube category codes that are

unpredictably unique, the production environment that has more members than the test environment, or removing the member from the data source.

To avoid potential problems, we recommend the following best practices when you build OLAP data sources:

- Use unique codes and keys within a dimension for the member keys.
- Define your OLAP and relational packages using unique conformed values for the source values (business keys) within similar dimensions or data values where drill-through between applications may be required.
- Ensure that the business keys and dimension metadata structure are the same in the production and test environments.
- Do not change the business keys in IBM Cognos Framework Manager in the production environment.
- Resolve the non-unique keys in a dimension in the data source before you build the cube.

Ensure that there are no duplicate source values in all levels of a dimension before you build a PowerCube. We do not recommend using the tilde character (~) in the category codes.

For more information, see the section about uniqueness in the IBM Cognos Series 7 *Step-by-Step Transformer*.

For information about PowerCubes migrated from IBM Cognos Series 7, see the IBM Cognos PowerPlay *Migration and Administration Guide*.

Conformed Dimensions

If you work with more than one dimensional data source, you may notice that some dimensions are structured the same, and some are not.

The reason that dimensions can be structured differently is that the data sources may serve different purposes.

For example, a Customer dimension appears in a Revenue data store, but not in an Inventory data store. However, the Products dimension and the Time dimension appear in both data stores.

Dimensions that appear in multiple data stores are conformed if their structure is identical for all of the following:

- hierarchy names
- level names
- level order
- internal keys

Drilling through is possible between different dimensional data stores only if the dimensions are conformed, and if the dimension data store is of the same vendor type, such as IBM Cognos PowerCube as the source and the target. For example, in two data stores for Revenue and Inventory that contain Products and Time dimensions, it is possible to define the Products and Time dimensions differently for each data store. However, for drill-through between the Products and Time dimensions to work, their structures must be identical in each data store.

If you are not sure whether your dimensions are conformed, then you should check with the data modeler to ensure that the drilling through will produce meaningful results.

IBM Cognos Business Intelligence does not support conformed dimensions generated by IBM Cognos Framework Manager for SAP BW data sources.

Dimensionally modeled Relational Data Sources

Ensure that each level contains a business key that has values that match your PowerCube or other DMR models. Also, you must also ensure that the **Root Business Key** property is set and uses the business key of the first level in the hierarchy. This helps to ensure that you have a conformed member unique name when attempting to drill through using members from this dimension.

Related concepts:

“Data Does Not Appear in a Target Report or the Wrong Data Appears” on page 514

If no data appears when you drill through to a target report or if the wrong data appears, the problem might be data source conformance. The business keys might be different or might be mismatched.

Related tasks:

“Unexpected or Empty Results When Drilling Through” on page 521

When you drill from a source report to a target report, there might be no data returned. This might be the correct result if there is no data that corresponds to the drill-through selections or if you do not have permission to view the data.

Business Keys

When drill-through access is defined from a member to a relational value, the business key of the member is passed by default.

This means that your relational target parameter must be set up using the data item with a matching value, which is most often the business key data item. You can also choose to pass the caption of the source metadata item.

For example, employees are usually uniquely identified by an employee number, not by their name, because their name is not necessarily unique. When you drill through from a dimensional member to a relational data item, the value provided is the business key. Therefore, the parameter in the target report must be defined to accept a business key value. The exact logic used to define the business key value supplied depends on the cube vendor. For IBM Cognos PowerCubes, the business key value is the **Source** property defined for the level in IBM Cognos Transformer. IBM Cognos Series 7 Transformer PowerCubes pass the source value if the drill-through flag was enabled before the cube was built. Otherwise, the category code is used.

In IBM Cognos Report Studio, you can determine what the member business key is using an expression such as `roleValue('_businessKey',[Camping Equipment])`. This expression is case-sensitive.

SSAS 2005 multipart business keys are not supported in drill-through operations.

Tip: When other users run your drill-through report, you may not want them to be prompted for a business key. In Report Studio, you can build a prompt page with a text that is familiar to the users, but filters on the business key. Your IBM Cognos Framework Manager modeler can also set the **Display Item Reference** option for the **Prompt Info** property to use the business key when the data item is used in a prompt.

Related concepts:

“Data Does Not Appear in a Target Report or the Wrong Data Appears” on page 514

If no data appears when you drill through to a target report or if the wrong data appears, the problem might be data source conformance. The business keys might be different or might be mismatched.

Related tasks:

“Unexpected or Empty Results When Drilling Through” on page 521

When you drill from a source report to a target report, there might be no data returned. This might be the correct result if there is no data that corresponds to the drill-through selections or if you do not have permission to view the data.

Scope

Scope is specific to drill-through definitions created using Drill-through Definitions in IBM Cognos Connection (package drill-through definitions). The scope you set defines when the target report is shown to the users, based on the items they have in the source report.

Usually, you define the scope of a drill-through path to match a parameter that it passes. For example, if a target report contains a list of employees, typically you want to display the report as an available drill-through choice only when a user is viewing employee names in a source report. If employee names are not in the source report and the scope was set on the employee name in the drill-through definition, the employee report does not appear on the list of available drill-through target reports in the **Go To** page. You can set the scope to a measure or to an item in the report.

In report-based drill-through access, where the drill-through path is associated with a specific report column, the column serves as the scope.

Mapped Parameters

Drill-through targets may contain existing parameters or you can add parameters to the target for greater control over the drill-through link.

You usually map all parameters in a drill-through target to items from the source.

When you map source items that are OLAP or DMR members to target parameters, you can select from a set of related member properties to satisfy the requirements of the target parameter. For a dimensional target, a dimensional source item uses the member unique name by default. For a relational target, a dimensional source item uses the business key by default.

For example, you could change the source member property that is used for a mapping to the member caption instead of the business key to match the parameter in a relational target. For a dimensional target, you could define a parameter that accepts a particular property (such as business key or parent unique name), then pass the appropriate source property to satisfy that target.

Note: If you define drill through between non-conformed dimensions, you should test carefully to ensure that the results behave as expected.

If you do not specify parameter mappings, then by default, you will be prompted for any parameters required in the target when you use the drill-through link. To customize this behavior, use the display prompt pages setting.

When the action is set to **Run using dynamic filtering**, then additional filtering is applied if names from the context in the source report match names of items in the target. Use this action as well when there are no parameters defined in the target.

If parameters are not mapped correctly, then you may receive an empty report, the wrong results, or an error message.

The source and target cannot contain identical parameter names when they are from different packages, even if the data structure is conformed. If the source and target are from the same package, there is no restriction.

If you have the necessary permissions, you can use the drill-through assistant to look at what source parameters are passed, and what target parameters are mapped for a given drill-through link.

You can change the dynamic drill-through filter behavior if you want drill-through to generate a filter using the Member Business Key instead of the default Member Caption. For more information, see *Changing Drill-Through Filter Behavior* in the *IBM Cognos Administration and Security Guide*.

Drilling Through on Dates Between PowerCubes and Relational Packages

The usual method of drilling through from OLAP to relational packages requires that the target report parameter is set using the business key in the relational data, which does not work well for dates.

OLAP data sources typically view dates as members, such as Quarter 1 2012, while relational data sources view dates as ranges, such as 1/Jan/2012 to 31/March/2012.

A special feature exists for drilling through between PowerCubes and relational packages. Ensure that the target report parameter is set up using `in_range`. The parameter must be of type date-time, and not integer.

An example follows:

```
[gosales_goretailers].[Orders].[Order date] in_range ?Date?
```

Also ensure that the drill-through definition maps the parameter at the dimension level and that the PowerCube date level is not set to suppress blank categories. Enabling the option to suppress blank categories in the Transformer model before you build the cube may cause the drill-through on dates to be unsuccessful. This happens because there are missing values in the range.

Set Up Drill-through Access in a Report

Set up drill-through access in a source report to link two reports containing related information.

You can then access related or more detailed information in one report (the target) by selecting one or more data item values from another report (the source). IBM Cognos passes values from the source to the target and uses the passed values to filter the target object. If the data in the source and target is conformed or if the data item names are the same, then the system may map the source values to filter the target (dynamic drill-through). If you require greater control, you may define parameters in the target object (parameterized drill-through).

For instructions about creating parameters in other kinds of targets, see the IBM Cognos Business Intelligence *Administration and Security Guide*.

When you define the drill-through path in IBM Cognos Report Studio, you can pass a value from a different data item that is hidden from the user for display purposes but still in the query. For example, users see the Product Name data item and can drill through on that item, but the drill-through definition passes the Product Number value for the product name the user chose. You can also define the target parameter to accept multiple values or a range of values from the data item in the drill-through source report or to accept a value from a parameter in the source report.

Drill-through definitions that have been authored inside a Report Studio report appear in the source report as blue underlined links. Users click the hyperlink to select the value they want passed to the target and to drill through to the target report. If a user selects multiple items within a single column then when the drill-through target report is run, the values from each selected row are passed to the target parameters. This occurs as an *and* condition.

You can also drill through within the same report by creating bookmarks. As well, you can create drill-through definitions in the source package instead of the Report Studio report. Users can use package drill-through definitions to navigate to a target report from an IBM Cognos Analysis Studio analysis, an IBM Cognos Query Studio report, an IBM Cognos PowerPlay Studio report or IBM Cognos PowerCube package, or a Report Studio report. For more information, see the *Administration and Security Guide*.

If you have the IBM Cognos Software Development Kit, you can use URLs to set up drill-through access to and from third-party sources.

You can also drill through from a map.

Related concepts:

“Example - Creating Drill-through Access in a Legacy Chart” on page 158

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a chart that shows the revenue for each product line and allows the reader to drill through from the revenue chart to view the product details for any item selected. You create a drill-through report to link two reports containing related information. You can then access related or more detailed information in one report by selecting a value in the chart. You create two reports: a target list report that contains the details for the item and a source report that contains the chart that shows the product line revenue.

Create a parameter in the target

Set up drill-through access in a source report to link two reports containing related information. You can then access related or more detailed information in one report (the target) by selecting one or more data item values from another report (the source).

If you are using an SAP BW data source for the target report and the target report contains a variable for a hierarchy node, values from the source report can be values only of the data item representing the leaf-level identifier of the hierarchy.

Before you begin

Before you begin, ensure that you have a report that will serve as the source report and another report that will serve as the target report.

Procedure

1. In IBM Cognos Report Studio, open the target report.
2. Create a parameter that will serve as the drill-through column or that will filter the report.

For example, to drill through or filter Product line, create the following parameter:

```
[Product line]=?prodline_p?
```

Tip: Use the operators `in` or `in_range` to enable the target report to accept multiple values or a range of values.

3. In the **Usage** box, specify what to do when a value for the target parameter is not passed as part of a drill through:

- To specify that users must select a value, click **Required**.

If a value for the target parameter is not passed, users are prompted to choose a value.

- To specify that users do not need to select a value, click **Optional**.

Users are not prompted to choose a value and so the value is unfiltered.

- To specify not to use the parameter, click **Disabled**.

The parameter is not used during the drill-through. It will also not be used in the report for any other purposes.

Tip: If the parameter is needed in the report for other reasons, then you can also specify not to use it in the drill-through definition (**Parameters** table, **Method**, **Do not use parameter**).

Create a drill-through definition

Create a drill-through definition to link two reports containing related information (the source report and the target report).

Drill-through definitions that have been authored inside an IBM Cognos Report Studio report appear in the source report as blue underlined links. Users click the hyperlink to select the value they want passed to the target and to drill through to the target report. If a user selects multiple items within a single column then when the drill-through target report is run, the values from each selected row are passed to the target parameters. This occurs as an *and* condition.

Before you begin

Before you begin, ensure that you have a report that will serve as the source report and another report that will serve as the target report.

Procedure

1. Check the drill-through target:
 - Confirm that the drill-through users have access to the target.
 - If necessary, check what parameters exist in the target.
2. Open the source report.

3. Click the element in the report that will serve as the starting point for the drill-through link.

You can select a data item that your report users are likely to choose to drill on for more detailed information, such as an Employee Name data item.

Tip: If you are passing only parameter values to the target report, you do not have to drill on a data item. Instead, you can drill on any object in the report, such as the report title. Therefore, you can drill from outside the context of a query.

4. Click the drill-through definitions button, or, from the **Properties** pane, double-click the **Drill-Through Definitions** property.
5. Click the new drill-through definition button.

A drill-through definition is created.

Tip: To change the drill-through name, click the rename button, type the new name, and click **OK**.

6. On the **Target Report** tab, click the ellipsis button next to the **Report** box and select the drill-through target report.
7. In the **Action** box, decide how users will view the target report when they click the drill-through link in the parent report:

- To view the latest data in IBM Cognos Viewer, select **Run the report**.
- To edit an IBM Cognos Query Studio, IBM Cognos Analysis Studio, or IBM Cognos PowerPlay Studio target, select **Edit the report**.
- To have IBM Cognos Business Intelligence match values from the selection context with data in the target (dynamic filtering), select **Run the report using dynamic filtering**.

Note: If you chose this option, any parameters in the target report are still used for the drill-through access.

- To view the most recently saved output version of the target report from IBM Cognos Connection, select **View the most recent report**.
 - To use the default action specified for the report in IBM Cognos Connection, select **(Default)**.
8. If the target report contains parameters, then, under the **Parameters** box, click the edit button.

Each required and optional parameter defined in the target report appears in the **Parameters** dialog box.

9. For each parameter, specify the **Method** of treatment:

- To specify not to pass any value, click **(Default)**.
- To specify not to use this parameter, click **Do not use parameter**.
The target report will not be filtered by this parameter.
- To pass values from a data item, click **Pass data item value**, click **Value**, and then click the data item.
Values for the selected data item are passed to the target report.
- To pass values from a source report parameter, click **Pass parameter value**, click **Value**, and then click the parameter.
Values for the selected parameter are passed to the target report.
- If you choose to pass parameters, and the source report is based on a dimensional package, then click an item from the drop-down list in the

Source metadata item properties column. You can pass the default property of the source metadata item (business key) or another property, such as the member caption.

10. Click **OK**.
11. If you chose to run the target report, in the **Format** box, click the output format for your report.

Tip: Click **(Default)** to run the report using the default format specified for the report in IBM Cognos Connection.

12. To open the target report in a new window, select the **Open in new window** check box.
13. In the **Display prompt pages** box, choose how to display prompt pages:
 - To always display prompt pages when the drill-through action occurs regardless of whether values were specified for the required parameter values, click **Always**.
 - To use the prompt settings of the target report (specified by the **Prompt for Values** check box in IBM Cognos Connection, **Report Properties**, **Report** tab) to determine whether to show the prompt pages, click **Based on the default prompt settings of the target report**.
 - To not display prompt pages when the required parameter values are provided by the drill-through definition, click **Only when required parameter values are missing**. This is the default setting.

Results

The drill-through text appears as a blue hyperlink in text items in the non-chart areas of the report. Report consumers can also start the drill-through action by clicking the **Go To** button or by right-clicking the item and clicking **Go To, Related links**. If you have the necessary permissions, you can view which parameters were passed from the source and how they are mapped in the target object from the **Go To** page using the drill-through assistant.


For more information, see the *Administration and Security Guide*.

Defining independent drill-through definitions for crosstabs


By default, you can create only one drill-through definition for fact cells in a crosstab, regardless of how many facts there are. This topic describes how to define different drill-through definitions for different measures in crosstab fact cells.

For example, a crosstab has Quantity and Revenue as measures. For the Quantity cells, you want to define a drill-through definition to a target report that contains more information about quantities sold. For the Revenue cells, you want to define a drill-through definition to a different target report that shows details about revenue generated.

Procedure

1. Open the source report.
2. On the toolbar, click the unlock icon .
3. In the crosstab, click the white space inside one of the fact cells of the measure for which you want to define a drill-through definition.

Do not click the measure text. You want to select the crosstab intersection and not the text item. In the **Properties** pane title bar, ensure that **Crosstab Intersection** appears.

4. In the **Properties** pane, set the **Define Contents** property to **Yes**. The text item in the crosstab intersection disappears.
5. Click the **Data Items** tab .
6. From the crosstab query, drag the measure that disappeared in step 4 to the empty crosstab intersection.
7. Right-click the measure in the crosstab intersection and then click **Drill-Through Definitions**.
8. Create the drill-through definition.

Results

A drill-through definition is defined for the selected measure. Repeat the steps to define different drill-through definitions for other measures in the crosstab. When users run the report, clicking values from different measures takes them to a different target report.

Specify the Drill-through Text

You can specify the drill-through text that appears when users can drill through to more than one target.

For example, if users from different regions view the report, you can show text in a different language for each region.

Procedure

1. Right-click the drill-through object and click **Drill-Through Definitions**.
2. If more than one drill-through definition exists for the object, in the **Drill-Through Definitions** box, click a drill-through definition.
3. Click the **Label** tab.
4. To link the label to a condition, in the **Condition** box, do the following:
 - Click **Variable** and click an existing variable or create a new one.
 - Click **Value** and click one of the possible values for the variable.
5. In the **Source type** box, click the source type to use.
6. If the source type is **Text**, click the ellipsis button that corresponds to the **Text** box and type text.
7. If the source type is **Data Item Value** or **Data Item Label**, click **Data Item** and click a data item.
8. If the source type is **Report Expression**, click the ellipsis button that corresponds to the **Report Expression** box and define the expression.
9. If the label is linked to a condition, repeat steps 5 to 8 for the remaining possible values.

Results

When users run the source report and click a drill-through link, the **Go to** page appears. The drill-through text you specified appears for each target. If you did not specify the drill-through text for a target, the drill-through name is used.

Example - Drill Through to a Hidden Report from a Report Studio Report

You want to set up a drill-through link from an employee satisfaction report created in IBM Cognos Report Studio to a hidden list report about compensation, also created in Report Studio.

The source report (**Employee Satisfaction 2012**) is based on the package GO Data Warehouse (analysis) which is modeled on a DMR data source. The target report (**Compensation (hidden)**) is based on the package GO Data Warehouse (query). You set up this drill-through connection from within Report Studio (report-based, or authored drill through) because you do not want to make a report about compensation available for drill through from any source report in the package. The target report is already hidden in the portal, so that it is unlikely to be run by anyone who does not use the drill through link.

You must have the IBM Cognos Business Intelligence samples from the deployment zip file IBM_Cognos_DrillThroughSamples installed to follow this exercise, and you must have access to Report Studio.

The **Compensation** report is a hidden report. You may be able to set whether hidden reports are visible (**My Preferences, General** tab) and whether you can hide reports. This capability is set by your administrator.

Check the Target Report

Check the target report to make sure the drill-through will work.

Procedure

1. Open the target report:
 - In IBM Cognos Connection, go to **Public Folders, Samples, Models, GO Data Warehouse (query), Report Studio Report Samples**.
 - Locate the report **Compensation (hidden)** and open it in Report Studio.

Tip: If you do not see the report, go to IBM Cognos Connection and confirm that you can view hidden reports (**My Preferences, General** tab).

2. In Report Studio, from the **Data** menu, click **Filters** and check what filter parameters are available.

You want to filter from the source report on department, not time, so you will only use the **pPosition** parameter in the drill-through definition.

3. In the report body, select the list column body **Position-department (level 3)** and review the data item properties.

Because the drill-through definition goes from DMR to relational, the data item values will need to match.

4. Close the **Compensation (hidden)** report.

Create and Test the Drill-Through Definition

Create and test the drill-through definition to make sure it works.

Before you begin

To run reports, or drill to targets that run reports in the delimited text (CSV), PDF, Microsoft Excel spreadsheet (XLS), or XML output formats, you require the

generate output capability for the specific format.

Procedure

1. Open the source report:
 - In IBM Cognos Connection, go to **Public Folders, Samples, Models, GO Data Warehouse (analysis), Report Studio Report Samples**.
 - Locate the **Employee Satisfaction 2012** report and open it in Report Studio.
2. Save the **Employee Satisfaction 2012** report with a new name, such as **Employee Satisfaction 2012 New**.

This is to keep the original report and drill-through definition intact for comparison.
3. In the table **Employee rankings and terminations by department**, select the column **Position-department (level 3)**.
4. In the properties pane, review the data item properties, to confirm that the data item names match values in the target report.
5. In the properties pane, under **Data**, double-click **Drill-through definitions**.
6. Select the definition **DrilltoHiddenRep** and delete it.

Note: In the following steps, you recreate the drill-through definition. For comparison, use the original sample report.
7. In the **Drill-through Definitions** box, click the new drill-through definition button.
8. Click the rename button, and type a name for the drill-through definition.

Tip: This is the name that consumers see when they select from a list of possible drill-through definitions in the final report.
9. In the **Target Report** tab, select the target report:
 - Under **Report**, click the ellipsis button.
 - Navigate to **GO Data Warehouse (query), Report Studio Report Samples**, and select the **Compensation (hidden)** report.

Tip: If you do not see the report, go to IBM Cognos Connection and confirm that you can see hidden reports (**My Preferences, General** tab).
10. Under **Action**, select **Run the report**.
11. Under **Parameters**, click the edit button.

A table of parameters available in the target report appears, showing the parameter **pPosition**.
12. Map the parameter from the **Compensation (Hidden)** report to the metadata in the **Employee Satisfaction 2012** report:
 - In the **Method** column, select **Pass data item value**, because the target report is based on a relational data source.
 - In the **Value** column, select **Position-department (level 3)**.

Tip: In this report, you pass values from the column where the drill-through is defined. In other cases, you might pass a related parameter. For example, you could drill through on employee name, but pass the employee number.
13. Save the report.
14. Run the report, and click a department to test the drill-through definition.

Results

When you test the drill-through link, the **Compensation (hidden)** report appears, filtered by the department you selected. The report appears as a drill-through target whether or not it is hidden in IBM Cognos Connection.

If your administrator has given you the **Drill Through Assistant** capability, then you can see additional information you right-click on the link and select **Go To** to see a list of drill-through targets. From the **Go To** page, you can see what source values are passed, and what target parameters are mapped.

Try it yourself - create a report with drill-through access to itself

You can create a report that drills through to itself so that users can view detailed information in the same report.

In this topic, you learn how to create a report that shows revenue by each retailer. Users can access detailed order information for a particular retailer.

It should take 20-25 minutes to complete this topic, and your report will look like this.

<u>Order Details: All Retailers</u>	
Retailer name	Revenue
1 for 1 Sports shop	6,432,250.32
4 Golf only	5,015,375.54
4 Your Eyes	873,022.36
Aarhus Sport	5,999,906.89
Accapamento	6,077,377.8
Accesorios Importados, S.A. de C.V.	7,945,373.51
AcquaVerde	12,696,927.89
ActiForme	2,005,590.67
Action Factory	8,613,520.15
Act'N'Up Fitness	13,661,733.09
Acute Sight	1,662,290.71
Advanced Climbing Ltd	1,008,869.51
Air frais	3,225,980.69
Air marin	8,248,477.5
Aktiv Markt	16,262,466.37
Aktive Freizeit	558,286.8
Aktive Markt	12,013,789.68
Algonquin Camping Supplies	12,105,107.18
All Season Camping Goods	6,133,822.91
All'aperto esperienza	6,756,555.8

Select a retailer in the Retailer list to view order details
No Data Available

Figure 62. A report with drill-through access to itself

Procedure

1. Create a new blank report that uses the **GO Data Warehouse (query)** package.
2. Add a table with two columns and one row.
3. Add a list object to each column in the table.
4. Open **Sales and Marketing (query)**, then open **Sales (query)**. Add these data items to the first list:
 - **Retailer name** in **Retailers**
 - **Revenue** in **Sales fact**

Tip: Use the **Source** tab .

5. Set the sort order for the **Retailer name** column to **Sort Ascending**.
6. Add these data items to the second list:
 - **Retailer name** in **Retailers**
 - **Order number** in **Sales order**
 - **Date** in **Time**
 - **Product** in **Products**
 - **Quantity** in **Sales fact**
 - **Revenue** in **Sales fact**

Tip: To simultaneously add all the data items to the list, Ctrl+click the items before dragging them to the list.

7. In the second list, select the **Retailer name** list column and in the **Properties** pane, set its **Render** property to **No**.
8. In the second list, create the following parameterized filter:
[Retailer name]=?Selected retailer?
9. Save the report.
10. In the left list, right-click the **Retailer name** column (and not the column title) and click **Drill-Through Definitions**.
11. Create a new drill-through definition.
12. Specify the report as the target report.
13. Under **Parameters**, click the edit button.
14. Set the **Selected retailer** parameter to pass data item values using the **Retailer name** data item.
15. In the **Toolbox** tab, add a value prompt under the table.
Because you are setting up drill-through access to the same report, you must add a prompt with a default value so that users are not prompted when they run the report.
16. In the **Prompt Wizard**, specify that the prompt is to use the existing parameter named **Selected retailer**, and click **Finish**.
17. Click the value prompt.
18. In the **Properties** pane, double-click the **Default Selections** property and add a simple selection named **NoRetailer**.
19. Set the following properties:
 - **Required** to **No**
 - **Hide Adornments** to **Yes**
 - **Visible** to **No**
20. Create a title for the report.

- a. In the **Toolbox** tab, add a block above the table.
 - b. Click the block and, in the **Properties** pane, set the class to **Report title area**.
 - c. Insert a text item above the table. Type the following text, adding a blank space at the end:
Order Details:
 - d. In the **Toolbox** tab, add the following layout calculation immediately following the text item:

```
if(ParamDisplayValue('Selected retailer')='NoRetailer')
then 'All Retailers' else (ParamDisplayValue('Selected retailer'))
```

When the report runs, the report title changes to reflect the retailer selected by the user. If no retailer is selected, 'All Retailers' appears.
 - e. Click the text item and the layout calculation and, in the **Properties** pane, set the class to **Report title text**.
21. Pause the pointer over the condition explorer button and click **Variables**.
Use conditional formatting to show a message above the second list when users have not selected a retailer from the first list.
 22. Create a Boolean variable named **HighLevel**:
ParamDisplayValue('Selected retailer')<>'NoRetailer'
 23. Pause the pointer over the page explorer button and click **Page1**.
 24. In the **Toolbox** tab, add a block above the second list.
 25. Insert a text item in the block with the following text:
Select a retailer in the Retailer list to view order details
 26. Set the font style for the text to bold.
 27. Click the text item and, in the **Properties** pane, set the **Style Variable** property to the **HighLevel** variable.
 28. Pause the pointer over the condition explorer and click the **Yes** value for the **HighLevel** variable.
 29. Set the **Visible** property for the text item to **No**.
 30. Triple-click the explorer bar to turn off conditional formatting.
 31. Run the report to view what it will look like for your users.

Results

A list appears on the left that shows revenue for each retailer. When users click a retailer, order information for the selected retailer appears in the second list. To return to the original report, in IBM Cognos Viewer, click **Previous Report**.

For more information, see the following references:

- “Using a table to control where objects appear” on page 353
- Add Relational Data to a Report
- Create a Parameter to Produce a Prompt
- Set Up Drill-through Access in a Report
- Create a Prompt Directly in a Report Page
- Using Calculations
- Calculation Components
- Add a Variable
- Hide and Show Objects

Drilling Through from IBM Cognos Series 7 to IBM Cognos BI

You can set up drill-through access from IBM Cognos Series 7 to IBM Cognos Business Intelligence. Specifically, you can drill through to an IBM Cognos BI report from an IBM Cognos Series 7 PowerPlay Web report or IBM Cognos Series 7 Visualizer report. Drill through is supported for both PowerCubes and other cubes.

You must complete steps in both IBM Cognos Series 7 and IBM Cognos BI to enable drill through. Refer to the IBM Cognos Series 7 documentation for the specific steps you must complete in the IBM Cognos Series 7 components. Cross references to the appropriate IBM Cognos Series 7 documents are included in the following sections.

Setting Up Drill-through Access from IBM Cognos Series 7 Visualizer

Setting up drill-through access from IBM Cognos Series 7 Visualizer to IBM Cognos Business Intelligence involves setting up the target report.

To set up drill-through access, you must do the following:

- Specify the IBM Cognos BI target and select the filters to add to the target report.

You must configure drill through to IBM Cognos BI for individual IBM Cognos Visualizer reports. For more information, see the IBM Cognos Visualizer *User Guide*.

- Create and test the target report.

Setting Up Drill-through Access from PowerPlay Web

Setting up drill-through access from IBM Cognos Series 7 PowerPlay Web to IBM Cognos Business Intelligence involves setting up target reports.

To set up drill-through access, you must do the following:

- For PowerCubes, specify drill-through targets for IBM Cognos BI reports in the Transformer model.

For more information, see the Transformer documentation.

- For other cubes, specify drill-through targets for IBM Cognos BI reports in IBM Cognos Series 7 PowerPlay Connect.

For more information, see the PowerPlay *OLAP Server Connection Guide*.

- Configure drill-through access in PowerPlay Server Administration.

In addition to enabling drill-through access to IBM Cognos BI, you must specify the location of the IBM Cognos BI server and the IBM Cognos BI folder that contains the target reports. For more information, see the PowerPlay *Enterprise Server Guide*.

- Select the filters to add to the target report.

In PowerPlay Enterprise Server Administration, enable and use IBM Cognos BI Assistance to identify the filter expressions required in the target report. For more information, see the PowerPlay *Enterprise Server Guide*.

- Create and test the target report.

Create and Test the Target for a Series 7 Report

You can create and test an IBM Cognos Series 7 report target to ensure the drill-through works properly.

When you create the target report, ensure that the names of the parameters you add are identical to the parameter names listed in the **Drill Through Assistant** page in IBM Cognos Series 7. However, the metadata item that you use in the target report for that parameter name does not have to be the identical label. The data values between the target parameter and the source value shown in the drill assistant must match. You may also need to change the type of operator in the target parameter from what is recommended in the **Drill Through Assistant**. For example, if the assistant recommends an = operator but you want to pass a date range, you should change the parameter operator in the target to in_range.

Before you begin

The target report must be based on a published package that contains the metadata items that you want to filter on, or contains items that are mapped to those metadata items.

Procedure

1. Start IBM Cognos Report Studio and create a new report.
2. Add the data items and other objects you want.
3. From the **Data** menu, click **Filters**.
4. In the **Detail Filters** tab, click the add button.
5. In the **Expression Definition** box, create the parameterized filter you want by typing the filter expression.
6. Click **OK**.
7. In the **Usage** box, click **Optional**.

If you do not make the filter optional, a prompt page appears when you drill through to the report.

8. Repeat steps 4 to 7 for other parameterized filters you want to add.
9. Save the report.

The report name must match what you specified as a target in the PowerCube, other cube, or IBM Cognos Series 7 Visualizer report.

10. Test the drill through in the IBM Cognos Series 7 PowerPlay report or IBM Cognos Visualizer report.

Chapter 20. Working with Multiple Pages

Divide a report into multiple pages and add navigation elements to make it easier to use.

Note: The pages that you see in the Page Explorer differ from physical, printed pages. For example, if you create page breaks in a long report, the Page Explorer could show only one page, but your report could include several physical pages when you print it.

Add a Page to a Report

Add pages to create a multiple-page report.

About this task


Reports may contain pages with a variety of content. For example, you are creating a sales report and you want to include general information about the company. You decide to create an introduction page to show this information. When you run the report, page 1 of the report is the introduction page and the following pages contain data

Tip: The TOC Report sample report in the GO Data Warehouse (query) package includes multiple pages. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Procedure

1. Pause the pointer over the page explorer button  and click **Report Pages**.

Tip: Click **Prompt Pages** to add a prompt page.

2. From the **Toolbox** tab , drag **Page** to the work area.
3. To change the order of pages, drag pages above or below other pages.
4. To associate a query to the page, in the **Properties** pane, set the **Query** property to the query.

Associate the page to a query to add data-related objects directly to the page header, body, or footer, such as data items and filters.

5. Double-click the page to open it in page design view.
6. Add objects to the page.

Page breaks, page sets, and page layers

You can create simple page breaks, advanced page sets, or page layers to associate pages with a query structure to force page breaks.

For example, a query contains the data item Product line, which is grouped. Creating a page set that is associated with this query adds page breaks for each product line. When working with dimensional data, you can use the **Page layers** area to show values on a separate page for each member.

When you are working with dimensional data, IBM Cognos Report Studio does not support page breaks or page sets that are based on custom groups.

Tip: The Global Bonus Report sample report in the GO Data Warehouse (analysis) package includes page sets. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Reports in Excel 2007 format

When you produce reports in Excel 2007 format, you can configure IBM Cognos Business Intelligence to dynamically name the Excel worksheet tabs, based on the data items that are used to break pages. For example, you specify to break pages by Product line. In Excel 2007 output, the five worksheet tabs that are generated are named Camping Equipment, Mountaineering Equipment, Personal Accessories, Outdoor Protection, and Golf Equipment. To dynamically name Excel worksheet tabs, ask your administrator to add the `RSVP.EXCEL.PAGEGROUP_WSNAME_ITEMVALUE` advanced setting to the report service. For more information, see the *IBM Cognos Business Intelligence Administration and Security Guide*.

If a report contains two page sets that use the same grouping data item, the suffix `<number>` is appended to the Excel tabs. For example, a report contains two page sets that use Product line as the grouping item. In the Excel output, worksheet tabs are named Camping Equipment_1, Golf Equipment_1, Camping Equipment_2, and so on. Similarly, page set header and footer pages are named Camping Equipment, Camping Equipment_2, Camping Equipment_3, and so on.

If a report contains nested page sets, worksheet tab names are a concatenation of the nested items separated by commas. For example, a report contains a page set with Product line as the grouping item. The page set has a nested page set that uses Product type as the grouping item. Examples of worksheet tab names that are generated are Camping Equipment,Cooking Gear and Camping Equipment,Lanterns.

Note: In Excel, tab names cannot exceed 30 characters. Tab names with more than 30 characters are truncated. If truncated tab names produces duplicate names, the prefix `s_<worksheet indexing>` is added to the names. For example, multiple pages are named Camping Equipment,Cooking Gear. The first tab name is Camping Equipment,Cooking Gea. The second tab name is `s_22Camping Equipment,Cooking`.

Create simple page breaks

Simple page breaks use data items to define where your report starts a new page.

Procedure

1. Click the data item at which the report should break to a new page.
2. From the **Structure** menu, do one of the following:
 - To create a page break without creating a master detail relationship, click **Set Page Break**.

This option only works if the data item is in a list or repeater. If the data item is in a crosstab or chart, IBM Cognos Report Studio creates a page break using a master detail relationship. Setting page breaks without using master detail relationships can improve performance when running the report.

- To create a page break using a master detail relationship, click **Set Page Break Using Master/Detail**.

Report Studio confirms the page break setting.

Tip: To modify simple page break settings, pause the pointer over the page

explorer button  and click **Report Pages**, and then select and modify the page set.



Create advanced page sets

You can use advanced page sets to define sets of pages within your report, and then customize the grouping and sorting for each page set.

About this task

You cannot create page sets if you set the option to show report pages as tabs in HTML output (**File > Report Properties**).


Procedure

1. Pause the pointer over the page explorer button  and click **Report Pages**.
2. Create the report pages.
3. From the **Toolbox** tab , drag the **Page Set** object to the **Report Pages** pane.
4. In the **Properties** pane, set the **Query** property to the query to associate with the page set.
5. Organize the pages in the report by dragging report pages to page sets.
6. Insert the page containing details in the **Detail Pages** folder.

Detail pages are the pages that repeat based on the items by which you group in the following step.

Tip: You can insert multiple detail pages into the same page set and link them using a master detail relationship.

7. Define the grouping structure for the page set:
 - Click the page set.
 - In the **Properties** pane, double-click the **Grouping & Sorting** property.
 - In the **Data Items** pane, drag the data item by which to group data items to the **Groups** folder in the **Groups** pane.
 - To sort the data within each group, in the **Data Items** pane, drag the data item by which to sort to the **Detail Sort List** folder, and then click the sort

order button  to specify the sort order. For more information about sorting data, see “Sorting Relational Data” on page 249 or “Sorting Dimensional Data” on page 295.

Note: Grouping an item for a page set is not the same as grouping a column in the layout. Grouping a column in the layout visually shows groups in a report. Grouping an item for a page set groups the item in the query. If you want to use an item that is already grouped in the layout, you must still perform step 7.

8. Repeat steps 3 to 7 to create other page sets.

Tip: You can nest page sets and join them by defining a master detail relationship. Create nested page sets to have pages occur within other pages.

For example, you want pages containing product type information to occur within pages containing product line information.

Join Nested Page Sets

If you have nested page sets in your report, define a master detail relationship between them to see data in the nested page set that is related to the data in the parent page set.

For example, you have a page set that shows pages of product line information. The page set contains a nested page set that shows pages of product type information. For each product line page, you want to see the related product type pages, as shown in the following example:

Product line_1


- Product type_1
- Product type_2
- Product type_3

Product line_2

- Product type_4
- Product type_5
- Product type_6

For more information about master detail relationships, see “Create a Master Detail Relationship” on page 307.

Procedure

1. Pause the pointer over the page explorer button  and click **Report Pages**.
2. In the **Report Pages** pane, click the nested page set.
3. In the **Properties** pane, double-click the **Master Detail Relationships** property.
4. Click the **New Link** button.
5. In the **Master Query** box, click the data item that provides the primary information.
6. Link the master data item to the details by doing one of the following:
 - To link to another data item in the detail query, in the **Detail Query** box, click the data item that provides the detailed information.
 - To link to a parameter, in the **Parameters** box, click the parameter that provides the detailed information.
7. Repeat steps 4 to 6 to create other links.

Tip: To delete a link, select it and press the Delete key.

Create Page Layers

When working with dimensional data, you can create page layers in a report to show values for each member on a separate page. For example, your report contains payroll information for the entire company. You want to view values for each department on a separate page.

After you create page layers, a caption appears in the header to indicate the contents of each page. You can navigate between the different pages using links below the report.

Creating page layers is similar to filtering using context. However, with context filters, values are filtered according to the member you add to the **Context filter** area. With page layers, the report is split into a separate page for each child of the member you add to the **Page layers** area.

To create more complex page layers in your reports, such as a report book with title and end pages, create page sets.

Procedure

1. In the source tree, select or search for one or more items on which to filter.
2. Drag the item into the **Page layers** section of the overview area.
The crosstab shows the results for the children of the selected item on separate pages, and a list appears under **Page layers**.




Tip: To navigate between pages, click **Page down** and **Page up** below the report.

3. To replace the page breaks with items from the same dimension, select an item from the list. To delete the page breaks, from the list, click **Delete**. To delete all the page breaks, right-click the **Page layers** area and click **Delete All**.

Example - Preparing a Product List Report

You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to create a multiple-page report showing all products sold by the company. You are asked to create title and end pages and to have each product line appear on a new page preceded by a header page and followed by a footer page.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (query)** package.
2. In the **Welcome** dialog box, click **Create a new report or template**.
3. In the **New** dialog box, click **List** and click **OK**.
4. From the **Source** tab , expand **Sales and Marketing (query)**, **Sales (query)**, and **Product**, and double-click the following:
 - **Product line**
 - **Product type**
 - **Product name**
5. Expand **Sales fact** and double-click **Product cost**.
6. Group the **Product line** and **Product type** columns.
7. Pause the pointer over the page explorer button  and click **Report Pages**.
8. From the **Toolbox** tab , drag **Page Set** to the work area and associate it to **Query1**.
9. From the **Toolbox** tab, drag **Page** to the work area four times to add four new pages.

10. For each page, click the page, and in the **Properties** pane, set the **Name** property as follows:
 - **Title page**
 - **End page**
 - **Product Line Header**
 - **Product Line Footer**
11. For each page you just created, add objects.
For example, add a text item to each page to uniquely identify it.
12. Rename the **Page1** page, which contains the list, to **List**.
13. Click the page set and, in the **Properties** pane, double-click the **Grouping & Sorting** property.
14. In the **Data Items** box, drag **Product line** to the **Groups** folder in the **Groups** box and click **OK**.
15. Organize the report pages into the following hierarchy by dragging them to the appropriate location.
 - a. Insert **Title page** as the first page in the report, before the page set.
 - b. In the page set, insert the **Product Line Header** page after **Product line**.
 - c. In the **Detail Pages** folder of the page set, insert the **List** page.
 - d. Insert the **Product Line Footer** page after the **List** page, at the same level in the hierarchy as the **Product Line Header** page.
 - e. Insert **End page** after the **Product Line Footer** page, at the same level in the hierarchy as **Title page**.




Figure 63. Hierarchy of pages in a report

Results

When you run the report, the following pages appear:

- Title page
- Product line header page
- A page for Product line_1
- Product line footer page
- Product line header
- A page for Product line_2
- Product line footer
- ...
- End page

Add a Bookmark

Add a bookmark so that users can quickly move from one part of a report to another. For example, a list report contains many rows of data. You add bookmarks so that users can move to specific rows.

You can also drill through to another report.

If you want to use page numbers to move from one part of a report to another, you can also create a table of contents.



Bookmarks work for reports produced in HTML format or PDF. In HTML format, they work best when viewing saved report outputs, as the entire report appears in a single HTML page. When reports are run interactively, more than one HTML page may be generated, and a bookmark works only if the target exists in the page currently being viewed.

If you run a saved report using a URL, and you specify a bookmark within the URL, you always go to the first page of the report. The bookmark defined in the URL is not honored. For more information about using URLs to run reports, see the *Administration and Security Guide*.

Tip: You can reduce the number of HTML pages generated when a report is run interactively by specifying a value for the **Rows Per Page** property for a data container in the report.

Tip: The Briefing Book sample report in the GO Sales (analysis) package includes bookmarks. For more information about The Sample Outdoors Company samples, see Appendix C, "Sample Reports and Packages," on page 525.

Procedure

1. From the **Toolbox** tab , drag a **Bookmark**  object to the report.
2. Click the bookmark and, in the **Properties** pane, set the **Source Type** property to a source type.

Source type	Description
Text	Creates a static bookmark using a text value. For example, a list has sections and you want users to jump from each section to the top of the report.
Report Expression	Creates a dynamic bookmark whose values are derived from an expression that you define.
Data Item Value	Creates a dynamic bookmark that has data as possible values. This is useful for creating a context-based bookmark. For example, a list has sections and you want users to jump from the top of the report to a specific section. Note: This source type appears only if the bookmark is inserted next to a data item.


Source type	Description
Data Item Label	<p>Creates a bookmark that has the label of a data item as its value. Use this source type to jump to the first occurrence of a data item label.</p> <p>For example, a list is divided into sections using Product line. You want users to jump to the first product line section that appears in the list rather than to a specific section, such as Camping Equipment.</p> <p>Note: This source type appears only if the bookmark is inserted next to a data item.</p>
Member Caption	In a crosstab, creates a dynamic bookmark that uses member captions as possible values.
Cell Value	In a crosstab, creates a dynamic bookmark that uses cell values as possible values.

- Set the property that appears under the source type you chose to the bookmark value.
For example, if the source type is **Data Item Value**, set the **Data Item Value** property to the data item.

- Right-click the object that will jump to the bookmark and click **Drill-Through Definitions**.

For example, right-click a data item, image, chart, or text item.

Tip: The object can exist in a different report, so you can jump from one report to another.

- Click the new drill-through definition button .
- Click the **Bookmark** tab.
- Click **Source type** and click one of the source types described in step 3.
Click the source type to use to produce the value needed to jump to the bookmark. For example, click **Data Item Values** if you want the value to come from a data item such as Product line.
- If you clicked one of the following source types, specify the value to use to jump to the bookmark.
 - For **Text**, click the ellipsis button next to **Text** and type a text value.
 - For **Data Item Value** or **Data Item Label**, in the **Data item** list, choose a data item.
 - For **Report Expression**, click the ellipsis button next to **Report expression** and define the expression.

Create a Table of Contents

You can create a table of contents that appears in the rendered output of your report. A table of contents is useful for reports that include sectioned items, grouped items, or multiple pages in the layout. The report output indicates page numbers and allows for easy navigation.

You can include multiple tables of contents in your report, which are useful if your report contains grouped lists. You can also add section numbers in front of entries in the table of contents by modifying the heading level property.

Table of contents entries are logical markers placed anywhere in a report. For example, you can place entries at the top of a page or in a list group header to mark each grouped data value. Although table of contents entries are visible in IBM Cognos Report Studio, they cannot be seen when a report is run.

A table of contents works only for reports produced in PDF or non-interactive HTML format. In HTML format, they work best when viewing saved report outputs, as the entire report appears in a single HTML page. When reports are run interactively, more than one HTML page may be generated, and a table of contents works only if the target exists in the page currently being viewed.

Tip: You can reduce the number of HTML pages generated when a report is run interactively by specifying a value for the **Rows Per Page** property for a data container in the report.


If you want to quickly move from one part of a report to another without using page numbers, you can add bookmarks.

Tip: The Briefing Book sample report in the GO Sales (analysis) package includes a table of contents. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Before you begin

You must first create a table of contents before adding entries in the report. All entries must be inserted after the table of contents in the report layout.

Procedure

1. From the **Toolbox** tab , drag the **Table of Contents** object to the new location, which can be anywhere in the report.
A table of contents placeholder appears.
2. Drag the **Table of Contents Entry** object to the location of your first table of contents marker.

Tip: You can also click **Insert Table of Contents Entry** from the **Structure** menu.



The new entry appears in the table of contents.

3. Double-click the **Double click to edit text** box of the new marker.
4. In the **Text** box, type the text to appear in the table of contents and click **OK**.
5. To edit the heading level of a table of contents entry, click the entry and, in the **Properties** pane, set the **Heading Level** property to the level.
The heading level is used to insert section numbers in front of entries in the table of contents using layout calculations.
6. When you finish creating the table of contents, run the report. By clicking the arrow to the right of the run report button, you can specify whether to run the report as HTML or PDF.



Example - Add a Table of Contents to a Report





You are a report author at The Sample Outdoors Company, which sells sporting equipment. You are requested to add a table of contents to an existing report so that users can more easily navigate your report.

Procedure

1. Open IBM Cognos Report Studio with the **GO Data Warehouse (analysis)** package.
2. Open the **Budget vs. Actual** sample report from the **Report Studio Report Samples** folder.
3. Create the report pages:
 - Pause the pointer over the page explorer button  and click **Report Pages**.
 - Click **Page1**, and then, in the **Properties** pane, set the **Name** property to **Budget vs. Actual Sales**.
 - Click the **Budget vs. Actual Sales** page and, from the **Edit** menu, click **Copy**.
 - From the **Edit** menu, click **Paste** to paste the copy of the page in the **Report Pages** pane.
 - Select the new page, and in the **Properties** pane, set the **Name** property to **Table of Contents**.
 - In the **Report Pages** pane, drag the **Table of Contents** page to the top of the list.
4. Pause the pointer over the page explorer button and click **Table of Contents**.
5. Delete the crosstab object:
 - Click somewhere in the report page.
 - In the **Properties** pane, click the select ancestor button  and click **Crosstab**.

Tip: You can also click the container selector (three orange dots) of the crosstab to select it.

 - Click the delete button .
6. Select the Camping Equipment block object and click the delete button.
7. Double-click the report title, type **Table of Contents**, and click **OK**.
8. From the **Toolbox** tab , drag a **Table of Contents** object onto the page.
9. Pause the pointer over the page explorer button and click **Budget vs. Actual Sales**.
10. From the **Toolbox** tab, drag a **Table of Contents Entry** object to the left of each region.
11. Pause the pointer over the page explorer button and click **Table of Contents**.
12. Double-click the first entry in the table of contents, type **Americas**, and click **OK**.
13. Rename the other table of contents entries as Asia Pacific, Northern Europe, Central Europe, and Southern Europe.
14. Save the report.
15. Number the table of contents entries:

- From the **Toolbox** tab, drag a **Layout Calculation** object to just before the word **Americas**.
 - In the **Report Expression** dialog box, on the **Functions** tab , expand the **Report Functions** folder and double-click the **TOCHeadingCount** expression.
 - At the end of the expression definition, type **1)** and click **OK**.
 - Repeat the previous three steps to add layout calculations before the other table of contents entries.
 - Ctrl+click only the five table of contents entries and not the five layout calculations.
 - In the **Properties** pane, double-click the **Padding** property and set the left padding to 10 px.
16. Change the color of table of contents entries:
- Ctrl+click the five layout calculations, the five table of contents entries, and the five page number calculations.
 - In the **Properties** pane, double-click the **Foreground Color** property and set the foreground color to blue.
17. Add links to the table of contents from another page:
- From the **Toolbox** tab, drag a **Bookmark** object to just before the title.
 - Select the bookmark and, in the **Properties** pane, double-click the **Label** property, type **TOC**, and click **OK**.
 - Pause the pointer over the page explorer button  and click **Budget vs. Actual Sales**.
 - From the **Toolbox** tab, drag a **Text Item** object to the right of the crosstab object.
 - In the **Text** dialog box, type **Return to the Table of Contents** and click **OK**.
 - Right-click the text object and click **Drill Through Definitions**.
 - Click the add button .
 - On the **Bookmark** tab, in the **Source Type** list, click **Text**.
 - Click the ellipsis button, type **TOC**, and then click **OK** twice.
18. Save the report.
19. Click the arrow to the right of the run report button  and click **Run Report - PDF**.

Results

On the first page, the table of contents appears. Clicking a region brings you to the corresponding page in the report. You can return to the table of contents by clicking **Return to the Table of Contents** at the end of the last page.

Table of Contents

1	Americas	2
2	Asia Pacific	2
3	Northern Europe	2
4	Central Europe	4
5	Southern Europe	4


Insert Page Numbers in a Report

You can insert page numbers in a report and specify the number style to use.

You can select a predefined page numbering scheme or create a custom scheme. You can easily insert page numbers using the **Page Number** object.

You can also manually create an expression to insert page numbers by inserting a layout calculation and using the different page report functions in the expression editor.

Procedure

1. From the **Toolbox** tab , drag **Page Number** to the report.


Tip: When you create a new report using one of the existing report layouts, **Page Number** is already inserted in the page footer.

2. Right-click the page number symbol and click **Edit Number Style**.
3. Choose the style to use.

The first three choices apply only to vertical page numbers. The remaining choices specify how vertical and horizontal page values appear.

Note: The 1 of 3 number style works only for reports produced in PDF or non-interactive HTML format. In HTML format, the 1 of 3 number style works when viewing saved report outputs, as the entire report appears in a single HTML page.

4. If you want to customize the choice that you made in the previous step, click

the edit button , make your changes, and click **OK**.

A custom number style is created. If you later choose a different number style, the custom style is removed from the list.

Tip: In the **Custom Number Style** dialog box, when you pause the pointer over a box, a tooltip describes how that box affects page numbers. For example, the **Separator Text** box contains the text, such as a hyphen, that separates page values for both vertical and horizontal pages.

Control Page Breaks and Page Numbering

You can control page breaks and page numbering in a list, crosstab, table, or report page by choosing any of these options.

The options that are available depend on which object you have selected. All the options for all the objects are described in the following table.

Option	Description
Keep with header	Keeps all headers on the same page with the number of detail rows specified.
Keep with footer	Keeps all footers on the same page with the number of detail rows specified.
Keep with previous	Keeps the object with the specified number of preceding objects on the same page, if space permits.
Keep with next	Keeps the object with the specified number of subsequent objects on the same page, if space permits.
Reset page count	Resets the page count after a page break to the value specified.
Reset page number	Resets the page number after a page break to the value specified.
Repeat every page	If the report renders multiple pages, this object is repeated on every page.
Allow contents to break across pages	Allows contents to break across pages. In lists and crosstabs, controls whether a cell is broken across pages, which is useful when there is a lot of text.

Option	Description
<p>Allow horizontal pagination</p>	<p>In PDF output, allows the columns of a list or crosstab to break across horizontal pages if they do not fit on a single page.</p> <p>Tip: In lists, you can select the Repeat every page option for list columns that show on every horizontal page.</p> <p>If the Allow horizontal pagination option is not selected, the size of the list or crosstab is scaled down when necessary so that it fits on a single page.</p> <p>Tip: The Horizontal Pagination sample report in the GO Sales (analysis) package includes horizontal pagination. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.</p> <p>If your report includes nested data frames such as a list within a list, horizontal pagination is supported on either the parent or child frame, but not both. If horizontal pagination is enabled on both the parent and child frame, it will be ignored on the child frame when the report runs. We recommend that you do not enable horizontal pagination on both the parent and child frames.</p> <p>Horizontal pagination is not supported for data containers, such as a list or crosstab, that are nested in repeater tables.</p> <p>You can also specify page number options that use compound numbering schemes. For example, you can use the numbering scheme 1-1, 1-2, 2-1, 2-2, and so on. For more information, see “Insert Page Numbers in a Report” on page 464.</p>
<p>Enable horizontal page numbering</p>	<p>Increments page numbers of horizontal pages separately from the main page numbers when you select a page numbering style that includes horizontal pages. For example, if a page has three page breaks horizontally and you selected the page number style 1a, the horizontal pages are numbered 1a, 1b, and 1c. If you did not select a numbering style that includes horizontal pages, the horizontal pages are all numbered 1 for the first vertical page, 2 for the second vertical page, and so on.</p> <p>If this option is not selected and there are horizontal pages, all pages are numbered sequentially. For example, if a report has two vertical pages and three horizontal pages, the PDF pages are numbered from 1 to 6. Pages 1 to 3 are the three horizontal pages for the first vertical page and pages 4 to 6 are the three horizontal pages for the second vertical page.</p>

Option	Description
Allow row contents to break across pages	In tables, allows the contents of a row to break across pages. For example, if a row contains four lines of text, the first two lines from the row appear on the first page, and the last two lines appear on the next page.
Repeat table rows on page break	In tables, if a row breaks across pages, repeats the rows that were previously rendered on each page. By default, table rows are repeated. Note: This option applies to saved reports only. In interactive HTML reports, table rows are always repeated even if this option is not selected.

You can also specify the style to use for page numbers.

Procedure

1. Click an object.
2. In the **Properties** pane, double-click the **Pagination** property.
3. Specify the page break and numbering options.

Creating a report booklet

In an IBM Cognos Report Studio report, you can add references to other reports to create a report booklet. Each report reference represents a booklet item.

About this task



You can insert or move report references before and after pages and page sets. However, you cannot add report references to a page set.

You can copy a report reference and paste it in a valid area in the report. If you try to paste a report reference in a page set, the report reference is added to the end of the report.

You can create a table of contents entry for a report reference. When the table of contents is generated, by default, the report name is used for the table of contents entry. You can edit the entry by selecting it in the table of contents. If the report name is changed, you must manually update the table of contents entry. If you change the order of pages in the report, the table of contents is automatically updated when it is generated.

You cannot add references to other reports if you set the option to show report pages as tabs in HTML output (**File > Report Properties**).

Procedure

1. Pause the pointer over the page explorer icon  and click **Report Pages**.
2. From the **Toolbox** tab , drag **Report Reference** to the **Report Pages** pane. The Choose Report window opens.
3. Locate the report that you want to add as a report reference and double-click it.

Tip: If you want to change the report reference, from the **Properties** pane, double-click the **Referenced Report** property and choose a different report.

4. Optional: Create a table of contents entry for the booklet item by modifying properties in the **Properties** pane, in the **Table of Contents** group.
 - a. Set the **Table of Contents Entry** property to **Yes**.
 - b. To roll up table of content entries for the booklet item into the report booklet, set the **Roll Up Table of Contents** property to **Yes**.
 - c. Specify the starting heading level for the booklet item by typing a value in the **Start Heading Level** property. For example, if you specify 2, all table of content entries for the booklet item have section numbers that start at 2.
5. To render prompt pages that exist in the booklet item when the report is run, set the **Show Prompt Pages** property to **Yes**.
6. Specify how to handle saved parameter values that come from the booklet item when the report is run by clicking one of the options in the **Saved Parameter Values** property.

Parameter values include signon, validation, and prompt information, and they are saved on the IBM Cognos server.

- If you do not want to use saved parameter values from the booklet item, select **Ignore**.
- If you want to use saved parameter values from the booklet item, select **Merge**.

When **Merge** is selected, parameter values that come from the booklet item are merged with parameter values that come from the report. If the same value exists for both the booklet item and the report, the booklet item value is ignored.

Producing tabbed reports

When you produce reports in HTML format, you can show each report page as a tab.

About this task

Report page names are used to name each tab in the output.

The option to show pages as tabs is not supported when a report is used as a report reference in a report booklet. This option is also not supported when a report contains page sets. Page sets are created in a report when you add a page set object, page layers, and page breaks.

In Excel output, each tab becomes a single sheet within the same workbook.

Procedure

1. Click **File > Report Properties**.
2. Click the **View pages as tabs** menu and select the location where you want the tabs to appear in browsers.

Chapter 21. Creating Report Templates

A report template is a pattern you use to build reports. Create your own report templates when you frequently produce the same type of report.

Tip: You can add your own report templates to the **New** dialog box that appears when you open IBM Cognos Report Studio. For more information, see the IBM Cognos Business Intelligence *Administration and Security Guide*.

Converting a Report to a Template

Convert a new or existing report to a template so it can be reused. You can use sample reports that are provided with IBM Cognos Report Studio.

About this task

When a report is converted to a template, any query-related information in the original report, such as data items, calculations, and filters, is removed from the template. When an IBM Cognos Active Report is converted to a template, query-related information that is removed also includes variables, connections between controls, and interactive behavior. However, variables, connections, and interactive behavior that use data items that were created in static controls remain in the template.

Procedure

1. Create a report or open an existing report.
2. Add objects to the work area.
3. From the **File** menu, click **Convert to Template**.
4. From the **File** menu, click **Save As** to save the template as a new file and keep the original report intact.

Related tasks:

“Convert an Existing Report to an Active Report” on page 194


You can leverage existing reports by converting them to active reports.

Create a New Template


Create a new template to provide report authors with a layout that they can use to create reports or they can apply to existing reports. IBM Cognos Query Studio and IBM Cognos Analysis Studio users can also use these templates. You can also use the template in Query Studio to define a layout for prompt pages.

When you create a new template, the **Source** tab  is empty; you can add only report objects.

Procedure

1. From the **File** menu, click **New**.
2. Click **Report Template** and click **OK**.
3. Pause the pointer over the page explorer button  and click the report page or prompt page to format.

Tip: To create a new report page or prompt page, click the **Report Pages** or **Prompt Pages** folder and drag the page to the **Report Pages** or **Prompt Pages** pane.

4. From the **Toolbox** tab , add the objects to the work area.

Note: If you add objects that are not supported by Query Studio, the objects will be ignored when you apply the template.

5. Save the template.

Chapter 22. Managing Existing Reports

After you have created a report, you can make changes or enhancements, such as setting up the report for bursting.

Before you modify an existing report, ensure that you have the proper security permissions. For more information, see the IBM Cognos Business Intelligence *Administration and Security Guide*.

Copy a Report to the Clipboard

You can copy a report specification to the clipboard so you can open it from the clipboard later.

This process is different for the Microsoft Internet Explorer and Mozilla Firefox Web browsers because the clipboard works differently in each Web browser.

Copy a Report to the Clipboard in Internet Explorer

This process is different for the Microsoft Internet Explorer and Mozilla Firefox Web browsers because the clipboard works differently in each Web browser.

Procedure

From the **Tools** menu, click **Copy To Clipboard**.

Copy a Report to the Clipboard in Firefox

This process is different for the Microsoft Internet Explorer and Mozilla Firefox Web browsers because the clipboard works differently in each Web browser.

Procedure

1. From the **Tools** menu, click **Copy To Clipboard**.
2. In the **Copy Report to Clipboard** dialog box, copy the entire report specification.
3. Open a text editor and paste the report specification.
4. Copy all the text from the text editor report specification.
Now the text is saved on your computer's clipboard.

Open a Report from the Clipboard

You can open a report specification that was previously copied to the clipboard.

To copy a report to the clipboard, see “Copy a Report to the Clipboard.” This is useful for importing an XML report specification from outside the IBM Cognos Business Intelligence environment.

Although IBM Cognos Report Studio attempts to validate the report specification, it is your responsibility to ensure that it is correct. For more information, see the IBM Cognos Software Developer Kit *Developer Guide*.

Procedure

From the **Tools** menu, click **Open Report from Clipboard**.

Open a File from Another Studio

You can open reports, templates, or analyses that were created in IBM Cognos Query Studio or IBM Cognos Analysis Studio in IBM Cognos Report Studio. All the capabilities of Report Studio are available to you so you can change formatting, layout, calculations, and queries.

You can also open a report, template, or analysis in Report Studio from IBM

Cognos Connection with the **Open with Report Studio** action .

Note: If you make and save changes to a Query Studio report or an Analysis Studio analysis in Report Studio, the report or analysis can no longer be opened in Query Studio and Analysis Studio.

Procedure

1. From the **File** menu, click **Open**.
2. Click the report, template, or analysis.
3. Click **Open**.

Analysis Studio Query Specification

IBM Cognos Analysis Studio defines each group of rows and columns as a set. When you import an analysis into IBM Cognos Report Studio, the report will have one query that processes all the sets found on the crosstab. Each set is defined by data items that segment and summarize the base set definition. To maintain reports converted from Cognos Analysis Studio, you must understand what each of these items represents and how they relate to each other.

Before you modify any of the data items in the Cognos Analysis Studio set definitions, we recommend that you fully understand each data item and its dependencies. Modifying the data items may cause unpredictable results and may slow the performance of your report.

The data items for a set specify the following:

- the set definition
- set segments, including which members were excluded and hidden individually
- filter rules for defining which members are to be retrieved
- calculations for Subtotal (N items), More & Hidden, Subtotal (included), Subtotal (excluded), and the total

For more information, see the *IBM Cognos Analysis Studio User Guide*.

- which subtotals should appear
- any user-defined calculations




Figure 64. Components of a Cognos Analysis Studio crosstab

The default measure identifies which measure is the default for the crosstab or chart. If no default measure is specified, the default measure may be empty.

Set Definitions

The following table shows the definitions and dependencies for the data items in the set definition.

Data item	Definition	Dependencies
<set name> (base)	Defines the set of members to be used for sorting, filtering, and summary operations. This data item provides a generic reference for all other data items and may reference one of the other set definitions.	None
<set name> (level)	Identifies the level for a level-based set.	None
<set name> (list)	Defines the list of members in a selection-based set.	None
<set name> (depth N)	Defines the set of members at N, number of levels down.	None
<set name> (named set)	References a predefined set.	None

Set Segments Definitions

The following table shows the definitions and dependencies for the data items in the set segment definition.

Data item	Definition	Dependencies
<set definition> (hidden list)	Lists the members that are manually hidden using the Hide command in Cognos Analysis Studio. This set appears when you try to unhide a member.	<set definition>
<set definition> (included set)	Lists the set of members after filters are applied and hidden items are excluded, but before the More limit is applied. Sort or order operations, if any, are defined in this data item.	<set definition> (hidden list)
<set definition> (visible items set)	Limits the set to show the number of members according to the More limit with a small tolerance. The tolerance allows showing the last two members if they are all that remain in the More portion of the set. The choice of visible members can be based on a sort order.	<set definition> (included set)
<set definition> (excluded list)	Identifies members that were manually excluded from the analysis. If no members were manually excluded, the expression defines an emptySet. This set appears when you try to remove a member from the Excluded items list in the Properties pane.	<set definition>

Filters

The following table shows the definitions and dependencies for the data items in the filter.

Data item	Definition	Dependencies
<set definition> (filter rules)	Specifies the user-defined filter rules to reduce the set definition using operators such as greater than or less than based on measures, calculations, or attributes.	<set definition>

Data item	Definition	Dependencies
<set definition> (excluded filters)	Removes members that were manually excluded from the results after applying the user-defined rules.	<set definition> (excluded list), <set definition> (filter rules)
<set definition> (filter top bottom)	Focuses on the members based on top / bottom / first <i>n</i> where <i>n</i> can be a count or a percentile. For more information about Top/Bottom filters, see the <i>IBM Cognos Analysis Studio User Guide</i> .	<set definition> (excluded filters) and totals for sets on the opposite axis
<set definition> (filter rules)	Specifies the user-defined filter rules to reduce the set definition using operators such as greater than or less than based on measures, calculations, or attributes.	<set definition>

Subtotals and Related Conditions

The following table shows the definitions and dependencies for the data items in the subtotals and related conditions.

Data item	Definition	Dependencies
<set definition> (subtotal)	Aggregates the visible items in the set.	<set definition> (visible items set)
<set definition> (subtotal display)	Shows the subtotal if the number of included items is greater than the number of visible items.	<set definition> (visible items set), <set definition> (included set), <set definition> (subtotal)
<set definition> (more and hidden subtotal)	Calculates the More & hidden subtotal by subtracting the aggregation of the included members from the aggregation of those members that were manually hidden or hidden by exceeding the maximum display limit. Not available for selection-based sets.	<set definition> (included set), <set definition> (visible items set), <set definition>
<set definition> (more and hidden subtotal as set)	Converts the More & hidden subtotal member to a set for use in set operations.	<set definition> (more and hidden subtotal)
<set definition> (more and hidden subtotal as member)	Generically references the More & hidden subtotal.	<set definition> (more and hidden subtotal)

Data item	Definition	Dependencies
<set definition> (more and hidden subtotal display)	Shows the More & hidden subtotal if the number of items hidden or clipped is greater than zero.	<set definition> (more and hidden subtotal)
<set definition> (included subtotal)	Calculates the Subtotal (included) . For selection-based sets, this data item references the summary data item for the set.	<set definition> (included set)
<set definition> (included subtotal display)	Shows the Subtotal (included) if any members passed the filter criteria.	<set definition> (included set)
<set definition> (excluded subtotal)	Calculates the value for Subtotal (excluded) . This data item is not available for selection-based sets.	<set definition> (total), <set definition> (included subtotal), <set definition>
<set definition> (excluded subtotal display)	Shows Subtotal (excluded) if the number of members in the filtered set is less than the base set. This means that the filter rule is filtering out something.	<set definition> (excluded subtotal), <set definition>
<set definition> (total)	Identifies the total for the set. This value is calculated directly from the data store. The expression used to calculate the summary depends on the set type: <ul style="list-style-type: none"> • Details-based set: The selected member. • Level-based and depth-based sets: The root member for the hierarchy. • Selection-based set: The aggregate, typically the sum, of the selected members. 	<set definition>

Managing Changes in the Package

If changes were made to the package that was used to create a report, the report must be updated.

When you open a report, IBM Cognos Report Studio automatically checks to see if the package has changed. If it has, a message appears indicating that the report will be updated to the latest version of the package. However, you may need to make additional changes to the report if


- the namespace name or query subject and data item names in the package have changed
- the name of the package has changed

Update a Name Reference

If the namespace name or query subject and data item names in the package have changed, you must update reports that were created with the package to reflect the change.

The names of data items in a report are a concatenation of the namespace name, the query subject name, and the data item name. For example, if you add Order number from the GO Data Warehouse (query) sample package to a filter expression, you will see [Sales (query)].[Sales order].[Order number] in the expression. Similarly, package filter names are a concatenation of the namespace name and the filter name.

Procedure

1. To update a data item name reference:
 - Click the data item.
 - In the **Properties** pane, double-click the **Expression** property.
 - In the **Expression Definition** box, update the data item name reference.
2. To update a package filter name reference:
 - From the **Data** menu, click **Filters** .
 - Double-click the package filter.
 - In the **Expression Definition** box, update the namespace name.

Change the Package

If the name of the package that were used to create a report has changed, you must change the package connection to update the report.

At the same time, you can also change the authoring language for the report.

Procedure

1. From the **File** menu, click **Report Package**.
2. Click **Another package** and choose the new package.
3. To change the authoring language, click the ellipsis button beside the **Language** box and choose a different report language.

You may need to update the report to reflect the change. For example, any filter expressions in the report must be modified to reflect the syntax rules of the new language.

4. Click **OK**.

The new package is loaded and the report is validated. If errors are found, the **Validation Errors** dialog box appears, showing the elements that must be updated to reflect the package change.



5. Click **Close**.
6. Make any required changes in the report to support the new package.
For example, you may need to link the data items in the report to the new package.

Tip: You can use Query Explorer to make the changes.

Chapter 23. Upgrading Reports

When you open a report that was created in a previous version of IBM Cognos Business Intelligence, it is automatically upgraded.

Any problems detected during the upgrade process appear as information

messages  and error messages  in the **Upgrade Information** dialog box. You must fix any errors in the report and then validate the report before you can run it. In some cases, the information or error message is linked to the location of the issue in your report. To go to the location of the issue, click the message, and then click **Select**. If only warnings and information appear in the dialog box, these will disappear when you click **OK**.

Tip: To view this dialog box again, from the **File** menu, click **Upgrade Information**.

After you upgrade a report to the most recent version of IBM Cognos BI, you can no longer open it with a previous version.

Lifecycle Manager

You can download IBM Cognos Lifecycle Manager from <http://www.ibm.com/> to help you test your reports. Lifecycle Manager is a verification tool that checks that your reports run and produce the same results in the new environment.

Lifecycle Manager is a Microsoft Windows operating system-based application for auditing upgrades to the latest version of IBM Cognos BI from IBM Cognos ReportNet 1.1 MR3 or MR4, and from IBM Cognos 8 versions 8.2, 8.3, or 8.4.

It provides a verification feature that validates, executes, and compares report results from two different IBM Cognos BI releases. This helps to identify upgrade and compatibility issues between releases. User interface design and status reporting functionality provide both a proven practice process and support for upgrade project planning and status reporting. Lifecycle Manager also automates much of the process of bundling the required files, such as reports and models, for the test case. For more information, see the Lifecycle Manager *User Guide*.

Upgrading Reports from IBM Cognos BI Version 8.4

When you upgrade to IBM Cognos Business Intelligence version 10 from IBM Cognos 8 BI version 8.4, some reports may look or behave differently after the upgrade. This section describes changes that you may encounter in your reports.

Upgrading Report Styles

IBM Cognos Business Intelligence includes a new default report style with updated colors and gradients. If your report uses a custom report template, your report will appear the same in this version of IBM Cognos Report Studio as it did in previous versions. By default, new reports and new report objects, such as lists and crosstabs, appear in the new report style.

If you want to continue to work with the previous 8.x report style, set the **Override 10.x styles with 8.x styles on new reports** option (**Tools, Options, Advanced** tab).

You can update the style of an upgraded report to use the new 10.x style (**File, Report Properties, Report styles, 10.x styles**).

For more information about report styles, see “Create and Modify Report and Object Styles” on page 365.

Upgrading Legacy Charts

IBM Cognos Report Studio version 10.1.0 includes a new default chart technology. You can continue to use and work with legacy charts or upgrade your legacy charts to current default charts.

When you open a report that uses legacy charts, the legacy charts are not upgraded to current default charts automatically. You can upgrade your legacy charts one at a time to current default charts. For more information, see “Convert Charts From One Type to Another” on page 107.

When you add a new chart to a report, Report Studio adds a current default chart. If you want to add new legacy charts or continue to work with existing legacy charts, set the **Use legacy chart authoring** option (**Tools, Options, Advanced** tab).

New Default for Hidden or Deleted Axis Titles

The default for rendering hidden or deleted axis titles has changed. This can change the size or placement of chart elements in your chart report output.

In previous versions of IBM Cognos Report Studio, hidden or deleted axis titles were defined and rendered as empty spaces in the report.

In Report Studio, Version 10.1.0, hidden or deleted axis titles are not rendered at all, so the space that was reserved for the title is available for other chart elements. This can affect the placement or size of chart elements, such as labels, the chart body, or the bars in a bar chart.

To make the charts appear the way they did in the previous version, set the x-axis' **Title** property to **Show** and then set the x-axis title's **Default Title** property to **No**. This adds the space for a custom axis title to the report specification but leaves the title blank.

Upgrading Reports with SAP BW Prompt Variables

When you upgrade reports that use SAP BW data sources and contain variables as prompts from version 8.3 SP2 to version 8.4 or 10.1.0, the upgrade may fail. Prompts that contained SAP BW variables are now empty. This occurs because a default setting in an IBM Cognos configuration file changed in version 8.4.

To successfully upgrade these reports, do one of the following:

1. Fully qualify all of the variables in the report by changing `[variable_name]` to `[infoquery].[variable_name]`.
2. Ask your IBM Cognos administrator to change the value for the `DetectSAPVariableUniqueness` parameter in the configuration file, as follows:
 - In the `c10_location\configuration` directory, locate the `qfs_config.xml` file.

- Find the DetectSAPVariableUniqueness parameter and change its value to false.
- Save the qfs_config.xml file.
- Restart the IBM Cognos service.

If more than one variable with the same name exists in the package, this change may cause problems.

Upgrading Reports from IBM Cognos BI Version 8.1 or 8.2

When you upgrade IBM Cognos Business Intelligence, some features in IBM Cognos BI may behave differently after the upgrade. When you upgrade reports, for example, changes in behavior may cause validation errors.

Members Containing No Data Are Not Suppressed for SAP BW

If you upgrade a crosstab report that uses a SAP BW data source and includes calculations, filters, or nesting, the suppression of null values may not occur as expected. You may see additional empty rows and columns.

By default, null values are suppressed for list and grouped list reports.

To effectively remove null values in crosstabs that use a SAP BW data source, insert individual members to create the report. You can also ensure that SAP BW members are assigned to proper dimension hierarchies and levels within the BW cube.

Thousands Separators Missing

You may encounter missing thousands separators in your reports in the following circumstances:

- The report contains an item that does not specify an explicit data format.
- The report item refers to another item in the same report.
- That second report item refers to an item in the IBM Cognos Framework Manager model with **Usage** property set to **Identifier** or **Attribute**.
- The model item does not specify an explicit format.

To restore the data formats, specify an explicit format either in the report item properties or in the model item properties.

RQP-DEF-0177 Error When Upgrading Reports


When you upgrade your report from IBM Cognos Business Intelligence, version 8.2, you encounter the following errors:

RQP-DEF-0177 An error occurred while performing operation 'sqlPrepareWithOptions' status='-120'.

UDA-SQL-0458 PREPARE failed because the query requires local processing of the data. The option to allow local processing has not been enabled.

This error occurs when the query requires local processing because some or all of its constructs are not supported by the database vendor. In IBM Cognos BI, version 8.2 and earlier, IBM Cognos BI proceeded with local processing. In version 8.3 and later versions, you must explicitly set the query Processing property to **Limited Local** in order to enable local processing.

Procedure

1. In IBM Cognos Report Studio, pause the pointer over the query explorer button  and click the query.
2. In the **Properties** pane, set the **Processing** property to **Limited Local**.

Upgrading Reports from IBM Cognos ReportNet

When you upgrade from IBM Cognos ReportNet, some reports may look or behave differently after the upgrade. The upgrade does not account for the following issues.

Undocumented and Unsupported Features

If advanced report authors used undocumented and unsupported features such as JavaScript that refer to IBM Cognos HTML objects, they may have to recreate the features to complete the upgrade of the report.

No Sort Order

Data may appear in a different order after upgrading. If sort order is important, ensure that the report or model specifies a sort order before upgrading.

Layout Errors

Layout errors are suppressed by default in ReportNet. IBM Cognos Business Intelligence does not suppress layout errors. Users may have to correct or remove report layout expressions that cause errors.

Report Format

If you used the default format in ReportNet, upgraded reports will retain that format. However, new reports in IBM Cognos Business Intelligence will use the IBM Cognos BI format. If you want a consistent style across all reports, you must edit the styles property in each report and select or deselect the **Use 1.x report styles** option.

Customized Style Sheets

If you edited the ReportNet style sheet (default_layout.css) or the IBM Cognos Business Intelligence stylesheet (globalreportstyles.css), reports will lose the formatting after upgrading. You must reapply the changes to the IBM Cognos BI stylesheets and copy the stylesheets to the IBM Cognos BI server and the Web server.

PDF Reports

PDF rendering in IBM Cognos Business Intelligence behaves like HTML rendering. After upgrading, PDF reports may have different font size, column wrapping, or word wrapping. You may have to change each affected report or change the default font in the IBM Cognos BI style sheet.

IF-THEN-ELSE Statements

If you use assignments of different data types after THEN and ELSE in ReportNet, the reports will generate invalid coercion errors after upgrading. You may have to recast the variables or change the assignments in the affected reports.

Solve Order

In previous versions of IBM Cognos Business Intelligence, you could specify the solve order for objects such as crosstab node members. Solve order is now specified for data items. When you upgrade a report, solve orders specified in the report are moved to data items.

For more information about solve order, see “Resolve Multiple Calculations for Crosstabs and Charts” on page 558.

Chart Behavior

In ReportNet, if a chart is created with a user-specified minimum value and all data values are below the minimum value, the chart starts at the user-specified minimum value and contains no data.

In IBM Cognos Business Intelligence, the same parameters result in a chart that ignores the user-specified minimum value and uses a range that includes all of the data values for the chart.

Database Only Processing of Queries

If you specified in ReportNet that the processing for a query should be Database Only, when you upgrade your report to IBM Cognos Business Intelligence, some processing may now occur locally.

Changes in the Behavior of Functions Between ReportNet 1.1 and IBM Cognos BI

In ReportNet 1.1, double counting could occur when applying count or count distinct to a query item. This occurred primarily when querying multiple query subjects that were joined 1-to-N in the model if the counted item existed in the query subject on the 1 side of the join. The explanation is that count or count distinct was applied after the join operation.

Count distinct worked only when the item to which count distinct was applied was the column used in the join. In this case, the column to be counted could have identical values for the different values used in the join condition.

In IBM Cognos Business Intelligence, improvements to the count functionality cannot be handled through an automatic upgrade. The new approach avoids double counting on the 1 side of a 1-to-N join. The explanation is that count or count distinct is now applied before the join operation.

There is now a lesser need to use count distinct and, when used, it will be successful more often. Count distinct is no longer required to overcome double counting. Instead, it can be used as intended to select distinct values that exist in a query subject.

When you want to count repeated occurrences of a value, we recommend that you do one of the following:

- Apply a count operation on a column based on a query in which an explicit join occurs.

This applies the count after the join.

- Count rows in a report by using a layout calculation object or by counting the literal value 1.

Appendix A. Accessibility Features

Accessibility features help users who have a physical disability, such as restricted mobility or limited vision, to use information technology products.

See the IBM Accessibility Center (<http://www.ibm.com/able>) for more information about the commitment that IBM has to accessibility.

Accessibility features in IBM Cognos Report Studio

There are several accessibility features in IBM Cognos Report Studio.

The major accessibility features are described in the following list:

- You can use command keys, or shortcut keys, to navigate through Report Studio. Shortcut keys directly trigger an action and usually make use of the Ctrl keys.
- Report Studio uses Web Accessibility Initiative—Accessible Rich Internet Applications (WAI-ARIA). This means that people with limited vision can use screen-reader software, along with a digital speech synthesizer, to listen to what is displayed on the screen.

Note: To take full advantage of the accessible features of Report Studio, use Mozilla Firefox version 4.0 or higher and Freedom Scientific JAWS version 12.0.

Keyboard Shortcuts

This product uses some standard Microsoft Windows and accessibility shortcut keys.

Action	Shortcut keys
Enables or disables the accessibility feature. You must restart IBM Cognos Report Studio after enabling or disabling this feature for it to take effect. The feature is disabled by default.	Ctrl+Alt+A Tip: You can also enable or disable the accessibility feature by selecting or clearing the Enable accessibility (requires restart) check box (Tools > Options > Advanced > Enable accessibility (requires restart)).
Opens the context menu for the selected item, if available.	Shift+F10
Switches focus from or to the main menu bar and the main worksheet.	Ctrl+F10
Opens the online help.	F1
Closes the Web browser window.	Alt+F4
Copies objects.	Ctrl+C
Pastes objects.	Ctrl+V
Closes objects, such as a dialog box, menu, drop-down list, or page.	Esc
Cycles through objects, such as the tabs in a dialog, the objects in a page, the cells in a list, the rows in a crosstab, or check boxes.	Tab, Shift+Tab, Arrow keys

Action	Shortcut keys
Selects the first or last item in a list.	Home/Pg Up or End/Pg Dn keys
Selects or clicks one or multiple objects, such as a radio button, menu or toolbar item, or node in a tree widget. In the Properties pane, expands or collapses a property group.	Space or Enter, Ctrl+space or Shift+space, Ctrl+Enter or Shift+Enter

Considerations to Improve Report Accessibility

Creating accessible reports ensures access of information to all users, with all levels of ability.

For example, people with a visual impairment may use screen reading technology to access the information in a report.

The following are some design considerations for creating accessible reports:

- Avoid using visual cues, such as bold text or color, to convey important information.
- Avoid using pictures and OLE Objects in PDF documents, as these items are tagged as artifacts and ignored by the screen reader.
- Avoid using conditional formatting to convey important information.
- When selecting color palettes for report objects, choose patterns or shades of gray.
- Ensure that there is a table corresponding to chart types that are rendered as images because the screen reader ignores this information.
- Deliver reports in HTML format, which is the most supported output format for most screen readers.
- Ensure that the report has a title.
- Gain an understanding for screen reading technology.
- Avoid spelling and grammatical errors, as they cause the screen reading software to misinterpret the information.
- Avoid using features like calendar boxes and up and down selections on time controls. Instead use prompts such as check boxes, radio buttons, combo boxes, and multi-select boxes.
- Ensure that the target application is accessible when using embedded Web applications or drill-through paths.
- Avoid using large, complex list or crosstab reports.
Displaying the information in multiple simple lists or crosstab reports is more manageable for assistive technology users.
- Add alternate text to images, charts, and other visual objects so that screen readers can provide context for them.
- When using tables, add summary text to provide context for the table content. If the top cells in a table behave as headers, designate these cells as headers so that screen readers can identify the relationships.
- Avoid using range prompt controls that contain radio buttons.

Figure 65. Range prompt with From and To sections

When users tab to a radio group, the focus should be in the selected radio button. In the case of range prompts, for both the From and To sections, the radio button groups start first in the tab order. However, the secondary input elements, which can be text boxes, drop-down lists, date edit boxes, and so on, are located before the selected radio button in the tab order. Instead of going to the selected radio button, the focus goes to the secondary input element. As a result, users using a screen reader do not know that the input element is one of two options.

Enable Accessible Report Outputs

If you want to include accessibility features, such as alternate text, summary text, designated cell headers in tables and accessible conditional layouts, you must enable these accessibility features in the report output.

You can enable accessible report outputs in one of the following ways:

- in the IBM Cognos Report Studio run options, so that the report has accessibility features enabled when you run the report from within Report Studio.
- in IBM Cognos Connection as a run option (**Run with options, Enable accessibility features**), so that report consumers can run the report once with accessibility features.
- in IBM Cognos Connection as a property (**Set properties, Report tab**), so that report consumers can always run the report with accessibility features.
- in IBM Cognos Connection, as a user preference (**My area, My preferences**), so that report consumers can enable accessibility features for all of their reports. Accessibility settings in the report properties overwrite this setting.
- in IBM Cognos Administration, as a server-wide option, so that all reports for all IBM Cognos users have accessibility features enabled. Accessibility settings in the user preferences and report properties overwrite this setting.

Administrators can also change a system-level setting that forces the accessibility features on or off regardless of any other settings.

For information about the last four options, see the IBM Cognos Connection *User Guide* or the IBM Cognos *Administration and Security Guide*.

Procedure

In Report Studio, from the **Run** menu, click **Run Options** and select the **Include accessibility features** check box.

Alternate text and summary text

To make reports accessible, you can add alternate text or summary text to objects such as images, charts, and tables. When a screen reader encounters one of these objects, it reads the text that you added to the object.

Related tasks:

“Customize Prompt Text” on page 337

You can customize the instructional text that appears around prompts. For example, a value prompt with multiple selections includes a **Select all** link below the choices that you can customize to text other than **Select all**. You can also specify translated text in many languages for international report users.

Add Alternate Text to Images and Charts

You can add alternate text for images, maps, and charts to make your reports accessible. When a screen reader encounters one of these objects, it reads the alternate text that you added to the object.



You can add translations for the text to support users in multiple languages. When users run a report, IBM Cognos Business Intelligence uses the alternate text in the appropriate language.

If you use images only for visual spacing in your report, leave the **Alternate Text** property empty.

Before you begin

For the report output to contain the alternate text, you must enable the accessibility features for the report. For more information, see “Enable Accessible Report Outputs” on page 487.

Procedure

1. Select the image or chart object.
2. In the **Properties** pane, click the select ancestor button  and select the **Image, Map**, or chart object.
3. Double-click the **Alternate Text** property.
4. Select **Specified text** and click the ellipsis button.
5. In the **Default text** box, type a description for the object, and click the add icon .
6. In the **Languages** dialog box, select the languages that apply to your text.
7. Double-click a language and type the translation of the text for each language and click **OK**.

Add Summary Text to Tables

You can provide summary text for crosstabs, lists, repeater tables, and table objects. This text provides context for the entire object to make your reports accessible. When a screen reader encounters one of these objects in HTML report outputs, it reads the description that you added to the object.

The table summary is not displayed in visual Web browsers. Only screen readers and speech browsers use the summary text. The summary text is usually read immediately before the table caption.


You can add translations for the text to support users in multiple languages. When users run a report, IBM Cognos Business Intelligence uses the summary text in the appropriate language.

If you use tables for report layout, leave the summary empty to indicate to screen readers that the table is used exclusively for visual layout and not for presenting tabular data.


Before you begin

For the report output to contain the summary text, you must enable the accessibility features for the report. For more information, see “Enable Accessible Report Outputs” on page 487.

Procedure

1. Select the crosstab, list, or table.
2. In the **Properties** pane, click the select ancestor button  and select the **Crosstab, List, Repeater Table, or Table** object.

Tip: You can also click the container selector (three orange dots) of the container to select it.

3. Double-click the **Summary Text** property.
4. Select **Specified text** and click the ellipsis button.
5. In the **Default text** box, type a description for the object, and click the add icon .
6. In the **Languages** dialog box, select the languages that apply to your text.
7. Double-click a language and type the translation of the text for each language.

Designate Cells as Headers in Tables

You can specify whether specific table cells are table headers. This allows screen readers and speech browsers to identify the relationships between the cells in your tables.

Before you begin

For the report output to contain the cell headers, you must enable the accessibility features for the report. For more information, see “Enable Accessible Report Outputs” on page 487.

Procedure

1. Select the table cells.
2. In the **Properties** pane, set the **Table Header** property to **Yes**.

Headings and emphasis

You can apply certain global classes to text objects to make the text easier to read for visually impaired users.

The following global classes are available to improve text readability for headings and blocks of text:

- Heading 1 through 6

Tip: In HTML output, these classes are converted to <h1> to <h6> tags.

- Emphasize Text and Strong Text

Tip: In HTML output, these classes are converted to and tags.

You apply one of these global classes to text by accessing the **Classes** property of the text and choosing the class that you want to apply.

Prompt control labels

You can associate labels to prompt controls to make the prompts accessible.

There are several methods that you can use to associate a label to a prompt control:

- Associate a text item to the prompt control.
- Insert the prompt control in a field set and use the caption of the field set to specify the label.
- Use HTML items to define a field set.

When a text item is associated to a prompt control, the text is read by screen readers when users tab to the control. When a prompt control is inserted in a field set, screen readers read the label of the field set when the focus moves to any input element within the field set.

Associating a text item to a prompt control in IBM Cognos Report Studio

Associate a text item to a prompt control to create a label for the prompt.

Before you begin

You must specify a name for the prompt control before you can associate a text item to the control.



Procedure

1. To specify a name for the prompt control, select the control, and in the Properties pane, type the name in the **Name** property.
2. Create a text item or select an existing text item.
3. In the Properties pane, in the **Label For** property, type the name of the prompt control.

Associating labels with prompt controls using field sets

You can associate labels with prompt controls using field sets.


Procedure

1. From the **Toolbox** tab , drag **Field Set** to the report.
2. Double-click the caption of the field set and type the text that you want to appear as the prompt control label.
3. From the **Toolbox** tab, drag a prompt control to the field set.
4. Optional: To hide the field set border so that only the prompt control border appears in the prompt page, set the border to none.
 - a. Select the field set.
 - b. In the **Properties** pane, click the **Border** property.
 - c. In the **Style** box, click **None**.
 - d. Under **Preview**, click the apply all borders icon  and click **OK**.

Associating labels with prompt controls using HTML items

Instead of using the field set object, you can associate labels with prompt controls using HTML items. You use the HTML items to create the field sets.

Procedure

1. From the **Toolbox** tab , drag **HTML Item** to the left of the prompt.
2. Click the HTML item.
3. In the **Properties** pane, double-click the **HTML** property.
4. In the **HTML** window, type the following text and click **OK**.

```
<fieldset style="border:0;">
<legend>Prompt label</legend>
```
5. From the **Toolbox** tab, drag **HTML Item** to the right of the prompt.
6. Click the HTML item.
7. In the **Properties** pane, double-click the **HTML** property.
8. In the **HTML** window, type the following text and click **OK**.

```
</fieldset>
```


Example - Conditionally Show a List Below a Chart for an Accessible Report

Charts are rendered as images in report outputs, such as HTML and PDF. As a result, they are difficult to navigate for visually impaired users and screen readers cannot convey the information shown in charts. To make your reports accessible, you can add a conditional layout that shows list or crosstab equivalents of the chart when the accessibility features are enabled for the report output.


To set up this conditional layout, use a conditional block that contains the list or crosstab and the report function **IsAccessible**. The **IsAccessible** function is a Boolean function that returns **Yes** (or true) when the accessibility features are enabled for the report output and **No** (or false) when the accessibility features are not enabled.



Therefore, the list or crosstab becomes conditional and appears only when the accessible report output option is enabled. In addition, you should add alternate text for the chart object so that screen readers can let users know that an accessible list or crosstab follows.

Procedure

1. Open IBM Cognos Report Studio with the sample GO Sales (query) package.
2. Create a new report with a pie chart.
3. Add data items to the chart. From the **Source** tab , do the following:
 - Expand **Sales (query)** and **Sales** and then insert **Quantity** in the **Default measure** area.
 - Expand **Products** and insert **Product line** in the **Series (Pie Slices)** area.
4. Run the report to see your chart.
5. Add alternate text for the pie chart:
 - Select the chart and, in the **Properties** pane, double-click the **Alternate Text** property.
 - Select **Specified text** and click the ellipsis button.

- Type default text for the chart, such as
A pie chart shows the quantity of sales by product line as a percentage of total sales. An equivalent list is below.

If you want to add the alternate text in additional languages, click the add button .

6. From the **Toolbox** tab , insert a **Conditional Blocks** object below the chart.
7. Select the conditional block and, from the **Properties** pane, double-click the **Block Variable** property.
8. Under **Variable**, select **New boolean variable** and type a name for the variable, such as **accessibility_condition**.
9. In the **Report Expression** dialog box, specify the expression that defines the variable:
 - From the **Functions** tab , expand **Report Functions** and insert the **IsAccessible** function to the **Expression Definition** box.
 - Type a closing bracket at the end of the function **IsAccessible ()** and click **OK**.
10. Select the conditional block and in the **Properties** pane, change the **Current Block** property to **Yes**.
11. From the **Toolbox** tab, add a list inside the conditional block.
12. Add the same data items from the chart to the list. From the **Source** tab, do the following:
 - Expand **Sales (query)** and **Products** and insert **Product line** in the list.
 - Expand **Sales** and insert **Quantity** as the second column in the list.
13. Add summary text for the list
 - Select the list and in the **Properties** pane, double-click the **Summary Text** property.
 - Select **Specified text** and click the ellipsis button.
 - Type default text for the list, such as
The first column lists all product lines and the second column lists sales quantities.

If you want to add the alternate text in additional languages, click the add button.
14. Select the conditional block and in the **Properties** pane, change the **Current Block** property to **No**.
15. From the **Run** menu, click **Run Options** and select the **Include accessibility features** check box.
16. Run the report.

Results

Because we just chose to include the accessibility features, you see both the chart and the list. Also, when a screen reader encounters the image for the chart, it reads the alternate text that you added.

If you clear the **Include accessibility features** check box and run the report again, you see only the chart.




Figure 66. Report showing both a pie chart and a list

IBM and accessibility

See the IBM Accessibility Center for more information about the commitment that IBM has to accessibility.

The IBM Accessibility Center is available online at <http://www.ibm.com/able>.

Appendix B. Troubleshooting

This appendix describes some common problems you may encounter.

For more troubleshooting problems, see the *IBM Cognos Business Intelligence Troubleshooting Guide*.

Problems Creating Reports

The topics in this section document problems you may encounter when creating reports.

Division by Zero Operation Appears Differently in Lists and Crosstabs

If you have a list that accesses a relational data source, a calculation containing a division by zero operation appears as a null value, such as an empty cell. In a crosstab, the division by zero operation appears as /0.

This happens when the **Avoid Division by Zero** property is set to **Yes**, which is the default.

To have a consistent display of null values in lists and crosstabs, define an if-then-else statement in the expression in the crosstab cell that changes the value /0 to the value null.

Application Error Appears When Upgrading a Report

When upgrading a report, the following error appears if the report contains data items in the page layout that are not in a data container:

RSV-SRV-0040 An application error has occurred. Please contact your Administrator.

This error occurs when IBM Cognos BI cannot determine the query reference for a data item. Such data items are identified by a small, red circle with a white x icon that appears in the lower left corner.

To correct the error, drag the data items into a container. If the container is a list, we recommend that you drag the data items into the list page header or footer, or the overall header or footer. If you want to see the first row of the item on each page or in the overall report, drag the item to the list page header or overall header. If you want to see the item's last row on each page or in the overall report, drag the item to the list page footer or overall footer.

Tip: If a header or footer does not exist, create it.

Nested List Report Containing a Data Item That is Grouped More Than Once Does Not Run After Upgrade

When you upgrade a nested list report that contains a data item that is grouped in both lists, the report does not run.

The following error occurs when the report is run against a dimensional data source and both lists are using the same query. This error does not occur if the report is run against a relational data source.

OP-ERR-0199: The query is not supported. The dimensions on the edge are inconsistent. The dataItems from dimension="[Product line]" must be adjacent.

For example, you have a list that contains the grouped items Product line and Product type and a nested list that contains the data items Year, Quarter, Product line, and Unit sale price. Year, Quarter, and Product line are grouped items in the nested list.

To resolve the issue, delete the data item that is grouped in both lists from the inner list.

Procedure

1. Click anywhere in the report.
2. In the **Properties** pane, click the select ancestor button and click the **List** link that represents the inner list.
3. Double-click the **Grouping & Sorting** property.
4. In the **Groups** pane, select the data item that you want and click the delete button.

Background Color in Template Does not Appear

When creating a Query Studio template in Report Studio, if you add a list object and change its background color, the color change does not appear when you apply the template to a Query Studio report.

To work around this issue, do one of the following:

- Edit the style sheet (CSS) classes for lists in Report Studio.
- Do not add any objects to the page body when you are creating a Query Studio template.
- Leave the page body blank.

Subtotals in Grouped Lists

When using an IBM Cognos PowerCube that contains a ragged hierarchy, if you group on the first level in the hierarchy, subtotals may appear in the wrong place or show wrong values.

To resolve the issue, group on the second level.

Chart Labels Overwrite One Another

In Report Studio and Query Studio, if you define a chart and render it in HTML or PDF format using the default sizes, the axis labels of the chart may overwrite each other.

To avoid this problem, make the chart wider or taller by modifying the height and width properties of the chart or enable the **Allow Skip** property.

Chart Shows Only Every Second Label

You create a report that includes a chart. The **Allow Skip** option is set to false, but when you run the report, labels are skipped.

This can occur if there is not enough room for all labels and the options **Allow 45 Degree Rotation**, **Allow 90 Degree Rotation**, and **Allow Stagger** are also set to false. IBM Cognos BI has no options for making the labels fit, so it skips every second label.

The solution is to select either **Allow 45 Degree Rotation**, **Allow 90 Degree Rotation**, or **Allow Stagger**.

Chart Gradient Backgrounds Appear Gray in Internet Explorer

In Report Studio, you can define a custom palette for a chart that includes a gradient. When the chart is rendered in HTML format in Microsoft Internet Explorer, the chart background appears gray. This is an Internet Explorer issue.

To avoid this problem, select the chart and define the color white as the chart background.

For more information, see the Microsoft Knowledge Base article # 294714 at <http://support.microsoft.com>.

Metadata Change in Oracle Essbase Not Reflected in Reports and in the Studios

When there is a metadata change on the Oracle Essbase server, the change is not immediately reflected in the metadata tree in the studios. In addition, when a report is run, the report does not pick up the republished changes.

To view the new structure, you must restart the IBM Cognos Content Manager server.

Relationships Not Maintained in a Report With Overlapping Set Levels

In a report, the relationship between nested or parallel member sets at overlapping levels in the same dimension may not always be maintained.

For example, a named set in the data source that contains members from both a Year and Month member is nested under Year, but is not properly grouped by year.

In another example, an error message such as this appears:

OP-ERR-0201 Values cannot be computed correctly in the presence of multiple hierarchies ([Product].[B1], [Product].[Product]) that each have a level based on the same attribute (Product).

This problem occurs in the following scenarios involving non-measure data items X and Y, which overlap in the same dimension:

- X and Y together as ungrouped report details
- Y nested under X
- Y appended as an attribute of a group based on X

When using named sets, or sets that cover more than one level of a hierarchy, do not use sets from the same dimension in more than one place in the same report. They should appear on only one level of one edge.

Summaries in Query Calculations Include Nulls with SAP BW Data Sources

When using an SAP BW data source in IBM Cognos Report Studio, null values in the database are returned in the result set and the count summary function includes the empty cells in the following scenarios:

- A query calculation includes an arithmetic calculation where one or more NULL operands and an aggregation is performed on the calculation.
- The result of a query calculation is a constant, such as `current_time` and `current_date`.

The count summary function should normally exclude null values.

To avoid this problem, for the first scenario, ensure that both operands do not return null values. For example, the original expression is `[num1]+[num2]`. Instead, use the following expression:

```
if ([num1] is null) then ( 0 ) else ([num1])
```

```
if ([num2] is null) then ( 0 ) else ([num2])
```

There is no workaround for the second scenario.

Creating Sections on Reports That Access SAP BW Data Sources

SAP BW data sources may have problems with sections in reports under different circumstances:

If a section in a report uses the lowest-level query item in a ragged hierarchy, such as the children of the not assigned node, the following BAPI error may appear:

```
BAPI error occurred in function module BAPI_MDDATASET_SELECT_DATA. Value <valueName> for characteristic <cubeName> unknown
```

Lowest-level Query Item in a Ragged Hierarchy

The solution is to remove the section from the lowest-level query item.

Several Multicubes with SAP Variables

The solution is to use one SAP multicube when creating sections in reports.

Related concepts:

“Tips for Working with Ragged or Unbalanced Hierarchies” on page 278

In ragged or unbalanced hierarchies, some members that are not at the lowest level of the hierarchy may have no descendants at one or more lower levels. Support for these hierarchy gaps in relational data sources is limited. More complete support is provided for OLAP data sources, but some reports may still result in unexpected behavior.

Error Characters (--) Appear in Reports

When you run a report, you see two dash (--) characters in your report instead of values.

These characters may appear if you use an OLAP data sources other than PowerCube and Microsoft SQL Server 2005 Analysis Services (SSAS), and you apply aggregation to calculations and measures that use rollups other than Sum (Total), Maximum, Minimum, First, Last, and Count.

All other types of rollup either fail or return error cells, which typically display as two dash characters (--).

This problem occurs in, but is not limited to, the following:

- footers
- aggregate function
- summary filters and detail filters that use a summary
- detail, summary, and context filters that select more than one member of a hierarchy that is used elsewhere on the report

If you are working with a SSAS 2005 data source, these characters may also appear in summary cells if you use an OR filter in the summary. To avoid this problem, do not use OR filters in summaries.

Columns, Rows, or Data Disappear With SSAS 2005 Cubes

Microsoft SQL Server 2005 Analysis Services (SSAS) has a feature called AutoExists that removes tuples that have no facts at the intersection of two hierarchies of the same dimension.

Columns, rows, or data can disappear if you set the default member of a hierarchy to a member that does not exist with every other member in the dimension. To avoid this problem, change the default member that caused the disappearance to a member that exists with all other members in the dimension.

Columns, rows, or data can also disappear if members are specified that result in one or more non-existent tuples. There is currently no workaround for this scenario. For more information, see Microsoft Knowledge Base article #944527 at <http://support.microsoft.com>.

You may also encounter unexpected results if the default member of a hierarchy is a member that doesn't also exist in all other hierarchies in the dimension, and if you query members from different hierarchies in the same dimension.

For example a crosstab includes the following (using the Adventure Works cube):

- Rows: Generate([Adventure_Works].[Account].[Accounts],set([Balance Sheet],[Units])) nested with children([Adventure_Works].[Department].[Departments]->:[YK].[Department].[Departments].&[1]])
- Column: [Adventure_Works].[Account].[Account Number].[Account Number]
- Measure: [Adventure_Works].[Measures].[Amount]

You run the report and notice that the query renders with some blanks cells. You then apply the simple detail filter [Amount]>1 and run the report. Only row labels are displayed and all data and columns are missing.

In the Adventure Works cube, the [Account].[Accounts] attribute has a default member set to [Net Income]. When evaluating the GENERATE set expression, SSAS looks in the entire cube space and looks at all coordinates for the [Account]

dimension. These coordinates include both [Account][Account Type].&[] and [Account].[Accounts].[Net Income]. Because these two coordinates don't exist within the same hierarchy, SSAS returns an empty set.

To avoid this problem the SSAS administrator must set the default member in the cube to a member that exists in all other hierarchies.

Function Unreliable with Sets

If you create an expression that uses the descendants function with sets, you may encounter unpredictable results. Some expected members may be missing or may have blank captions or labels.

This problem occurs if the descendants function uses a set as its first parameter instead of a single member and if the descendants function is nested under another data item from the same hierarchy.

To avoid this problem, replace the first parameter in the descendants function with the function `currentmember(H)`, where H is the hierarchy of the desired set and under which the expression is nested. For example, use `descendants(currentmember(H))`.

Searching for values might return unexpected results

In the expression editor, when searching for values for a data item, the results you obtain might contain unexpected results if the data item is not a string data type. Because you can edit the expression for a data item, IBM Cognos Business Intelligence cannot determine with certainty what the data type is.

Therefore, IBM Cognos Business Intelligence guesses the data type of the data item by looking at its aggregate and rollup aggregate set.

Related tasks:

“Browse or Search the Values of a Data Item” on page 247

When building expressions in the expression editor, you can browse the data of a data item. This is useful when you do not know how a particular value is stored in the database. For example, you want to filter a report so that it shows data for only New South Wales. The actual value in the database for New South Wales is NSW, and this is what you must insert in the filter expression to obtain the correct results.

Report Differences Between TM1 Executive Viewer and IBM Cognos Business Intelligence with TM1 Data Sources

When using an IBM Cognos TM1 data source, comparable reports created in an IBM Cognos Business Intelligence studio and in TM1 Executive Viewer may contain different cell values. This occurs because the TM1 Executive Viewer product uses an algorithm for selecting default members for non-projected dimensions that differs slightly from traditional OLAP clients.

To avoid this problem, when filtering your reports in the IBM Cognos Business Intelligence studios, use context filters that match the default selections shown in the Executive Viewer user interface. This ensures that the cell values in IBM Cognos Business Intelligence match the values in Executive Viewer.

Order of Metadata Tree Differs for TM1 Data Sources

When using an IBM Cognos TM1 data source, the order of members in the metadata tree of the **Source** tab of an IBM Cognos Business Intelligence studio may differ from the order shown in TM1 Architect.

By default, TM1 Architect renders members of hierarchies using a slightly different algorithm than does IBM Cognos BI. IBM Cognos BI automatically renders member metadata from TM1 data sources in hierarchical order.

From within TM1 Architect, if you want to see how an IBM Cognos BI studio will render a hierarchy, click the **Hierarchy Sort** button.

MSR-PD-0012 error when importing external data

When you try to import an external data file, you receive an MSR-PD-0012 error.

MSR-PD-0012: Unable to upload the specified external data file. It exceeds the permitted file size of "0(KB)", as specified by your system administrator.

This error occurs when the size of the file you are trying to import is greater than the value specified for the **Maximum external data file size (KB)** governor in the Framework Manager model.

To resolve the issue, the modeler must update the governor, save the model, and republish the package.

MSR-PD-0013 error when importing external data

When you try to import an external data file, you receive an MSR-PD-0013 error.

MSR-PD-0013: Unable to upload the specified external data file. It exceeds the permitted maximum number of rows "0", as specified by your system administrator.

This error occurs when the number of lines in the file you are trying to import is greater than the value specified for the **Maximum external data row count** governor in the Framework Manager model.

To resolve the issue, the modeler must update the governor, save the model, and republish the package.

Problems Calculating Data

The topics in this section document problems you may encounter when calculating or summarizing data.

Unexpected Summary Values in Nested Sets

If a report contains nested sets, summaries other than the inner set summaries may contain unexpected values. For example, you insert a summary in a crosstab that contains a set with years in the rows.

	Revenue
2012	1,495,891,100.9
2013	1,117,336,274.07
Total	2,613,227,374.97

Figure 67. Example of revenue numbers for the years 2012 and 2013

You then nest a product line set within years.

		Revenue
2012	Camping Equipment	500,382,422.83
	Golf Equipment	230,110,270.55
2013	Camping Equipment	352,910,329.97
	Golf Equipment	174,740,819.29
Total		2,613,227,374.97

Figure 68. Example of revenue numbers for the listed products for the years 2012 and 2013

Notice that the summary value does not change to represent the total of the new values. This occurs because the within set aggregation used with dimensional packages does not take into account sets that are nested below the set that is summarized.

To show the correct summary values, if the inner and outer sets do not belong to the same dimension, you can nest a copy of the inner summary item under the outer summary item, as follows.

		Revenue
2012	Camping Equipment	500,382,422.83
	Golf Equipment	230,110,270.55
	Total	730,492,693.38
2013	Camping Equipment	352,910,329.97
	Golf Equipment	174,740,819.29
	Total	527,651,149.26
Total	Total	1,258,143,842.64

Figure 69. Example of the combined aggregate set for the years 2012 and 2013

Null Results for Calculations Using SAP BW Data Sources

When using a SAP BW data source, the expression you use in your calculation is evaluated as a null value if your expression contains a null item. For example, in the calculation `some_expression = result`, the result is null if a row or column that the expression references includes a null value.

To avoid obtaining null values as the result of your calculations, suppress null values before you create the calculation.

Incorrect Results with IBM Cognos PowerCubes and Time Measures

If a report uses an IBM Cognos PowerCube data source and a combination of data items, you will encounter incorrect results.

The following combination of data items in a report that uses an IBM Cognos PowerCube data source will give incorrect results.

- a measure with a **Time State Rollup** set to **Average** or **Weighted Average**
- an aggregate (*members from time dimension*) expression
- an intersection with a member in a relative time hierarchy

To avoid incorrect results, do not use this combination in your reports.

Incorrect Results in Summaries When Using OLAP Data Sources

When using an OLAP data source, summaries that use for clauses give incorrect results.

This occurs because for clauses require access to the detail rows of the fact table. OLAP data sources do not have detail rows.

For example, this report uses a dimensionally-modeled relational (DMR) data source and contains the following summaries:

- mx: maximum ([Revenue] for [Year (ship date)])
- mx2: maximum (Aggregate([Revenue]) for [Year (ship date)])

Year	Quarter	Revenue	mx	mx2
2010	Q1 2010	221,704,705.31	252,408.9	235,750,316.25
	Q2 2010	222,143,384.57	252,408.9	235,750,316.25
	Q3 2010	235,750,316.25	252,408.9	235,750,316.25
	Q4 2010	234,754,397.59	252,408.9	235,750,316.25
2010 - Summary		914,352,803.72		
2011	Q1 2011	293,228,460.53	292,402.7	306,706,702.72
	Q2 2011	278,180,759.96	292,402.7	306,706,702.72
	Q3 2011	281,079,666.95	292,402.7	306,706,702.72
	Q4 2011	306,706,702.72	292,402.7	306,706,702.72
2011 - Summary		1,159,195,590.16		
2012	Q1 2012	344,124,267.07	363,575.08	391,874,462.51
	Q2 2012	391,874,462.51	363,575.08	391,874,462.51
	Q3 2012	378,118,012.54	363,575.08	391,874,462.51
	Q4 2012	381,774,358.78	363,575.08	391,874,462.51
2012 - Summary		1,495,891,100.9		
2013	Q1 2013	471,624,367.69	349,132.3	479,269,923.82
	Q2 2013	479,269,923.82	349,132.3	479,269,923.82
	Q3 2013	166,441,982.56	349,132.3	479,269,923.82
2013 - Summary		1,117,336,274.07		
Overall - Summary		4,686,775,768.85		

Figure 70. Example list report that uses a dimensionally-modeled relational data source and revenue for four years

Notice that the mx and mx2 values are different, where mx2 is based on visible data, but mx is not. This result is correct.

The following report uses an OLAP data source and contains the same summaries.

Year	Quarter	Revenue	mx	mx2
2010	2010 Q 1	221,704,705.31	235,750,316.25	235,750,316.25
	2010 Q 2	222,143,384.57	235,750,316.25	235,750,316.25
	2010 Q 3	235,750,316.25	235,750,316.25	235,750,316.25
	2010 Q 4	234,754,397.59	235,750,316.25	235,750,316.25
2010 - Summary		914,352,803.72		
2011	2011 Q 1	293,228,460.53	306,706,702.72	306,706,702.72
	2011 Q 2	278,180,759.96	306,706,702.72	306,706,702.72
	2011 Q 3	281,079,666.95	306,706,702.72	306,706,702.72
	2011 Q 4	306,706,702.72	306,706,702.72	306,706,702.72
2011 - Summary		1,159,195,590.16		
2012	2012 Q 1	344,124,267.07	391,874,462.51	391,874,462.51
	2012 Q 2	391,874,462.51	391,874,462.51	391,874,462.51
	2012 Q 3	378,118,012.54	391,874,462.51	391,874,462.51
	2012 Q 4	381,774,358.78	391,874,462.51	391,874,462.51
2012 - Summary		1,495,891,100.90		
2013	2013 Q 1	471,624,367.69	479,269,923.82	479,269,923.82
	2013 Q 2	479,269,923.82	479,269,923.82	479,269,923.82
	2013 Q 3	166,441,982.56	479,269,923.82	479,269,923.82
	2013 Q 4		479,269,923.82	479,269,923.82
2013 - Summary		1,117,336,274.07		
Overall - Summary		4,686,775,768.85		

Figure 71. Example list report that uses a dimensional data source and revenue for four years

In the example report, mx and mx2 values are now the same. Both summaries are based on visible data. The mx value is incorrect.

Incorrect results also appear for footer summaries.

To avoid this problem, when using OLAP data sources, ensure that the parameter that precedes the for clause is an aggregate function.

Problems Filtering Data

The topics in this section document problems you may encounter when filtering data.

Unexplained Discrepancies in Number Calculations

You might find unexplained discrepancies in number calculations due to round-off errors.

For example:

- You run regression tests and find differences in numbers. They are different only because of the rounding off of decimal places.
- You choose not display zeros in reports, but the zeros are displayed anyway because there are decimal places (0.00000000000000426, for example) that are rounded off to zero in reports.

Round-off problems are not specific to IBM Cognos software. They can occur in any environment where rounding off occurs.

Binary Round-Off Errors

Discrepancies in calculations might occur due to binary round-off errors. For example, if the number 1.1 is represented as a binary floating point number and your report format includes a large number of decimal places, the number 1.1 might actually be something like 1.099999999999997.

If your report is formatted to use only one decimal point, decimal round-off takes place, compensating for the binary round-off. So the number appears to be 1.1 when it is really 1.099999999999997. When the number is used in calculations, you might get round-off errors. For example, Microsoft Excel calculations use binary numbers (without rounding off decimal places) but formatting in reports shows rounded off decimal places, which can create small discrepancies.

Division Round-Off Errors

Calculations that involve division typically incur round-off errors, regardless of how the numbers are represented. Examples of such calculations are Average and Percent of Base.

Design Guidelines to Minimize Round-Off Effect

The best solution is to change the underlying database schema or cube model but that may not always be possible. Another solution is to minimize the round-off effect by following these guidelines when authoring reports and creating models in IBM Cognos Framework Manager and external OLAP cubes:

- Avoid storing data in floating point format whenever possible. This is especially true for currency values, which should be stored as either fixed-point decimals or as integers with a scale value such as 2.

For example, in a cube, the Revenue for Camping Equipment in 2012 is \$20,471,328.88. If revenue details are stored as floating point numbers, round-off errors might occur when revenue is calculated.

The round up errors might have slight differences, depending on the order of calculation. If revenue for Products is calculated first and revenue for Time is calculated second, you might get a different round-off error than if Time is calculated first and Products is calculated second.

Total revenue might be calculated as the number shown in the previous example. Or there might be slight discrepancies, for example, \$20,471,328.8800001 as opposed to \$20,471,328.88. The internal number might be slightly different than what is displayed. The number might even be for different runs of the same report, depending on the order that the OLAP engine uses for calculation.

- In reports, avoid division whenever possible. When division is unavoidable, try to do it as late as possible in the calculation process. For example, instead of `Total([Revenue]/1000)`, use `Total([Revenue])/1000`.
- When doing comparisons, add a margin to allow for round-off. For example, you may want `[Profit %]` to be a fractional value formatted as a percentage with no decimals. However, the filter `[Profit %]<>0` (or `[Profit %] NOT BETWEEN 0 and 0`) rejects zero values and may still return values that appear to be 0% after formatting.

To avoid this, filter in one of these two ways:

- [Profit %] NOT BETWEEN -0.005 and 0.005
- ([Profit %] <- 0.005) OR ([Profit %]> 0.005)

Note that 0.005 is equivalent to 0.5%, which displays as either 0% or 1%, depending on floating point precision losses.

In some cases, you may prefer control round-off errors by rounding values explicitly. For example, instead of [Profit %], use round([Profit %],2).

- Recalculate numbers every time instead of reusing calculations that might contain rounded off decimals.

There might be additional considerations for Microsoft Analysis Services 2005/2008, especially when comparing report results from different runs (as happens in Lifecycle Manager). Refer to Microsoft documentation for more information.

Error when filtering on a `_make_timestamp` column

You cannot filter on a `_make_timestamp` column. If you do that, the following error messages appear:

```
UDA-SQL-0114 The cursor supplied to the operation "sqlOpenResult" is inactive
UDA-SQL-0206 The OLEDB driver returned the following value: HRESULT= DB_E_CANTCONVERTVALUE
RSV-SRV-0025 Unable to execute this request
```

The solution is to apply the filter after aggregation, and not before.

Problems Running Reports

The topics in this section document problems you may encounter when viewing or running reports.

Report Runs Slowly

The following is a list of questions that will help you to troubleshoot a slow report.

- Does your IBM Cognos environment conform with the supported environments?
- Has the report always been slow or did it recently become slow?

If it recently became slow, can you identify an event that occurred just before the report began to run slowly? Events could include changes to configuration settings, changes to tuning settings, a recent upgrade where your previous settings have not been applied, an introduction of firewalls or proxies, changes to existing firewalls or proxies, changes to virus scans on temp directories, or temporary table space restrictions on the database. This event could have caused the change in report performance.

- Is the performance slow for all reports or just one report?

If all reports are slow, the issue may be due to your environment or database. If all reports from a specific package are slow, the issue may be due to the model design. If just one report is slow, the issue may be due to a specific report element.

- How many queries does your report contain?

The number of queries on the report will proportionally affect the report execution time.

- Does the report run slowly for everyone, or just for one user?

If the report runs slowly for just one user, the issue may be due to something in that user's environment, such as virus scanning, page file size or location settings, or their location on the network.

- Is the report burst or run often by many people?
If many people are running the same report at the same time, you may need to scale your environment or consider using dispatcher routing rules to direct all requests for a specific package or group of users to a specific server or server group. For more information, see the *IBM Cognos Business Intelligence Administration and Security Guide*.
- Do your queries require local processing?
The following report elements require local processing: crosstabs and charts, master relationships, unions or joins, multiple fact queries, bursting, and non-vendor specific functions. Local processing requires the IBM Cognos server to compute operations on the result set returned by the database, which can impact the SQL execution time.
- Does your environment use a Custom Authentication Provider?
Using a Custom Authentication Provider could cause a memory leak if the code is not destroying objects correctly.
- Have you reviewed the logs in the *c10_location/logs* directory and the audit logs?
They may help you identify the source of the problem. Monitoring your processes, such as the Java and Business Intelligence bus processes could also identify excessive memory use.
- Is your environment tuned correctly?
For more information, see the Performance Tuning Settings for IBM Cognos 8 Business Intelligence and the IBM Cognos 8 Business Intelligence Performance Tuning Cheat Sheet documents.
- Have you recently upgraded?
Ensure that any tuning settings that were applied to your previous installation are applied to the new environment. Ensure that your models have been verified, upgraded, and republished. Verify that the IBM Cognos Framework Manager governor that allows enhanced model portability at runtime is not enabled. Depending on your upgrade method, you may also need to open and save the reports again after upgrading.

The following tips may help you improve report performance.

- Change the order in which items are queried from the database. For more information, see “Working with Relational Queries” on page 250 or “Working with Dimensional Queries” on page 297.
- Create sections without creating master detail relationships. For more information, see “Divide Data into Sections” on page 232.
- Share queries between lists and repeaters.
You can share an identical query between data containers that use it. To share a query, data containers must be lists, repeaters, or repeater tables and must use the same grouping structure and list of properties. The data containers cannot be part of a master detail relationship. Sharing queries improves performance by minimizing the number of queries executed against the database.
To share a query, set the **Share Result Set** property for the data container to **Yes**.
- Convert queries to SQL. For more information, see “Convert a Query to SQL” on page 261 for relational reporting or “Convert a Query to SQL” on page 311 for dimensional reporting.

- Avoid using functions with limited support, as indicated by the quality of service indicators. For more information, see “Insert a Query Calculation” on page 264 for relational reporting or “Quality of Service Indicators” on page 555 for dimensional reporting.
- Be aware of the limitations of creating expressions with SAP BW data sources. For more information, see “Using Microsoft Excel Functions with SSAS 2005 Data Sources” on page 557.
- Use Select & Search prompts instead of value prompts if your list of prompts is long. For more information, see “Build Your Own Prompt and Prompt Page” on page 329.
- Provide your own prompt values in a prompt to avoid accessing the database. For more information, see “Specify Prompt Values” on page 338.
- Suppress null cells using filters. For more information, see “Suppress Null Cells Using Filters” on page 407.
- Set page breaks without creating master detail relationships. For more information, see “Page breaks, page sets, and page layers” on page 453.
- Do not modify IBM Cognos Analysis Studio set definitions. For more information, see “Analysis Studio Query Specification” on page 472.
- Do not put filters on non-identifiers.
- Avoid combining large hierarchy levels and sets in a drill-through report in a way that creates large queries. For more information, see “Recommendation - Drilling Down in Very Large Data Sources” on page 324.
- Use database functions when possible. For more information, see Appendix F, “Using the expression editor,” on page 575.
- Use fixed width objects in PDF reports by setting their **Size & Overflow** properties. For more information, see “Set List Properties” on page 67, “Set Crosstab Properties” on page 73, “Customizing Chart Properties” on page 108, or “Set Map Properties” on page 184.

The following are Proven Practices (www.ibm.com) documents that may help you improve your report performance.

- Performance Tuning Settings for IBM Cognos 8 Business Intelligence
- IBM Cognos 8 Business Intelligence Performance Tuning Cheat Sheet
- Writing Efficient OLAP Queries
- Cognos 8 Business Intelligence (BI) on IBM AIX® best practices
- IBM Cognos ReportNet and Java Heap

The *IBM Cognos Business Intelligence Installation and Configuration Guide* also includes a section on performance maintenance.

Summaries in a report do not correspond to the visible members

If a crosstab or chart created in IBM Cognos Report Studio using a dimensional data source has a context-dependent set function such as filter or topCount on an edge, summaries do not correspond to the visible members.

This problem occurs because a summary that has the **Use Set Aggregation** set to **Yes**, which produces an expression that contains the within set clause, uses a set that is dependent on the members that it intersects with on the opposite edge. For example, the following crosstab has the top three products returned as columns. The expression used to generate the columns is

topCount ([Product],3,[Return quantity])

where [Product] is the level.

Return quantity	BugShield Lotion	BugShield Extreme	Sun Shelter 30	Total	Minimum
Americas	25,219	19,870	13,814	62,392	17,303
Asia Pacific	22,822	19,171	6,389	54,758	12,765
Northern Europe	8,325	14,634	4,065	32,936	8,325
Central Europe	17,627	13,854	14,089	45,570	13,854
Southern Europe	7,196	4,726	5,401	20,220	5,790
Total	81,189	72,255	43,758	215,876	58,037
Minimum	7,196	4,726	4,065	20,220	5,790

Figure 72. A crosstab showing that the summary values for all rows do not correspond to the visible members.

The summary values for **Total** and **Minimum** for all rows except **Central Europe** do not correspond to the member values in the crosstab. This means that the top three products returned in all regions except for Central Europe are not Bug Shield Lotion, Bug Shield Extreme, and Sun Shelter 30. Note that the summary values for **Total** and **Minimum** for all columns do correspond to the visible member values. That is because those summary values represent the total and minimum quantities returned for those three products in each region.

You can see what the top three products returned in each region are by dragging the columns to the right of the rows.

Americas	BugShield Lotion	25,219
	BugShield Extreme	19,870
	TrailChef Water Bag	17,303
	Minimum	17,303
	Total	62,392
Asia Pacific	BugShield Lotion	22,822
	BugShield Extreme	19,171
	Single Edge	12,765
	Minimum	12,765
	Total	54,758
Northern Europe	BugShield Extreme	14,634
	Star Peg	9,977
	BugShield Lotion	8,325
	Minimum	8,325
	Total	32,936
Central Europe	BugShield Lotion	17,627
	Sun Shelter 30	14,089
	BugShield Extreme	13,854
	Minimum	13,854
	Total	45,570

Figure 73. A single-edge crosstab showing the Total Returned Products and Minimum Returned Products for each region

To obtain summary values that reflect the visible members, modify the expression of the data item containing the context-dependent set function so that it includes a tuple that is locked to the default member of every hierarchy that appears on the opposite edge. For this example, modify the expression to the following:

```
topCount ([Product],3,tuple([Return quantity], defaultMember([Retailer site])))
```

where [Product] is the level and [Retailer site] is the hierarchy.

When you run the report, all summary values reflect the visible members in the crosstab.

Return quantity	BugShield Lotion	BugShield Extreme	Sun Shelter 30	Total	Minimum
Americas	25,219	19,870	13,814	58,903	13,814
Asia Pacific	22,822	19,171	6,389	48,382	6,389
Northern Europe	8,325	14,634	4,065	27,024	4,065
Central Europe	17,627	13,854	14,089	45,570	13,854
Southern Europe	7,196	4,726	5,401	17,323	4,726
Total	81,189	72,255	43,758	197,202	42,848
Minimum	7,196	4,726	4,065	17,323	4,065

Figure 74. A crosstab showing the return quantity of products in different regions of the world

Cannot Find the Database in the Content Store (Error QE-DEF-0288)

You cannot retrieve data from the selected database when running a report from IBM Cognos Query Studio, IBM Cognos Connection, or Report Studio.

The following error message appears:

QE-DEF-0288 Unable to find the database...

If this error does not occur when you are logged on as an administrator, then to solve the problem, ensure that the user has permissions to the signon embedded. If this error always occurs, the data source has not been created. Create the data source with the name mentioned in the error message.

Parse Errors When Opening or Running an Upgraded Report

Earlier versions of ReportNet and IBM Cognos Business Intelligence included the `cast_date` function for reports that run on an Oracle database. This function does not exist for Oracle in IBM Cognos 8.1.2 MR1 and later versions. If a report that uses an Oracle database includes the `cast_date` function, parse errors will be received when you try to open or run the report.

Overflow Error Occurs When a Value in a Crosstab Is More Than 19 Characters

In a crosstab report, values support a maximum of 19 characters, including the decimal point. If a value exceeds 19 digits, an overflow error occurs. By default, the decimal precision is set to 7 digits, which restricts the number of integers to 11 digits.

To use more than 11 integers, you must edit the `qfs_config.xml` file in the `c10_location\configuration` directory. For more information, see the section about reducing decimal precision in the *IBM Cognos Business Intelligence Administration and Security Guide*.

The ORA-00907 Error Appears When Running a Report


When using an Oracle 9.2 data source, under certain circumstances, multiple or nested join operations may fail and produce the following error.

ORA-00907: missing right parenthesis

A query that uses both a left outer join and an ON clause condition returns zero values instead of null values.

A Report or Analysis Does Not Run Because of Missing Items

You attempt to run a report or analysis and a message indicates that one or more items are missing or changed. Each missing item is listed by its MUN (member unique name). The MUN includes the complete path within the hierarchy for the

item. When you place your cursor on an item in the **Source** tab , the MUN for that item is displayed in a tooltip. This situation may occur if members have been removed from or changed in the data source. It may also occur when you attempt to run a report that uses items to which you do not have access. For example, an administrator may create an analysis that includes items that you do not have the correct permission to access.

The solution is to find a suitable replacement in the **Source** tab, and drag it to the **New Item** column. The report or analysis will then run.

Cannot View Burst Report

When you burst a report, each burst output is sent to the associated list of recipients.

If a list of recipients contains invalid entries, the following occurs:

- The burst output is not saved to IBM Cognos Content Manager. Consequently, you cannot view the burst output in IBM Cognos Connection.
- If you choose to send the output by email, only valid recipients will receive an email. Although the output is sent as an attachment if you select the **Attach the report** check box, no link is generated if you select the **Include a link to the report** check box.
- The following error message appears in the run history for the report, where parameter 1 is the burst key, parameter 2 is the list of recipients, and parameter 3 contains the error messages returned by Content Manager:

An error occurred while saving the output for the burst instance <param type="string" index="1"/> with the recipients (<param type="string" index="2"/>). Here are the details: <param type="string" index="3"/>

Note: The list of recipients includes both the valid and invalid recipients.

For example, a report is set up to burst on Country or Region, and the recipients are managers. Running the report produces the following countries and regions and recipients:

- Canada: John, Mary
- US: Peter, Frank
- France: Danielle, Maryse

Frank is an invalid recipient. The burst outputs for Canada and France are saved to Content Manager, but not the U.S. output. If you choose to send an e-mail to each recipient and you selected the **Include a link to the report** check box, the e-mail to Peter will not contain a link to the output for US. The error message that is generated will contain Peter and Frank as values for parameter 2 with no indication as to which is invalid.

Procedure

1. View the error message in the run history for the report.
2. From the list of recipients, determine which recipients are invalid.
You may need to consult with your administrator to find out which recipients are invalid.
3. Correct or remove the invalid recipients.
Correcting or removing invalid recipients will depend on how the list of recipients was defined, such as through a calculated field or a burst table.
4. Run the report again.

A report upgraded from ReportNet does not retain its original look

When you upgrade a report to IBM Cognos Business Intelligence, a new style sheet is applied that changes the look of the report.

To preserve the formatting that was used in the original report, you can select a different style sheet. This retains the original look of the report and specifies that any new items added to the report, such as list columns or crosstab levels, have the original formatting applied to them.

Procedure

1. In IBM Cognos Report Studio, from the **File** menu, click **Report Properties**.
2. Click **Report styles** and select **1.x styles**.

Measure Format Disappears in SSAS 2005

Microsoft SQL Server 2005 Analysis Services (SSAS) does not propagate formatting through calculations. IBM Cognos compensates for this whenever possible, but cannot guarantee to do so in all cases. As a result, if you are working with a Microsoft SSAS cube, any calculation (other than a non-count summary) that is based on or intersects with a formatted measure, such as a currency, may lose the measure format. This may also happen if you use a detail filter or context filter (slicer).

For example, a crosstab includes members on one edge and a measure with formatting, such as a currency symbol and decimal places, applied on the other edge. When you run the report, you see the formatting for each cell. However, if you add a detail filter, such as `measure > 1` and run the report, all the formatting disappears.

Additionally, the fine details of the MDX generated by IBM Cognos Business Intelligence can change from release to release. As the SSAS behavior depends on the MDX generated, the loss of formatting in reports might not occur in a future release.

To avoid this problem, specify explicit formatting for the affected row, column, or cell.

Drill-through Links are Not Active in the Safari Browser

When viewing a PDF report in the Macintosh Safari browser, you cannot open hyperlinks. This is because the Macintosh Safari browser does not have the necessary Adobe Acrobat plug-in.

To avoid this problem, use the HTML format when creating drill-through reports that may be viewed in Safari.

Data Does Not Appear in a Target Report or the Wrong Data Appears

If no data appears when you drill through to a target report or if the wrong data appears, the problem might be data source conformance. The business keys might be different or might be mismatched.

For example, the business key for Camping Equipment might be 100 in the data source for the source report and 1 in the data source for the target report, in which case no data appears in the target report. Another example might be that the business key for Camping Equipment is 100 in the data source for the source report but, in the data source for the target report, 100 is the business key for Golf Equipment, in which case the wrong data appears in the target report.

To solve the problem, ensure that business keys have the same value in both data sources. If there are cases where data does not appear to match, contact your database administrator or data modeler.

For more information about data source conformance, search for "conformed dimensions" and "business keys" in the *IBM Cognos Transformer User Guide*.

You might also want to see "Unexpected or Empty Results When Drilling Through" on page 521.

Related concepts:

"Conformed Dimensions" on page 436

If you work with more than one dimensional data source, you may notice that some dimensions are structured the same, and some are not.

"Business Keys" on page 437

When drill-through access is defined from a member to a relational value, the business key of the member is passed by default.

A Running Total in Grouped Reports Gives Unexpected Results

You have a running total calculation in a grouped report that returns unexpected values.

Because tabulation of the running total calculation depends on the order in which the grouping is executed, you must ensure that the grouped totals are tabulated before applying the running total.

To ensure that the grouping is executed in correct order, define a running total calculation as a freestanding calculation outside the query subject in IBM Cognos Framework Manager, and ensure that the Regular Aggregate property is set to Automatic.

This may also be an issue with other running, moving, and ranking aggregations.

Recursive evaluation error

You run a report and encounter the following error.

```
PCA-ERR-0057 Recursive evaluation has exceeded limit. Calculated member trace: COG_OQP_USR_Aggregate
COG_OQP_INT_m2: COG_OQP_INT_m1: COG_OQP_USR_Aggregate(Retailer Type): COG_OQP_INT_m2: COG_OQP_INT_m1
```

COG_OQP_USR_Aggregate(Retailer Type): COG_OQP_INT_m2: COG_OQP_INT_m1: COG_OQP_USR_Aggregate(Retailer Type)
COG_OQP_INT_m2: COG_OQP_INT_m1

You may encounter this error when two or more data items form a recursive evaluation. For example, in this error, the calculation of Aggregate(Retailer Type) is dependent on a column expression while at the same time the column expression is dependent on Aggregate(Retailer Type). Therefore, the cyclic relationship cannot be resolved.

To avoid this problem, ensure that calculations do not have cyclic relationships.

Arithmetic Overflow Error When Running a Report in PDF Format

If you use a Microsoft SQL Server 2005 data source and your report includes aggregations, you may encounter the following error when you run your report in PDF format:

RQP-DEF-0177 An error occurred while performing operation 'sqlOpenResult' status='-28'. UDA-SQL-0114 The cursor supplied to the operation "sqlOpenResult" is inactive. UDA-SQL-0564 [Microsoft OLE DB Provider for SQL Server] Arithmetic overflow error converting expression to data type int. (SQLSTATE=22003, SQLERRCODE=8115)

This error occurs because the action is performed in the database, and the database data type is too small.

This error did not occur in IBM Cognos Business Intelligence version 8.3 or earlier because aggregation was processed locally, by the Business Intelligence server. In version 8.4 or later, aggregation is processed at the database level.

To avoid this problem, increase the size of the the database data type.

RQP-DEF-0177 An error occurred while performing operation 'sqlPrepareWithOptions' status='-69' UDA-SQL-0043 Error

You cannot run a report in IBM Cognos Report Studio or IBM Cognos Query Studio, and the following error messages appear.

RQP-DEF-0177 An error occurred while performing operation 'sqlPrepareWithOptions' status='-69' UDA-SQL-0043 The underlying database detected an error during processing the SQL request.[NCR][ODBC Teradata Driver][Teradata Database] Partial string matching requires character operands

These error messages do not indicate an IBM Cognos Application Firewall problem.

There is a problem with your data source not converting numeric data items. Ask your administrator to consult the topic *Enable Conversion of Numeric Search Keys to Strings in Queries* in the *IBM Cognos Business Intelligence Administration and Security Guide*.

Unable to View Active Reports in Mozilla Firefox

When you try to view an active report in the Mozilla Firefox browser, you may see a blank page or the following message.

Your report is ready and will download to your Web browser in a few moments.

However, the report never appears. This problem occurs in the following scenarios:


- You try to open the saved output of an active report in IBM Cognos Connection.
- You try to run an active report from within IBM Cognos Report Studio.

The issue is with the UnMHT add-on, and was reported on the UnMHT Warehouse Web site.

A solution was implemented for each scenario to work around the issue when using the Mozilla Firefox browser.

- When you try to view an active report in IBM Cognos Connection, instead of opening directly, the download dialog box appears, prompting you to open or save the report.

- In Report Studio, the default action is **Download Active Report** when clicking

the run report button .

Note that if you click the drop-down arrow and choose **Run Active Report**, the report will not render.

Problems with viewing saved Active Report output in Mozilla Firefox 8 or later versions

When you try to view saved Active Report output in Mozilla Firefox 8 or later, you receive errors. The problem also occurs when you try to insert a saved active report in a workspace in IBM Cognos Workspace.

No problems occur when you use an earlier version of Firefox. In Firefox 8 and above, you see the following errors:

Error: ReferenceError: HTMLISIndexElement is not defined

Error: TypeError: _IS1 is undefined

The problem occurs because HTMLISIndexElement was deprecated as of Firefox 8. To resolve the problem, rerun the active report and create a new saved output version using IBM Cognos Business Intelligence 10.2.1 or later.

Tip: If you must rerun many active reports, you can create a job in IBM Cognos Connection to run multiple reports. For more information, see the *IBM Cognos Connection User Guide*.

Problems with large SAP BW queries

When you are working with an SAP BW data source, if your report includes a data set greater than 1,000,000 cells, you might encounter an XQE error.

XQE-CON-0007 XQE error encountered: XSB-ERR-0022 Execution of MDX failed: XSB-ERR-0038 SAP Error executing BAPI BAPI_MDDATASET_SELECT_DATA: com.cognos.xqe.data.providers.olap.sbwodp.bapi.JBapiSAPException: RFC Error: MDX result contains too many cells (more than 1 million).

To avoid this error, set the **Processing** property for the query to **Limited Local**. This option allows the report to process locally.

Master Detail or Burst Reports with Charts or Crosstabs May Result in Denial of Service

When running a master detail or burst report that includes a chart or crosstab, disk space exhaustion may cause the report or other requests to fail. A large set of burst keys or master rows may produce one or more charts per detail, resulting in many master detail executions. This may cause the temp folder to accumulate many gigabytes of temporary files containing data required for successful chart rendering.

To avoid this issue, we recommend that you test large master detail or burst reports that include charts or crosstabs to determine the potential peak disk requirements for the report.

PCA-ERR-0087 error when you run a large report

You run a large report and you receive a PCA-ERR-0087 error that indicates that the report exceeds the maximum number of tuples allowed.

PCA-ERR-0087 The "crossJoinSet" operator is not applicable. The limit on the number of tuples per edge has been exceeded (<value>).

This error appears when there is an item in a query that has no relationship to the rest of the data or does not make sense in the query.

To resolve the problem, review the query for unrelated items. If an item is found, redesign the query or apply a filter on the item to reduce the number of results returned.

If you still receive the error, ask your administrator to modify the maximum number of tuples setting in IBM Cognos Business Intelligence. The setting is an XML attribute named `maxTuplesPerEdge`. For more information, see the *IBM Cognos Business Intelligence Administration and Security Guide*.

Differences in the appearance of charts that are run in different formats or on different operating systems

IBM Cognos Report Studio charts can appear differently when reports are run in different formats or on different operating systems. For example, donut and pie charts can appear smaller in reports that are run on the Linux on System z[®] operating system compared to the Windows operating system.

The differences in appearance occur only with Report Studio default charts. Report Studio legacy charts are not affected. When default charts are rendered in HTML or PDF, the following font-related problems might occur.

- The font that is used in HTML output is different than the font used in PDF output.
- Some chart items appear misaligned. For example, a pie chart might show smaller pies in PDF output than in HTML output.
- The font that is used in the chart is different from the expected font.
- The font that is used in the chart is different when you run the chart in different operating systems.

There are two possible causes to the font-related problems.

- The Java Runtime Environment (JRE) used by IBM Cognos Business Intelligence did not find the font that is specified in the chart, and substituted the font with a different font.
- An unknown default font is specified.

To resolve the problem, ask your administrator to configure JRE to find the installed fonts on the Cognos BI server. There are two ways that you can configure JRE to find the installed fonts:

- Copy the installed fonts to the `jre/lib/fonts` folder.
For example, to use the Cognos BI default font Andale WT, copy `Andalewt.ttf` from the `c10_location/bin/fonts` folder to `jre/lib/fonts`.
- Configure the JRE font search path to point to the location where the fonts are installed.

On AIX, set the shell environment variable `JAVA_FONTS=<list of directories>`

Tip: Setting this variable is equivalent to setting the properties `java.awt.fonts` and `sun.java2d.fontpath`.

The default fonts configuration in your Cognos BI server default style sheet can also cause font-related problems, particularly when the operating system is UNIX. On UNIX systems, fonts must be purchased and installed. To ensure that a specific font is used, perform one of the following tasks:

- Ask your administrator to update the Cognos BI server default style sheet to reflect the fonts that are installed on the server.
- Update the chart fonts that are used in your report to use that font, and do not rely on any default fonts.

Tip: For information about changing the default font for reports, see the technote *How to change the default font for reports in Cognos 8 BI* in the IBM Support Portal (<http://www.ibm.com/support/>).

Out-of-memory errors with reports that are run in interactive HTML format

Out-of-memory errors occur when you run a report in interactive HTML format. The errors do not occur when you run the report in other formats, such as PDF or saved HTML.

Out-of-memory errors occur in reports that contain many objects that require memory intensive processing, such as crosstabs and charts that are linked together with master-detail relationships. Running reports in interactive HTML can consume more memory than running reports in other formats. When a report is run in interactive HTML, data sets are kept in memory for all pages in the report. For report formats like PDF, data sets are released from memory after the report is rendered.

Under certain conditions, you can exceed the memory limitations of a 32-bit configuration of the Cognos BI server report server component when you interact with an interactive HTML report. For example, scrolling through a report page by page or drilling up or drilling down can consume more memory and processing capacity in interactive HTML than in other output formats.

Charts in PDF Output Show Unexpected Results

Charts, when viewed in PDF output, have different levels of interaction support, depending on the version of Adobe Acrobat Reader and the style of chart element.

Adobe Reader version 5 does not support tooltips. Drill up and down and Go to links have limited support, due to technical limitations. Only rectangular areas in charts, such as bars, columns, horizontal labels on the axis, or legend labels can be enabled for drill or Go to interaction. Non-rectangular areas, such as pie slices in pie charts, cannot be enabled for drill or Go to interactions.

Adobe Reader version 6 and 7 supports tooltips, drill up and down, and Go to links for all chart types. When chart elements overlap or are separated by only a few pixels, the interactive region may be smaller than the area shown.

Result set of a multi-fact query contains blanks

The result set of a multi-fact query contains blanks in some columns, even though there is a conformed dimension that should join the records from both fact tables.

When IBM Cognos Business Intelligence processes a multi-fact query, it breaks it up into two single fact queries (each with items from a single star in the star schema), then stitches the results of both of those queries together to create a single result set. You can see the two queries and stitching in the native SQL generated for the multi-fact query in Report Studio.

Stitching these queries together is not the same as joining tables in the model. Stitching the two sides together requires a stitch key that exists in each single fact query as a unique value for the row. The rows from the two single fact queries are then matched 1:0, based on the stitch key values. The stitching must be 1:0. Otherwise, you can get double counting of measure data, or exclude rows that should be included. The stitching also means that it is possible for a row from one of the single fact queries to not have a corresponding row from the other single fact query, leading to blanks in the result set.

When the fact tables contain non-conformed dimensions between them, there is not a suitable stitch key among the query items selected. As a result, IBM Cognos BI creates one using RSUM, and joins the results of the two queries. For more information, see the topic Multiple-fact, Multiple-grain Query on Non-Conformed Dimensions in *Guidelines for Modeling Metadata Guide*.

When there is a conformed dimension, it is still possible to not have a suitable stitch key, depending on what items are used in the query and other model design factors. In such cases, IBM Cognos BI uses the conformed dimensions and the row numbers from the results of each query to create a stitch key. If one single fact query returns more rows than the other, there are blanks in the result.

To resolve the problem, it might be possible to avoid splitting the query by changing the model. For more information, see Resolving Queries That Should Not Have Been Split in the *Framework Manager User Guide*. If you cannot avoid splitting the query and the report needs these two result sets to be joined differently, create two separate, single-fact queries in Report Studio, create a join between them, and define the join links and cardinality as needed.

Cognos Statistics object is not displayed in a report

An IBM Cognos Statistics object is not displayed in a report.

Each removed statistical object is replaced with an image in the report:



Figure 75. Image that replaces statistical objects in upgraded reports

A warning also is displayed in the Upgrade Information window for each statistical object that is replaced with the image.

Beginning with IBM Cognos Business Intelligence version 10.2.1, IBM Cognos Statistics is no longer available.

To ensure that reports that were created in previous releases and that contain statistical objects run, statistical objects are removed when the reports are upgraded.

Tip: Queries, and their data items, that are associated to statistical objects are not removed from upgraded reports.

You can use IBM SPSS Statistics to perform statistical reporting and analysis.

Maps are missing when a report is run in IBM Cognos BI 10.2.2 or later

When a report that was created in IBM Cognos BI 10.2.1.1 or earlier, and contains maps, is run in IBM Cognos BI 10.2.2 or later, the maps are missing.

IBM Cognos BI 10.2.2 and later uses new maps. To fix existing reports that contain maps that come from earlier versions of IBM Cognos BI, the following choices are available:

1. You can continue to use the maps that are in earlier versions IBM Cognos BI. Ask your administrator to copy the map files from the earlier version of IBM Cognos BI to the current version of IBM Cognos BI that you are using.
2. You can upgrade your reports so that they use the new maps.

Related concepts:

“New maps in IBM Cognos BI 10.2.2” on page 182

IBM Cognos Business Intelligence 10.2.2 contains new maps that replace the maps that are in previous releases.

Problems When Drilling Through

The topics in this section document problems you may encounter when drilling through reports.

Cannot Drill Through Between PowerCubes Because MUNs Do Not Match

We recommend that business keys be unique throughout the dimension for PowerCubes. These keys are used as the source value for levels in a hierarchy of a dimension. If the values are not unique throughout the dimension, the corresponding Category Code values may be generated with tildes.

For example, if a category for the Product Line level has a source value of 101 and a category in the Product Type level has a source value of 101, the Category Code value for the Product Type level is automatically generated with a unique value such as 101~245. The Category Code values are used in the Member Unique Name (MUN) for each member, for example, **[Sales and Marketing].[Products].[Products].[Product type]->:[PC].[@MEMBER].[101~245]**.

Because these values are generated automatically, they cannot be guaranteed from one cube build to the next or in a build for another cube with the same dimension structure using the same source values. Therefore, drilling from one PowerCube to another on what appears to be the same member might not work since the MUNs might not match.

If the MUNs do not match, consult the cube modellers to see if the business keys can be made unique throughout the dimension. If this is not likely, or might take some time to resolve, you can use calculations to pass the source value from one PowerCube to another for drill-through.

For more information about drill-through access, see the Drill-Through Access chapter in the *IBM Cognos Business Intelligence Administration and Security Guide*.

Procedure

1. In the target report, create a filter with the following syntax: `filter([Hierarchy or Level], roleValue('_businessKey', [Hierarchy or Level])) = ?Parameter?)`

For example: `filter([Sales Cube].[Products].[Products].[Product type], roleValue('_businessKey', [Sales Cube].[Products].[Products].[Product type])) = ?Prod Type?)`

2. In the source report, create a Query Calculation which is used to pass the business key (source value) to the target report by mapping it to the target parameter in the drill-through definition. Use the following syntax:

`roleValue('_businessKey', [Hierarchy or Level])`

For example:

`roleValue('_businessKey', [sales_and_marketing].[Products].[Products].[Product type])`

Unexpected or Empty Results When Drilling Through

When you drill from a source report to a target report, there might be no data returned. This might be the correct result if there is no data that corresponds to the drill-through selections or if you do not have permission to view the data.

In other cases, if no data or the wrong data appears, the source item might not be mapped to the target correctly or the values in the data sources might not be conformed (the values do not match in both data sources).

If you have the necessary permissions, you can debug drill-through definitions by using the drill-through assistant from the **Go To** page (right-click the selection in the source report and select **Go To**). You can view the passed source values and the mapping to the target report parameters. You can use this tool for both authored and package drill-through definitions.

You might be able to correct the problem by modifying the parameter mapping in the drill-through definition. For example, when you drill from a cube to a relational data source, sometimes no data is returned or the wrong data is returned

because the business key values in the two data sources do not match. You can change the drill-through definition to pass the caption of the IBM Cognos PowerCube member instead of the business key, but you must also change the target report to filter on the corresponding string value and not the business key value.

However, it is best to ensure the data sources are conformed. In this example, the business keys in the cube should match the business keys in the relational source. Filtering on a key is more efficient than filtering on a larger string that may or may not be indexed in the database.

For more information on data source conformance, search for "conformed dimensions" and "business keys" in the *IBM Cognos Transformer User Guide*.

Procedure

1. Ensure that the target report filters on a string value that matches the caption being passed from the PowerCube.
2. Edit the drill-through definition as follows:
 - If the drill-through definition was created in IBM Cognos Report Studio, open the report, and go to the drill-through definition associated with the drill-through source object. On the parameter mapping page, select **Member Caption** in the **Property to pass** column.
 - If the drill-through definition was created in the source package, go to IBM Cognos Connection, **Drill-Through Definitions**, and open the package drill-through definition. On the **Target** tab of the drill-through definition, select **Member Caption** in the **Property to pass** column for the appropriate parameter.

Results

When you drill through, instead of the business key, the caption is passed to the target.

You might also want to see "Data Does Not Appear in a Target Report or the Wrong Data Appears" on page 514. For more information about drill-through access, see the Drill-Through Access chapter in the *IBM Cognos Business Intelligence Administration and Security Guide*.

Related concepts:

"Conformed Dimensions" on page 436

If you work with more than one dimensional data source, you may notice that some dimensions are structured the same, and some are not.

"Business Keys" on page 437

When drill-through access is defined from a member to a relational value, the business key of the member is passed by default.

Cannot Drill Through From a Relational Source to a Cube

By default, you cannot drill through from a relational data source to a cube. This is because a cube expects a Member Unique Name (MUN) as a parameter value and relational sources do not use MUNs.

Members have properties which include a business key and a caption. If either of these match data items within the relational source, drilling through can be performed as long as the cube target report is authored in Report Studio.

If the source data source has a query item, for example display name, that corresponds to a member property in the target cube, for example caption, you must create the parameter on the caption in the target report.

To pass the data item to the cube target, do the following:

- In the cube target report, create a parameter that accepts the caption of the member. This parameter should be created in a Query Calculation object from the **Toolbox** tab with the following syntax. Type the following

```
filter([ Hierarchy or Level],caption([Hierarchy of Level]) = ?Parameter?)
```

For example:

```
filter([sales_and_marketing].[Products].[Products].[Product line],  
caption([sales_and_marketing].[Products].[Products].[Product line])  
= ?Product Line?)
```

For more information about drill-through access, see the Drill-Through Access chapter in the *IBM Cognos Business Intelligence Administration and Security Guide*.

Calculations Do Not Appear in the Target Report

If you drill through to PowerPlay Studio from a report in Report Studio, Analysis Studio, or PowerPlay Studio, calculations on the edges in the target report might not appear.

For example, you have a target report with the calculation Personal Accessories+100 as a column in a crosstab report. When you drill through from a source report to the target report, if Personal Accessories is filtered out of the target report (Personal Accessories is not one of the items that is returned on the column edge), then the Personal Accessories+100 calculation does not appear. Personal Accessories has been filtered out of the target report and is not available to fulfill the calculation.

To see the calculations in the target report, ensure the items used in the calculations are returned in the result set (not filtered out). For more information and examples, see *Understanding Drill-Through Behavior in IBM Cognos 8* at developerWorks (www.ibm.com/developerworks).

Nested Crosstab Only Filters on Some Items

If you perform a parameter-based drill-through from a source report to a Report Studio target report with two or more dimensions nested on a row or column, you may encounter unexpected results depending on the filters applied to the target report.

For example, a target Report Studio report has the following two filters:

- [sales_and_marketing_mdc].[Order method].[Order method].[Order method type]=?Order Method Type?
- [sales_and_marketing_mdc].[Retailers].[Retailers].[Region]=?Region?

Order method type and Region both have filters, but Product line does not. A drill-through definition mapped to the appropriate parameters, in this case Order method type and Region, is created.

When the source report is run and the intersection of Outdoor protection, Northern Europe, and Telephone is selected to drill through to the target report, the order

method type and region display as expected, but all product lines are returned. This is because there are filters on Order method type and Region but not Product line.

For more information and examples, see *Understanding Drill-Through Behavior in IBM Cognos 8* at developerWorks (www.ibm.com/developerworks).

Data is Not Filtered in the Target Report After Drill-Through

You drill through to a target report, but no filtering occurs in the target report. For example, you drill through on a crosstab intersection of Camping Equipment and 2010 and expect to see only data for Camping Equipment for 2010 in the target report. Instead you see all products for all years. This occurs because the target report has no filters for the parameters that were passed.

To solve the problem, ensure that the target report has the correct filters. In the previous example, the correct filters in the target report are Product line and Year. Alternatively, you can enable Dynamic Drill-Through in a package-based drill-through definition.

Drill-through links in active reports do not work

When viewing an active report that contains drill-through links in Microsoft Internet Explorer 8 and later, the links do not work.

Clicking on a drill-through link produces an error like the following:

The search path "<drill_through_target_search_path>" is invalid. An object may contain invalid syntax, or an unsupported character, or the user account in the namespace may not have sufficient privileges. Check the object to ensure that the target destination location does not contain special characters.

Details

CM-REQ-4069 The property "na" is unknown. Replace it with a valid property.

When clicking a link in an active report, you are attempting to move from a local domain (the active report MHT file on your computer) to the IBM Cognos Business Intelligence server's domain. Internet Explorer views this as a potential risk. To resolve the problem, make the following changes to the security settings in Internet Explorer.

Procedure

1. Click **Tools, Internet Options**.
2. Click the **Security** tab.
3. Click **Trusted sites** and then click **Sites**.
4. In the **Add this website to the zone** box, type the IBM Cognos BI server's domain.
5. Click **Add** and then **Close**.
6. Click **Custom level**.
7. In the **Scripting** section, under **Enable XSS filter**, click **Disable** and then click **OK** twice.

Appendix C. Sample Reports and Packages

Sample reports are included with IBM Cognos Business Intelligence. When installed, you can find them in the **Public Folders** tab in IBM Cognos Connection.

The Sample Outdoors Company

The Sample Outdoors Company samples illustrate product features and technical and business best practices.

You can also use them for experimenting with and sharing report design techniques and for troubleshooting. As you use the samples, you can connect to features in the product.

The Sample Outdoors Company, or GO Sales, or any variation of the Sample Outdoors name, is the name of a fictitious business operation whose sample data is used to develop sample applications for IBM and IBM customers. Its fictitious records include sample data for sales transactions, product distribution, finance, and human resources. Any resemblance to actual names, addresses, contact numbers, or transaction values, is coincidental. Unauthorized duplication is prohibited.

Samples outline

The samples consist of the following:

- Two databases that contain all corporate data, and the related sample models for query and analysis
- Sample cubes and the related models
- A metrics data source including associated metrics and a strategy map for the consolidated company, and a model for Metric extracts.
- Reports, queries, query templates, and workspaces

To run interactive reports, scripts are required. To see all the reports included in the samples packages, copy the files from the samples content installation into deployment folder and then import the deployments into the IBM Cognos Business Intelligence product.

Security

Samples are available to all users.

The Sample Outdoors Group of Companies

To make designing examples faster, especially financial examples, some general information about The Sample Outdoors Company is useful.

To look for samples that use particular product features, see the individual sample descriptions in this section.

Revenue for The Sample Outdoors Company comes from corporate stores and from franchise operations. The revenues are consolidated from the wholly-owned subsidiaries. There are six distinct organizations, each with its own departments and sales branches. Five of these are regionally-based companies.

The sixth company, GO Accessories:

- Has its own collection of products, differentiated from the other GO companies by brand, name, price, color and size.
- Sells from a single branch to all regions and retailers.
- Functions both as an operating company based in Geneva, and as a part owner of the three GO subsidiaries in Europe.

The following diagram illustrates the consolidated corporate structure of the Sample Outdoors Company. The diagram also includes the percentage changes in ownership for GO Central Europe, and the reporting currency and GL (general ledger) prefix for each subsidiary. In year 1, GO Asia Pacific owns 60% of GO Central Europe, and in year 3, its ownership decreases to 50%. In year 1, GO Accessories owns 40% of GO Central Europe, and in year 3 its ownership increases to 50%.




Figure 76. Consolidated corporate structure of the Sample Outdoors Company

Each corporation in the Sample Outdoors Company has the same departmental structure and the same general ledger (GL) structure, as shown in the following table. Divisions may not report in the same currencies. For example, the Americas subsidiary reports in US dollars, but the Corporate division local currency reports in Canadian dollars, and the Operations division local currency is pesos.

Table 9. Departmental structure

Division (GL)	Department (GL)
Corporate (1700)	Sales (1720)
	Marketing (1750)
	IS&T (1760)
	Human Resources (1730)
	Finance (1740)
	Procurement (1710)
Operations (1800)	Production and Distribution (1820)
	Customer Service (1820)

Each corporation has a complete chart of accounts. Most of the accounts, such as those under non-personnel expenses, are at the department level, and contain only summary amounts. For example, although each marketing department has expenses, the cost is unspecified at the transaction level where marketing promotions occur.

Employees

The Sample Outdoors data contains a full list of employees in all divisions, departments, and locations.

Data is available for reports about bonuses (Global Bonus report) and sales commissions (Sales Commissions for Central Europe report), training (Employee Training by Year report), and performance reviews and employee satisfaction surveys (Employee Satisfaction 2012). If you use Metric Studio, sample metrics for human resources are also available.

In the GO Data Warehouse (analysis) package, groups of measures and the related dimensions are organized into folders. The employees are organized in hierarchies for region and manager, to make different kinds of aggregation easy to report on. Aggregation has been defined for the Employee Position Summary measures, so that Position count and Planned position count aggregate correctly at each level of time: monthly, quarterly, or yearly. For example, see the Planned Headcount report.

The employees are also listed in a sample LDIF file which could be used for any LDAP IBM product authentication including Tivoli®. This authentication directory is necessary for IBM Cognos Planning samples. No other samples depend on security profiles.

Sales and marketing

Data about sales and marketing is available for all of the companies in the Sample Outdoors group.

GO Accessories has richer details to support analysis examples. For example, see the Revenue vs % Profit Margin by Product Brand analysis, based on the Sales and Marketing cube. Marketing and sales campaigns are tied to the Sample Outdoors regional companies.

Overall, the GO companies have experienced solid growth across most product lines (Sales Growth Year Over Year), in all regions (Revenue by GO Subsidiary 2011), because of factors like an increase in repeat business and new or improved products, such as the high margin sunglasses product line. In the product lines sold by the five regional companies (all but GO Accessories) promotions have had mixed success (Promotion Success by Campaign, Bundle and Quarter). If you use Metric Studio, this can also be seen in the sample metrics.

Customer surveys

The data also contains information from customer surveys. For example, the product line that includes bug spray, sun screen, and so on has not been successful (Product Satisfaction - Outdoor Protection 2011) and a source of retailer dissatisfaction may be the level of customer service rather than the returns (Customer Returns and Satisfaction). If you use Metric Studio, this information can also be monitored in metrics.

Sales outlets

Revenue from the corporate outlets is available at the transaction level. Revenue from the franchise outlets is available at the consolidated level only (Sales and Marketing cube). Metrics about retailers show that the number of new retail outlets has dropped over the time period covered by this data.

GO Accessories sells worldwide, and sells only accessories. Transaction data for GO Accessories is the primary source for analysis of product by brand, color and size. The other five subsidiaries in the group of companies are regional and sell all product lines for retailers in their region. For example, the report Top 10 Retailers in 2011 uses sparklines and list data to review revenues at the retailer level.

Sample Outdoors database, models, and packages

The Sample Outdoors Framework Manager models illustrate modeling techniques and support the samples.

The models are based on the GO data warehouse and the GO sales transactional database and are the basis for the sample reports and queries. Each model contains two packages for publishing analysis (dimensional) and query views of the data.

You must have access to Framework Manager, the modeling tool in IBM Cognos Business Intelligence, to look at the sample models. You may also need to set up the sample databases and connections.

GO Data Warehouse

The GO Data Warehouse model, `great_outdoors_data_warehouse.cpf`, is based on the database GOSALESDW. It contains data about human resources, sales and marketing, and finance, grouped into business areas. In the Database view, the three business areas are grouped into separate namespaces. The Database view contains a fourth namespace (GO Data) for the common information.

The Database view is very similar to the structure of the underlying database. All tables (database query subjects) are unchanged. This enables IBM Cognos BI to retrieve metadata directly from the package in most cases, instead of using a metadata call to the database. The following changes and additions have been made in the Database view:

- Joins have been added as necessary.
- To allow for aggregation at different levels of granularity, some model query subjects have been created. For example, see the relationships between Time and Sales or Sales fact.
- To allow single joins to be made between the lookup tables and each level in a dimension, lookup tables have been copied. For example, see the Products lookup tables.

The Business view contains only model query subjects, with no joins. The following changes and additions have been made in the Business view:

- Calculations were added to the model query subjects. For example, the time dimension contains language calculations.
- Where the database has multiple hierarchies, new dimensions have been created to organize each hierarchy. For example, the employee hierarchies are organized into several categories, such as manager and region.

The GO Sales transactional database

The GO Sales model, `great_outdoors_sales.cpf`, is based on the GOSALES database, which is structured as a transactional database. It contains principally sales data.

The Database view is very similar to the underlying database structure. The following changes and additions have been made in the Database view:

- To make it possible to join the fact tables to the time dimension, model query subjects and multipart joins have been used.
- Other joins have been added as necessary.

The Business view contains only model query subjects, with no joins. The following changes and additions have been made in the Business view:

- Calculations were added to the model query subjects.
- Model query subjects that were created in the Database view to enable joins on the time dimension have been linked as reference shortcuts.
- Where the database has multiple hierarchies, new dimensions have been created to organize each hierarchy.
- Sales Staff is a subset of the slowly changing Employee dimension. There is no unique Employee key in GO Sales, so a filter retrieves the current record only. This model does not use historical data.

The samples PowerCubes

The following cubes are delivered with the Sample Outdoors samples in English, French, German, Japanese and Chinese:

- `sales_and_marketing.mdc`
- `employee_expenses.mdc`
- `go_accessories.mdc`
- `go_americas.mdc`
- `go_asia_pacific.mdc`
- `great_outdoors_sales_en.mdc`
- `great_outdoors_7.mdc`

The samples packages

The Sample Outdoors samples include six packages. A brief description of each available package is provided.

Go Data Warehouse (analysis) is a dimensionally modeled view of the GOSALESDW database. This package can be used in all studios, including IBM Cognos Analysis Studio. Using this package you can drill up and down.

Go Sales (analysis) is a dimensionally modeled view of the GOSALES database. This package can be used in all studios, including Analysis Studio. Using this package you can drill up and down.

Go Data Warehouse (query) is a non-dimensional view of the GOSALESDW database. This package can be used in all studios except Analysis Studio, and is useful for reporting when there is no need for drilling up and down.

Go Sales (query) is a non-dimension view of the GOSALES database. This package can be used in all studios except Analysis Studio, and is useful for reporting when there is no need for drilling up and down.

Sales and Marketing (cube) is an OLAP package, based on the sales_and_marketing.mdc cube.

Great Outdoor Sales (cube) is an OLAP package, based on the great_outdoors_sales_en.mdc cube.

Note: The OLAP packages, Great Outdoor Sales (cube) and Sales and Marketing (cube), are not multilingual. The IBM_Cognos_PowerCube.zip archive contains five versions of each package; one in English, French, German, Japanese and Chinese.

Samples in the Sample Outdoors Sales (cube) package

The following report is found in the Sample Outdoors Sales (cube) package.

Consecutive Periods Comparison

This report shows the revenue and gross profit for Camping Equipment and Personal Accessories, as well as quantity for Camping Equipment, in two consecutive periods selected by the user.

Samples in the Sales and Marketing (Cube) Package

The following reports are some of the reports found in the Sales and Marketing (Cube) package.

Actual vs. Planned Revenue

This report shows the actual revenue versus planned revenue by order method and year. This report is also a target for the measure based scope drill-through from other reports in the same package.

This report uses the following features:

- lists
- filters
- multiple prompts

- grouping
- sorting
- summarizing

Historical Revenue

This prompted report shows a 13-month rolling forecast of monthly and year-to-date revenue.

This report uses the following features:

- filters
- cascading prompts
- combination charts
- axis titles

Revenue by Date Range

This report shows revenue for a date range that is specified on a prompt page.

This report uses the following features:

- lists
- crosstabs
- context filters
- custom headers and footers
- multiple prompts
- calculations

Revenue by Product Brand (2011)

This report shows the revenue and gross profit by product filtered by the product brand. There is always product turnover, so the report conditionally highlights products that are discontinued.

This report uses the following features:

- lists
- filters
- prompts
- combination charts
- bar charts
- HTML items
- grouping
- sorting
- axis titles

Same Month Prior Year

This report shows sales volume by product line in one or more months. The report is filtered by a prompt for month. The report generates totals for the selected months and for the same months in the prior year.

This report uses the following features:

- crosstabs

- prompts
- custom headers and footers

Selected Retailer Country or Region

This report uses the revenue from a selected country or region as a baseline value for a set of countries or regions. A chart shows the difference in revenue for each country and region as it compares to the base country and region. The report is filtered by a prompt for country and region.

This report uses the following features:

- crosstabs
- bar charts
- tables to control where objects appear

Top Retailers by Country or Region

This report shows the top 10 retailers by country or region. It is used as source for drill-through to the Total Revenue by Country or Region report.

This report uses the following features:

- crosstabs
- prompts
- filters
- line charts
- prompt pages
- query calculations
- calculations
- singletons
- bar charts
- custom headers and footers

Samples in the GO Data Warehouse (analysis) Package

The following reports are some of the reports found in the GO Data Warehouse (analysis) package.

Sample reports that were created in Report Studio are located in the Active Report folder and the Report Studio Report Samples folder.

Budget vs. Actual

This report shows three years of data by retailer and retailer site for the camping equipment product line. Each year includes budget and actual data.

This report uses the following features:

- summarizing
- crosstabs
- context filters

Core products results

This active report shows revenue data for the core products Camping Equipment and Golf Equipment.

This list report uses two drop-down list controls to filter data by the following criteria:

- core product
- country or region

Customer Returns and Satisfaction

This report shows the customer satisfaction survey results for Asia Pacific in 2013. It highlights the customers who are the least satisfied. It also provides information about customers with the highest number of product returns.

This report uses the following features:

- combination charts
- customizing the color and size of a chart
- lists
- formatting a list
- conditional highlighting
- filters
- custom headers and footers
- colors
- lineage
- text items
- grouping
- baselines
- summarizing
- calculations
- drilling through

Employee Satisfaction 2012

This report shows employee satisfaction survey results by department, compared to targets and industry standards. It also shows employee rankings and terminations.

This report uses the following features:

- crosstabs
- conditional highlighting
- combination charts
- lineage
- text items
- calculations

Employee Training by Year

This report shows employee training data for the selected year and quarter(s). A bar chart shows training costs by region and a crosstab shows data for the selected quarter(s).

This report uses the following features:

- context filters
- cascading prompts

- bar charts
- customizing the color of a chart
- crosstabs
- calculations

Eyewear Revenue by Brand and Size

This report shows a summary of eyewear revenue by brand and compares two prompted retailer sites. The report is filtered by prompts for region, retailer type, and year.

This report uses the following features:

- prompts
- bar charts
- lists
- conditional styles
- calculations
- text items
- custom headers and footers
- combination charts
- axis titles
- crosstabs
- grouping

Global Bonus Report

This list report shows employees who received more than \$2,500 bonus in a year by region. It is grouped by country or region. It also shows how much the sales target was exceeded for each region.

This report uses the following features:

- lists
- page sets (page breaks by country or region with different sorting and grouping)
- multiple prompts and parameters
- calculations
- filters
- conditional highlighting
- hidden objects
- lineage

GO Balance Sheet as at Dec 31 2012

This is the Balance sheet report for Americas where current year data is compared to the previous year data. Analysts can see negative trends under Variance where negative percentages are highlighted.

This report uses the following features:

- conditional highlighting
- padding
- crosstabs
- text items

- context filters

Sample Outdoors Company Balance Sheet as at Dec 31 2012

This report shows a simple balance sheet with assets, liabilities, and equity for 2012 with a 2011 comparative. It uses IBM Cognos Workspace Advanced. The IBM Cognos Business Intelligence Getting Started guide provides a step-by-step example of how to create this report.

This report uses the following feature:

- crosstabs

Manager Profile

This report shows information about managers, including salary, bonuses, and all compensations grouped by year.

This report uses the following features:

- column charts
- lists
- grouping
- summarizing
- custom chart palette
- prompts

New order methods

This active report shows revenue by order method, with focus on the new order methods.

This list report has the following features:

- check box control that allows you to filter data by new order method
- sorting by year or new order method

Planned Headcount

This chart report shows headcount variance compared to the plan for each organization for 2013.

This report uses the following features:

- progressive column charts
- templates
- hidden objects
- custom headers and footers
- lists
- baselines

Positions to Fill

This report shows a list of department names, positions, longest days to fill the positions, and ranking. The report uses a prompt for the year and is a drill-through target for the Recruitment report.

This report uses the following features:

- combination charts
- lists
- prompts
- baselines

Promotion Plan Revenue

This report shows the planned revenue for all the promotions of a selected campaign. It is a drill-through target for the Top 10 Promotions by Retailer report that is based on the Sales and Marketing (cube) package.

This report uses the following features:

- prompts
- bar charts
- crosstabs
- axis titles

Promotion Success

This report shows the financial results of the company's promotions. It shows how much of the company's total revenue is attributable to each promotional campaign.

This report uses the following features:

- prompt pages
- HTML items
- summarizing
- axis titles
- bar charts
- lists
- grouping

Quantity Sold vs. Shipped and Inventory

This report compares the quantity of goods sold and shipped with the opening and closing inventory levels.

This report uses the following features:

- filters
- combination charts
- defined y-axes
- custom headers and footers

Recruitment Report

This report shows a variety of recruitment techniques for certain positions or organizations.

This report uses the following features:

- drilling through
- crosstabs
- prompt pages
- colors

- floating object adjustment
- custom headers and footers

Return Quantity by Order Method

This report shows quantity sold, number of returns, and percentage of returns (with those greater than 5% highlighted) by return reason for each product in the Outdoor Protection product line.

This report uses the following features:

- filters
- lists
- conditional highlighting
- grouping

Returned Items

This report shows the number of returned items by return reason and retailer type. A column chart shows returned items by product line and region for the selected date range.

This report uses the following features:

- date and time prompts
- crosstabs
- bar charts
- drilling down
- text items
- sorting

Returns by Damage, Failed Orders and Complaints in 2012

This report shows quality measures based on product returns.

This report uses the following features:

- pie charts
- crosstabs
- indented text
- singletons
- calculations
- drilling through
- text items
- custom headers and footers

Returns by Failed Orders in 2012

This report shows quality measures based on product returns and focuses on failed orders.

This report uses the following features:

- pie charts
- crosstabs
- indented text

- singletons
- drilling through
- calculations, including the tuple function

Returns by Order Method

This report shows product returns and reasons filtered on the order method. The Getting Started guide provides a step-by-step example of how to create this report.

This report uses the following features:

- bar charts
- prompts
- crosstabs
- filters
- custom headers and footers

Returns by Order Method - Prompted Chart

This prompted chart report shows product returns and reasons filtered on a prompted order method.

This report uses the following features:

- bar charts
- prompts
- crosstabs
- filters
- custom headers and footers

Revenue by GO Subsidiary 2011

This prompted chart report shows 2011 quarterly revenues for each GO subsidiary.

This report uses the following features:

- templates
- colors
- prompts
- hyperlinks
- customizing charts
- singletons
- bar charts
- drilling through
- layout calculations
- pie charts
- calculations
- combination charts
- text items
- blocks
- sorting

Sales Commissions for Central Europe

This report shows an annual summary of sales commissions, revenues, and gross profit for each branch in Central Europe. It also compares actual commission expenses with planned commission expenses.

This report uses the following features:

- prompts
- calculations
- bar charts
- lists
- conditional highlighting
- drilling through
- custom headers and footers
- axis titles

Sales Growth Year Over Year

This report shows annual sales growth in both percentage and dollar amounts.

This report uses the following features:

- bar charts
- lists
- filters
- sorting
- baselines
- axis titles

Sales target by region

This active report shows sales target by region, including the percentage differences between planned and actual revenue.

Succession Report

This report shows the succession data by department and status for percent ready in a column chart. It also contains a detailed crosstab for the managers associated with the possible successors.

This report uses the following features:

- drilling through to the Manager Profile report
- filters
- lists
- grouping

Top 10 Retailers for 2011

This report shows the top 10 retailers for 2011 by revenue and sales target.

This report uses the following features:

- bar charts
- lists
- filters

- multiple queries
- combination charts
- line charts
- notes
- axis titles
- text items
- custom headers and footers

Samples in the GO Data Warehouse (query) Package

The following reports are some of the reports found in the GO Data Warehouse (query) package.

Sample reports that were created in Report Studio are located in the Active Report folder and the Report Studio Report Samples folder.

Advertising-cost vs revenue

This active report shows the advertising cost vs revenue by year. Tab controls are used for grouping similar report items.

Bursted Sales Performance Report

This list report shows how to burst a product sales report to a sales manager for Northern Europe sales staff. To successfully burst this report, IBM Cognos Business Intelligence must be configured to use an email server.

This report uses the following features:

- lists
- bursting
- conditional highlighting
- filters
- calculations
- summarizing
- blocks
- custom headers and footers
- sorting
- grouping

Employee Expenses (report)

This report is used as a data source for the Employee Expenses Power Cube.

This report uses the following feature:

- lists

Health Insurance

This report is used as a data source for the Employee Expenses Power Cube.

This report uses the following features:

- lists
- filters

Pension Plan

This report is used as a data source for the Employee Expenses Power Cube.

This report uses the following features:

- lists
- filters

Regular Salary

This report is used as a data source for the Employee Expenses Power Cube.

This report uses the following features:

- lists
- filters

TOC Report

This report takes advantage of the bookmark object to allow a user to navigate through this report easily. This report should be run in PDF or saved HTML format. The report contents show a product order table and an expected volume fact table.

This report uses the following features:

- lists
- bookmarks
- background color
- multiple pages
- grouping

Total Revenue by Country or Region

This report summarizes revenue for Retailer Country or Region and Product Line. It is also a drill-through target for the Top Retailers by Country or Region and Revenue by Order Method reports.

This report uses the following features:

- crosstabs
- combination charts
- summarizing
- tables to control where objects appear

Samples in the GO Sales (analysis) Package

The following reports are some of the reports found in the GO Sales (analysis) package.

2011 Quarterly Sales Forecast

This report shows the sales forecast by product line and region for each quarter in 2011.

This report uses the following features:

- lists
- summarizing

- grouping
- sorting

2011 Sales Summary

This report summarizes revenue and gross profit for 2011 and shows the top sales representatives by revenue and quantity sold.

This report uses the following features:

- lists
- filters
- combination charts
- axis titles
- custom headers and footers
- conditions

Samples in the GO Sales (query) Package

The following reports are some of the reports found in the GO Sales (query) package.

Sample reports that were created in Report Studio are located in the Active Report folder and the Report Studio Report Samples folder.

Active Report Techniques

This report demonstrates common active report and dashboard features and functionality.

Briefing Book

This report shows a Briefing Book style of report.

This report uses the following features:

- multiple pages
- crosstabs
- multiple queries
- filters
- pie charts
- singletons
- tables of contents
- bookmarks
- PDF options
- horizontal pagination
- sorting
- custom headers and footers
- text items

Film strip

This active report shows detailed sales facts in different charts. Deck controls are used for navigation.

Horizontal Pagination

This report shows crosstabs rendered across several horizontal pages. The first crosstab shows the fit-to-page behavior while the second crosstab shows the horizontal pagination.

This report uses the following features:

- multiple pages
- horizontal pagination
- crosstabs
- custom headers and footers

Matrix-chart and graph

This active report shows a summary of sales facts for each province or state in the Americas. Clicking a category in the map displays the data in a list.

Order Invoices - Donald Chow, Sales Person

This report generates invoices for all the sales by Donald Chow.

This report uses the following features:

- lists
- adding list row cells
- calculations
- formatting tables
- calculations
- filters
- grouping
- tables to control where objects appear

No Data

Each page of this report presents a different option for dealing with a No Data condition. It also generates invoices of sales for the Order Invoices - Donald Chow, Sales Person report in the GO Sales (query) package.

This report uses the following features:

- crosstabs
- custom headers and footers
- no data
- lists

PDF Page Properties

The two pages of this report appear with different Page Orientation (portrait and landscape) when the report is run in PDF format.

This report uses the following features:

- crosstabs
- lists
- page orientation
- PDF options

- custom headers and footers

Product details

This active report shows attributes as color, size, and description for products.

Sales analysis

This active report shows interactions with charts. Clicking a pie series in a chart filters the product line selected.

Sales Dashboard

This active report focuses on sales details by region and product brand. Describes the top performers and the best performance by region.

Singletons on Page Body

This report uses singleton results to display information with no data relationship in the same layout context.

This report uses the following features:

- singletons
- tables
- custom headers and footers

Table of Contents

This report shows two Tables of Contents: one for the main pages and another for the appendices.

This report uses the following features:

- crosstabs
- pie charts
- bookmarks
- tables
- tables of contents
- custom headers and footers
- hyperlinks

Visualization sample reports

The following reports are found in the Visualization Sample Reports folder.

Employee Satisfaction - Accessible

This report shows employee satisfaction survey results by department, compared to targets and industry standards. It also shows employee rankings and terminations.

This report contains accessibility features. You must enable accessible report outputs to include the accessibility features.

Related tasks:

“Enable Accessible Report Outputs” on page 487

If you want to include accessibility features, such as alternate text, summary text, designated cell headers in tables and accessible conditional layouts, you must

enable these accessibility features in the report output.

Returns by Order Method - Accessible

This report contains a chart that shows product returns and reasons filtered by order method.

This report contains accessibility features. You must enable accessible report outputs to include the accessibility features.

Related tasks:

“Enable Accessible Report Outputs” on page 487

If you want to include accessibility features, such as alternate text, summary text, designated cell headers in tables and accessible conditional layouts, you must enable these accessibility features in the report output.

Revenue by Order Method - Accessible

List report grouped by year that shows revenue and quantity sold by order method. It also indicates whether the quantity sold target of one million and the revenue target of one billion were reached.

This report contains accessibility features. You must enable accessible report outputs to include the accessibility features.

Related tasks:

“Enable Accessible Report Outputs” on page 487

If you want to include accessibility features, such as alternate text, summary text, designated cell headers in tables and accessible conditional layouts, you must enable these accessibility features in the report output.

Sales Growth Year Over Year - Accessible

This report shows annual sales growth in both percentage and dollar amounts.

This report contains accessibility features. You must enable accessible report outputs to include the accessibility features.

Related tasks:

“Enable Accessible Report Outputs” on page 487

If you want to include accessibility features, such as alternate text, summary text, designated cell headers in tables and accessible conditional layouts, you must enable these accessibility features in the report output.

Interactive Samples

The following reports are some of the reports found in the Interactive Samples folder.

Bursting Sales Performance Report

This list report shows how to burst a product sales report to a sales manager for Northern Europe sales staff. To successfully burst this report, IBM Cognos Business Intelligence must be configured to use an email server.

This report uses the following features:

- lists
- bursting
- conditional highlighting

- filters
- calculations
- summarizing
- blocks
- custom headers and footers
- sorting
- grouping

Percentage Calculation (by year)

This prompted report shows a percentage calculation based on a particular year.

This report uses the following features:

- lists
- pie charts

Recruitment Report

This report shows a variety of recruitment techniques for certain positions or organizations.

This report uses the following features:

- drilling through
- crosstabs
- prompt pages
- colors
- floating object adjustment
- custom headers and footers

Revenue by GO Subsidiary 2011

This prompted chart report shows 2011 quarterly revenues for each GO subsidiary.

This report uses the following features:

- templates
- colors
- prompts
- hyperlinks
- customizing charts
- singletons
- bar charts
- drilling through
- layout calculations
- pie charts
- calculations
- combination charts
- text items
- blocks
- sorting

Rolling and Moving Averages

This report shows the rolling and moving average count for the return quantity. A prompt uses a macro to provide static choices within a time dimension.

This report uses the following features:

- prompts
- calculations
- crosstabs
- combination charts

Top 10 Retailers for 2011

This report shows the top 10 retailers for 2011 by revenue and sales target.

This report uses the following features:

- bar charts
- lists
- filters
- multiple queries
- combination charts
- line charts
- notes
- axis titles
- text items
- custom headers and footers

Prompt API samples

The following reports are some of the reports found in the Samples_Prompt_API folder.

Related reference:

Appendix H, "Prompt API for IBM Cognos BI," on page 1005

The JavaScript Prompt API provides report authors with a method of customizing prompt interaction in the reports they author.

Clear prompt selections

This report demonstrates using the prompt API to clear selections from all prompts.

Date prompt presets

This report uses the prompt API to provide the user with a set of prompt selection presets based on today's date.

Display all prompt values ignoring user selections

This report uses the prompt API to display all the values in the prompt, whether they are selected or not.

Display user selected prompt values

This report uses the prompt API to display the prompt values selected by the user.

Filter country by letter

This report uses a custom prompt control to provide parameters to filter the report.

Limit date prompt selection by database value

This report demonstrates limiting the selection of a date to a value less than or equal to a latest date value in a query item.

Limit numeric prompt selection by database value

This report demonstrates limiting the selection of a value less than or equal to a largest value in a query item.

Limit time between two dates

This report demonstrates preventing the user from selecting a date range greater than 10 days.

Limit user selection to two items

This report shows how to validate prompt values to stop the user from selecting more than two items.

Pass parameter via hidden prompt

This report demonstrates setting the value of a hidden prompt.

Personal default prompt selections - set selections

This report allows the user to save a set of default prompt selections for use in subsequent reports. The prompt selections are saved to browser cookies for reuse in other reports.

Personal default prompt selections - use selections

This report shows how to use the personal default prompt selections.

Validate prompt values when button pushed

This sample shows how to validate prompt values when a prompt button is clicked.

Validate type-in postal code values

The report uses the prompt API to validate user input character by character as the user types to ensure that a valid postal code is entered.

Validate type-in product line code

The report uses the prompt API to validate user input as the user types.

Appendix D. Limitations when using dimensional data sources

There are limitations when authoring or running reports against dimensional data sources.

Running a Report Against a Dimensional Data Source

You can cancel a report that is running against Microsoft SQL Server Analysis Services only during the initial portion of its execution. After this time, the report runs to completion.

The same behavior applies to SAP BW data sources.

In IBM Cognos Framework Manager, you can also control the number of levels within a hierarchy from which members, or values, are extracted from the hierarchy to populate a tree prompt.

For SAP BW, you can reduce the number of hierarchy levels to limit the number of nodes by setting the SAP BW variable property `trimHierarchyLevels` to 1. This removes the lowest level from the hierarchy prior to creating the list of nodes.

Units of Measure Notation

When running a report against an SAP BW data source, units of measure are included in the same column as the data values, separated by one space. For example, Celsius and Fahrenheit notations are appended to the end of the value.

If you see an asterisk character (*), one of the following was detected:

- an unknown currency
- a value with an unknown or questionable unit of measure, such as a mixed currency calculation or rollup

Mixed currency values occur when you calculate values with different currencies.

This behavior occurs when you are using an IBM Cognos cube as a data source.

This behavior also occurs for SAP BW data sources.

Unsupported SAP Variable Properties

The following SAP variable properties are not supported:

- Exclusionary ranges appear as an inclusionary prompt.
- Mandatory not initial appears as a mandatory prompt.

When using Business Explorer (BEx) to define variables in your SAP data source, avoid using exclusionary ranges and the mandatory not initial property.

Limitations When Using Set Expressions in List Reports

In list reports, we recommend that you avoid using set expressions. When in a list, set expressions, such as TopCount, may produce fewer rows than in the corresponding crosstab.

For example, the following list includes Year in the first column, followed by a column containing an expression that returns the top three months by revenue. Only three rows appear in the report and they correspond to the top three months across all years. If you group by Year, the report still shows only three months. However, the corresponding crosstab, you see three months for each year.

Year	Top 3 Months	Revenue
2013	March 2013	171,457,960.73
2013	July 2013	166,441,982.56
2013	June 2013	161,995,729.54

	Revenue	Revenue
2010	December 2010	84,197,463.09
	June 2010	82,169,806.98
	July 2010	80,723,457.3
2011	December 2011	109,868,142.48
	November 2011	103,650,656.99
	June 2011	100,066,807.17
2012	June 2012	141,875,242.63
	December 2012	130,525,197.76
	August 2012	129,235,970.16
2013	March 2013	171,457,960.73
	July 2013	166,441,982.56
	June 2013	161,995,729.54

Figure 77. List showing the top three revenue months in 2013, and the corresponding crosstab

In crosstab reports in IBM Cognos Business Intelligence, set evaluation is always done in the context of what the set is nested under in the report. However, in list reports set evaluation is done independently of the grouping. For example, if the first column contains Country or Region instead of Year, you see the top three months for each country or region (across all years) in both cases.

In the case of different dimensions, you can force context independence by replacing [Revenue] in the topCount expression with tuple ([Revenue], X), where X is the default member of the hierarchy that contains Month.

However, for nested levels in the same hierarchy, there is no such workaround at this time.

Limitations When Using Clauses in Summary Functions

A summary function that uses a for clause may yield unexpected results. These may include error messages, warnings, incorrect numbers, and more or fewer than expected rows, columns, or chart points and lines.

To avoid these problems, ensure that the parameters that follow the for clause adhere to the following constraints:

- Parameters must be simple data item references.
- All data items in the parameter list must appear on every list, crosstab, or chart that uses that summary.
- For any edge used in the for clause, data items listed in the for clause must start with the first data item on that edge.
- Data items must be listed in the order in which they appear on each edge of the report with no gaps.
- In crosstabs and charts, there must be no sibling data items that are considered details. Summaries are normally not considered details.
- Section headers must not be included in the parameter list.

If following these constraints does not resolve the problems and your report uses dimensional data with no detail or summary filters, consider using the within set clause instead of the for clause.

Limited Support for Relational Functions When Used with OLAP Data Sources

When working with an OLAP data source, we recommend that you not use relational functions, such as substring and concatenation functions, in a report that also contains a measure with the **Aggregate Function** property set to **Calculated** or **Automatic** in the model. If you do so, you may encounter unexpected results. For example, some summaries are calculated using the **Minimum** function instead of the aggregate function derived from the individual query items.

In the expression editor, an exclamation mark (!) that precedes a function indicates that the function is not naturally supported for that data source. IBM Cognos Business Intelligence uses a local approximation for that function. Because an approximation is used, performance can be degraded and the results may not be what you expect.

For example, you create an IBM Cognos Query Studio report that contains the data items Product line and Retailer site count. The footer summary is set to **Calculated**. You then insert a calculated column that returns the first three characters of the Product line item, which uses the relational concatenation function. The footer summary now shows the lowest gross margin value.

Product line	First Three Characters	Retailer Site Count
Camping Equipment	Cam	632
Mountaineering Equipment	Mou	265
Personal Accessories	Per	810
Outdoor Protection	Out	639
Golf Equipment	Gol	367
Summary		265

Figure 78. A report that contains a calculated footer summary

Related concepts:

“Summarizing Data Dimensionally” on page 280

Summarize data in your reports to obtain totals, averages, and so on.

Limitations When Summarizing Measures in DMR Data Sources

There are limitations when summarizing dimensionally-modeled relational (DMR) measures and semi-additive measures in crosstabs using the aggregation function `count distinct`, `median`, `standard-deviation`, or `variance`. The following limitations can produce empty or error cells when the report is run:

- The aggregation function must apply to all members of a level or all children of a member.
- To use OLAP functions in detail filters that are applied to a dimension that is not in the report, or is at a level below what is being reported, only the functions `children`, `level`, `members`, `roleValue`, and `rootMembers` will work.
- You cannot define detail filters that reference one or more measures and are set to **After auto aggregation**.
- You cannot define context filters that have more than one member from a dimension that does not appear in the report.
- Context filters that have more than one member from a dimension that appears in the report produce errors in all cells that are ancestors of the slicer members.
- If a crosstab has a row that is a set of members from one dimension (dimension A) and another row that is a set of members from another dimension (dimension B), and a context filter containing members from dimension A is defined, error cells are produced in the row that contains members from dimension B.
- If a context filter contains members from a dimension, and a crosstab has a row that is a set of members from a higher level than the slicer members, error cells are produced for that row.
- Error cells are produced when drilling down on a crosstab that has two nested levels.

If you do not consider these limitations in a calculation, the report may return inaccurate results.

If there is a non-measure calculation that returns a constant or contains a summary function, and the calculation has a lower solve order than the measure being aggregated, error cells are returned for the aggregated measure.

In list reports, error cells are produced as a result of these limitations if the list uses an OLAP function other than `children`, `filter`, `level`, `members`, `roleValue`, and `rootMembers`.

Limitations When Filtering Dimensional Data Sources

Avoid combining context filters (slicers) with dimensional constructs that involve members from hierarchies that are used elsewhere in the report. This combination gives results that are often not what you might expect and that may change in a future release.

Dimensional data sources provide implicit rollup at all levels of each dimensional hierarchy. Context filters and slicers with more than one member invalidate any pre-computed rollup of members at hierarchy levels above the level at which the filter applies.

The following types of filtering are safe for dimensional reporting:

- Context filters (slicers) with one or more explicit, non-calculated members per hierarchy, if those hierarchies are not used elsewhere in the report.

- Expressions that use the filter function (not in a slicer), comparing measure, tuple, or attribute values.

Nesting Incomplete Sets

When you nest sets (especially sets of explicit members, and sets that result from the functions such as filter and intersect), there may be members at one nesting level that have no corresponding members that can appear nested below them. In such cases, filtering results may not be what you expect: the higher-level members may or may not appear in the result.

While this is most commonly seen within a single hierarchy, it can also happen across different hierarchies and dimensions.

To avoid this problem, ensure that the lower-level sets are constructed to ensure that they are never empty for any of the members in the higher-level set. For example, you could filter only the top level set and nest only the complete set of descendants at the desired levels below.

Error Characters (--) When Filtering

When you use slicers or context filters with a calculated fact or measure, you may see two dashes (--) as values for some or all of the cells in the report that represent aggregates that are calculated in the database (aggregation is set to **Automatic**). This means that the data source is unable to compute these values.

You can avoid this error by using an explicit rollup rule or aggregation function such as **Total**. However, do this only if you are familiar with the data and absolutely certain that this is the appropriate answer for that report.

Time Hierarchies

Error characters also appear in summaries if your report includes a time hierarchy and you use two or more members from a different time hierarchy as a context filter. To avoid the error, use only one member as the context filter.

Filters in Queries and Sub-queries

For dimensional data sources, filters in queries and sub-queries are considered equivalent. The same applies to slicers.

Limitations When Specifying the Scope of Summary Filters with Dimensional Data Sources

When you specify the scope for a summary filter, consider the following limitations. The scope of a summary filter

- must refer to a grouped data item for list reports. Otherwise, you encounter the following error:
OP-ERR-0212 The summary filter scope (Scope1) found in the query (Query1) is not valid. It must refer to a grouped query item.
- can refer to multiple data items, but it can refer to only one data item per edge of the crosstab. Otherwise, you encounter the following error:
OP-ERR-0213 The summary filter scope (Scope1) found in the query (Query1) is not valid. Referencing more than one query item from the same edge is not supported.

- must refer to a level and cannot refer to a measure. Otherwise, you encounter the following error:
OP-ERR-0209 The summary filter scope (Scope1) found in the query (Query1) is not valid. It must refer to a level.
- must refer to a data item that is projected on an edge of the crosstab. If the scope of a summary filter refers to a data item that was deleted from the report layout, you may encounter unexpected results. Otherwise, you encounter the following error:
OP-ERR-0213 The summary filter scope (Scope1) found in the query (Query1) is not valid. Referencing more than one query item from the same edge is not supported.
- must refer to unique data items. For example, the summary filter cannot refer to the same data item more than once.

Limitations When Filtering Data Using an SAP BW Data Source

If you are working with an SAP BW data source, you must consider additional exceptions when applying filters.

If you apply a filter and a sort to an item that corresponds to the leaf-level of a recursive hierarchy, siblings may appear in the report even though the aggregated values are correct. Siblings are characteristic values with the same parent as the filtered member.

Each level in an SAP BW hierarchy has an item with the same name as the level and a role of `_businessKey`. Such items are known as level identifiers. The level identifier must be an exact value for the operators `=`, `<`, and `>` to work. For example, for the filter `[Office] > 'Chicago'` to work, the value 'Chicago' must exist in the data source. If you do not know the exact values, you can apply the filter to one of the attribute items associated with the level, such as `[OfficeLongName] > 'C'`. Filters on non-identifiers are possible, but they are slower because SAP BW data sources are optimized for queries based on level identifiers.

When filtering time-related data, only the level identifier items of the time-related characteristics in SAP BW, such as `0CALDAY` and `0CALMONTH`, should be used for performing anything other than equality filters. All other (attribute) items in these hierarchies are formatted string representations of the characteristic values with which they are associated. These formatted values sort alphanumerically and not chronologically.

Using Prompt Expressions in Filters

If you create a filter expression using report item attributes, such as the following, no data is returned.

```
[ report item attribute ] = ?prompt?
```

To resolve the problem, do one of the following:

- Fully qualify the item by using items from the source tree instead of data items from the report.
- Use prompt controls in the report instead of hand coded prompts.

Considerations when Creating Calculations

Consider the following information and limitations when creating dimensional calculations.

Calculation Solve Order

When calculations in the rows and columns of a report intersect, calculations are performed in the following order: addition or subtraction, multiplication or division, aggregation (rollup), and then the remaining arithmetic functions.

The remaining functions are as follows:

- absolute, round, average, minimum, maximum, medium, count
- percentage, % difference (growth), or % of total
- rank, quartile, quantile, percentile

If both calculations have the same precedence, for example, if they are both business functions, then the row calculation takes precedence.

You can override the order of precedence by changing the solve order property. For more information, see “Resolve Multiple Calculations for Crosstabs and Charts” on page 558.

Length of Expressions

When creating layout calculations that use complex expressions, limit the length of the expression to less than 1,000 tokens. A token is a keyword, identifier, constant, or special character symbol that the server identifies when it parses the SQL. For example, the expression $1+1+1+1+1+1+1+1+1$ contains approximately 28 tokens, whereas the expression $1+1+1\dots+1$ (400 times) contains more than 1000 tokens.

Tip: The Sales Commissions for Central Europe sample report in the GO Data Warehouse (analysis) package includes expressions. For more information about The Sample Outdoors Company samples, see Appendix C, “Sample Reports and Packages,” on page 525.

Quality of Service Indicators

Not all data sources support functions the same way. The data modeler can set a quality of service indicator on functions to give a visual clue about the behavior of the functions. Report authors can use the quality of service indicators to determine which functions to use in a report.

The quality of service indicators are:

- not available (X)

The function is not available for any data source in the package.

- limited availability (!!)

The function is not available for some data sources in the package.

- limited support (!)

The function is available for all data sources in the package but is not naturally supported for that data source. IBM Cognos Business Intelligence uses a local approximation for that function. Because an approximation is used, performance can be poor and the results may not be what you expect.

- unconstrained (check mark)

The function is available for all data sources.

Using Quotation Marks in Literal Strings

When inserting literal strings in an expression, you must enclose the string in single quotation marks. If the string contains a quotation mark, it must be escaped. For example, if you want to insert the string `ab'c`, you must type `'ab"c'`.


Limitations of calculations in dimensional reporting

You should use only the expressions and functions available in IBM Cognos Report Studio or IBM Cognos Workspace Advanced, and follow their syntax.

Minimal checking exists for calculations. If your calculation uses an invalid expression, your report results may contain unexpected values.

In addition, you should define member summaries as follows:

```
summary_function (currentMeasure within set set_reference)
```

where *set_reference* is a level or set inserted from the **Source** tab .

Unless otherwise required, *summary_function* should be the aggregate function. If you use an explicit summary function, you may encounter problems with measures (such as profit margin, distinct count, and so on) that have complex rollup values, and/or scenario or account dimension members that do not roll up.

Know your data, and confirm with the owner of the cube where overriding the automatic aggregation is safe.

Because of these limitations, summaries of calculations may not provide reliable values. For convenience, you may have to build reports where row summaries and calculated member columns intersect. In such reports, these intersections may contain unexpected values. In contrast, row calculations intersecting with column aggregates using the aggregate function are safe because the calculation is performed on the reliably summarized values.

Units of Measure

When creating calculations, you may encounter problems with the units of measure. For example, the calculation `Cost * Cost` returns the unit of measure `*` (asterisk) instead of a currency unit of measure. To avoid this problem, change the format of the corresponding column to obtain the desired unit of measure.

Limitation When Using Dimensional Functions with Running and Moving Summaries

IBM Cognos Business Intelligence does not currently support queries that contain both dimensional functions and running summaries or moving summaries. For example, when you drill down in a report, the query uses the dimensional function `children`, which is not compatible with running and moving summaries. Running and moving summaries are supported for only the overall level of a dimension.

Creating Expressions Using SAP BW Data Sources

You must consider the following when creating expressions using an SAP BW data source, or you may not get the results you expect.

- The case and if/then/else constructs are not supported in filters.

- The query item identifier of the leaf-level of the 0CALDAY characteristic and its presentation hierarchies is of type date. When the values for the query item identifier are presented in IBM Cognos Report Studio, they are formatted as dates. These formatted values should not be used in filter expressions. The correct date constant format for use in expressions is YYYY-MM-DD.
- You can apply a comparison expression with an operator other than equals to a query item that represents a level identifier. However, level identifiers are more efficient for identifying specific values. Range comparisons must be performed on the IBM Cognos application server, which slows down the performance of the report.

Using Microsoft Excel Functions with SSAS 2005 Data Sources

If you are working with a Microsoft SQL Server 2005 Analysis Services (SSAS) data source and you want to use Microsoft Excel VBA functions such as ROUNDDOWN in MDX queries, the following Microsoft Office features must be installed on the SSAS server:

- Microsoft Office Excel
- Microsoft Visual Basic for Applications

To see a list of Excel VBA functions, see the Microsoft Web site (<http://www.microsoft.com>).

If these Microsoft Office features are not installed on the SSAS 2005 server, and you use Excel VBA functions, you encounter an error such as the following: YK-ERR-0008 The data provider returned an error message: "The '[Excel].[ROUNDDOWN]' function does not exist."

This error occurs because the OLAP server cannot process the function since Excel function libraries are missing.

For more information, see the Microsoft Knowledge Base article 932214 at <http://support.microsoft.com>.

Concatenating Strings

When IBM Cognos Business Intelligence concatenates strings locally and if any of the involved strings contain null values, the result of the concatenation is an empty cell or a null value. This occurs because IBM Cognos BI requires that an expression that involves a null value returns a null value. Many databases ignore null strings when they perform concatenations. For example, if you concatenate strings A, B, and C, and if string B is a null value, the database may concatenate only strings A and C.

Intersecting Calculations in Crosstabs and Charts

An intersection point in a crosstab or chart can contain a value that is derived from multiple calculations.

If the query expressions for the row and column that intersect in a crosstab both include calculations, the intersecting value is the result of performing both calculations. The second calculation is performed on the result of the first calculation. If you change the order in which the calculations are performed, the resulting value at the intersection point changes.

The solve order is a positive numeric value that you assign to data items. Negative values are not supported. The data item with the lowest value is calculated first, followed by the next higher value, and so on. The data item with the highest solve order is computed last. If you do not specify a solve order, the default value of 0 is used. In crosstabs, if more than one data item has the same solve order, column items are calculated first and row items are calculated second.

For example, a crosstab contains the columns Revenue, Sales target, and a column that calculates the percentage by which actual revenue exceeds target revenue. The crosstab contains a row for each Year and a summary row that calculates the overall totals for each of the three columns. The cell where the percentage calculation and the overall total calculation intersect contains only one value. By default, IBM Cognos Business Intelligence calculates the column percentage first and the summary row last. The value that appears at the intersection is therefore a sum of the percentages, which is not a meaningful result. The value is more meaningful if the overall percentage is calculated after the actual and sales target revenues are summed. Specifying a solve order for the percentage calculation that is higher than the overall total calculation gives the following result:

	Revenue	Sales target	Percentage by which Actual Exceeds Target
2010	\$914,352,803.72	\$812,885,300.00	12%
2011	\$1,159,195,590.16	\$1,036,923,300.00	12%
2012	\$1,495,891,100.90	\$1,332,553,100.00	12%
2013	\$1,117,336,274.07	\$1,023,006,840.00	9%
Total	\$4,686,775,768.85	\$4,205,368,540.00	11%

Figure 79. Crosstab showing a calculation that has a solve order specified

It is not necessary to specify the solve order for the overall total calculation. Because the default solve order is 0, setting the solve order for the percentage calculation to a value higher than 0 is sufficient.

Nested Calculations in Crosstabs

If a crosstab contains nested calculations, the calculations are performed in the following order by default:

1. outermost calculation on the columns
2. innermost calculation on the columns
3. outermost calculation on the rows
4. innermost calculation on the rows

If there are solve order ties, column items are calculated before row items and outer nesting items are calculated before inner nesting items.

Resolve Multiple Calculations for Crosstabs and Charts

If an intersection in a crosstab or chart contains a value that is derived from multiple calculations, you can specify the order in which to perform the calculations. The solve order must be a positive numeric value. The calculations are performed from lowest to highest solve order value.


Setting the **Rollup Aggregate Function** property to **Calculated** for a data item assigns a solve order that is higher than any other data item in a query unless a

solve order is explicitly specified. If there are multiple data items that have the **Rollup Aggregate Function** property set to **Calculated**, the normal rules for solve order apply.

Procedure

1. Click the data item for which to specify the solve order.

A data item can have only one solve order value. Consequently, if a data item is in a query that is used in more than one context and you want the data item to have a different solve order in each context, you must use a separate data item.

Tip: In crosstabs, to specify the solve order for the default measure, click the crosstab and, in the **Properties** pane, click the select ancestor button  and click **Crosstab**. Or you can click the container selector (three orange dots) of the crosstab to select it.

2. In the **Properties** pane, set the **Solve Order** property to an integer value.

Tip: To specify the solve order for the default measure, click **Default Measure Solve Order**.

Resolve Query Calculations that Intersect with Calculated Measures Defined in Microsoft Analysis Services

Microsoft SQL Server Analysis Services (SSAS) data sources may include data source calculations. Because IBM Cognos Business Intelligence cannot predict the presence of a solve order on such calculations, setting the **Solve Order** property may not resolve the solve order correctly. You can suppress potentially meaningless results when querying dimensional data sources that include data source calculations. In the following example, the columns **YTD Change** and **YTD Growth** are data source calculated members and the summary values for these two columns were suppressed.

Revenue	Prior YTD	YTD	YTD Change	YTD Growth
Camping Equipment	290,355,466.50	352,910,329.97	62,554,863.47	21.54%
Personal Accessories	329,883,402.11	443,693,449.85	113,810,047.74	34.50%
Outdoor Protection	5,942,944.77	4,471,025.26	-1,471,919.51	-24.77%
Golf Equipment	138,993,560.79	174,740,819.29	35,747,258.50	25.72%
Mountaineering Equipment	93,654,629.48	141,520,649.70	47,866,020.22	51.11%
Total(Product line)	858,830,003.65	1,117,336,274.07	--	--


Figure 80. Crosstab showing revenue by product line with a summary row

When a query-defined calculated member and a data source calculated member intersect, the value is the result of performing both calculations. The second calculation is performed on the result of the first calculation. Whether the final value is meaningful depends on the order in which the calculations are performed. Because IBM Cognos BI cannot determine the presence of these members ahead of time, it cannot automatically determine the correct solve order.

In most cases, SSAS 2005 gives the expected results when no solve order is defined in the cube. Therefore, when using SSAS 2005, you do not need to set either the **Solve Order** property in the query or the **Calculation Intersection** property.

Note: Dimensionally-modeled relational (DMR) data sources query one or more underlying relational databases, and therefore cannot contain data source calculations. They are not considered dimensional data sources in the context of this topic.

Procedure

1. Pause the pointer over the query explorer button  and click the query that contains the data item for which to suppress values.
2. In the **Data Items** pane, click the data item.
3. In the **Properties** pane, set the **Calculation Intersection** property to **Show "Not applicable"**.

Results

When a query-defined calculated member and a data source calculated member intersect, the resulting value is suppressed. If the intersecting members do not contain data source calculations, the value is not suppressed.

Null (Missing) Values in Calculations and Summaries

The data source that you use determines how null (or missing) values are handled in calculations, summaries, and other expressions.

Null values represent missing data values. For example, a new eyewear product, called Abby, is introduced in 2012. Therefore there are no sales in 2011. If you create a report with the years 2011 and 2012, the values for sales of Abby for the year 2011 are null (missing).

By default, null values appear as blank cells in a crosstab or list report. You can change the default to specify the display of other characters, such as the word null, by changing the data format of the **Missing Value Characters** property for the cells or report. For more information, see "Set the Default Data Formats" on page 403.

Arithmetic Operations

Null values in arithmetic operations yield different results depending on the type of data source.

In Microsoft SQL Server Analysis Services (SSAS) and Cubing Services data sources, a null value in arithmetic operations is treated as follows:

- In operations such as addition (+), a null value yields the same result as zero ($9 + \text{NULL} = 9$)
- In operations such as multiplication (*), a null value yields a null result ($9 * \text{NULL} = \text{NULL}$)

You can accommodate this behavior by using more complex expressions such as the following:

- `if ([M] is not NULL, then ([M]) else (0)`
- `if ([M] is not NULL, then (<expression involving M> else NULL)`

In relational and other OLAP data sources the result of an operation that includes a null value is always null. For example, $9 + \text{NULL} = \text{NULL}$.

Equality Comparisons

Equality comparisons, such as equal to (=) and not equal to (<>), compare two values and return a Boolean value of true or false.

For all data sources, equality comparisons are treated as tests for missing data. Inequality comparisons are treated as tests for non-missing data.

For example, NULL=NULL is true and NULL=0 is false.

Ordered Comparisons

In ordered comparisons, such as rank and quantile functions, null values are handled as follows.

For relational data sources, the result of the comparison is always false. For example, NULL < 1 is false.

For Microsoft SSAS, Cubing Services, and other OLAP data sources, the null value is treated as zero. For example, NULL < 1 is true.

Boolean Functions

In Boolean operations, such as or, null values are handled as follows.

For relational and dimensionally-modeled relational data sources, the result of a Boolean operation is always null. Boolean functions are used in conditions and the null result is treated as a false condition. For example, NULL OR TRUE = NULL (FALSE)

For Microsoft SSAS, Cubing Services, and other OLAP data sources, the null value is treated as if it is false. For example, NULL OR TRUE = TRUE.

Summary Functions

All summary functions, such as aggregate, average, and maximum, ignore null values. For all functions except count, if all values in the expression are null, the result is null. For count, if all values in the expression are null, the result is zero.

For example, if the value for Quantity for 2013 is 10 and the values for 2011 and 2012 are null, then the average is as follows:

- average ([Quantity] within set set([2012], [2013])) = 10
- average ([Quantity] within set set([2012], [2011])) = NULL

The count is as follows:

- count ([Quantity] within set set([2012], [2013])) = 1
- count ([Quantity] within set set([2012], [2011])) = 0

String Operations

For all data sources, the result of string operations, such as concatenation (||), that include a null value is always null.

For example, 'A' || NULL = NULL and NULL || NULL = NULL.

Dimensional Coercion Rules

IBM Cognos Business Intelligence uses dimensional coercion rules to automatically convert dimensional types to better match other types. These conversions help you build simpler expressions, making them easier to understand. In addition to the implicit rules that IBM Cognos BI provides, you can make explicit data type conversions using various functions, such as `children`.

IBM Cognos BI supports the following types of coercion:

- coercion of an object of one dimensional type into another, such as a level into a member set
- coercion of a dimensional object into a numeric, date, time, or string value, such as a numeric measure into a numeric value

Coercion rules are applied to expressions and data items. In expressions, an operator or function may require operands to be of a particular dimensional type. When an operand is not of the required type, one or more coercion rules may be applied to coerce the operand to the appropriate type. Coercion rules may also be applied to data items to coerce the data item to a collection of members or values.

Function Operands

The following describes how coercion rules are applied to function operands:

- If the operand is of the required type, no coercion is required.
- If the function operand is supposed to be a numeric value, it is coerced into one. A coercion rule exists for each type of dimensional object coercion.
- If the function operand is supposed to be a dimensional object and a coercion exists to coerce the operand to the required type, the coercion is applied.
- If no coercion exists, an error message with the code `QE-DEF-0478` appears to indicate that an unsupported conversion of a dimensional object from the source to target type occurred.

Comparison and Other Symmetric Operators

Binary operators that accept operands of more than one type, such as equals (=) and `in`, need both operands to be the same dimensional type.

No coercion is possible between value domains (numeric, date, time, and string) or between members and values. Consequently, if either operand is a value type, both must be in the same value domain and converted explicitly using a function. Otherwise, the query fails.

Members and member set operands are valid only with the operators equals (=), not equals (<>), `in`, and `not in`, where the right side of the expression is a member, member set, or prompt. Only the following are valid:

- `[member / member set] = [member]`
- `[member / member set] <> [member]`
- `[member / member set] = ?p?`
- `[member / member set] <> ?p?`
- `[member / member set] in ([member], ...)[member / member set] not in ([member], ...)`
- `[member / member set] in ([member set])[member / member set] not in ([member set])[member / member set] in ?p?[member / member set] not in ?p?`

Exceptions

For the left operand, member sets are supported in detail and summary filter expressions, but not in expressions that use the `filter` function. Members are not supported in detail and summary filters, but they may be used in expressions that use the `filter` function.

The `in_range` operator is not supported for members and member sets.

Normal coercion rules apply to these operands.

NULL operands are considered values, rather than members.

Examples

The following examples illustrate how coercion is applied to levels in expressions with operators.

```
[Sales].[Products].[].[Product Line] = [Sales].[Products].[].[Product Line]->[Outdoor Equipment]
```

The left operand is coerced to the following member set:

```
members ([Sales].[Products].[].[Product Line])
```

The following expressions are invalid:

- `[Sales].[Products].[].[Product Line] = NULL`
- `[Sales].[Products].[].[Product Line] + 1`
- `[Sales].[Products].[].[Product Line] = 'Canada'`
- `[Sales].[Products].[].[Product Line] > 2000`

The following examples illustrate how coercion is applied to members in expressions with operators. In each example, the left operand is coerced to a value of the current cell at this member:

```
(tuple ([Sales].[Products].[].[Product Line]->[Outdoor Equipment]))
```

- `[Sales].[Products].[].[Product Line]->[Outdoor Equipment] = NULL`
- `[Sales].[Products].[].[Product Line]->[Outdoor Equipment] + 1`
- `[Sales].[Products].[].[Product Line]->[Outdoor Equipment] > 2000`
- `[Sales].[Products].[].[Product Line]->[Outdoor Equipment] + 'Canada'`

Coercion Rules for Dimensional Objects

The following table describes coercion rules that are applied when coercing an object of one dimensional type into another.

Note: Measures and Member Unique Names (MUNs) are considered members.

Source type	Target type	Result
Measure dimension	Hierarchy	A measure dimension can be used without any conversion as a hierarchy.

Source type	Target type	Result
Measure dimension	Member set	The member set contains the members of the measure dimension. This coercion is done in two steps. First, measure dimensions are coerced to hierarchies, and then hierarchies are coerced to member sets.
Hierarchy	Member set	A set containing the members of the hierarchy.
Level	Member set	A set containing the members of the level. The equivalent expression is members (<i>level</i>).
Measure	Member	A measure can be used without any conversion as a member.
Measure	Tuple	This coercion is done in two steps. First, measures are coerced to members, and then members are coerced to tuples.
Measure	Member set	This coercion is done in two steps. First, measures are coerced to members, and then members are coerced to member sets.
Member	Tuple	The tuple consists of the member. The equivalent expression is tuple (<i>member</i>).
Member	Member set	The set consists of the member. This coercion is done in two steps. First, members are coerced to tuples, and then tuples are coerced to member sets.

Coercion Rules for Numeric and String Values


The following table describes the coercion rules for expressions or prompts that return a numeric or string value. These rules apply to functions and operators that require an operand of a particular data type, as well as to binary operators that require operands of the same type.

Source type	Target type	Result
Measure	Number, Date/Time, or String	The result is the value of the measure at the current cube intersection.

Source type	Target type	Result
Member	Number	The result is the value of the cell at the cube intersection specified by the member. This coercion is done in two steps. First, members are coerced to tuples, and then tuples are coerced to the target type.
Tuple	Number	The value of the cell at the cube intersection specified by the tuple. The equivalent expression is value (<i>operand or parameter</i>).

Coercion Paths

The following diagram shows how coercion rules are connected. The expression that coerces a source node type to a target node type is built by following the path that connects them. A dotted line indicates a coercion that does not require an explicit conversion function. This occurs whenever the source type is a specialization of the target type. For example, every measure is a member so you can use measures without conversion wherever a member is required.




Recommendation - Use Member Unique Name (MUN) Aliases

If you are working with a dimensional data source, use MUN aliases to simplify building reports and expressions. In addition, you can tie the MUN back to the member in the package.

When working with dimensional data sources, IBM Cognos Business Intelligence uses MUNs to uniquely identify members. MUNs are very complex. For example, the MUN for the member 2012 might appear as

[great_outdoors_company].[Years].[Years].[Year]->:[PC] . [@MEMBER] . [20120101-20121231].

When you build expressions that involve members, the use of MUNs makes these expressions difficult to read and maintain.

Tip: To view the MUN of a member, in the **Source** tab , right-click the member and click **Properties**.

IBM Cognos Report Studio has an option that automatically generates an alias for MUNs (**Tools > Options > Report tab > Alias member unique names**). The MUN alias is a data item that has the MUN as its definition. For the previous example, you would see 2012 as the MUN alias in the **Expression** property for the data item. If the MUN alias is not enabled, in the **Expression** property, you would see the complex MUN for 2012.

Important: Do not modify or rename MUN aliases, because they will lose their connection to their respective members in the package.

Running a Report That Contains Members

If you are using members in a report and your modeler has updated the data source in a way that changes member unique names, the following problems may arise when you run the report.

- If the report queries an OLAP data source, you receive an error message explaining that some specific members cannot be found.
- If the report queries a dimensionally modeled relational (DMR) data source, data items whose member unique names have changed do not appear in the report. Calculations that refer to members that have changed no longer contain values from the members.

To resolve these problems, you must update the member unique names in the report. Open the query that contains the members that you need to update in Query Explorer. Delete the member from the pane in which it appears and reinsert it from the **Source** tab. For example, if you inserted the member as a detail filter, delete it from the **Detail Filters** pane and reinsert it.

Limitations When Formatting Empty Cells in SAP BW Data Sources

When working with SAP BW data sources, if the SAP BW server administrator configured custom formatting for empty cells on the SAP BW server, this custom format does not appear in IBM Cognos Business Intelligence reports. Ask your administrator to configure the formatting of empty cells in IBM Cognos BI.

Related tasks:

“Suppress Empty Cells” on page 407

Sparse data may result in crosstabs showing empty cells. For example, a crosstab that matches employees with products results in many rows of empty values for the revenue measure if the employee does not sell those products.

Appendix E. Limitations When Producing Reports in Microsoft Excel Format

There are limitations when producing reports in Microsoft Excel format.

Unable to Load Images from the IBM Cognos Business Intelligence Content Store in a Report

If a report contains an image whose URL points to the IBM Cognos Business Intelligence content store, the Microsoft Excel spreadsheet software generates an access violation error and shuts down.

This problem is a known issue in the Microsoft knowledge base, and Microsoft is currently investigating the problem. This problem occurs only in Excel 2002.

Blank Worksheet Appears

If the Microsoft Excel spreadsheet software cannot download a worksheet within a timeout period, Excel may instead open a blank worksheet.

Warning Message Appears When Excel Opens an IBM Cognos Business Intelligence Report

Each time the Microsoft Excel spreadsheet software opens an IBM Cognos Business Intelligence report, a warning message appears.

The warning message is as follows:

Some of the files in this Web page are not in the expected location. Do you want to download them anyway? If you are sure the Web page is from a trusted source, click Yes.

The Excel workbook in HTML/XML format requires the presence of the file `filelist.xml`. IBM Cognos BI does not allow the creation of local files on the client side. In addition, a local file that contains URLs introduces a security issue. Consequently, this message will appear whenever you open an IBM Cognos BI report in Excel. If you see this error message, click **Yes** to open the report.

Spreadsheet Content Not Saved for Reports Saved in XLS Format

If you open a report that was saved in XLS format or run a report in XLS format, and security settings in your Web browser are set so that you are prompted to open or save the report, do not click **Save**. If you save the report, the spreadsheet content will not be saved. This is because Microsoft Excel reports in Microsoft Office 2000 HTML format use relative paths to the spreadsheets. The relative URL paths are no longer available when you open a saved XLS report.

Instead, click **Open** first and then choose to save the report.

Unable to Load Excel Report in Netscape 7.01

This version of IBM Cognos Business Intelligence does not support loading Microsoft Excel reports in Netscape 7.01.

Unable to Nest Labels in Charts

Currently, it is not possible to specify nested labels for the category axis via XML.

Data Series Are Truncated

The Microsoft Excel spreadsheet software may group data series or categories differently when compared to a chart produced by IBM Cognos Business Intelligence.

A 1 KB buffer limit in Excel limits the maximum number of data series per chart to 120. Data series over 120 are truncated.

Colors Different From Those in HTML or PDF

If an IBM Cognos Business Intelligence report contains a chart that uses custom colors, the Microsoft Excel spreadsheet software may not be able to add the custom color to the Excel color palette. Excel will attempt to match the custom color to one of its available standard colors. As a result, colors in Excel may vary from those seen in HTML or PDF.

We recommend that you use standard colors in charts.

Repeating Pie Charts

If you have a report that has repeating pie charts and you define a chart title, the Microsoft Excel spreadsheet software will show each pie with a title that is a concatenation of the chart title and the data series. For example, if the chart title is Quantity Sold by Order Method and Product Line and the data series is Order method, the title of each pie in Excel will be Quantity Sold by Order Method and Product Line, *order method*.

Unable to Skip Discrete Axis Labels

In IBM Cognos Business Intelligence charts, you can control the skipping of discrete axis labels. This feature is not supported in Microsoft Excel charts.

Unsupported IBM Cognos BI Formatting

About 30% of the formatting functions available in IBM Cognos Business Intelligence are not supported in the Microsoft Excel spreadsheet software.

In particular, Excel does not allow changing locale-dependent formatting attributes, such as the following:

- Decimal Separator
- Exponential Symbol
- Group Separator
- Monetary Decimal Separator
- AM String

- Day Name
- Day Short Name
- Decimal Delimiter Symbol
- Month Name
- Month Short Name
- PM String

In addition, Excel does not support the following:

- Format Width
- International Currency Symbol
- List Separator
- Percent Symbol (Excel does not support percent symbols for charts)
- Multiplier
- Overline Text Format
- PerMill Symbol
- Plus Sign
- Scale (Excel has a different scaling formula than IBM Cognos BI)
- Calendar (Excel does not allow changing the calendar)
- Era Name
- First Day Of Week
- Show Era

Cells Contain Series of

Cells in the Microsoft Excel spreadsheet software have a limit of 255 characters. If your report contains text strings that are longer than 255 characters, they will be formatted as text and appear as #####.

To resolve this problem, use fewer characters.

Table and Column Widths

The Microsoft Excel spreadsheet software does not support using percentages to determine the width of tables.

If the report contains only one table, the value of the width attribute for the Table element in the report specification determines the width of the table in the Excel worksheet. If the report contains more than one table, Excel determines the width of all the tables in the worksheet. If the tables are nested, the width specified for the outer table is used and, if necessary, the width is adjusted to accommodate data in the nested tables. The columns and rows around the table are merged to preserve the appearance of the nested table. When you save the workbook, only a single table is saved per worksheet.

Secure Socket Layer (SSL) Is Not Supported in Some Excel Formats and Versions

SSL is supported for only the Microsoft Excel 2002 format in Microsoft Excel 2002 and Microsoft Excel 2003.

Number Formats Become Currency Formats in Japanese Excel

A report uses the Number data format and you save it as Microsoft Excel output. When you open the report in the Japanese version of Microsoft Excel, the data format is listed as Currency rather than Number. This occurs because Japanese Excel interprets the standard Number data format slightly differently than other versions of Excel.

The value appears correctly in Number format. For example, if you specified five digits as your number format, five digits still appear. In Excel, click the **Custom** number format to see the exact format string being used.

Reports Show Data in Wrong Columns

A report contains a large amount of data that is presented using a large number of nested report objects, such as tables and blocks. When the report is produced in Microsoft Excel format, some of the data appears in the wrong columns. This occurs because Excel has a 64K limit on how many nested cell objects can appear in a single spreadsheet.

To solve this problem, you can redesign the report to present the data using non-nested structures.

Unable to Access Reports on Remote Servers

You cannot access a report in Microsoft Excel format on a remote server.

To resolve this problem, you must change the hostname portion of the gateway URI from localhost to either the IP address of the computer or the computer name. You do this using IBM Cognos Configuration.

Drill-through Reports Are Not Supported in Excel

IBM Cognos Business Intelligence does not support drill-through for reports in Microsoft Excel format.

Map Reports Are Not Supported in Excel

IBM Cognos Business Intelligence does not support map reports in Microsoft Excel format.

Unsupported Excel Formatting

IBM Cognos Business Intelligence does not support some formatting.

The following formatting functions that are available in the Microsoft Excel spreadsheet software are not supported by IBM Cognos BI:

- background images in table cells
- Excel-specific headers and footers
- text flow and justification
- floating text objects
- white space, normal, and wrap text formatting
- maximum characters

Some layouts do not show exactly in HTML and PDF due to Excel limitations.

Hyperlink Buttons Are Not Supported in Excel

The Microsoft Excel spreadsheet software does not support hyperlink buttons.

Unable to View Reports in Excel Format Sent as Email Attachments

IBM Cognos Business Intelligence can send Microsoft Excel reports in HTML and XML format by email. However, you cannot open them directly from the email message.

Save the Excel email attachments to your computer and view them from there.

Many items on axis produces empty chart in Excel

If a chart contains many items on the x-axis, an empty chart is generated when the report output format is Microsoft Excel 2002.

This problem is caused by a limitation in Excel 2002 for chart data strings. To work around the problem, produce the report in Excel 2007 format. Excel 2007 does not have this limitation.

Chart legend titles are not supported in Excel

The Microsoft Excel spreadsheet software does not support chart legend titles.

Unsupported Chart Properties in Excel

The following IBM Cognos Business Intelligence chart properties are not supported in the Microsoft Excel spreadsheet software:

- tool tips
- conditional text
- depth
- visual angle
- show values
- marker text location
- show baseline
- new note
- new marker
- truncation text and allow n-degrees rotation category labels
- border
- margin
- box type
- font and font alignment
- footer
- subtitle
- regression line
- baseline
- Include Zero For Auto Scale
- Summarize Small Slices

- Summarize Small Items

In addition, IBM Cognos BI makes sure that Excel reuses the same color palette that is defined in IBM Cognos BI. However, Excel can only use the first 16 colors from the IBM Cognos BI palette. If the number of categories in a chart exceeds 16, the rest of the colors are taken from the default Excel palette.

Unsupported Chart Types in Excel

About 30% of the chart types available in IBM Cognos Business Intelligence are not matched in the Microsoft Excel spreadsheet software.

The following chart types appear differently or are not supported. Charts that are not supported appear as a default column chart in Excel.

- Bipolar charts
- Bubble charts
 - Excel does not support regression lines.
- Bullet charts
 - Excel does not support rectangle fills. As a result, the colored regions in bullet charts do not appear in Excel output.
- Combination charts
 - In Excel, combination charts appear as two-dimensional. If a three-dimensional or two-dimensional combination chart includes only an area, column, or line chart, only the one chart appears.
- Gauge charts
- Donut charts
 - Excel may fill in the donut hole to accommodate extra measures. Excel shows donut three-dimensional charts as donut charts.
- Maps
 - In Excel, no chart appears.
- Matrix charts
- Metrics range charts
 - In Excel, they appear as combination charts with two line charts for the tolerance bars.
- Pareto charts
 - In Excel, the cumulative line is not displayed.
- Pie charts
 - Excel shows only one type of pie chart and may show it at a different angle.
- Progressive column charts
- Polar charts
 - In Excel, a scatter chart appears instead.
- Quadrant charts
- Radar charts
 - Excel does not support stacked area radar charts. Excel names area radar charts as filled radar charts. Excel shows radar charts as radar with markers.
- Scatter charts
 - In Excel, three-dimensional scatter charts appear as two-dimensional scatter charts. The z-axis is dropped.
- 100% stacked bar and column charts

Clustered (side-by-side) stacked column charts are not supported in Excel. Only one column is rendered in the Excel output. For example, you have a 100% stacked column chart with Product line and Order method as columns. In the Excel output, columns for only Product line appear in the chart, but both Product line and Order method appear in the legend.

Cell Height and Width Are Incorrect

The width and height of cells that contain data with curly brackets {} or parentheses () may appear incorrectly.

This is because the Microsoft Excel spreadsheet software uses different word wrapping algorithms than IBM Cognos Business Intelligence.

Appendix F. Using the expression editor

An expression is any combination of operators, constants, functions, and other components that evaluates to a single value. You build expressions to create calculation and filter definitions. A calculation is an expression that you use to create a new value from existing values that are contained within a data item. A filter is an expression that you use to retrieve a specific subset of records.

Build expressions that use the following components.

Operators

Operators specify what happens to the values on either side of the operator. Operators are similar to functions, in that they manipulate data items and return a result.

(

Identifies the beginning of an expression.

Syntax

(expression)

)

Identifies the end of an expression.

Syntax

(expression)

*

Multiplies two numeric values.

Syntax

value1 * value2

,

Separates expression components.

Syntax

expression (parameter1, parameter2)

/

Divides two numeric values.

Syntax

value1 / value2

||

Concatenates, or joins, strings.

Syntax

string1 || string2

+

Adds two numeric values.

Syntax

value1 + value2

-

Subtracts two numeric values or negates a numeric value.

Syntax

value1 - value2
or
- value

<

Compares the values that are represented by "value1" against "value2" and retrieves the values that are less than "value2".

Syntax

value1 < value2

<=

Compares the values that are represented by "value1" against "value2" and retrieves the values that are less than or equal to "value2".

Syntax

value1 <= value2

<>

Compares the values that are represented by "value1" against "value2" and retrieves the values that are not equal to "value2".

Syntax

value1 <> value2

=

Compares the values that are represented by "value1" against "value2" and retrieves the values that are equal to "value2".

Syntax

value1 = value2

>

Compares the values that are represented by "value1" against "value2" and retrieves the values that are greater than "value2".

Syntax

value1 > value2

->

Separates the components in a literal member expression.

Syntax

[namespace].[dimension].[hierarchy].[level]->[L1]

>=

Compares the values that are represented by "value1" against "value2" and retrieves the values that are greater than or equal to "value2".

Syntax

value1 >= value2

and

Returns "true" if the conditions on both sides of the expression are true.

Syntax

argument1 and argument2

auto

Works with summary expressions to define the scope to be adjusted based on the grouping columns in the query. The scope is context-dependent.

Syntax

aggregate_function (expression AUTO)

between

Determines if a value falls in a given range.

Syntax

expression between value1 and value2

Example

[Revenue] between 200 and 300

Result

Returns the number of results with revenues between 200 and 300.

Result data

Revenue	Between
\$332.06	false
\$230.55	true
\$107.94	false

case

Works with when, then, else, and end. Case identifies the beginning of a specific situation, in which when, then, and else actions are defined.

Syntax

```
case expression { when expression then expression } [ else  
expression ] end
```

contains

Determines if "string1" contains "string2".

Syntax

```
string1 contains string2
```

currentMeasure

Keyword that can be used as the first argument of member summary functions. This function appears in the Total Revenue by Country sample report in the GO Data Warehouse (query) package.

Syntax

```
aggregate_function ( currentMeasure within set expression )
```

default

Works with the lookup construct.

Syntax

```
lookup (....) in (....) default (....)
```

distinct

A keyword used in an aggregate expression to include only distinct occurrences of values. See also the function unique.

Syntax

```
distinct dataItem
```

Example

```
count ( distinct [OrderDetailQuantity] )
```

Result

1704

else

Works with the if or case constructs. If the if condition or the case expression are not true, then the else expression is used. This function appears in the Top 10 Retailers for 2005 sample report in the GO Data Warehouse (analysis) package.

Syntax

```
if ( condition ) then .... else ( expression ) , or case .... else ( expression ) end
```

end

Indicates the end of a case or when construct.

Syntax

```
case .... end
```

ends with

Determines if "string1" ends with "string2".

Syntax

```
string1 ends with string2
```

escape

Determines if "string1" matches the pattern of "string2", with the character "char" optionally used to escape characters in the pattern string.

Syntax

```
string1 LIKE string2 [ ESCAPE char ]
```

Example 1

```
[PRODUCT_LINE] like 'G%'
```

Result

All product lines that start with 'G'.

Example 2

```
[PRODUCT_LINE] like '%Ga%' escape 'a'
```

Result

All the product lines that end with 'G%'.

for

Works with summary expressions to define the scope of the aggregation in the query.

Syntax

```
aggregate_function ( expression for expression { , expression } )
```

for all

Works with summary expressions to define the scope to be all the specified grouping columns in the query. See also the for clause.

Syntax

```
aggregate_function ( expression for ALL expression { , expression } )
```

for any

Works with summary expressions to define the scope to be adjusted based on a subset of the grouping columns in the query. Equivalent to the for clause.

Syntax

```
aggregate_function ( expression for ANY expression { , expression } )
```

for report

Works with summary expressions to set the scope to be the whole query. See also the for clause. This function appears in the Customer Returns and Satisfaction sample report in the GO Data Warehouse (analysis) package.

Syntax

aggregate_function (expression for report)

if

Works with the then and else constructs. If defines a condition; when the if condition is true, the then expression is used. When the if condition is not true, the else expression is used. This function appears in the Top 10 Retailers for 2005 sample report in the GO Data Warehouse (analysis) package.

Syntax

if (condition) then (expression) else (expression)

in

Determines if "expression1" exists in a given list of expressions.

Syntax

expression1 in (expression_list)

in_range

Determines if "expression1" exists in a given list of constant values or ranges.

Syntax

expression1 in_range { constant : constant [, constant : constant] }

Example 1

```
[code] in_range { 5 }
```

Result

This is equivalent to [code] = 5.

Example 2

```
[code] in_range { 5: } }
```

Result

This is equivalent to [code] >= 5.

Example 3

```
[code] in_range { :5 }
```

Result

This is equivalent to [code] <= 5.

Example 4

```
[code] in_range { 5:10 }
```

Result

This is equivalent to ([code] >= 5 and [code] <= 10).

Example 5

```
[code] in_range { :5,10,20: }
```

Result

This is equivalent to ([code] <= 5 or [code] = 10 or [code] >= 20).

is missing

Determines if "value" is undefined in the data.

Syntax

```
value is missing
```

is null

Determines if "value" is undefined in the data.

Syntax

```
value is null
```

is not missing

Determines if "value" is defined in the data.

Syntax

```
value is not missing
```

is not null

Determines if "value" is defined in the data.

Syntax

```
value is not null
```

like

Determines if "string1" matches the pattern of "string2", with the character "char" optionally used to escape characters in the pattern string.

Syntax

```
string1 LIKE string2 [ ESCAPE char ]
```

Example 1

```
[PRODUCT_LINE] like 'G%'
```

Result

All product lines that start with 'G'.

Example 2

```
[PRODUCT_LINE] like '%Ga%' escape 'a'
```

Result

All the product lines that end with 'G%'.

lookup

Finds and replaces data with a value you specify. It is preferable to use the case construct.

Syntax

```
lookup ( name ) in ( value1 --> value2 ) default ( expression )
```

Example

```
lookup ( [Country] ) in ( 'Canada'--> ( [List Price] * 0.60),  
'Australia'--> ( [List Price] * 0.80 ) ) default ( [List Price] )
```

not

Returns TRUE if "argument" is false or returns FALSE if "argument" is true.

Syntax

```
NOT argument
```

or

Returns TRUE if either of "argument1" or "argument2" are true.

Syntax

```
argument1 or argument2
```

prefilter

Performs a summary calculation before applying the summary filter.

Syntax

```
summary_function ([expression] prefilter)
```

Example

```
total ( [Quantity] for report prefilter )  
summaryFilter: total(  
  [Quantity] for [ProductNo] ) > 50000
```

Result

Sums the quantities in a report before the summary filter is applied.

Result data

PNo	Total	Total	Total
88	54928	298140	2215354
89	51126	298140	2215354
90	69996	298140	2215354
94	69004	298140	2215354
95	53086	298140	2215354

rows

Counts the number of rows output by the query. Use with Count ().

Syntax

count (ROWS)

rows

Counts the number of rows output by the query. Use with Count ().

Note: Supported only in dynamic query mode.

Syntax

count (ROWS [expression])

starts with

Determines if "string1" starts with "string2".

Syntax

string1 starts with string2

then

Works with the if or case constructs. When the if condition or the when expression are true, the then expression is used. This function appears in the Top 10 Retailers for 2005 sample report in the GO Data Warehouse (analysis) package.

Syntax

if (condition) then ..., or case expression when expression
then end

when

Works with the case construct. You can define conditions to occur when the WHEN expression is true.

Syntax

case [expression] when ... end

Summaries

This list contains predefined functions that return either a single summary value for a group of related values or a different summary value for each instance of a group of related values.

Statistical functions

This list contains predefined summary functions of statistical nature.

corr

Returns the coefficient of correlation of a set of number pairs. This is computed as follows: $\text{COVAR_POP}(\text{numeric_expression1}, \text{numeric_expression2}) / (\text{STDDEV_POP}(\text{numeric_expression1}) * \text{STDDEV_POP}(\text{numeric_expression2}))$

Note: Supported only in dynamic query mode.

Syntax

```
corr ( numeric_expression1 , numeric_expression2 [ auto ] )  
corr ( numeric_expression1 , numeric_expression2 for [ all|any ]  
expression { , expression } )  
corr ( numeric_expression1 , numeric_expression2 for report )
```

Example

```
corr ( Cost , Margin for report)
```

Result

The coefficient of correlation between Cost and Margin.

Result data

Cost	Margin	corr (Cost, Margin for report)
4	0.33	0.0872648
5	0.28	0.0872648
9.22	0.23	0.0872648
15.93	0.28	0.0872648
34.97	0.3	0.0872648

covariance-pop

Returns the population covariance of a set of number pairs.

Note: Supported only in dynamic query mode.

Syntax

```
covariance-pop ( numeric_expression1 , numeric_expression2 )  
covariance-pop ( numeric_expression1 , numeric_expression2 for  
[ all|any ] expression { , expression } )  
covariance-pop ( numeric_expression1 , numeric_expression2 for  
report )
```

Example

```
covariance-pop ( Cost , Margin for report)
```

Result

The population covariance between Cost and Margin.

Result data

Cost	Margin	covariance-pop (Cost, Margin for report)
4	0.33	0.032384
5	0.28	0.032384
9.22	0.23	0.032384
15.93	0.28	0.032384
34.97	0.3	0.032384

covariance-samp

Returns the sample covariance of a set of number pairs.

Note: Supported only in dynamic query mode.

Syntax

```
covariance-samp ( numeric_expression1 , numeric_expression2 )
covariance-samp ( numeric_expression1 , numeric_expression2 for
[ all|any ] expression { , expression } )
covariance-samp ( numeric_expression1 , numeric_expression2 for
report )
```

Example

```
covariance-samp ( Cost , Margin for report)
```

Result

The sample covariance between Cost and Margin.

Result data

Cost	Margin	covariance-samp (Cost, Margin for report)
4	0.33	0.04048
5	0.28	0.04048
9.22	0.23	0.04048
15.93	0.28	0.04048
34.97	0.3	0.04048

regression-average-x

Returns the average of the independent variable (numeric_expression2) of the regression line.

Note: Supported only in dynamic query mode.

Syntax

```
regression-average-x ( numeric_expression1 , numeric_expression2 )
regression-average-x ( numeric_expression1 , numeric_expression2 for
[ all|any ] expression { , expression } )
regression-average-x ( numeric_expression1 , numeric_expression2 for
report )
```

Example

```
regression-average-x ( Cost , Margin for report)
```

Result

The average of Margin within the regression line for Cost and Margin.

Result data

Cost	Margin	regression-average-x (Cost, Margin for report)
4	0.33	0.284
5	0.28	0.284
9.22	0.23	0.284
15.93	0.28	0.284
34.97	0.3	0.284

regression-average-y

Returns the average of the dependent variable (numeric_expression1) of the regression line.

Note: Supported only in dynamic query mode.

Syntax

```
regression-average-y ( numeric_expression1 , numeric_expression2 )
regression-average-y ( numeric_expression1 , numeric_expression2 for
[ all|any ] expression { , expression } )
regression-average-y ( numeric_expression1 , numeric_expression2 for
report )
```

Example

```
regression-average-y ( Cost , Margin for report)
```

Result

The average of Cost within the regression line for Cost and Margin.

Result data

Cost	Margin	regression-average-y (Cost, Margin for report)
4	0.33	13.824
5	0.28	13.824
9.22	0.23	13.824
15.93	0.28	13.824
34.97	0.3	13.824

regression-count

Returns the number of non-null numbers used to fit the regression line.

Note: Supported only in dynamic query mode.

Syntax

```
regression-count ( numeric_expression1 , numeric_expression2 )
regression-count ( numeric_expression1 , numeric_expression2 for
[ all|any ] expression { , expression } )
regression-count ( numeric_expression1 , numeric_expression2 for
report )
```

Example

```
regression-count ( Cost , Margin for report)
```

Result

The number of non-null numbers used to fit the regression line for Cost and Margin.

Result data

Cost	Margin	regression-count (Cost, Margin for report)
4	0.33	5
5	0.28	5

Cost	Margin	regression-count (Cost, Margin for report)
9.22	0.23	5
15.93	0.28	5
34.97	0.3	5

regression-intercept

Returns the y-intercept of the regression line. This is computed as follows:
 $AVG(\text{numeric_expression1}) - REGR_SLOPE(\text{numeric_expression1}, \text{numeric_expression2}) * AVG(\text{numeric_expression2})$

Note: Supported only in dynamic query mode.

Syntax

```
regression-intercept ( numeric_expression1 , numeric_expression2 )
regression-intercept ( numeric_expression1 , numeric_expression2 for
[ all|any ] expression { , expression } )
regression-intercept ( numeric_expression1 , numeric_expression2 for
report )
```

Example

```
regression-intercept ( Cost , Margin for report)
```

Result

The y-intercept of the regression line for Cost and Margin.

Result data

Cost	Margin	regression-intercept (Cost, Margin for report)
4	0.33	5.18015038
5	0.28	5.18015038
9.22	0.23	5.18015038
15.93	0.28	5.18015038
34.97	0.3	5.18015038

regression-r2

Returns the coefficient of determination (also known as "R-squared" or "goodness of fit") of the regression line. This value is computed based on the following conditions: IF VAR_POP(numeric_expression2) = 0 THEN NULL IF VAR_POP(numeric_expression1) = 0 AND VAR_POP(numeric_expression2) <> 0 THEN 1 IF VAR_POP(numeric_expression1) > 0 and VAR_POP(numeric_expression2) <> 0 THEN POWER(CORR (numeric_expression1, numeric_expression2))

Note: Supported only in dynamic query mode.

Syntax

```
regression-r2 ( numeric_expression1 , numeric_expression2 )
regression-r2 ( numeric_expression1 , numeric_expression2 for
[ all|any ] expression { , expression } )
regression-r2 ( numeric_expression1 , numeric_expression2 for
report )
```

Example

regression-r2 (Cost , Margin for report)

Result

The coefficient of determination of the regression line for Cost and Margin.

Result data

Cost	Margin	regression-r2 (Cost, Margin for report)
4	0.33	0.00761514
5	0.28	0.00761514
9.22	0.23	0.00761514
15.93	0.28	0.00761514
34.97	0.3	0.00761514

regression-slope

Returns the slope of the regression line. This is computed as follows:

$\text{COVAR_POP}(\text{numeric_expression1}, \text{numeric_expression2}) / \text{VAR_POP}(\text{numeric_expression2})$

Note: Supported only in dynamic query mode.

Syntax

```
regression-slope ( numeric_expression1 , numeric_expression2 )  
regression-slope ( numeric_expression1 , numeric_expression2 for  
[ all|any ] expression { , expression } )  
regression-slope ( numeric_expression1 , numeric_expression2 for  
report )
```

Example

regression-slope (Cost , Margin)

Result

The slope of the regression line for Cost and Margin.

Result data

Cost	Margin	regression-slope (Cost, Margin for report)
4	0.33	30.43609023
5	0.28	30.43609023
9.22	0.23	30.43609023
15.93	0.28	30.43609023
34.97	0.3	30.43609023

regression-sxx

Returns the following computation after eliminating NULL pairs:

$\text{REGR_COUNT}(\text{numeric_expression1}, \text{numeric_expression2}) * \text{VAR_POP}(\text{numeric_expression2})$

Note: Supported only in dynamic query mode.

Syntax

```
regression-sxx ( numeric_expression1 , numeric_expression2 )  
regression-sxx ( numeric_expression1 , numeric_expression2 for  
[ all|any ] expression { , expression } )  
regression-sxx ( numeric_expression1 , numeric_expression2 for  
report )
```

Example

```
regression-sxx ( Cost , Margin for report)
```

Result

The sxx computation of the regression line for Cost and Margin.

Result data

Cost	Margin	regression-sxx (Cost, Margin for report)
4	0.33	0.00532
5	0.28	0.00532
9.22	0.23	0.00532
15.93	0.28	0.00532
34.97	0.3	0.00532

regression-sxy

Returns the following computation after eliminating NULL pairs:
REGR_COUNT(numeric_expression1, numeric_expression2) *
COVAR_POP(numeric_expression1, numeric_expression2)

Note: Supported only in dynamic query mode.

Syntax

```
regression-sxy ( numeric_expression1 , numeric_expression2 )  
regression-sxy ( numeric_expression1 , numeric_expression2 for  
[ all|any ] expression { , expression } )  
regression-sxy ( numeric_expression1 , numeric_expression2 for  
report )
```

Example

```
regression-sxy ( Cost , Margin for report)
```

Result

The sxy computation of the regression line for Cost and Margin.

Result data

Cost	Margin	regression-sxy (Cost, Margin for report)
4	0.33	0.16192
5	0.28	0.16192
9.22	0.23	0.16192
15.93	0.28	0.16192
34.97	0.3	0.16192

regression-syy

Returns the following computation after eliminating NULL pairs:
REGR_COUNT(numeric_expression1, numeric_expression2) *
VAR_POP(numeric_expression1)

Note: Supported only in dynamic query mode.

Syntax

```
regression-syy ( numeric_expression1 , numeric_expression2 )  
regression-syy ( numeric_expression1 , numeric_expression2 for  
[ all|any ] expression { , expression } )  
regression-syy ( numeric_expression1 , numeric_expression2 for  
report )
```

Example

```
regression-syy ( Cost , Margin for report)
```

Result

The syy computation of the regression line for Cost and Margin.

Result data

Cost	Margin	regression-syy (Cost, Margin for report)
4	0.33	647.15932
5	0.28	647.15932
9.22	0.23	647.15932
15.93	0.28	647.15932
34.97	0.3	647.15932

standard-deviation

Returns the standard deviation of selected data items.

Syntax

```
standard-deviation ( expression [ auto ] )  
standard-deviation ( expression for [ all|any ] expression { ,  
expression } )  
standard-deviation ( expression for report )
```

Example

```
standard-deviation ( ProductCost )
```

Result

Returns a value indicating the deviation between product costs and the average product cost.

standard-deviation-pop

Computes the population standard deviation and returns the square root of the population variance.

Syntax

```
standard-deviation-pop ( expression [ auto ] )  
standard-deviation-pop ( expression for [ all|any ] expression { ,  
    expression } )  
standard-deviation-pop ( expression for report )
```

Example

```
standard-deviation-pop ( ProductCost )
```

Result

Returns a value of the square root of the population variance.

standard-deviation-samp

Computes the sample standard deviation and returns the square root of the population variance.

Note: Supported only in dynamic query mode.

Syntax

```
standard-deviation-samp ( expression [ auto ] )  
standard-deviation-samp ( expression for [ all|any ] expression { ,  
    expression } )  
standard-deviation-samp ( expression for report )
```

Example

```
standard-deviation-samp ( ProductCost )
```

Result

Returns a value of the square root of the sample variance.

variance

Returns the variance of selected data items.

Syntax

```
variance ( expression [ auto ] )  
variance ( expression for [ all|any ] expression { , expression } )  
variance ( expression for report )
```

Example

```
variance ( Product Cost )
```

Result

Returns a value indicating how widely product costs vary from the average product cost.

variance-pop

Returns the population variance of a set of numbers after discarding the nulls in this set.

Syntax

```
variance-pop ( expression [ auto ] )  
variance-pop ( expression for [ all|any ] expression { ,  
    expression } )  
variance-pop ( expression for report )
```

Example

```
variance-pop ( Qty )
```

Result

For each row, returns the population variance of a set of numbers after discarding the nulls in this set.

variance-samp

Returns the sample variance of a set of numbers after discarding the nulls in this set.

Note: Supported only in dynamic query mode.

Syntax

```
variance-samp ( expression [ auto ] )  
variance-samp ( expression for [ all|any ] expression { ,  
    expression } )  
variance-samp ( expression for report )
```

Example

```
variance-samp ( Qty )
```

Result

For each row, returns the sample variance of a set of numbers after discarding the nulls in this set.

aggregate

Returns a calculated value using the appropriate aggregation function, based on the aggregation type of the expression. This function appears in the Budget vs. Actual sample report in the GO Data Warehouse (analysis) package.

Syntax

```
aggregate ( expression [ auto ] )  
aggregate ( expression for [ all|any ] expression { , expression } )  
aggregate ( expression for report )
```

average

Returns the average value of selected data items. Distinct is an alternative expression that is compatible with earlier versions of the product.

Syntax

```
average ( [ distinct ] expression [ auto ] )  
average ( [ distinct ] expression for [ all|any ] expression { ,  
    expression } )  
average ( [ distinct ] expression for report )
```

Example

```
average ( Sales )
```

Result

Returns the average of all Sales values.

count

Returns the number of selected data items excluding null values. Distinct is an alternative expression that is compatible with earlier versions of the product. All is supported in DQM mode only and it avoids the presumption of double counting a data item of a dimension table.

Syntax

```
count ( [ all | distinct ] expression [ auto ] )
count ( [ all | distinct ] expression for [ all|any ] expression { ,
  expression } )
count ( [ all | distinct ] expression for report )
```

Example

```
count ( Sales )
```

Result

Returns the total number of entries under Sales.

maximum

Returns the maximum value of selected data items. Distinct is an alternative expression that is compatible with earlier versions of the product.

Syntax

```
maximum ( [ distinct ] expression [ auto ] )
maximum ( [ distinct ] expression for [ all|any ] expression { ,
  expression } )
maximum ( [ distinct ] expression for report )
```

Example

```
maximum ( Sales )
```

Result

Returns the maximum value out of all Sales values.

median

Returns the median value of selected data items.

Syntax

```
median ( expression [ auto ] )
median ( expression for [ all|any ] expression { , expression } )
median ( expression for report )
```

minimum

Returns the minimum value of selected data items. Distinct is an alternative expression that is compatible with earlier versions of the product.

Syntax

```
minimum ( [ distinct ] expression [ auto ] )
minimum ( [ distinct ] expression for [ all|any ] expression { ,
  expression } )
minimum ( [ distinct ] expression for report )
```

Example

```
minimum ( Sales )
```

Result

Returns the minimum value out of all Sales values.

moving-average

Returns a moving average by row for a specified set of values of over a specified number of rows. The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources.

Syntax

```
moving-average ( numeric_expression , numeric_expression [ at  
expression { , expression } ] [ <for-option> ] [ prefilter ] )  
moving-average ( numeric_expression , numeric_expression  
[ <for-option> ] [ prefilter ] )  
<for-option> ::= for expression { , expression }|for report|auto
```

Example

```
moving-average ( Qty , 3 )
```

Result

For each row, returns the quantity and a moving average of the current row and the preceding two rows.

Result data

Qty	Moving-Average (Qty, 3)
200	200
700	450
400	433.3333
200	433.3333
200	266.6667
500	300.0000

moving-total

Returns a moving total by row for a specified set of values over a specified number of rows. The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources.

Syntax

```
moving-total ( numeric_expression , numeric_expression [ at  
expression { , expression } ] [ <for-option> ] [ prefilter ] )  
moving-total ( numeric_expression , numeric_expression  
[ <for-option> ] [ prefilter ] )  
<for-option> ::= for expression { , expression }|for report|auto
```

Example

```
moving-total ( Qty , 3 )
```

Result

For each row, returns the quantity and a moving total of the current row and the preceding two rows.

Result data

Qty	Moving-Total (Qty, 3)
200	200
700	900
400	1300
200	1300
200	800
500	900

percentage

Returns the percent of the total value for selected data items. The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources. This function appears in the Percentage Calculation (by year) interactive sample report.

Syntax

```
percentage ( numeric_expression [ at expression { , expression } ]
[ <for-option> ] [ prefilter ] )
percentage ( numeric_expression [ <for-option> ] [ prefilter ] )
<for-option> ::= for expression { , expression }|for report|auto
```

Example

```
percentage ( Sales 98 )
```

Result

Returns the percentage of the total sales for 1998 that is attributed to each sales representative.

Result data

Employee	Sales 98	Percentage
Gibbons	60646	7.11%
Flertjan	62523	7.35%
Corneil	22396	2.63%

percentile

Returns a value, on a scale of one hundred, that indicates the percent of a distribution that is equal to or below the selected data items. The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources.

Syntax

```
percentile ( numeric_expression [ at expression { , expression } ]
[ <for-option> ] [ prefilter ] )
percentile ( numeric_expression [ <for-option> ] [ prefilter ] )
<for-option> ::= for expression { , expression }|for report|auto
```

Example

```
percentile ( Sales 98 )
```

Result

For each row, returns the percentage of rows that are equal to or less than the quantity value of that row.

Result data

Qty	Percentile (Qty)
800	1
700	0.875
600	0.75
500	0.625
400	0.5
400	0.5
200	0.25
200	0.25

quantile

Returns the rank of a value within a range that you specify. It returns integers to represent any range of ranks, such as 1 (highest) to 100 (lowest). The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources.

Syntax

```
quantile ( numeric_expression , numeric_expression [ at expression { ,  
  expression } ] [ <for-option> ] [ prefilter ] )  
quantile ( numeric_expression , numeric_expression [ <for-option> ]  
  [ prefilter ] )  
<for-option> ::= for expression { , expression }|for report|auto
```

Example

```
quantile ( Qty , 4 )
```

Result

Returns the quantity, the rank of the quantity value, and the quantity values broken down into 4 quantile groups (quartiles).

Result data

Qty	Rank	Quantile (Qty, 4)
800	1	1
700	2	1
600	3	2
500	4	2
400	5	3
400	5	3
200	7	4
200	7	4

quartile

Returns the rank of a value, represented as integers from 1 (highest) to 4 (lowest), relative to a group of values. The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources.

Syntax

```
quartile ( numeric_expression [ at expression { , expression } ]  
[ <for-option> ] [ prefilter ] )  
quartile ( numeric_expression [ <for-option> ] [ prefilter ] )  
<for-option> ::= for expression { , expression } | for report | auto
```

Example

```
quartile ( Qty )
```

Result

Returns the quantity and the quartile of the quantity value represented as integers from 1 (highest) to 4 (lowest).

Result data

Qty	Quartile (Qty)
450	1
400	1
350	2
300	2
250	3
200	3
150	4
100	4

rank

Returns the rank value of selected data items. The sort order is optional; descending order (DESC) is assumed by default. If two or more rows tie, then there is a gap in the sequence of ranked values (also known as Olympic ranking). The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources. Distinct is an alternative expression that is compatible with earlier versions of the product. Null values are ranked last. This function appears in the Top 10 Retailers for 2005 sample report in the GO Data Warehouse (analysis) package.

Syntax

```
rank ( expression [ ASC|DESC ] { , expression [ ASC|DESC ] } [ at  
expression { , expression } ] [ <for-option> ] [ prefilter ] )  
rank ( [ distinct ] expression [ ASC|DESC ] { , expression  
[ ASC|DESC ] } [ <for-option> ] [ prefilter ] )  
<for-option> ::= for expression { , expression } | for report | auto
```

Example

```
rank ( Sales 98 )
```

Result

For each row, returns the rank value of sales for 1998 that is attributed to each sales representative. Some numbers are skipped when a tie between rows occurs.

Result data

Employee	Sales 98	Rank
Gibbons	60000	1
Flertjan	50000	2
Cornel	50000	2
Smith	48000	4

running-average

Returns the running average by row (including the current row) for a set of values. The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources.

Syntax

```
running-average ( numeric_expression [ at expression { ,
  expression } ] [ <for-option> ] [ prefilter ] )
running-average ( numeric_expression [ <for-option> ] [ prefilter ] )
<for-option> ::= for expression { , expression }|for report|auto
```

Example

```
running-average ( Qty )
```

Result

For each row, returns the quantity and a running average of the current and the previous rows.

Result data

Name	Qty	Avg	Running-Average for name
Smith	7	5	7
Smith	3	5	5
Smith	6	5	5.33
Smith	4	5	5
Wong	3	4	3
Wong	5	4	4

running-count

Returns the running count by row (including the current row) for a set of values. The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources.

Syntax

```
running-count ( numeric_expression [ at expression { , expression } ]
[ <for-option> ] [ prefilter ] )
running-count ( numeric_expression [ <for-option> ] [ prefilter ] )
<for-option> ::= for expression { , expression }|for report|auto
```


Example

```
running-count ( Qty )
```

Result

For each row, returns the quantity and a running count of the position of the current row.

Result data

Name	Qty	Count	Running-Count for name
Smith	7	4	1
Smith	3	4	2
Smith	6	4	3
Smith	4	4	4
Wong	3	3	1
Wong	5	3	2

running-difference

Returns a running difference by row, calculated as the difference between the value for the current row and the preceding row, (including the current row) for a set of values. The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources.

Syntax

```
running-difference ( numeric_expression [ at expression { ,  
  expression } ] [ <for-option> ] [ prefilter ] )  
running-difference ( numeric_expression [ <for-option> ]  
  [ prefilter ] )  
<for-option> ::= for expression { , expression }|for report|auto
```

Example

```
running-difference ( Qty )
```

Result

For each row, returns the quantity and a running difference between the value for the current row and the preceding row.

Result data

Name	Qty	Running-Difference for name
Smith	7	NULL
Smith	3	-4
Smith	6	3
Smith	4	-2
Wong	3	-1
Wong	5	2

running-maximum

Returns the running maximum by row (including the current row) for a set of values. The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources.

Syntax

```
running-maximum ( numeric_expression [ at expression { ,  
  expression } ] [ <for-option> ] [ prefilter ] )  
running-maximum ( numeric_expression [ <for-option> ] [ prefilter ] )  
<for-option> ::= for expression { , expression }|for report|auto
```

Example

```
running-maximum ( Qty )
```

Result

For each row, returns the quantity and a running maximum of the current and previous rows.

Result data

Name	Qty	Max	Running-Maximum (Qty) for name
Smith	2	7	2
Smith	3	7	3
Smith	6	7	6
Smith	7	7	7
Wong	3	5	3
Wong	5	5	5

running-minimum

Returns the running minimum by row (including the current row) for a set of values. The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources.

Syntax

```
running-minimum ( numeric_expression [ at expression { ,  
  expression } ] [ <for-option> ] [ prefilter ] )  
running-minimum ( numeric_expression [ <for-option> ] [ prefilter ] )  
<for-option> ::= for expression { , expression }|for report|auto
```

Example

```
running-minimum ( Qty )
```

Result

For each row, returns the quantity and a running minimum of the current and previous rows.

Result data

Name	Qty	Min	Running-Minimum (Qty) for name
Smith	7	2	7
Smith	3	2	3
Smith	6	2	3
Smith	2	2	2
Wong	4	3	4
Wong	5	3	4

running-total

Returns a running total by row (including the current row) for a set of values. The "<for-option>" defines the scope of the function. The "at" option defines the level of aggregation and can be used only in the context of relational datasources.

Syntax

```
running-total ( numeric_expression [ at expression { ,
  expression } ] [ <for-option> ] [ prefilter ] )
running-total ( numeric_expression [ <for-option> ] [ prefilter ] )
<for-option> ::= for expression { , expression } | for report | auto
```

Example

```
running-total ( Qty )
```

Result

For each row, returns the quantity and a running total of the current and previous rows.

Result data

Name	Qty	Total	Running-Total (Qty) for name
Smith	2	18	2
Smith	3	18	5
Smith	6	18	11
Smith	7	18	18
Wong	3	12	3
Wong	5	12	8

total

Returns the total value of selected data items. Distinct is an alternative expression that is compatible with earlier versions of the product. This function appears in the Budget vs. Actual sample report in the GO Data Warehouse (analysis) package.

Syntax

```
total ( [ distinct ] expression [ auto ] )
total ( [ distinct ] expression for [ all | any ] expression { ,
  expression } )
total ( [ distinct ] expression for report )
```

Example

```
total ( Sales )
```

Result

Returns the total value of all Sales values.

Member Summaries

This list contains predefined functions that return either a single summary value for a set of members or a different summary value for each member of a set of members.

aggregate

Returns a calculated value using the appropriate aggregation function based on the aggregation type of the expression.

Syntax

```
aggregate ( < currentMeasure|numeric_expression > within set  
set_expression )  
aggregate ( < currentMeasure|numeric_expression > within <  
detail|aggregate > expression )
```

average

Returns the average value of the selected data items.

Syntax

```
average ( < currentMeasure|numeric_expression > within set  
set_expression )  
average ( < currentMeasure|numeric_expression > within <  
detail|aggregate > expression )
```

Example

```
average ( Sales )
```

Result

Returns the average of all Sales values.

count

Returns the number of selected data items excluding null values.

Syntax

```
count ( < currentMeasure|numeric_expression > within set  
set_expression )  
count ( < currentMeasure|numeric_expression > within <  
detail|aggregate > expression )
```

Example

```
count ( Sales )
```

Result

Returns the total number of entries under Sales.

maximum

Returns the maximum value of selected data items.

Syntax

```
maximum ( < currentMeasure|numeric_expression > within set  
set_expression )  
maximum ( < currentMeasure|numeric_expression > within <  
detail|aggregate > expression )
```

Example

```
maximum ( Sales )
```

Result

Returns the maximum value out of all Sales values.

median

Returns the median value of selected data items.

Syntax

```
median ( < currentMeasure|numeric_expression > within set  
set_expression )  
median ( < currentMeasure|numeric_expression > within <  
detail|aggregate > expression )
```

minimum

Returns the minimum value of selected data items.

Syntax

```
minimum ( < currentMeasure|numeric_expression > within set  
set_expression )  
minimum ( < currentMeasure|numeric_expression > within <  
detail|aggregate > expression )
```

Example

```
minimum ( Sales )
```

Result

Returns the minimum value out of all Sales values.

percentage

Returns the percent of the total value for the selected data items.

Syntax

```
percentage ( numeric_expression [ tuple member_expression { ,  
member_expression } ] within set set_expression )
```

Example

```
percentage ( [gosales].[sales measures].[quantity] tuple [gosales].  
[Staff].[].[department] -> [West] within set children ( [gosales].  
[Staff].[].[Staff] ) )
```

percentile

Returns a value, on a scale from 0 to 100, that indicates the percent of a distribution that is equal to or below the selected data items.

Syntax

```
percentile ( numeric_expression [ tuple member_expression { ,  
member_expression } ] within set set_expression )
```

quantile

Returns the rank of a value for the specified range. It returns integers to represent any range of ranks, such as 1 (highest) to 100 (lowest).

Syntax

```
quantile ( numeric_expression , numeric_expression [ tuple  
member_expression { , member_expression } ] within set  
set_expression )
```

quartile

Returns the rank of a value, represented as integers from 1 (highest) to 4 (lowest), relative to a group of values.

Syntax

```
quartile ( numeric_expression [ tuple member_expression { ,  
member_expression } ] within set set_expression )
```

rank

Returns the rank value of the selected data items. The type of ranking returned (Olympic, dense, or serial) is data source dependent. The sort order is optional; DESC is assumed by default.

Syntax

```
rank ( numeric_expression [ ASC|DESC ] [ tuple member_expression { ,  
member_expression } ] within set set_expression )
```

Example

```
rank ( [gosales].[sales measures].[quantity] tuple [gosales].[Staff].  
[].[department] -> [West] within set children ( [gosales].[Staff].[.  
[Staff] ) )
```

standard-deviation

Returns the standard deviation of the selected data items.

Syntax

```
standard-deviation ( < currentMeasure|numeric_expression > within set  
set_expression )  
standard-deviation ( < currentMeasure|numeric_expression > within <  
detail|aggregate > expression )
```

standard-deviation-pop

Returns the standard deviation population of the selected data items.

Syntax

```
standard-deviation-pop ( < currentMeasure|numeric_expression > within  
set set_expression )  
standard-deviation-pop ( < currentMeasure|numeric_expression > within  
< detail|aggregate > expression )
```

total

Returns the total value of the selected data items.

Syntax

```
total ( < currentMeasure|numeric_expression > within set  
set_expression )  
total ( < currentMeasure|numeric_expression > within <  
detail|aggregate > expression )
```

variance

Returns the variance of the selected data items.

Syntax

```
variance ( < currentMeasure|numeric_expression > within set  
set_expression )  
variance ( < currentMeasure|numeric_expression > within <  
detail|aggregate > expression )
```

variance-pop

Returns the variance population of the selected data items.

Syntax

```
variance-pop ( < currentMeasure|numeric_expression > within set  
set_expression )  
variance-pop ( < currentMeasure|numeric_expression > within <  
detail|aggregate > expression )
```

Constants

A constant is a fixed value that you can use in an expression.

date

Inserts the current system date.

date-time

Inserts the current system date and time.

time with time zone

Inserts a zero time with time zone.

timestamp with time zone

Inserts an example of a timestamp with time zone.

interval

Inserts a zero interval: 000 00:00:00.000.

interval year

Inserts a zero year interval: 0 year.

interval month

Inserts a zero month interval: 0 month.

interval year to month

Inserts a zero year to month interval: 0000-00 year to month.

interval day

Inserts a zero day interval: 0 day.

interval hour

Inserts a zero hour interval: 0 hour.

interval minute

Inserts a zero minute interval: 0 minute.

interval second

Inserts a zero second interval: 0 second.

interval day to hour

Inserts a zero day to hour interval: 0 00 day to hour.

interval day to minute

Inserts a zero day to minute interval: 0 00:00 day to minute.

interval day to second

Inserts a zero day to second interval: 0 00:00:00.000000000 day to second.

interval hour to minute

Inserts a zero hour to minute interval: 00:00 hour to minute.

interval hour to second

Inserts a zero hour to second interval: 00:00:00.000000000 hour to second.

interval minute to second

Inserts a zero minute to second interval: 00:00.000000000 minute to second.

null

Inserts "null" if the expression conditions are not met.

number

Inserts the number 0, which can be replaced with a new numeric value.

string

Inserts an empty string as two single quotation marks between which you can type a string.

time

Inserts the current system time.

Constructs

This list contains constructs and templates that can be used to create an expression. Templates combine multiple functions into a group. For example, the search case template includes the case, when, else, and end functions.

if then else

This construct is the template for an if...then...else statement. This construct appears in the Top 10 Retailers for 2005 sample report in the GO Data Warehouse (analysis) package.

Syntax

```
IF ([Country] = 'Canada') THEN ([List Price] * 0.60) ELSE ([List Price])
```

in_range

This is the template for an in_range expression.

Syntax

```
[code] IN_RANGE { :30 , 40, 50, 999: }
```

Example 1

```
[code] IN_RANGE { 5 }
```

Result

This is equivalent to [code] = 5.

Example 2

```
[code] IN_RANGE { 5: }
```

Result

This is equivalent to [code] >= 5.

Example 3

```
[code] IN_RANGE { :5 }
```

Result

This is equivalent to [code] <= 5.

Example 4

```
[code] IN_RANGE { 5:10 }
```

Result

This is equivalent to ([code] >= 5 and [code] <= 10).

Example 5

```
[code] IN_RANGE { :5,10,20: }
```

Result

This is equivalent to ([code] <= 5 or [code] = 10 or [code] >= 20).

search case

This construct is the template for a search case, including the CASE, WHEN, ELSE, and END functions.

Syntax

```
CASE WHEN [Country] = 'Canada' THEN ([List Price] * 0.60) WHEN
[CountryCode] > 100 THEN [List Price] * 0.80
ELSE [List Price] END
```

simple case

This construct is the template for a simple case, including the CASE, WHEN, ELSE, and END functions.

Syntax

```
CASE [Country] WHEN 'Canada' THEN ([List Price] * 0.60) WHEN
'Australia' THEN [List Price] * 0.80
ELSE [List Price] END
```

Business Date/Time Functions

This list contains business functions for performing date and time calculations.

_add_seconds

Returns the time or datetime, depending on the format of "time_expression", that results from adding "integer_expression" seconds to "time_expression".

Syntax

```
_add_seconds ( time_expression, integer_expression )
```

Example 1

```
_add_seconds ( 13:04:59 , 1 )
```

Result

```
13:05:00
```

Example 2

```
_add_seconds ( 2002-04-30 12:10:10.000, 1 )
```

Result

```
2002-04-30 12:10:11.000
```

Example 3

```
_add_seconds ( 2002-04-30 00:00:00.000, 1/100 )
```

Note that the second argument is not a whole number. This is supported by some database technologies and increments the time portion.

Result

```
2002-04-30 00:00:00.010
```

_add_minutes

Returns the time or datetime, depending on the format of "time_expression", that results from adding "integer_expression" minutes to "time_expression".

Syntax

```
_add_minutes ( time_expression, integer_expression )
```

Example 1

```
_add_minutes ( 13:59:00 , 1 )
```

Result

14:00:00

Example 2

```
_add_minutes ( 2002-04-30 12:59:10.000, 1 )
```

Result

2002-04-30 13:00:10.000

Example 3

```
_add_minutes ( 2002-04-30 00:00:00.000, 1/60 )
```

Note that the second argument is not a whole number. This is supported by some database technologies and increments the time portion.

Result

2002-04-30 00:00:01.000

_add_hours

Returns the time or datetime, depending on the format of "time_expression", that results from adding "integer_expression" hours to "time_expression".

Syntax

```
_add_hours ( time_expression, integer_expression )
```

Example 1

```
_add_hours ( 13:59:00 , 1 )
```

Result

14:59:00

Example 2

```
_add_hours ( 2002-04-30 12:10:10.000, 1 )
```

Result

2002-04-30 13:10:10.000,

Example 3

```
_add_hours ( 2002-04-30 00:00:00.000, 1/60 )
```

Note that the second argument is not a whole number. This is supported by some database technologies and increments the time portion.

Result

```
2002-04-30 00:01:00.000
```

_add_days

Returns the date or datetime, depending on the format of "date_expression", that results from adding "integer_expression" days to "date_expression".

Syntax

```
_add_days ( date_expression, integer_expression )
```

Example 1

```
_add_days ( 2002-04-30 , 1 )
```

Result

```
2002-05-01
```

Example 2

```
_add_days ( 2002-04-30 12:10:10.000, 1 )
```

Result

```
2002-05-01 12:10:10.000
```

Example 3

```
_add_days ( 2002-04-30 00:00:00.000, 1/24 )
```

Note that the second argument is not a whole number. This is supported by some database technologies and increments the time portion.

Result

```
2002-04-30 01:00:00.000
```

_add_months

Adds "integer_expression" months to "date_expression". If the resulting month has fewer days than the day of month component, then the last day of the resulting month is returned. In all other cases the returned value has the same day of month component as "date_expression".

Syntax

```
_add_months ( date_expression, integer_expression )
```

Example 1

```
_add_months ( 2012-04-15 , 3 )
```

Result

2012-07-15

Example 2

```
_add_months ( 2012-02-29 , 1 )
```

Result

2012-03-29

Example 3

```
_last_of_month ( _add_months ( 2012-02-29 , 1 ) )
```

Result

2012-03-31

Example 4

```
_add_months ( 2012-01-31 , 1 )
```

Result

2012-02-29

Example 5

```
_add_months ( 2002-04-30 12:10:10.000 , 1 )
```

Result

2002-05-30 12:10:10.000

_add_years

Adds "integer_expression" years to "date_expression". If the "date_expression" is February 29 and resulting year is non leap year, then the resulting day is set to February 28. In all other cases the returned value has the same day and month as "date_expression".

Syntax

```
_add_years ( date_expression, integer_expression )
```

Example 1

```
_add_years ( 2012-04-15 , 1 )
```

Result

2013-04-15

Example 2

```
_add_years ( 2012-02-29 , 1 )
```

Result

2013-02-28

Example 3

```
_add_years ( 2002-04-30 12:10:10.000 , 1 )
```

Result

```
2003-04-30 12:10:10.000
```

_age

Returns a number that is obtained from subtracting "date_expression" from today's date. The returned value has the form YYYYMMDD, where YYYY represents the number of years, MM represents the number of months, and DD represents the number of days.

Syntax

```
_age ( date_expression )
```

Example

```
_age ( 1990-04-30 ) (if today's date is 2003-02-05)
```

Result

```
120906, meaning 12 years, 9 months, and 6 days.
```

_day_of_week

Returns the day of week (1 to 7), where 1 is the first day of the week as indicated by the second parameter (1 to 7, 1 being Monday and 7 being Sunday). Note that in ISO 8601 standard, a week begins with Monday being day 1.

Syntax

```
_day_of_week ( date_expression, integer )
```

Example

```
_day_of_week ( 2003-01-01 , 1 )
```

Result

```
3
```

_day_of_year

Returns the day of year (1 to 366) in "date_expression". Also known as Julian day.

Syntax

```
_day_of_year ( date_expression )
```

Example

```
_day_of_year ( 2003-03-01 )
```

Result

```
61
```

_days_between

Returns a positive or negative number representing the number of days between "date_expression1" and "date_expression2". If "date_expression1" < "date_expression2", then the result will be a negative number.

Syntax

```
_days_between ( date_expression1 , date_expression2 )
```

Example

```
_days_between ( 2002-04-30 , 2002-06-21 )
```

Result

-52

_days_to_end_of_month

Returns a number representing the number of days remaining in the month represented by "date_expression".

Syntax

```
_days_to_end_of_month ( date_expression )
```

Example

```
_days_to_end_of_month ( 2002-04-20 14:30:22.123 )
```

Result

10

_first_of_month

Returns a date or datetime, depending on the argument, by converting "date_expression" to a date with the same year and month but with the day set to 1.

Syntax

```
_first_of_month ( date_expression )
```

Example 1

```
_first_of_month ( 2002-04-20 )
```

Result

2002-04-01

Example 2

```
_first_of_month ( 2002-04-20 12:10:10.000 )
```

Result

2002-04-01 12:10:10.000

_last_of_month

Returns a date or datetime, depending on the argument, that is the last day of the month represented by "date_expression".

Syntax

```
_last_of_month ( date_expression )
```

Example 1

```
_last_of_month ( 2002-01-14 )
```

Result

```
2002-01-31
```

Example 2

```
_last_of_month ( 2002-01-14 12:10:10.000 )
```

Result

```
2002-01-31 12:10:10.000
```

_make_timestamp

Returns a timestamp constructed from "integer_expression1" (the year), "integer_expression2" (the month), and "integer_expression3" (the day). The time portion defaults to 00:00:00.000 .

Syntax

```
_make_timestamp ( integer_expression1, integer_expression2,  
integer_expression3 )
```

Example

```
_make_timestamp ( 2002 , 01 , 14 )
```

Result

```
2002-01-14 00:00:00.000
```

_months_between

Returns a positive or negative integer number representing the number of months between "date_expression1" and "date_expression2". If "date_expression1" is earlier than "date_expression2", then a negative number is returned.

Syntax

```
_months_between ( date_expression1, date_expression2 )
```

Example

```
_months_between ( 2002-04-03 , 2002-01-30 )
```

Result

```
2
```


_shift_timezone

Shifts a timestamp value from one time zone to another time zone. This function honors the Daylight Savings Time when applicable. If the first argument is of type "timestamp", then the second and third arguments represent the "from" and "target" time zones, respectively. If the first argument is of type "timestamp with time zone", then the "from" time zone is already implied in the first argument therefore the second argument represents the "target" time zone. The data type of the first argument will also determine the data type of the return value. The second and third arguments are of type "string" and represent time zone identifiers. A list of these identifiers can be found below. Note: using this function will cause local processing.

Note: Supported only in dynamic query mode.

Syntax

```
_shift_timezone ( timestamp_value , from_time_zone ,  
target_time_zone )  
_shift_timezone ( timestamp_with_time_zone_value , target_time_zone )
```

Example 1

```
_shift_timezone( 2013-06-30 12:00:00 , 'EST' , 'GMT' )
```

Result

```
2013-06-30 16:00:00
```

Example 2

```
_shift_timezone( 2013-11-30 12:00:00-05:00 , 'PST' )
```

Result

```
2013-11-30 09:00:00-08:00
```

Example 3

Time zone abbreviations:

Result data

```
GMT (GMT+00:00) Greenwich Mean Time  
UTC (GMT+00:00) Coordinated Universal Time  
WET (GMT+00:00) Western Europe Time: Lisbon, Faeroe Islands, Canary  
Islands  
ECT (GMT+01:00) European Central Time: Amsterdam, Brussels, Paris,  
Rome, Vienna  
MET (GMT+01:00) Middle European Time  
ART (GMT+02:00) Egypt Time: Cairo, Damascus, Beirut, Amman, Nicosia  
CAT (GMT+02:00) Central African Time: Johannesburg, Blantyre, Harare,  
Tripoli  
EET (GMT+02:00) Eastern Europe Time: Athens, Kiev, Sofia, Minsk,  
Bucharest, Vilnius, Tallinn  
EAT (GMT+03:00) East Africa Time: Addis Ababa, Asmera, Kampala,  
Nairobi, Mogadishu, Khartoum  
NET (GMT+04:00) Near East Time  
PLT (GMT+05:00) Pakistan Lahore Time  
IST (GMT+05:30) Indian Time  
BST (GMT+06:00) Bangladesh Time  
VST (GMT+07:00) Vietnam Time  
CTT (GMT+08:00) Asia, Hong Kong S.A.R. of China  
JST (GMT+09:00) Japan Time: Tokyo
```

ACT (GMT+09:30) Australian Central Time: Darwin
AET (GMT+10:00) Australian Eastern Time: Sydney, Melbourne, Canberra
SST (GMT+11:00) Solomon Time
AGT (GMT-03:00) Argentina Time
BET (GMT-03:00) Brazil Eastern Time: Sao Paulo, Buenos Aires
CNT (GMT-03:30) Newfoundland Time: St. Johns
PRT (GMT-04:00) Puerto Rico and U.S. Virgin Islands Time
EST (GMT-05:00) Eastern Time: Ottawa, New York, Toronto, Montreal, Jamaica, Porto Acre
CST (GMT-06:00) Central Time: Chicago, Cambridge Bay, Mexico City
MST (GMT-07:00) Mountain Time: Edmonton, Yellowknife, Chihuahua
PST (GMT-08:00) Pacific Time: Los Angeles, Tijuana, Vancouver
AST (GMT-09:00) Alaska Time: Anchorage, Juneau, Nome, Yakutat
HST (GMT-10:00) Hawaii Time: Honolulu, Tahiti
MIT (GMT-11:00) Midway Islands Time: Midway, Apia, Niue, Pago Pago

Example 4

A customized time zone identifier may also be used, using the format GMT(+|-)HH:MM. For example, GMT-06:30 or GMT+02:00.

A more complete

list of time zone identifiers (including longer form identifiers such as "Europe/Amsterdam") may be found in the "i18n_res.xml" file from the product's configuration folder.

_week_of_year

Returns the number of the week of the year of "date_expression" according to the ISO 8601 standard. Week 1 of the year is the first week of the year to contain a Thursday, which is equivalent to the first week containing January 4th. A week starts on Monday (day 1) and ends on Sunday (day 7).

Syntax

```
_week_of_year ( date_expression )
```

Example

```
_week_of_year ( 2003-01-01 )
```

Result

1

_years_between

Returns a positive or negative integer number representing the number of years between "date_expression1" and "date_expression2". If "date_expression1" < "date_expression2" then a negative value is returned.

Syntax

```
_years_between ( date_expression1, date_expression2 )
```

Example

```
_years_between ( 2003-01-30 , 2001-04-03 )
```

Result

1

`_ymdint_between`

Returns a number representing the difference between "date_expression1" and "date_expression2". The returned value has the form YYYYMMDD, where YYYY represents the number of years, MM represents the number of months, and DD represents the number of days.

Syntax

```
_ymdint_between ( date_expression1 , date_expression2 )
```

Example

```
_ymdint_between ( 1990-04-30 , 2003-02-05 )
```

Result

120906, meaning 12 years, 9 months and 6 days.

Block Functions

This list contains functions used to access members of a set, usually in the context of Analysis Studio.

`_firstFromSet`

Returns the first members found in the set up to "numeric_expression_maximum" + "numeric_expression_overflow". If "numeric_expression_maximum" + "numeric_expression_overflow" is exceeded, then only the maximum number of members are returned. For a set that has only a few members more than the specified numeric_expression_maximum, the numeric_expression_overflow allows the small set of extra members to be included. If the set has more members than the overflow allows, then only the numeric_expression_maximum members will be returned.

Syntax

```
_firstFromSet ( set_expression , numeric_expression_maximum ,  
numeric_expression_overflow )
```

Example 1

```
_firstFromSet ( [great_outdoors_company].[Products].[Products].  
[Product line] , 2 , 8 )
```

Result

Returns the five members in the Product line set. The first two members are returned within the maximum and the following three members are returned as the overflow.

Result data

```
Camping Equipment  
Golf Equipment  
Mountaineering Equipment  
Outdoor Protection  
Personal Accessories
```

Example 2

```
_firstFromSet ( [great_outdoors_company].[Products].[Products].  
[Product line] , 2 , 2 )
```

Result

Camping Equipment, Golf Equipment

_remainderSet

Returns the set containing "member_expression" when the size of "set_expression" is greater than "numeric_expression"; i.e., a new member will be generated if the number of members in "set_expression" is larger than the specified "numeric_expression".

Syntax

```
_remainderSet ( member_expression, set_expression ,  
numeric_expression )
```

Example

```
_remainderSet ( member ( aggregate ( currentMeasure within set  
[great_outdoors_company].[Products].[Products].[Product line] ) ,  
'Product Aggregate' , 'Product Aggregate' , [great_outdoors_company].  
[Products].[Products] ) , [great_outdoors_company].[Products].  
[Products].[Product line] , 1 )
```

Result

Quantity sold for Product Aggregate

Aster Data

Aster Data String

overlay

Returns the "string_exp1" replacing "string_exp2" from character position numeric_exp.

Syntax

```
overlay ( string_exp1, string_exp2, numeric_exp1 [, numeric_exp2] )
```

btrim

Returns string_exp1 after removing the longest string of characters in string_exp2.

Syntax

```
btrim( string_exp1 [, string_exp2] )
```

initcap

Returns "string_exp", with the first letter of each word in uppercase and all other letters in lowercase. Words are delimited by white space or characters that are not alphanumeric.

Syntax

```
initcap ( string_exp )
```

lpad

Returns "string_exp1" padded to length "integer_exp" with occurrences of "string_exp2". If "string_exp1" is longer than "integer_exp", the appropriate portion of "string_exp1" is returned.

Syntax

```
lpad ( string_exp1, integer_exp [ , string_exp2 ] )
```

ltrim

Returns "string_exp1", with leading characters removed up to the first character not in "string_exp2", e.g., ltrim('xyxXxyAB', 'xy') returns 'XxyAB'.

Syntax

```
ltrim ( string_exp1 [ , string_exp2 ] )
```

md5

Returns the MD5 hash of "string_exp1".

Syntax

```
md5 ( string_exp1 )
```

to_hex

Returns the hexadecimal string representation of "numeric_exp1".

Syntax

```
to_hex ( numeric_exp1 )
```

repeat

Returns the "string_exp" repeated "numeric_exp1" times.

Syntax

```
repeat ( string_exp, numeric_exp1 )
```

replace

Returns "string_exp" having replaced "string_exp2" with "string_exp3".

Syntax

```
replace( string_exp, string_exp2, string_exp3)
```

rpad

Returns "string_exp1" right-padded to length "integer_exp" with occurrences of "string_exp2". If "string_exp1" is longer than "integer_exp", the appropriate portion of "string_exp1" is returned. If "string_exp2" is not specified, then spaces are used.

Syntax

```
rpad ( string_exp1, integer_exp [ , string_exp2 ] )
```

rtrim

Returns "string_exp1", with final characters removed after the last character not in "string_exp2", e.g., rtrim('ABxXxyx', 'xy') returns 'ABxX'. If "string_exp2" is not specified, the final space characters are removed.

Syntax

```
rtrim ( string_exp1 [ , string_exp2 ] )
```

split_part

Returns "numeric_exp" field having split "string_exp1" on "string_exp2".

Syntax

```
split_part ( string_exp1 , string_exp2 , numeric_exp )
```

Aster Data Data Type Formatting

to_char

Returns the string representation of "exp" with the format of "string_exp". "Exp" can be either a date value or a numeric value.

Syntax

```
to_char ( exp , string_exp )
```

to_date

Converts "string_exp1" to a date value as specified by the format "string_exp2".

Syntax

```
to_date ( string_exp1 , string_exp2 )
```

to_number

Converts "string_exp1" to a numeric value as specified by the format "string_exp2".

Syntax

```
to_number ( string_exp1, string_exp2 )
```

to_timestamp

Converts "string_exp1" to a timestamp value as specified by the format "string_exp2".

Syntax

```
to_timestamp ( string_exp1, string_exp2 )
```

Aster Data Math

log

Returns the base 10 logarithm of "numeric_exp1" or logarithm to the base "numeric_exp2".

Syntax

```
log ( numeric_exp1[, numeric_exp2] )
```

ln

Returns the natural logarithm of "numeric_exp1".

Syntax

```
ln ( numeric_exp )
```

cbrt

Returns the cube root of "numeric_exp1".

Syntax

```
cbrt ( numeric_exp )
```

pi

Returns the constant of pi.

Syntax

```
pi ( )
```

Aster Data Trigonometry

acos

Returns the arccosine of "numeric_exp" in radians. The arccosine is the angle whose cosine is "numeric_exp".

Syntax

```
acos ( numeric_exp )
```

asin

Returns the arcsine of "numeric_exp" in radians. The arcsine is the angle whose sine is "numeric_exp".

Syntax

```
asin ( numeric_exp )
```

atan

Returns the arctangent of "numeric_exp" in radians. The arctangent is the angle whose tangent is "numeric_exp".

Syntax

```
atan ( numeric_exp )
```

atan2

Returns the arctangent of the x and y coordinates specified by "numeric_exp1" and "numeric_exp2", respectively, in radians. The arctangent is the angle whose tangent is "numeric_exp2" / "numeric_exp1".

Syntax

```
atan2 ( numeric_exp1, numeric_exp2 )
```

cos

Returns the cosine of "numeric_exp", where "numeric_exp" is an angle expressed in radians.

Syntax

```
cos ( numeric_exp )
```

cot

Returns the cotangent of "numeric_exp", where "numeric_exp" is an angle expressed in radians.

Syntax

```
cot ( numeric_exp )
```

degrees

Returns the degrees where "numeric_exp" is an angle expressed in radians.

Syntax

```
degrees ( numeric_exp )
```

radians

Returns the radians where "numeric_exp" is an angle expressed in degrees.

Syntax

radians (numeric_exp)

sin

Returns the sine of "numeric_exp", where "numeric_exp" is an angle expressed in radians.

Syntax

sin (numeric_exp)

tan

Returns the tangent of "numeric_exp", where "numeric_exp" is an angle expressed in radians.

Syntax

tan (numeric_exp)

ascii

Returns a number representing the ASCII code value of the leftmost character of "string_exp", e.g., ascii('A') is 65.

Syntax

ascii (string_exp)

chr

Returns the character that has the ASCII code value specified by "integer_exp". "Integer_exp" should be between 0 and 255.

Syntax

chr (integer_exp)

current_schema

Returns the name of the current schema

Syntax

current_schema ()

translate

Returns "string_exp1", with each occurrence of each character in "string_exp2" replaced by its corresponding character in "string_exp3".

Syntax

translate (string_exp1, string_exp2, string_exp3)

date_trunc

Returns the timestamp to the specified precision.

Syntax

date_trunc (string_exp, timestamp_exp)

version

Returns the string value of the database version.

Syntax

version ()

DB2

DB2 Math

log

Returns the natural logarithm of "numeric_expression".

Syntax

```
log ( numeric_expression )
```

log10

Returns the base ten logarithm of "numeric_expression".

Syntax

```
log10 ( numeric_expression )
```

rand

Generates a random number using "integer_expression" as a seed value.

Syntax

```
rand ( integer_expression )
```

DB2 Trigonometry

acos

Returns the arccosine of "numeric_expression" in radians. The arccosine is the angle whose cosine is "numeric_expression".

Syntax

```
acos ( numeric_expression )
```

asin

Returns the arcsine of "numeric_expression" in radians. The arcsine is the angle whose sine is "numeric_expression".

Syntax

```
asin ( numeric_expression )
```

atan

Returns the arctangent of "numeric_expression" in radians. The arctangent is the angle whose tangent is "numeric_expression".

Syntax

```
atan ( numeric_expression )
```

atanh

Returns the hyperbolic arctangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
atanh ( numeric_expression )
```

atan2

Returns the arctangent of the x and y coordinates specified by "numeric_expression1" and "numeric_expression2", respectively, in radians. The arctangent is the angle whose tangent is "numeric_expression2" / "numeric_expression1".

Syntax

```
atan2 ( numeric_expression1 , numeric_expression2 )
```

cos

Returns the cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cos ( numeric_expression )
```

cosh

Returns the hyperbolic cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cosh ( numeric_expression )
```

cot

Returns the cotangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cot ( numeric_expression )
```

degrees

Returns "numeric_expression" radians converted to degrees.

Syntax

```
degrees ( numeric_expression )
```

sin

Returns the sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
sin ( numeric_expression )
```

sinh

Returns the hyperbolic sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
sinh ( numeric_expression )
```

tan

Returns the tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

`tan (numeric_expression)`

tanh

Returns the hyperbolic tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

`tanh (numeric_expression)`

ascii

Returns the ASCII code value of the leftmost character of the argument as an integer.

Syntax

`ascii (string_expression)`

Example

`ascii (a)`

Result

Returns 65, the ASCII code value of "a".

ceiling

Returns the smallest integer greater than or equal to "numeric_expression".

Syntax

`ceiling (numeric_expression)`

Example

`ceiling (0.75)`

Result

Returns 0.8.

char

Returns a string representation of a date/time value or a decimal number.

Syntax

`char (expression)`

chr

Returns the character that has the ASCII code value specified by "integer_expression". "Integer_expression" should be between 0 and 255.

Syntax

`chr (integer_expression)`

Example

```
chr ( 65 )
```

Result

Returns a, the character for the ASCII code value of 65.

concat

Returns a string that is the result of concatenating "string_expression1" with "string_expression2".

Syntax

```
concat ( string_expression1, string_expression2 )
```

Example

```
concat ( [Sales target (query)].[Sales staff].[First name], [Sales  
target (query)].[Sales staff].[Last name] )
```

Result

Returns the first name and last name; e.g., Bob Smith.

date

Returns a date from a single input value. "Expression" can be a string or integer representation of a date.

Syntax

```
date ( expression )
```

Example

```
date ( '1998-01-08' )
```

Result

Returns 8 January 1998.

day

Returns the day of the month (1-31) from "date_expression". "Date_expression" can be a date value or a string representation of a date.

Syntax

```
day ( date_expression )
```

Example

```
day ( '1998-01-08' )
```

Result

Returns 8.

dayname

Returns a character string containing the data source-specific name of the day (for example, Sunday through Saturday or Sun. through Sat. for a data source that uses

English, or Sonntag through Samstag for a data source that uses German) for the day portion of "date_expression". "Date_expression" can be a date value or a string representation of a date.

Syntax

```
dayname ( date_expression )
```

Example

```
dayname ( '1998-01-08' )
```

Result

Returns Thursday.

dayofweek

Returns the day of the week in "date_expression" as an integer in the range 1 to 7, where 1 represents Sunday. "date_expression" can be a date value or a string representation of a date.

Syntax

```
dayofweek ( date_expression )
```

Example

```
dayofweek ( '1998-01-08' )
```

Result

Returns 5.

dayofweek_iso

Returns the day of the week in "date_expression" as an integer in the range 1 to 7, where 1 represents Monday. "date_expression" can be a date value or a string representation of a date.

Syntax

```
dayofweek_iso ( date_expression )
```

Example

```
dayofweek_iso ( '1998-01-08' )
```

Result

Returns 4.

dayofyear

Returns the day of the year in "date_expression" as an integer in the range 1 to 366. "Date_expression" can be a date value or a string representation of a date.

Syntax

```
dayofyear ( date_expression )
```

Example

```
dayofyear ( current_date )
```

Result

Returns the day of the year for the current date; e.g., if it was January 28, the expression would return 28.

days

Returns an integer representation of a date. "Expression" can be a date value or a string representation of a date.

Syntax

```
days ( expression )
```

dec

Returns the decimal representation of "string-expression" using "precision-integer" and "scale-integer". The "decimal-character" can be used to specify the single-byte character constant used to delimit the decimal digits in "string-expression". The "string-expression" must be formatted as an SQL Integer or Decimal constant.

Alternate syntax: `dec (numeric-expression [, precision-integer [, scale-integer]])` Returns the decimal representation of "numeric-expression" using "precision-integer" and "scale-integer".

Syntax

```
dec ( string-expression [ , precision-integer [ , scale-integer [ , decimal-character ] ] ] )
```

decimal

Returns the decimal representation of "string-expression" using "precision-integer" and "scale-integer". The "decimal-character" can be used to specify the single-byte character constant used to delimit the decimal digits in "string-expression". The "string-expression" must be formatted as an SQL Integer or Decimal constant.

Alternate syntax: `decimal (numeric-expression [, precision-integer [, scale-integer]])` Returns the decimal representation of "numeric-expression" using "precision-integer" and "scale-integer".

Syntax

```
decimal ( string-expression [ , precision-integer [ , scale-integer [ , decimal-character ] ] ] )
```

difference

Returns an integer value representing the difference between the values returned by the data source-specific soundex function for "string_expression1" and "string_expression2". The value returned ranges from 0 to 4, with 4 indicating the best match. Note that 4 does not mean that the strings are equal.

Syntax

```
difference ( string_expression1 , string_expression2 )
```

Example 1

```
difference ([Sales target (query)].[Sales staff].[First name],[Sales (query)].[Retailers].[Contact first name])
```

Result

0

Example 2

```
difference ([Sales target (query)].[Sales staff].[First name],[Sales target (query)].[Sales staff].[First name])
```

Result

4

digits

Returns the character string representation of a non-floating point number.

Syntax

```
digits ( numeric_expression )
```

double

Returns the floating-point representation of an expression. "Expression" can either be a numeric or string expression.

Syntax

```
double ( expression )
```

event_mon_state

Returns the operational state of a particular state monitor.

Syntax

```
event_mon_state ( string_expression )
```

float

Returns the floating-point representation of a number.

Syntax

```
float ( numeric_expression )
```

hex

Returns the hexadecimal representation of a value.

Syntax

```
hex ( expression )
```

hour

Returns the hour, an integer from 0 (midnight) to 23 (11:00 pm), from "time_expression". "Time_expression" can be a time value or a string representation of a time.

Syntax

```
hour ( time_expression )
```

Example

```
hour ( 01:22:45 )
```

Result

Returns 1.

insert

Returns a string where "integer_expression2" characters have been deleted from "string_expression1" beginning at "integer_expression1" and where "string_expression2" has been inserted into "string_expression1" at its start. The first character in the string is at position 1.

Syntax

```
insert ( string_expression1, integer_expression1,  
integer_expression2, string_expression2 )
```

integer

Returns the integer representation of an expression. "Expression" can be a numeric value or a string representation of a number.

Syntax

```
integer ( expression )
```

Example

```
integer ( 84.95 )
```

Result

85

int

Returns the integer representation of an expression. "Expression" can be a numeric value or a string representation of a number.

Syntax

```
int ( expression )
```

Example

```
int ( 84.95 )
```

Result

85

julian_day

Returns an integer value representing the number of days from January 1, 4712 BC (the start of the Julian date calendar) to the date value specified in "expression". "Expression" can be a date value or a string representation of a date.

Syntax

```
julian_day ( expression )
```


Example

```
julian_day ( '2009-06-29' )
```

Result

```
2455012.22130739595741034
```

lcase

Returns "string_expression" with all uppercase characters shifted to lowercase.

Syntax

```
lcase ( string_expression )
```

Example

```
lcase ( [Sales (query)].[Sales staff].[Last name] )
```

Result

Returns last names with no uppercase letters.

left

Returns the leftmost "integer_expression" characters of "string_expression".

Syntax

```
left ( string_expression, integer_expression )
```

Example

```
left ( [Sales (query)].[Sales staff].[Last name] , 3 )
```

Result

Returns the first three characters of each last name.

length

Returns the length of the operand in bytes. Exception: double byte string types return the length in characters.

Syntax

```
length ( expression )
```

Example

```
length ( [Sales (query)].[Sales staff].[Record start date] )
```

Result

Returns 4; dates always return a value of 4.

locate

Returns the starting position of the first occurrence of "string_expression1" within "string_expression2". The search starts at position start "integer_expression" of "string_expression2". The first character in a string is at position 1. If "string_expression1" is not found, zero is returned.

Syntax

```
locate ( string_expression1, string_expression2 [ ,  
integer_expression ] )
```

Example

```
locate ( A, [Sales (query)].[Sales staff].[Last name] , 2 )
```

Result

Returns the position of the character A in the last names starting at the second character of the last name.

long_varchar

Returns a long string.

Syntax

```
long_varchar ( string_expression )
```

ltrim

Returns "string_expression" with leading spaces removed.

Syntax

```
ltrim ( string_expression )
```

Example

```
ltrim ( [Sales (query)].[Sales staff].[Last name] )
```

Result

Returns last names with any leading spaces removed.

microsecond

Returns the microsecond (time-unit) part of a value. "Expression" can be a timestamp or a string representation of a timestamp.

Syntax

```
microsecond ( expression )
```

Example

```
microsecond ( 01:45:34.056 )
```

Result

Returns 056.

midnight_seconds

Returns an integer value in the range 0 to 86400 representing the number of seconds between midnight and time value specified in the argument. "Expression" can be a time value, a timestamp or a string representation of a time.

Syntax

```
midnight_seconds ( expression )
```

Example

```
midnight_seconds ( 01:45:34.056 )
```

Result

Returns 6334.

minute

Returns the minute (an integer from 0-59) from "time_expression".
"Time_expression" can be a time value, a timestamp, or a string representation of a time.

Syntax

```
minute ( time_expression )
```

Example

```
minute ( 01:45:34.056 )
```

Result

Returns 45.

month

Returns the month (an integer from 1-12) from "date_expression".

Syntax

```
month ( date_expression )
```

Example

```
month ( 2005-11-01 )
```

Result

Returns 11.

monthname

Returns a character string containing the data source-specific name of the month (for example, January through December or Jan. through Dec. for an English data source, or Januar through Dezember for a German data source) for the month portion of "date_expression".

Syntax

```
monthname ( date_expression )
```

Example

```
monthname ( 2005-11-01 )
```

Result

November

quarter

Returns the quarter in "date_expression" as a number in the range 1 to 4, where 1 represents January 1 through March 31.

Syntax

```
quarter ( date_expression )
```

Example

```
quarter ( 2005-11-01 )
```

Result

Returns 4.

radians

Returns the number of radians converted from "numeric_expression" degrees.

Syntax

```
radians ( numeric_expression )
```

repeat

Returns a string consisting of "string_expression" repeated "integer_expression" times.

Syntax

```
repeat ( string_expression, integer_expression )
```

Example

```
repeat ( XYZ, 3 )
```

Result

Returns XYZXYZXYZ.

replace

Replaces all occurrences of "string_expression2" in "string_expression1" with "string_expression3".

Syntax

```
replace ( string_expression1, string_expression2, string_expression3 )
```

Example

```
replace ( [Sales (query)].[Sales staff].[Position code], A, a )
```

Result

Returns position codes with all occurrences of "A" replaced by "a".

right

Returns the rightmost "integer_expression" characters of "string_expression".

Syntax

`right (string_expression, integer_expression)`

Example

`right ([Sales (query)].[Sales staff].[Position code], 3)`

Result

Returns the rightmost 3 characters of each position code.

round

Returns "numeric_expression" rounded to "integer_expression" places to the right of the decimal point. If "integer_expression" is negative, "numeric_expression" is rounded to the nearest absolute value "integer_expression" places to the left of the decimal point. Rounding takes place before data formatting is applied.

Syntax

`round (numeric_expression, integer_expression)`

Example

`round (3.14159265, 3)`

Result

Returns 3.142.

rtrim

Returns "string_expression" with trailing spaces removed.

Syntax

`rtrim (string_expression)`

Example

`rtrim ([Sales (query)].[Sales staff].[Last name])`

Result

Returns last names with any spaces at the end of the name removed.

second

Returns the second (an integer from 0-59) from "time_expression".

Syntax

`second (time_expression)`

Example

`second (01:45:34.056)`

Result

Returns 34.

sign

Returns an indicator of the sign of "numeric_expression": +1 if "numeric_expression" is positive, 0 if zero, or -1 if negative.

Syntax

```
sign ( numeric_expression )
```

Example

```
sign ( [Revenue] )
```

Result

Returns + for positive values and - for negative values.

smallint

Returns the small integer representation of a number.

Syntax

```
smallint ( expression )
```

soundex

Returns a 4 character string code obtained by systematically abbreviating words and names in "string_expression" according to phonetics. Can be used to determine if two strings sound the same. For example, does sound-of ('SMITH') = sound-of ('SMYTH').

Syntax

```
soundex ( string_expression )
```

space

Returns a string consisting of "integer_expression" spaces.

Syntax

```
space ( integer_expression )
```

Example

```
space ( 5 )
```

Result

Returns 5 spaces.

substr

Returns the substring of "string_expression" that starts at position "integer_expression1" for "integer_expression2" characters. The first character in "string_expression" is at position 1.

Syntax

```
substr ( string_expression , integer_expression1 [ ,  
integer_expression2 ] )
```

Example

```
substr ( [Sales (query)].[Sales staff].[Position code], 3 , 5 )
```

Result

Returns characters 3 to 7 of the position codes.

table_name

Returns an unqualified name of a table or view based on the object name in "string_expression1" and the schema name given in "string_expression2". It is used to resolve aliases.

Syntax

```
table_name ( string_expression1 [ , string_expression2 ] )
```

table_schema

Returns the schema name portion of the two-part table or view name based on the object name in "string_expression1" and the schema name in "string_expression2". It is used to resolve aliases.

Syntax

```
table_schema ( string_expression1 [ , string_expression2 ] )
```

time

Returns a time from a value.

Syntax

```
time ( expression )
```

timestamp

Returns a timestamp from a value or a pair of values. "Expression1" must represent a date value, and "expression2" must represent a time value.

Syntax

```
timestamp ( expression1 [ , expression2 ] )
```

Example

```
timestamp ( 11 November 2005 , 12:00:00.000000 )
```

Result

Returns 2005-11-11-12:00:00.000000.

timestamp_iso

Returns a datetime in the ISO format (yyyy-mm-dd hh:mm:ss.nnnnnn) converted from the IBM format (yyyy-mm-dd-hh.mm.ss.nnnnnn). If "expression" is a time, it inserts the value of the CURRENT DATE for the date elements and zero for the fractional time element.

Syntax

```
timestamp_iso ( expression )
```

Example

```
timestamp_iso ( 11 November 2005 , 12:00:00.000000 )
```

Result

Returns 2005-11-11 12:00:00.000000.

timestampdiff

Returns an estimated number of intervals of type "expression1" based on the difference between two timestamps. "Expression2" is the result of subtracting two timestamp types and converting the result to CHAR. Valid values of "expression1" are: 1 Fractions of a second; 2 Seconds; 4 Minutes; 8 Hours; 16 Days; 32 Weeks; 64 Months; 128 Quarters; 256 Years.

Syntax

```
timestampdiff ( expression1, expression2 )
```

to_char

Returns the string representation of a timestamp with the format of "string_expression".

Syntax

```
to_char ( timestamp_expression , string_expression )
```

to_date

Converts "expression1" to a datetime value as specified by the format "string_expression2". The first argument "expression1" may be of type string or numeric.

Syntax

```
to_date ( expression1 , string_expression2 )
```

Example

```
to_date ( '2013-02-27 15:13:14' , 'YYYY-MM-DD HH24:MI:SS' )
```

Result

Returns datetime with value '2013-02-27 15:13:14'.

translate

Returns "string_expression1" in which characters from "string_expression3" are translated to the equivalent characters in "string_expression2". "String_expression4" is a single character that is used to pad "string_expression2" if it is shorter than "string_expression3". If only "string_expression1" is present, then this function translates it to uppercase characters.

Syntax

```
translate ( string_expression1 [ , string_expression2,  
string_expression3 [ , string_expression4 ] ] )
```


Example 1

```
translate ( 'abcdefg' )
```

Result

Returns ABCDEFG.

Example 2

```
translate ( 'mnop' , n, m , - )
```

Result

Returns n-nlop.

trunc

Returns "numeric_expression1" truncated to "numeric_expression2" places to the right of the decimal point. If "numeric_expression2" is negative, "numeric_expression1" is truncated to the absolute value of "numeric_expression2" places to the left of the decimal point.

Syntax

```
trunc ( numeric_expression1, numeric_expression2 )
```

Example

```
trunc ( 3.14159265, 3 )
```

Result

Returns 3.141.

truncate

Returns "numeric_expression1" truncated to "numeric_expression2" places to the right of the decimal point. If "numeric_expression2" is negative, "numeric_expression1" is truncated to the absolute value of "numeric_expression2" places to the left of the decimal point.

Syntax

```
truncate ( numeric_expression1, numeric_expression2 )
```

Example

```
truncate ( 3141.59265, -3 )
```

Result

Returns 3.

ucase

Returns "string_expression" with all lowercase characters shifted to uppercase.

Syntax

```
ucase ( string_expression )
```

Example

```
ucase ( XY896Zbcd789 )
```

Result

Returns XY896ZBCED789.

value

Returns the first non-null argument (or null if all arguments are null). The Value function takes two or more arguments.

Syntax

```
value ( expression_list )
```

Example

```
value ( [Unit cost], [Unit price], [Unit sale price] )
```

Result

Returns the first non-null value.

varchar

Returns a VARCHAR representation of expression, with length numeric_expression.

Syntax

```
varchar ( expression [ , numeric_expression ] )
```

week

Returns the week of the year in "date_expression" as an integer value in the range 1 to 53.

Syntax

```
week ( date_expression )
```

Example

```
week ( 11 November 2005 )
```

Result

Returns 45.

year

Returns the year from "date_expression".

Syntax

```
year ( date_expression )
```

Example

```
year ( 11 November 2005 )
```

Result

Returns 2005.

Greenplum

Greenplum String

overlay

Returns the "string_expression1" replacing "string_expression2" from character position "numeric_expression".

Syntax

```
overlay ( string_expression1 , string_expression2 ,  
numeric_expression1 [ , numeric_expression2 ] )
```

btrim

Returns "string_expression1" after removing the longest string of characters in "string_expression2".

Syntax

```
btrim ( string_expression1 [ , string_expression2 ] )
```

initcap

Returns "string_expression" with the first letter of each word in uppercase and all other letters in lowercase. Words are delimited by white space or characters that are not alphanumeric.

Syntax

```
initcap ( string_expression )
```

lpad

Returns "string_expression1" padded to length "integer_expression" with occurrences of "string_expression2". If "string_expression1" is longer than "integer_expression", the appropriate portion of "string_expression1" is returned.

Syntax

```
lpad ( string_expression1 , integer_expression [ , string_expression2  
] )
```

ltrim

Returns "string_expression1", with leading characters removed up to the first character not in "string_expression2"; for example, ltrim ('xyxXxyAB' , 'xy') returns XxyAB.

Syntax

```
ltrim ( string_expression1 [ , string_expression2 ] )
```

md5

Returns the MD5 hash of "string_expression1".

Syntax

```
md5 ( string_expression1 )
```

to_hex

Returns the hexadecimal string representation of "numeric_expression1".

Syntax

```
to_hex ( numeric_expression1 )
```

repeat

Returns the "string_expression" repeated "numeric_expression1" times.

Syntax

```
repeat ( string_expression , numeric_expression1 )
```

replace

Returns "string_expression" having replaced "string_expression2" with "string_expression3".

Syntax

```
replace ( string_expression , string_expression2 , string_expression3)
```

rpad

Returns "string_expression1" right-padded to length "integer_expression" with occurrences of "string_expression2". If "string_expression1" is longer than "integer_expression", the appropriate portion of "string_expression1" is returned. If "string_expression2" is not specified, then spaces are used.

Syntax

```
rpad ( string_expression1 , integer_expression [ , string_expression2 ] )
```

rtrim

Returns "string_expression1", with final characters removed after the last character not in "string_expression2"; for example, rtrim ('ABxXxyx' , 'xy') returns ABxX. If "string_expression2" is not specified, the final space characters are removed.

Syntax

```
rtrim ( string_expression1 [ , string_expression2 ] )
```

split_part

Returns "numeric_expression" field having split "string_expression1" on "string_expression2".

Syntax

```
split_part ( string_expression1 , string_expression2 ,  
numeric_expression )
```

Greenplum Data type formatting

to_char

Returns the string representation of "expression" with the format of "string_expression". "Expression" can either be a date value or a numeric value.

Syntax

```
to_char ( expression , string_expression )
```

to_date

Converts "string_expression1" to a date value as specified by the format "string_expression2".

Syntax

`to_date (string_expression1 , string_expression2)`

to_number

Converts "string_expression1" to a numeric value as specified by the format "string_expression2".

Syntax

`to_number (string_expression1 , string_expression2)`

to_timestamp

Converts "string_expression1" to a timestamp value as specified by the format "string_expression2".

Syntax

`to_timestamp (string_expression1 , string_expression2)`

Greenplum Math

log

Returns the base 10 logarithm of "numeric_expression1" or logarithm to the base "numeric_expression2".

Syntax

`log (numeric_expression1 [, numeric_expression2])`

ln

Returns the natural logarithm of "numeric_expression1".

Syntax

`ln (numeric_expression)`

cbrt

Returns the cube root of "numeric_expression1".

Syntax

`cbrt (numeric_expression)`

pi

Returns the constant of pi.

Syntax

`pi ()`

Greenplum Trigonometry

acos

Returns the arccosine of "numeric_expression" in radians. The arccosine is the angle whose cosine is "numeric_expression".

Syntax

`acos (numeric_expression)`

asin

Returns the arcsine of "numeric_expression" in radians. The arcsine is the angle whose sine is "numeric_expression".

Syntax

```
asin ( numeric_expression )
```

atan

Returns the arctangent of "numeric_expression" in radians. The arctangent is the angle whose tangent is "numeric_expression".

Syntax

```
atan ( numeric_expression )
```

atan2

Returns the arctangent of the x and y coordinates specified by "numeric_expression1" and "numeric_expression2", respectively, in radians. The arctangent is the angle whose tangent is "numeric_expression2" / "numeric_expression1".

Syntax

```
atan2 ( numeric_expression1 ,numeric_expression2 )
```

cos

Returns the cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cos ( numeric_expression )
```

cot

Returns the cotangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cot ( numeric_expression )
```

degrees

Returns the degrees where "numeric_expression" is an angle expressed in radians.

Syntax

```
degrees ( numeric_expression )
```

radians

Returns the radians where "numeric_expression" is an angle expressed in degrees.

Syntax

```
radians ( numeric_expression )
```

sin

Returns the sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
sin ( numeric_expression )
```

tan

Returns the tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
tan ( numeric_expression )
```

ascii

Returns a number representing the ascii code value of the leftmost character of "string_expression"; for example, `ascii ('A')` is 65.

Syntax

```
ascii ( string_expression )
```

chr

Returns the character that has the ASCII code value specified by "integer_expression". "Integer_expression" should be between 0 and 255.

Syntax

```
chr ( integer_expression )
```

current_database

Returns the name of the current database.

Syntax

```
current_database ()
```

current_schema

Returns the name of the current schema.

Syntax

```
current_schema ()
```

{current_user}**Syntax**

```
{current_user}
```

{session_user}**Syntax**

```
{session_user}
```

translate

Returns "string_expression1" with each occurrence of each character in "string_expression2" replaced by its corresponding character in "string_expression3".

Syntax

```
translate ( string_expression1 , string_expression2 ,  
string_expression3 )
```

date_trunc

Returns the timestamp to the specified precision.

Syntax

```
date_trunc ( string_expression , timestamp_expression )
```

version

Returns the string value of the database version.

Syntax

```
version ( )
```

Informix

Informix Math

log10

Returns the logarithm of "numeric_expression" to base 10.

Syntax

```
log10 ( numeric_expression )
```

logn

Returns the natural logarithm of "numeric_expression".

Syntax

```
logn ( numeric_expression )
```

root

Returns the root value of "numeric_expression1". Requires at least one numeric argument (the radians argument). If only "numeric_expression1" is supplied, 2 is used as a default value for "numeric_expression2". Zero cannot be used as the value of "numeric_expression2".

Syntax

```
root ( numeric_expression1 [ , numeric_expression2 ] )
```

Informix Trigonometry

acos

Returns the arccosine of "numeric_expression" in radians. The arccosine is the angle whose cosine is "numeric_expression".

Syntax

```
acos ( numeric_expression )
```

asin

Returns the arcsine of "numeric_expression" in radians. The arcsine is the angle whose sine is "numeric_expression".

Syntax

```
asin ( numeric_expression )
```


atan

Returns the arctangent of "numeric_expression" in radians. The arctangent is the angle whose tangent is "numeric_expression".

Syntax

```
atan ( numeric_expression )
```

atan2

Returns the arctangent of the x and y coordinates specified by "numeric_expression1" and "numeric_expression2", respectively, in radians. The arctangent is the angle whose tangent is "numeric_expression1".

Syntax

```
atan2 ( numeric_expression1 , numeric_expression2 )
```

cos

Returns the cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cos ( numeric_expression )
```

sin

Returns the sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
sin ( numeric_expression )
```

tan

Returns the tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
tan ( numeric_expression )
```

cardinality

Returns the number of elements in a collection column (SET, MULTISSET, LIST).

Syntax

```
cardinality ( string_expression )
```

char_length

Returns the number of logical characters in "string_expression". The number of logical characters can be distinct from the number of bytes in some East Asian locales.

Syntax

```
char_length ( string_expression )
```

concat

Returns a string that is the result of concatenating, or joining, "string_expression1" to "string_expression2".

Syntax

```
concat ( string_expression1 , string_expression2 )
```

Example

```
concat ( [Sales (query)].[Sales staff].[First name], [Sales (query)].  
[Sales staff].[Last name] )
```

Result

Returns the first name and last name; e.g., Bob Smith.

date

Returns the date value of "string_expression", "date_expression", or "integer_expression".

Syntax

```
date ( string_expression|date_expression|integer_expression )
```

day

Returns an integer that represents the day of the month (1-31).

Syntax

```
day ( date_expression )
```

extend

Adjusts the precision of a datetime or date expression. The expression cannot be a quoted string representation of a date value. If you do not specify first and last qualifiers, the default qualifiers are year to fraction (3). If the expression contains fields that are not specified by the qualifiers, the unwanted fields are discarded. If the first qualifier specifies a larger (more significant) field than what exists in the expression, the new fields are filled in with values returned by the current function. If the last qualifier specifies a smaller (less significant) field than what exists in the expression, the new fields are filled in with constant values. A missing month or day field is filled in with 1, and missing hour to fraction fields are filled in with 0.

Syntax

```
extend ( date_expression , ' { ' year to second ' } ' )
```

Example

```
extend ( some_date_column , { year to second } )
```

hex

Returns the hexadecimal encoding of "integer_expression".

Syntax

```
hex ( integer_expression )
```

initcap

Returns "string_expression" with the first letter of each word in uppercase and all other letters in lowercase. A word begins after any character other than a letter. Thus, in addition to a blank space, symbols such as commas, periods, and colons can introduce a new word.

Syntax

```
initcap ( string_expression )
```

length

Returns the number of bytes in "string_expression", not including any trailing blank spaces. For byte or text "string_expression", length returns the full number of bytes, including any trailing blank spaces.

Syntax

```
length ( string_expression )
```

lpad

Returns "string_expression1" left-padded by "string_expression2" to the total number of characters specified by "integer_expression". The sequence of "string_expression2" occurs as many times as necessary to make the return string the length specified by "integer_expression".

Syntax

```
lpad ( string_expression1 , integer_expression , string_expression2 )
```

mdy

Returns a type date value with three expressions that evaluate to integers that represent the month (integer_expression1), day (integer_expression2), and year (integer_expression3).

Syntax

```
mdy ( integer_expression1 , integer_expression2 ,  
      integer_expression3 )
```

month

Returns an integer corresponding to the month portion of "date_expression".

Syntax

```
month ( date_expression )
```

nvl

Returns the value of "expression1" if "expression1" is not NULL. If "expression1" is NULL, then returns the value of "expression2".

Syntax

```
nvl ( expression1 , expression2 )
```

Example

```
nvl ( [Unit sale price] , [Unit price] )
```

Result

Returns the unit sale price, or returns the unit price if the unit sale price is NULL.

octet_length

Returns the number of bytes in "string_expression", including any trailing spaces.

Syntax

```
octet_length ( string_expression )
```

replace

Returns "string_expression1" in which every occurrence of "string_expression2" is replaced by "string_expression3". If you omit the "string_expression3" option, every occurrence of "string_expression2" is omitted from the return string.

Syntax

```
replace ( string_expression1 , string_expression2 [ ,  
string_expression3 ] )
```

Example

```
replace ( [Sales (query)].[Products].[Product line code] , - )
```

Result

Returns all product line codes without the character "-"

round

Returns the rounded value of "numeric_expression". If you omit "integer_expression", the value is rounded to zero digits or to the units place. The digit range of 32 (+ and -) refers to the entire decimal value. Rounding takes place before data formatting is applied.

Syntax

```
round ( numeric_expression [ , integer_expression ] )
```

Example

```
round (125, -1)
```

Result

130

rpad

Returns "string_expression1" right-padded by "string_expression2" to the total number of characters specified by "integer_expression". The sequence of "string_expression2" occurs as many times as necessary to make the return string the length specified by "integer_expression".

Syntax

```
rpad ( string_expression1 , integer_expression , string_expression2 )
```

substr

Returns the substring of "string_expression" that starts at position "integer_expression1" for "integer_expression2" characters. The first character in

"string_expression" is at position 1. If you omit "integer_expression2", returns the substring of "string_expression" that starts at position "integer_expression1" and ends at the end of "string_expression".

Syntax

```
substr ( string_expression , integer_expression1 [ ,  
integer_expression2 ] )
```

Example

```
substr ( [Sales (query)].[Sales staff].[Position code], 3 , 5 )
```

Result

Returns characters 3 to 7 of the position codes.

to_char

Returns the character string "date_expression" with the specified "string_expression" formatting. You can use this function only with built-in data types.

Syntax

```
to_char ( date_expression [ , string_expression ] )
```

to_date

Returns "string_expression1" as a date according to the date format you specify in "string_expression2". If "string_expression1" is NULL, then a NULL value is returned.

Syntax

```
to_date ( string_expression1 , string_expression2 )
```

trunc

Returns the truncated value of "numeric_expression". If you omit "integer_expression", then "numeric_expression" is truncated to zero digits or to the unit's place. The digit limitation of 32 (+ and -) refers to the entire decimal value.

Syntax

```
trunc ( numeric_expression [ , integer_expression ] )
```

weekday

Returns an integer that represents the day of the week of "date_expression". Zero (0) represents Sunday, one (1) represents Monday, and so on.

Syntax

```
weekday ( date_expression )
```

year

Returns a four-digit integer that represents the year of "date_expression".

Syntax

```
year ( date_expression )
```

MS Access Cast

cast_decimal

Returns the value of "expression" cast as a decimal.

Syntax

```
cast_decimal ( expression )
```

cast_float

Returns the value of "expression" cast as a float.

Syntax

```
cast_float ( expression )
```

cast_integer

Returns the value of "expression" cast as an integer.

Syntax

```
cast_integer ( expression )
```

Example

```
cast_integer ( 84.95 )
```

Result

84

cast_numeric

Returns "string_expression" cast as a numeric value.

Syntax

```
cast_numeric ( string_expression )
```

cast_real

Returns the value of "expression" cast as a real value.

Syntax

```
cast_real ( expression )
```

cast_smallint

Returns "expression" cast as a small integer.

Syntax

```
cast_smallint ( expression )
```

cast_varchar

Returns the value of "expression" cast as a variable character field.

Syntax

```
cast_varchar ( expression )
```

MS Access Math

log

Returns the natural logarithm of "numeric_expression".

Syntax

log (numeric_expression)

rand

Generates a random number using "integer_expression" as a seed value.

Syntax

rand (integer_expression)

MS Access Trigonometry

atan

Returns the arctangent of "numeric_expression" in radians. The arctangent is the angle whose tangent is "numeric_expression".

Syntax

atan (numeric_expression)

cos

Returns the cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

cos (numeric_expression)

sin

Returns the sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

sin (numeric_expression)

tan

Returns the tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

tan (numeric_expression)

ascii

Returns the ascii code value of the leftmost character of "string_expression".

Syntax

ascii (string_expression)

ceiling

Returns the smallest integer greater than or equal to "numeric_expression".

Syntax

`ceiling (numeric_expression)`

chr

Returns the character that has the ASCII code value specified by "integer_expression". "Integer_expression" should be between 0 and 255.

Syntax

`chr (integer_expression)`

concat

Returns a string that is the result of concatenating, or joining, "string_expression1" to "string_expression2".

Syntax

`concat (string_expression1 , string_expression2)`

Example

```
concat ( [Sales (query)].[Sales staff].[First name], [Sales (query)].  
[Sales staff].[Last name] )
```

Result

Returns the first name and last name; e.g., Bob Smith.

curdate

Returns a date value representing the current date of the computer that the database software runs on.

Syntax

`curdate ()`

curtime

Returns a time value representing the current time of the computer that the database software runs on.

Syntax

`curtime ()`

dayname

Returns a character string containing the data source-specific name of the day (for example, Sunday through Saturday or Sun. through Sat. for an English data source, or Sonntag through Samstag for a German data source) for the day portion of "date_expression".

Syntax

`dayname (date_expression)`

dayofmonth

Returns the day of the month (1-31) from "date_expression". Returns the days field (a signed integer) from "interval_expression".

Syntax

`dayofmonth (date_expression | interval_expression)`

dayofweek

Returns the day of the week in "date_expression" as an integer (1-7), where 1 represents Monday.

Syntax

`dayofweek (date_expression)`

dayofyear

Returns the day of the year in "date_expression" as an integer (1-366).

Syntax

`dayofyear (date_expression)`

hour

Returns the hour from "time_expression" as an integer from 0 (midnight) to 23 (11:00 pm).

Syntax

`hour (time_expression)`

instr

Searches "string_expression1" for the first occurrence of "string_expression2" and returns an integer specifying the position of "string_expression2". "Integer_expression1" sets the starting position for the search. If "integer_expression1" is omitted, the search begins at the first character position of "string_expression1". "Integer_expression2" specifies the type of string comparison. "Integer_expression1" is required if "integer_expression2" is specified.

Syntax

`instr ([integer_expression1 ,] string_expression1 ,
string_expression2 [, integer_expression2])`

lcase

Returns "string_expression" with all uppercase characters converted to lowercase.

Syntax

`lcase (string_expression)`

left

Returns the leftmost "integer_expression" characters of "string_expression".

Syntax

`left (string_expression , integer_expression)`

Example

`left ([Sales (query)].[Sales staff].[Last name] , 3)`

Result

Returns the first three characters of each last name.

length

Returns the number of characters in "string_expression", excluding trailing blanks and the string termination character.

Syntax

```
length ( string_expression )
```

locate

Returns the starting position of the first occurrence of "string_expression1" within "string_expression2". The search starts at position "integer_expression" of "string_expression2". The first character in a string is at position 1. If "string_expression1" is not found, then zero is returned.

Syntax

```
locate ( string_expression1 , string_expression2 [ ,  
integer_expression ] )
```

ltrim

Returns "string_expression" with leading spaces removed.

Syntax

```
ltrim ( string_expression )
```

minute

Returns the minute (an integer from 0-59) from "time_expression".

Syntax

```
minute ( time_expression )
```

month

Returns the month (an integer from 1-12) from "date_expression".

Syntax

```
month ( date_expression )
```

monthname

Returns a character string containing the data source-specific name of the month (for example, January through December or Jan. through Dec. for an English data source, or Januar through Dezember for a German data source) for the month portion of "date_expression".

Syntax

```
monthname ( date_expression )
```

Example

```
monthname ( 2005-11-01 )
```

Result

November

now

Returns a datetime value representing the current date and time of the computer that the database software runs on.

Syntax

```
now ( )
```

position

Returns the starting position of "string_expression1" in "string_expression2". The first character in a string is at position 1.

Syntax

```
position ( string_expression1 , string_expression2 )
```

quarter

Returns the quarter in "date_expression" as a number (1-4), where 1 represents January 1 through March 31.

Syntax

```
quarter ( date_expression )
```

right

Returns the rightmost "integer_expression" characters of "string_expression".

Syntax

```
right ( string_expression , integer_expression )
```

round

Returns "numeric_expression" rounded to the nearest value "integer_expression" places right of the decimal point. If "integer_expression" is negative, "numeric_expression" is rounded to the nearest absolute value "integer_expression" places to the left of the decimal point. Rounding takes place before data formatting is applied.

Syntax

```
round ( numeric_expression , integer_expression )
```

Example

```
round (125, -1)
```

Result

130

rtrim

Returns "string_expression" with trailing spaces removed.

Syntax

```
rtrim ( string_expression )
```

Example

```
rtrim ( [Sales (query)].[Sales staff].[Last name] )
```

Result

Returns last names with any spaces at the end of the name removed.

sign

Returns an indicator of the sign of "numeric_expression", +1 if positive, 0 if zero, or -1 if negative.

Syntax

```
sign ( numeric_expression )
```

space

Returns a string consisting of "integer_expression" spaces.

Syntax

```
space ( integer_expression )
```

substr

Returns the substring of "string_expression" that starts at position "integer_expression1" for "integer_expression2" characters. The first character in "string_expression" is at position 1.

Syntax

```
substr ( string_expression , integer_expression1 ,  
integer_expression2 )
```

Example

```
substr ( [Sales (query)].[Sales staff].[Position code], 3 , 5 )
```

Result

Returns characters 3 to 7 of the position codes.

substring

Returns the substring of "string_expression" that starts at position "integer_expression1" for "integer_expression2" characters. The first character in "string_expression" is at position 1.

Syntax

```
substring ( string_expression , integer_expression1 ,  
integer_expression2 )
```

Example

```
substring ( [Sales (query)].[Sales staff].[Position code], 3 , 5 )
```

Result

Returns characters 3 to 7 of the position codes.

truncate

Returns "string_expression" with trailing spaces removed.

Syntax

```
truncate ( string_expression )
```

ucase

Returns "string_expression" with all lowercase characters converted to uppercase.

Syntax

```
ucase ( string_expression )
```

week

Returns the week of the year in "date_expression" as an integer value (1-53), where 1 represents the first week of the year.

Syntax

```
week ( date_expression )
```

year

Returns the year from "date_expression".

Syntax

```
year ( date_expression )
```

MySQL

MySQL String

lpad

Returns "string_expression1" padded to length "integer_expression" with occurrences of "string_expression2". If "string_expression1" is longer than "integer_expression", the appropriate portion of "string_expression1" is returned.

Syntax

```
lpad ( string_expression1 , integer_expression [ , string_expression2 ] )
```

ltrim

Returns "string_expression1", with leading characters removed up to the first character not in "string_expression2"; for example, ltrim ('xyxXxyAB' , 'xy') returns XxyAB.

Syntax

```
ltrim ( string_expression1 [ , string_expression2 ] )
```

hex

Returns the hexadecimal string representation of "numeric_expression1".

Syntax

```
hex ( numeric_expression1 )
```

repeat

Returns the "string_expression" repeated "numeric_expression1" times.

Syntax

```
repeat ( string_expression , numeric_expression1 )
```

replace

Returns "string_expression" having replaced "string_expression2" with "string_expression3".

Syntax

```
replace ( string_expression , string_expression2 , string_expression3 )
```

reverse

Returns "string_expression" reversed.

Syntax

```
reverse ( string_expression )
```

right

Returns the rightmost "numeric_expression" characters from "string_expression1".

Syntax

```
right ( string_expression1 , numeric_expression )
```

rpad

Returns "string_expression1" right-padded to length "integer_expression" with occurrences of "string_expression2". If "string_expression1" is longer than "integer_expression", the appropriate portion of "string_expression1" is returned. If "string_expression2" is not specified, then spaces are used.

Syntax

```
rpad ( string_expression1 , integer_expression [ , string_expression2 ] )
```

rtrim

Returns "string_expression1", with final characters removed after the last character not in "string_expression2"; for example, rtrim ('ABxXxyx' , 'xy') returns ABxX. If "string_expression2" is not specified, the final space characters are removed.

Syntax

```
rtrim ( string_expression1 [ , string_expression2 ] )
```

soundex

Returns a soundex string of "string_expression1".

Syntax

```
soundex ( string_expression1 )
```

MySQL Math

log

Returns the base 10 logarithm of "numeric_expression1" or logarithm to the base "numeric_expression2".

Syntax

```
log ( numeric_expression )
```

ln

Returns the natural logarithm of "numeric_expression1".

Syntax

```
ln ( numeric_expression )
```

pi

Returns the constant of pi.

Syntax

```
pi ( )
```

MySQL Trigonometry

acos

Returns the arccosine of "numeric_expression" in radians. The arccosine is the angle whose cosine is "numeric_expression".

Syntax

```
acos ( numeric_expression )
```

asin

Returns the arcsine of "numeric_expression" in radians. The arcsine is the angle whose sine is "numeric_expression".

Syntax

```
asin ( numeric_expression )
```

atan

Returns the arctangent of "numeric_expression" in radians. The arctangent is the angle whose tangent is "numeric_expression".

Syntax

```
atan ( numeric_expression )
```

atan2

Returns the arctangent of the x and y coordinates specified by "numeric_expression1" and "numeric_expression2", respectively, in radians. The arctangent is the angle whose tangent is "numeric_expression2" / "numeric_expression1".

Syntax

```
atan2 ( numeric_expression1 ,numeric_expression2 )
```

cos

Returns the cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cos ( numeric_expression )
```

cot

Returns the cotangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cot ( numeric_expression )
```

degrees

Returns the degrees where "numeric_expression" is an angle expressed in radians.

Syntax

```
degrees ( numeric_expression )
```

radians

Returns the radians where "numeric_expression" is an angle expressed in degrees.

Syntax

```
radians ( numeric_expression )
```

sin

Returns the sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
sin ( numeric_expression )
```

tan

Returns the tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
tan ( numeric_expression )
```

ascii

Returns a number representing the ASCII code value of the leftmost character of "string_expression"; for example, `ascii ('A')` is 65.

Syntax

```
ascii ( string_expression )
```

database

Returns the current database name

Syntax

```
database ()
```

schema

Returns the current schema name

Syntax

```
schema ()
```


session_user

Return the user name returned by the client

Syntax

`session_user ()`

system_user

Return the user name returned by the client

Syntax

`system_user ()`

version

Returns the string value of the database version.

Syntax

`version ()`

Netezza

Netezza Math

log

Returns the logarithm of "numeric_expression2" to the base "numeric_expression1". When the optional argument "numeric_expression1" is not specified, the base 10 is used.

Syntax

`log ([numeric_expression1 ,] numeric_expression2)`

Netezza Trigonometry

acos

Returns the arccosine of "numeric_expression" in radians. The arccosine is the angle whose cosine is "numeric_expression".

Syntax

`acos (numeric_expression)`

asin

Returns the arcsine of "numeric_expression" in radians. The arcsine is the angle whose sine is "numeric_expression".

Syntax

`asin (numeric_expression)`

atan

Returns the arctangent of "numeric_expression" in radians. The arctangent is the angle whose tangent is "numeric_expression".

Syntax

`atan (numeric_expression)`

atan2

Returns the arctangent of the x and y coordinates specified by "numeric_expression1" and "numeric_expression2", respectively, in radians. The arctangent is the angle whose tangent is "numeric_expression2" / "numeric_expression1".

Syntax

```
atan2 ( numeric_expression1 , numeric_expression2 )
```

cos

Returns the cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cos ( numeric_expression )
```

degrees

Returns the degrees where "numeric_expression" is an angle expressed in radians.

Syntax

```
degrees ( numeric_expression )
```

radians

Returns the radians where "numeric_expression" is an angle expressed in degrees.

Syntax

```
radians ( numeric_expression )
```

sin

Returns the sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
sin ( numeric_expression )
```

tan

Returns the tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
tan ( numeric_expression )
```

Netezza Fuzzy**le_dst**

Returns a value indicating how different the two input strings are, calculated according to the Levenshtein edit distance algorithm.

Syntax

```
le_dst ( string_expression1 , string_expression2 )
```

dle_dst

Returns a value indicating how different the two input strings are, calculated according to the Damerau-Levenshtein distance algorithm

Syntax

`dle_dst (string_expression1 , string_expression2)`

Netezza Phonetic

nysiis

Returns a Soundex representation of "string_expression" using the New York State Identification and Intelligence System (NYSIIS) variation of Soundex.

Syntax

`nysiis (string_expression)`

dbl_mp

Returns a composite 32-bit value of "string_expression".

Syntax

`dbl_mp (string_expression)`

pri_mp

Returns the 4 character primary metaphone string from "numeric_expression" returned by `dbl_mp`.

Syntax

`pri_mp (numeric_expression)`

sec_mp

Returns the 4 character secondary metaphone string from "numeric_expression" returned by `dbl_mp`.

Syntax

`sec_mp (numeric_expression)`

score_mp

Returns a score for how closely "numeric_expression" and "numeric_expression2" match.

Syntax

`score_mp (numeric_expression , numeric_expression2 ,
numeric_expression3 , numeric_expression4 , numeric_expression5 ,
numeric_expression6)`

ascii

Returns a number representing the ASCII code value of the leftmost character of "string_expression"; for example, `ascii ('A')` is 65.

Syntax

`ascii (string_expression)`

chr

Returns the character that has the ASCII code value specified by "integer_expression". "Integer_expression" should be between 0 and 255.

Syntax

`chr (integer_expression)`

decode

Compares "expr" to each search value one by one. If "expr" is equal to a search, then it returns the corresponding result. If no match is found, it returns "default". If "default" is omitted, it returns null.

Syntax

```
decode ( expr , search , result [ , search , result]... [ , default] )
```

initcap

Returns "string_expression", with the first letter of each word in uppercase, all other letters in lowercase. Words are delimited by white space or characters that are not alphanumeric.

Syntax

```
initcap ( string_expression )
```

instr

Searches "string_expression1" starting at position "integer_expression1" for the "integer_expression2" occurrence of "string_expression2". If "integer_expression1" is negative then the search is backwards from the end of "string_expression1". Returns an integer indicating the position of "string_expression2".

Syntax

```
instr ( string_expression1 , string_expression2 [ ,  
integer_expression1 [ , integer_expression2 ] ] )
```

lpad

Returns "string_expression1" padded to length "integer_expression" with occurrences of "string_expression2". If "string_expression1" is longer than "integer_expression", the appropriate portion of "string_expression1" is returned.

Syntax

```
lpad ( string_expression1 , integer_expression [ , string_expression2  
] )
```

ltrim

Returns "string_expression1", with leading characters removed up to the first character not in "string_expression2"; for example, ltrim ('xyxXxyAB' , 'xy') returns XxyAB.

Syntax

```
ltrim ( string_expression1 [ , string_expression2 ] )
```

months_between

Returns the number of months from "date_expression1" to "date_expression2". If "date_expression1" is later than "date_expression2" then the result will be a positive number. The days and time portions of the difference are ignored, i.e., the months are not rounded, except if "date_expression1" and "date_expression2" are the last days of a month.

Syntax

```
months_between ( date_expression1 , date_expression2 )
```

next_day

Returns the datetime of the first weekday named by "string_expression" that is later than "datetime_expression". The return value has the same hours, minutes, and seconds as "datetime_expression".

Syntax

```
next_day ( datetime_expression , string_expression )
```

nvl

Returns the value of "expression1" if "expression1" is not NULL. If "expression1" is NULL, then returns the value of "expression2".

Syntax

```
nvl ( expression1 , expression2 )
```

Example

```
nvl ( [Unit sale price] , 0 )
```

Result

Returns the unit sale price, or returns 0 if the unit sale price is NULL.

round

Returns "numeric_expression" rounded to the nearest value "integer_expression" places right of the decimal point. If "integer_expression" is negative, "numeric_expression" is rounded to the nearest absolute value "integer_expression" places to the left of the decimal point; for example, round (125, -1) rounds to 130.

Syntax

```
round ( numeric_expression [ , integer_expression ] )
```

rpad

Returns "string_expression1" right-padded to length "integer_expression" with occurrences of "string_expression2". If "string_expression1" is longer than "integer_expression", the appropriate portion of "string_expression1" is returned. If "string_expression2" is not specified, then spaces are used.

Syntax

```
rpad ( string_expression1 , integer_expression [ , string_expression2 ] )
```

rtrim

Returns "string_expression1", with final characters removed after the last character not in "string_expression2"; for example, rtrim ('ABxXxyx' , 'xy') returns ABxX. If "string_expression2" is not specified, the final space characters are removed.

Syntax

```
rtrim ( string_expression1 [ , string_expression2 ] )
```

substr

Returns the substring of "string_expression" that starts at position "integer_expression1". The first character in "string_expression" is at position 1. "Integer_expression2" can be used to select fewer characters; by default it selects characters to the end of the string.

Syntax

```
substr ( string_expression , integer_expression1 [ ,  
integer_expression2 ] )
```

{current_db}

Syntax

```
{current_db}
```

{current_user}

Syntax

```
{current_user}
```

{session_user}

Syntax

```
{session_user}
```

to_char

Returns the string representation of "expression" with the format of "string_expression". "Expression" can be either a date value or a numeric value.

Syntax

```
to_char ( expression [ , string_expression ] )
```

to_date

Converts "expression1" to a date value as specified by the format "string_expression2". The first argument "expression1" may be of type string or numeric.

Syntax

```
to_date ( expression1 , string_expression2 )
```

Example

```
to_date ( '2013-02-27' , 'YYYY-MM-DD' )
```

Result

Returns date with value '2013-02-27'.

to_number

Converts "string_expression1" to a numeric value as specified by the format "string_expression2".

Syntax

```
to_number ( string_expression1 , string_expression2 )
```

translate

Returns "string_expression1", with all occurrences of each character in "string_expression2" replaced by its corresponding character in "string_expression3".

Syntax

```
translate ( string_expression1 , string_expression2 ,  
string_expression3 )
```

date_trunc

Truncates "date_expression1" to a value as specified by the format "string_expression1".

Syntax

```
date_trunc ( string_expression1 , date_expression1 )
```

trunc

Truncates digits from "numeric_expression1" using "numeric_expression2" as the precision.

Syntax

```
trunc ( numeric_expression1 [ , numeric_expression2 ] )
```

version

Returns the "string_expression1" value of the database version.

Syntax

```
version ( )
```

Oracle

Oracle Math

log

Returns the logarithm of "numeric_expression2" to the base "numeric_expression1". When the optional argument "numeric_expression1" is not specified, the base used is the constant e (which is approximately equal to 2.71282).

Syntax

```
log ([ numeric_expression1 , ] numeric_expression2 )
```

Oracle Trigonometry

acos

Returns the arccosine of "numeric_expression" in radians. The arccosine is the angle whose cosine is "numeric_expression".

Syntax

```
acos ( numeric_expression )
```

asin

Returns the arcsine of "numeric_expression" in radians. The arcsine is the angle whose sine is "numeric_expression".

Syntax

```
asin ( numeric_expression )
```

atan

Returns the arctangent of "numeric_expression" in radians. The arctangent is the angle whose tangent is "numeric_expression".

Syntax

```
atan ( numeric_expression )
```

atan2

Returns the arctangent of the x and y coordinates specified by "numeric_expression1" and "numeric_expression2", respectively, in radians. The arctangent is the angle whose tangent is "numeric_expression2" / "numeric_expression1".

Syntax

```
atan2 ( numeric_expression1 ,numeric_expression2 )
```

cos

Returns the cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cos ( numeric_expression )
```

cosh

Returns the hyperbolic cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cosh ( numeric_expression )
```

sin

Returns the sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
sin ( numeric_expression )
```

sinh

Returns the hyperbolic sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
sinh ( numeric_expression )
```

tan

Returns the tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
tan ( numeric_expression )
```

tanh

Returns the hyperbolic tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
tanh ( numeric_expression )
```

add_months

Returns the datetime resulting from adding "integer_expression" months to "date_expression".

Syntax

```
add_months ( date_expression , integer_expression )
```

ascii

Returns a number representing the ASCII code value of the leftmost character of "string_expression".

Syntax

```
ascii ( string_expression )
```

Example

```
ascii ( 'A' )
```

Result

Returns '65'

ceil

Returns the smallest integer greater than or equal to "numeric_expression".

Syntax

```
ceil ( numeric_expression )
```

char_length

Returns the number of logical characters in "string_expression". The number of logical characters can be distinct from the number of bytes in some East Asian locales.

Syntax

```
char_length ( string_expression )
```

chr

Returns the character that has the ASCII code value specified by "integer_expression". "Integer_expression" should be between 0 and 255.

Syntax

```
chr ( integer_expression )
```

concat

Returns a string that is the result of concatenating, or joining, "string_expression1" to "string_expression2".

Syntax

```
concat ( string_expression1 , string_expression2 )
```

Example

```
concat ( [Sales (query)].[Sales staff].[First name], [Sales (query)].  
[Sales staff].[Last name] )
```

Result

Returns the first name and last name; e.g., Bob Smith.

decode

Compares "expression" to each search value one by one. If "expression" is equal to a search, then it returns the corresponding result. If no match is found, it returns "default", or if "default" is omitted, it returns null.

Syntax

```
decode ( expression , search , result [ , search , result ]... [ ,  
default ] )
```

dump

Returns internal representation of "expression" with the format of "numeric_expression1" starting from position "numeric_expression2" for "numeric_expression3" characters.

Syntax

```
dump ( expression [ , numeric_expression1 [ , numeric_expression2 [ ,  
numeric_expression3 ] ] ] )
```

greatest

Returns the greatest value in "expression_list".

Syntax

```
greatest ( expression_list )
```

initcap

Returns "string_expression" with the first letter of each word in uppercase and all other letters in lowercase. Words are delimited by white space or characters that are not alphanumeric.

Syntax

```
initcap ( string_expression )
```

instr

Searches "string_expression1" starting at position "integer_expression1" for the "integer_expression2" occurrence of "string_expression2". If "integer_expression1" is negative, then the search occurs backwards from the end of "string_expression1". Returns an integer indicating the position of "string_expression2".

Syntax

```
instr ( string_expression1, string_expression2 [ ,  
integer_expression1 [ , integer_expression2 ] ] )
```

instrb

Searches "string_expression1" starting at position "integer_expression1" for the "integer_expression2" occurrence of "string_expression2". If "integer_expression1" is negative, then the search occurs backwards from the end of "string_expression1". Returns the position (byte number) where "string_expression2" was found.

Syntax

```
instrb ( string_expression1, string_expression2 [ ,  
integer_expression1 [ , integer_expression2 ] ] )
```

least

Returns the least value in "expression_list".

Syntax

```
least ( expression_list )
```

length

Returns the number of characters in "string_expression".

Syntax

```
length ( string_expression )
```

lengthb

Returns the number of bytes in "string_expression".

Syntax

```
lengthb ( string_expression )
```

lpad

Returns "string_expression1" left-padded to the length defined by "integer_expression" with occurrences of "string_expression2". If "string_expression1" is longer than "integer_expression", the appropriate portion of "string_expression1" is returned.

Syntax

```
lpad ( string_expression1, integer_expression [ ,  
string_expression2 ] )
```

ltrim

Returns "string_expression1" with leading characters removed up to the first character not in "string_expression2".

Syntax

```
ltrim ( string_expression1 [ , string_expression2 ] )
```

Example

```
ltrim ( 'xyxXxyAB' , 'xy' )
```

Result

XxyAB

months_between

Returns the number of months from "date_expression1" to "date_expression2". If "date_expression1" is later than "date_expression2" then the result will be a positive number. The days and time portion of the difference are ignored, so the months are not rounded unless "date_expression1" and "date_expression2" are the last days of a month.

Syntax

```
months_between ( date_expression1 , date_expression2 )
```

new_time

Returns the datetime in "new_timezone" for "datetime_expression" in "old_timezone". "Old_timezone" and "new_timezone" can be one of 'AST', 'ADT', 'BST', 'BDT', 'CST', 'CDT', 'EST', 'EDT', 'HST', 'HDT', 'MST', 'MDT', 'NST', 'PST', 'PDT', 'YST', or 'YDT'.

Syntax

```
new_time ( datetime_expression , old_timezone , new_timezone )
```

next_day

Returns the datetime of the first weekday named by "string_expression" that is later than "datetime_expression". The return value has the same format as "datetime_expression".

Syntax

```
next_day ( datetime_expression , string_expression )
```

nls_initcap

Returns "string_expression1" with the first letter of each word in uppercase and all other letters in lowercase. A word begins after any character other than a letter. Thus, in addition to a blank space, symbols such as commas, periods, and colons can introduce a new word. "String_expression2" specifies the sorting sequence.

Syntax

```
nls_initcap ( string_expression1 [ , string_expression2 ] )
```

nls_lower

Returns "string_expression1" with all letters in lowercase. "String_expression2" specifies the sorting sequence.

Syntax

```
nls_lower ( string_expression1 [ , string_expression2 ] )
```

nls_upper

Returns "string_expression1" with all letters in uppercase. "String_expression2" specifies the sorting sequence.

Syntax

```
nls_upper ( string_expression1 [ , string_expression2 ] )
```

nvl

Returns the value of "expression1" if "expression1" is not NULL. If "expression1" is NULL, then returns the value of "expression2".

Syntax

```
nvl ( expression1 , expression2 )
```

Example

```
nvl ( [Unit sale price] , 0 )
```

Result

Returns the unit sale price, or returns 0 if the unit sale price is NULL.

replace

Replaces all occurrences of "string_expression2" in "string_expression1" with "string_expression3". If "string_expression3" is not specified, then it removes all occurrences of "string_expression2".

Syntax

```
replace ( string_expression1 , string_expression2 [ ,  
string_expression3 ] )
```

round

Returns "numeric_expression" rounded to the nearest value "integer_expression" places right of the decimal point. If "integer_expression" is negative, "numeric_expression" is rounded to the nearest absolute value "integer_expression" places to the left of the decimal point. Rounding takes place before data formatting is applied.

Syntax

```
round ( numeric_expression [ , integer_expression ] )
```

Example

```
round ( 125 , -1 )
```

Result

Returns 130

rpad

Returns "string_expression1" right-padded to length "integer_expression" with occurrences of "string_expression2". If "string_expression1" is longer than "integer_expression", the appropriate portion of "string_expression1" is returned. If "string_expression2" is not specified, then occurrences of "string_expression2" are replaced with spaces.

Syntax

```
rpad ( string_expression1 , integer_expression [ ,  
      string_expression2 ] )
```

rtrim

Returns "string_expression1" with the final characters removed after the last character not in "string_expression2". If "string_expression2" is not specified, the final space characters are removed.

Syntax

```
rtrim ( string_expression1 [ , string_expression2 ] )
```

Example

```
rtrim ( 'ABxXxyx' , 'xy' )
```

Result

Returns 'ABxX'

sign

Returns an indicator of the sign of "numeric_expression", +1 if positive, 0 if zero, or -1 if negative.

Syntax

```
sign ( numeric_expression )
```

soundex

Returns a character string containing the phonetic representation of "string_expression".

Syntax

```
soundex ( string_expression )
```

substr

Returns the substring of "string_expression" that starts at position "integer_expression1" for "integer_expression2" characters or to the end of "string_expression" if "integer_expression2" is omitted. The first character in "string_expression" is at position 1.

Syntax

```
substr ( string_expression , integer_expression1 [ ,  
      integer_expression2 ] )
```

Example

```
substr ( [Sales (query)].[Sales staff].[Position code], 3 , 5 )
```

Result

Returns characters 3 to 7 of the position codes.

substrb

Returns the substring of "string_expression" that starts at position "numeric_expression1" and ends after "numeric_expression2" bytes. The first byte

in "string_expression" is at position 1. If you omit "numeric_expression2", returns the substring of "string_expression" that starts at position "numeric_expression1" and ends at the end of "string_expression".

Syntax

```
substrb ( string_expression , numeric_expression1 [ ,  
         numeric_expression2 ] )
```

Example

```
substrb ( [Sales (query)].[Sales staff].[Position code], 3 , 5 )
```

Result

Returns characters 3 to 7 of the position codes.

{sysdate}

Returns a datetime value representing the current date and time of the computer that the database software runs on.

Syntax

```
{ sysdate }
```

to_char

Returns the string representation of "expression" with the format of "string_expression". "Expression" can be either a date value or a numeric value.

Syntax

```
to_char ( expression [ , string_expression ] )
```

to_date

Converts "expression1" to a datetime value as specified by the format "string_expression2". The first argument "expression1" may be of type string or numeric. "String_expression3" specifies the format elements, such as language.

Syntax

```
to_date ( expression1 [ , string_expression2 [ ,  
         string_expression3 ] ] )
```

Example 1

```
to_date ( '2013-02-27 15:13:14' , 'YYYY-MM-DD HH24:MI:SS' )
```

Result

Returns datetime with value '2013-02-27 15:13:14'.

Example 2

```
to_date ( '2013-02-27 15:13:14' , 'YYYY-MM-DD HH24:MI:SS' ,  
         'NLS_DATE_LANGUAGE = American' )
```

Result

Returns datetime with value '2013-02-27 15:13:14'.

to_number

Converts "string_expression1" to a numeric value as specified by the format "string_expression2". "String_expression3" specifies the format elements, such as currency information.

Syntax

```
to_number ( string_expression1 , string_expression2 ,  
            string_expression3 )
```

translate

Returns "string_expression1" with all occurrences of each character in "string_expression2" replaced by the corresponding character in "string_expression3".

Syntax

```
translate ( string_expression1 , string_expression2 ,  
            string_expression3 )
```

trunc

Truncates "date_expression" using the format specified by "string_expression". For example, if "string_expression" is 'year', then "date_expression" is truncated to the first day of the year.

Syntax

```
trunc ( date_expression , string_expression )
```

Example

```
trunc ( 2003-08-22 , 'year' )
```

Result

Returns 2003-01-01.

trunc

Truncates digits from "numeric_expression1" using "numeric_expression2" as the precision.

Syntax

```
trunc ( numeric_expression1 , numeric_expression2 )
```

{user}

Returns the username of the current Oracle user.

Syntax

```
{ user }
```

vsize

Returns the number of bytes in the internal representation of "expression". "Expression" must be a string expression.

Syntax

```
vsize ( expression )
```

Paracel

Paracel String

overlay

Returns the "string_expression1", replacing "string_expression2" from character position numeric_expression.

Syntax

```
overlay ( string_expression1 , string_expression2 ,  
numeric_expression1 [ , numeric_expression2 ] )
```

ltrim

Returns "string_expression1", with leading characters removed up to the first character not in "string_expression2"; for example, ltrim ('xyxXxyAB' , 'xy') returns XxyAB.

Syntax

```
ltrim ( string_expression1 [ , string_expression2 ] )
```

replace

Returns "string_expression", having replaced "string_expression2" with "string_expression3".

Syntax

```
replace ( string_expression , string_expression2 , string_expression3  
)
```

rtrim

Returns "string_expression1", with final characters removed after the last character not in "string_expression2"; for example, rtrim ('ABxXxyx' , 'xy') returns ABxX. If "string_expression2" is not specified, the final space characters are removed.

Syntax

```
rtrim ( string_expression1 [ , string_expression2 ] )
```

Paracel Data type formatting

to_char

Returns the string representation of "expression" with the format of "string_expression". "Expression" can be either a date value or a numeric value.

Syntax

```
to_char ( expression , string_expression )
```

to_date

Converts "string_expression1" to a date value as specified by the format "string_expression2".

Syntax

```
to_date ( string_expression1 , string_expression2 )
```

to_number

Converts "string_expression1" to a numeric value as specified by the format "string_expression2".

Syntax

to_number (string_expression1 , string_expression2)

Paracel Math**cbrt**

Returns the cube root of "numeric_expression1".

Syntax

cbrt (numeric_expression)

pi

Returns the constant of pi.

Syntax

pi ()

current_database

Returns the name of the current database.

Syntax

current_database ()

current_schema

Returns the name of the current schema

Syntax

current_schema ()

{current_user}**Syntax**

{current_user}

{session_user}**Syntax**

{session_user}

translate

Returns "string_expression1", with each occurrence of each character in "string_expression2" replaced by its corresponding character in "string_expression3".

Syntax

translate (string_expression1 , string_expression2 , string_expression3)

version

Returns the string value of the database version.

Syntax

version ()

Postgres String

overlay

Returns the "string_expression1" replacing "string_expression2" from character position numeric_expression.

Syntax

```
overlay ( string_expression1 , string_expression2 ,  
numeric_expression1 [ , numeric_expression2 ] )
```

btrim

Returns string_expression1 after removing the longest string of characters in "string_expression2".

Syntax

```
btrim ( string_expression1 [ , string_expression2 ] )
```

initcap

Returns "string_expression", with the first letter of each word in uppercase and all other letters in lowercase. Words are delimited by white space or characters that are not alphanumeric.

Syntax

```
initcap ( string_expression )
```

lpad

Returns "string_expression1" padded to length "integer_expression" with occurrences of "string_expression2". If "string_expression1" is longer than "integer_expression", the appropriate portion of "string_expression1" is returned.

Syntax

```
lpad ( string_expression1 , integer_expression [ , string_expression2  
] )
```

ltrim

Returns "string_expression1", with leading characters removed up to the first character not in "string_expression2"; for example, ltrim ('xyxXxyAB' , 'xy') returns XxyAB.

Syntax

```
ltrim ( string_expression1 [ , string_expression2 ] )
```

md5

Returns the MD5 hash of "string_expression1".

Syntax

```
md5 ( string_expression1 )
```

to_hex

Returns the hexadecimal string representation of "numeric_expression1".

Syntax

```
to_hex ( numeric_expression1 )
```

repeat

Returns the "string_expression" repeated "numeric_expression1" times.

Syntax

```
repeat ( string_expression , numeric_expression1 )
```

replace

Returns "string_expression" with "string_expression2" replaced with "string_expression3".

Syntax

```
replace ( string_expression , string_expression2 , string_expression3)
```

rpad

Returns "string_expression1" right-padded to length "integer_expression" with occurrences of "string_expression2". If "string_expression1" is longer than "integer_expression", the appropriate portion of "string_expression1" is returned. If "string_expression2" is not specified, then spaces are used.

Syntax

```
rpad ( string_expression1 , integer_expression [ , string_expression2 ] )
```

rtrim

Returns "string_expression1", with final characters removed after the last character not in "string_expression2"; for example, rtrim ('ABxXxyx' , 'xy') returns ABxX. If "string_expression2" is not specified, the final space characters are removed.

Syntax

```
rtrim ( string_expression1 [ , string_expression2 ] )
```

split_part

Returns "numeric_expression" field having split "string_expression1" on "string_expression2".

Syntax

```
split_part ( string_expression1 , string_expression2 ,  
numeric_expression )
```

Postgres Data type formatting

to_char

Returns the string representation of "expression" with the format of "string_expression". "Expression" can be either a date value or a numeric value.

Syntax

```
to_char ( expression , string_expression )
```

to_date

Converts "string_expression1" to a date value as specified by the format "string_expression2".

Syntax

```
to_date ( string_expression1 , string_expression2 )
```

to_number

Converts "string_expression1" to a numeric value as specified by the format "string_expression2".

Syntax

```
to_number ( string_expression1 , string_expression2 )
```

to_timestamp

Converts "string_expression1" to a timestamp value as specified by the format "string_expression2". Alternate syntax: to_timestamp (numeric-expression)
Converts an Unix epoch clock time to a timestamp value.

Syntax

```
to_timestamp ( string_expression1 , string_expression2 )
```

Postgres Math

log

Returns the base 10 logarithm of "numeric_expression1" or logarithm to the base "numeric_expression2".

Syntax

```
log ( numeric_expression1 [ , numeric_expression2 ] )
```

ln

Returns the natural logarithm of "numeric_expression1".

Syntax

```
ln ( numeric_expression )
```

cbrt

Returns the cube root of "numeric_expression1".

Syntax

```
cbrt ( numeric_expression )
```

div

Returns the integer quotient of "numeric_expression1" divided by "numeric_expression2".

Syntax

```
div ( numeric_expression1 , numeric_expression2 )
```

pi

Returns the constant of pi.

Syntax

```
pi ( )
```

Postgres Trigonometry

acos

Returns the arccosine of "numeric_expression" in radians. The arccosine is the angle whose cosine is "numeric_expression".

Syntax

`acos (numeric_expression)`

asin

Returns the arcsine of "numeric_expression" in radians. The arcsine is the angle whose sine is "numeric_expression".

Syntax

`asin (numeric_expression)`

atan

Returns the arctangent of "numeric_expression" in radians. The arctangent is the angle whose tangent is "numeric_expression".

Syntax

`atan (numeric_expression)`

atan2

Returns the arctangent of the x and y coordinates specified by "numeric_expression1" and "numeric_expression2", respectively, in radians. The arctangent is the angle whose tangent is "numeric_expression2" / "numeric_expression1".

Syntax

`atan2 (numeric_expression1 , numeric_expression2)`

cos

Returns the cosine of "numeric_expression", where "numeric_expression" is an angle expressed in radians.

Syntax

`cos (numeric_expression)`

cot

Returns the cotangent of "numeric_expression", where "numeric_expression" is an angle expressed in radians.

Syntax

`cot (numeric_expression)`

degrees

Returns the degrees where "numeric_expression" is an angle expressed in radians.

Syntax

`degrees (numeric_expression)`

radians

Returns the radians where "numeric_expression" is an angle expressed in degrees.

Syntax

`radians (numeric_expression)`

sin

Returns the sine of "numeric_expression", where "numeric_expression" is an angle expressed in radians.

Syntax

```
sin ( numeric_expression )
```

tan

Returns the tangent of "numeric_expression", where "numeric_expression" is an angle expressed in radians.

Syntax

```
tan ( numeric_expression )
```

ascii

Returns a number representing the ASCII code value of the leftmost character of "string_expression"; for example, `ascii ('A')` is 65.

Syntax

```
ascii ( string_expression )
```

chr

Returns the character that has the ASCII code value specified by "integer_expression". "Integer_expression" should be between 0 and 255.

Syntax

```
chr ( integer_expression )
```

{current_db}**Syntax**

```
current_database()
```

{current_catalog}**Syntax**

```
{current_catalog}
```

{current_schema}**Syntax**

```
{current_schema}
```

{current_user}**Syntax**

```
{current_user}
```

{session_user}**Syntax**

```
{session_user}
```

translate

Returns "string_expression1", with each occurrence of each character in "string_expression2" replaced by its corresponding character in "string_expression3".

Syntax

```
translate ( string_expression1 , string_expression2 ,  
string_expression3 )
```

date_trunc

Returns the timestamp to the specified precision.

Syntax

```
date_trunc ( string_expression , timestamp_expression )
```

version

Returns the string value of the database version.

Syntax

```
version ( )
```

Red Brick

ceil

Returns the smallest integer greater than or equal to "numeric_expression" or "string_expression". Note that "string_expression" must represent a valid numeric value.

Syntax

```
ceil ( numeric_expression|string_expression )
```

concat

Returns a string that is the result of concatenating, or joining, "string_expression1" to "string_expression2".

Syntax

```
concat ( string_expression1 , string_expression2 )
```

Example

```
concat ( [Sales (query)].[Sales staff].[First name], [Sales (query)].  
[Sales staff].[Last name] )
```

Result

Returns the first name and last name; e.g., Bob Smith.

{current_user}

Returns the database username (authorization ID) of the current user.

Syntax

```
{ current_user }
```

date

Returns a date value. "Expression" can be either characters or a timestamp.

Syntax

```
date ( expression )
```

dateadd

Adds "interval" to "datetime_expression" and returns a result that is the same datetime data type as "datetime_expression". "Datepart" refers to the year, month, day, hour, minute, second. "Interval" must be an integer and "datetime_expression" can be a date, time, or timestamp.

Syntax

```
dateadd ( { datepart } , interval, datetime_expression )
```

datediff

Determines the difference between two datetime expressions and returns an integer result in "datepart" units. "Datepart" refers to a year, month, day, hour, minute, or second. "Datetime_expression1" and "datetime_expression2" can be dates, times, or timestamps.

Syntax

```
datediff ( { datepart } , datetime_expression1, datetime_expression2 )
```

datetimeame

Extracts "datepart" of "datetime_expression" and returns its value as a character string. "Datepart" refers to a year, month, day, hour, minute, or second. "Datetime_expression" can be a date, a time, or a timestamp.

Syntax

```
datetimeame ( { datepart } , datetime_expression )
```

dec

Converts "expression" to a decimal value with the data type decimal (precision, scale). The default value of precision is 9. The default value of scale is 0.

Syntax

```
dec ( expression , [ precision , scale ] )
```

decimal

Converts "expression" to a decimal value with the data type decimal (precision, scale). The default value of precision is 9. The default value of scale is 0.

Syntax

```
decimal ( expression , [ precision , scale ] )
```

decode

Compares and converts "expression" to another value. If "expression" matches "target", it is replaced, otherwise it is replaced by "default" or null if no default is specified. The expressions can be any data type as long as they are all the same data type.

Syntax

```
decode ( expression , target , replacement [ ,default ] )
```

float

Converts "numeric_expression" into a double-precision floating-point value.

Syntax

```
float ( numeric_expression )
```

ifnull

Tests "expression" for missing values and replaces each one with "substitute". If "expression" is null, "substitute" is returned, otherwise it returns the value of "expression". The expressions can be any data type as long as they are all the same data type.

Syntax

```
ifnull ( expression, substitute )
```

int

Converts "numeric_expression" into an integer value and returns an integer value. If "numeric_expression" is null, it returns null.

Syntax

```
int ( numeric_expression )
```

integer

Converts "numeric_expression" into an integer value and returns an integer value. If "numeric_expression" is null, it returns null.

Syntax

```
integer ( numeric_expression )
```

Example

```
integer ( 84.95 )
```

Result

85

length

Returns an integer result specifying the number of characters in "string_expression". If "string_expression" is null, it returns null.

Syntax

```
length ( string_expression )
```

lengthb

Returns an integer result specifying the number of bytes in "string_expression". If "string_expression" is null, it returns null.

Syntax

```
lengthb ( string_expression )
```

ltrim

Removes leading blanks from "string_expression". If "string_expression" is null, it returns null.

Syntax

```
ltrim ( string_expression )
```

nullif

Returns null if both "expression1" and "expression2" have the same value. If they have different values, the value of "expression1" is returned. "Expression1" and "expression2" can be any data type as long as they are the same data type.

Syntax

```
nullif ( expression1 , expression2 )
```

positionb

Returns an integer that is relative to the beginning byte position of "string_expression1" in "string_expression2". If "string_expression1" is not located, the result is 0. If "string_expression1" is of zero length, the result is 1. If "string_expression1" is null, an error message is returned. If "string_expression2" is null, the result is 0.

Syntax

```
positionb ( string_expression1, string_expression2 )
```

real

Returns a real value. If "numeric_expression" is null, it returns null.

Syntax

```
real ( numeric_expression )
```

round

Returns "numeric_expression" rounded to the nearest value "integer_expression" places to the right of the decimal point. If "integer_expression" is negative, "numeric_expression" is rounded to the nearest absolute value "integer_expression" places to the left of the decimal point. Rounding takes place before data formatting is applied.

Syntax

```
round ( numeric_expression , integer_expression )
```

Example

```
round (125, -1)
```

Result

130

rtrim

Removes trailing blanks from "string_expression". If "string_expression" is null, it returns null.

Syntax

`rtrim (string_expression)`

Example

```
rtrim ( [Sales (query)].[Sales staff].[Last name] )
```

Result

Returns last names with any spaces at the end of the name removed.

sign

Determines the sign of "numeric_expression", and returns 1 for a positive value, -1 for a negative value, and 0 for zero.

Syntax

`sign (numeric_expression)`

string

Converts "expression" to a character string. "Expression" can be either numeric or datetime.

Syntax

`string (expression [, length [, scale]])`

substr

Returns a substring of "string_expression" that begins at position "start_integer" and continues for "length_integer" characters. If "length_integer" is not specified, a substring from "start_integer" to the end of "string_expression" is returned.

Syntax

`substr (string_expression , start_integer , length_integer)`

Example

```
substr ( [Sales (query)].[Sales staff].[Position code], 3 , 5 )
```

Result

Returns characters 3 to 7 of the position codes.

substrb

Returns a substring of "string_expression" that begins at position "start_integer" and continues for "length_integer" bytes. If "length_integer" is not specified, a substring from "start_integer" to the end of "string_expression" is returned.

Syntax

`substrb (string_expression , start_integer , length_integer)`

time

Creates a time value from "expression", which can be a character string or a time-stamp data type expression.

Syntax

`time (expression)`

timestamp

Creates a time-stamp value from "timestamp_expression", which is a character string.

Syntax

`timestamp (timestamp_expression)`

timestamp

Creates a time-stamp value from "time_expression" and "date_expression". If either "time_expression" or "date_expression" is null, the resulting time-stamp expression is also null.

Syntax

`timestamp (date_expression , time_expression)`

to_char

Converts "source_date" to the character string specified by "format_string". "Source_date" can be a date, time, or timestamp data type.

Syntax

`to_char (source_date, format_string)`

SAP BW

SAP BW Trigonometry

arccos

Returns the arccosine of "numeric_expression" in radians. The arccosine is the angle whose cosine is "numeric_expression".

Syntax

`arccos (numeric_expression)`

arcsin

Returns the arcsine of "numeric_expression" in radians. The arcsine is the angle whose sine is "numeric_expression".

Syntax

`arcsin (numeric_expression)`

arctan

Returns the arctangent of "numeric_expression" in radians. The arctangent is the angle whose tangent is "numeric_expression".

Syntax

`arctan (numeric_expression)`

cos

Returns the cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

cos (numeric_expression)

sin

Returns the sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

sin (numeric_expression)

tan

Returns the tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

tan (numeric_expression)

coshyp

Returns the hyperbolic cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

coshyp (numeric_expression)

sinhyp

Returns the hyperbolic sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

sinhyp (numeric_expression)

tanhyp

Returns the hyperbolic tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

tanhyp (numeric_expression)

SAP BW Math

log10

Returns the base ten logarithm of "numeric_expression".

Syntax

log10 (numeric_expression)

Salesforce.com

Note: Supported only in dynamic query mode.

Date Functions

CALENDAR_MONTH

Returns a number representing the calendar month of "date_expression".

Syntax

CALENDAR_MONTH (date_expression)

Example

CALENDAR_MONTH ('2012-02-29')

Result

2

CALENDAR_QUARTER

Returns a number representing the calendar quarter of "date_expression".

Syntax

CALENDAR_QUARTER (date_expression)

Example

CALENDAR_QUARTER ('2012-02-29')

Result

1

CALENDAR_YEAR

Returns a number representing the calendar year of "date_expression".

Syntax

CALENDAR_YEAR (date_expression)

Example

CALENDAR_YEAR ('2012-02-29')

Result

2012

DAY_IN_MONTH

Returns a number representing the day in the month of "date_expression".

Syntax

DAY_IN_MONTH (date_expression)

Example

DAY_IN_MONTH ('2012-02-29')

Result

29

DAY_IN_WEEK

Returns a number representing the day of the week for "date_expression" 1 for Sunday, 7 for Saturday.

Syntax

DAY_IN_WEEK (date_expression)

Example

```
DAY_IN_WEEK ( '2012-02-29' )
```

Result

4 (Wednesday)

DAY_IN_YEAR

Returns a number representing the day in the year for "date_expression".

Syntax

```
DAY_IN_YEAR ( date_expression )
```

Example

```
DAY_IN_YEAR ( '2012-02-29' )
```

Result

60

DAY_ONLY

Returns a date representing the day portion of "dateTime_expression".

Syntax

```
DAY_ONLY ( dateTime_expression )
```

Example

```
DAY_ONLY ( '2012-02-29T23:00:01Z' )
```

Result

2012-02-29

FISCAL_MONTH

Returns a number representing the fiscal month of "date_expression". This differs from CALENDAR_MONTH() if your organization uses a fiscal year that does not match the Gregorian calendar. If your fiscal year starts in March, 1 for March 12 for February.

Syntax

```
FISCAL_MONTH ( date_expression )
```

Example

```
FISCAL_MONTH ( '2012-02-29' )
```

Result

12

FISCAL_QUARTER

Returns a number representing the fiscal quarter of "date_expression". This differs from CALENDAR_QUARTER() if your organization uses a fiscal year that does not match the Gregorian calendar. If your fiscal year starts in July, 1 for July 15 and 4 for June 6

Syntax

```
FISCAL_QUARTER ( date_expression )
```

Example

```
FISCAL_QUARTER ( '2012-02-29' )
```

Result

3

FISCAL_YEAR

Returns a number representing the fiscal year of "date_expression". This differs from CALENDAR_YEAR() if your organization uses a fiscal year that does not match the Gregorian calendar.

Syntax

```
FISCAL_YEAR ( date_expression )
```

Example

```
FISCAL_YEAR ( '2012-02-29' )
```

Result

2012

HOUR_IN_DAY

Returns a number representing the hour in the day for "dateTime_expression".

Syntax

```
HOUR_IN_DAY ( dateTime_expression )
```

Example

```
HOUR_IN_DAY ( '2012-02-29T23:00:01Z' )
```

Result

23

WEEK_IN_MONTH

Returns a number representing the week in the month for "date_expression". The first week is from the first through the seventh day of the month

Syntax

```
WEEK_IN_MONTH ( date_expression )
```

Example

```
WEEK_IN_MONTH ( '2012-02-29' )
```

Result

5

WEEK_IN_YEAR

Returns a number representing the calendar week of a "date_expression". The first week is from January 1 through January 7

Syntax

WEEK_IN_YEAR (date_expression)

Example

WEEK_IN_YEAR ('2012-02-29')

Result

9

convertCurrency

Converts "numeric_expression" to the user's currency when multicurrency is enabled.

Syntax

convertCurrency (numeric_expression)

convertTimezone

Converts "dateTime_expression" to the user's time zone.

Syntax

convertTimezone (dateTime_expression)

SQL Server**SQL Server Math****log**

Returns the natural logarithm of "numeric_expression".

Syntax

log (numeric_expression)

log10

Returns the base ten logarithm of "numeric_expression".

Syntax

log10 (numeric_expression)

pi

Returns the constant value of pi as a floating point value.

Syntax

pi ()

rand

Generates a random number using "integer_expression" as the seed value.

Syntax

rand (integer_expression)

SQL Server Trigonometry

acos

Returns the arccosine of "numeric_expression" in radians. The arccosine is the angle whose cosine is "numeric_expression".

Syntax

```
acos ( numeric_expression )
```

asin

Returns the arcsine of "numeric_expression" in radians. The arcsine is the angle whose sine is "numeric_expression".

Syntax

```
asin ( numeric_expression )
```

atan

Returns the arctangent of "numeric_expression" in radians. The arctangent is the angle whose tangent is "numeric_expression".

Syntax

```
atan ( numeric_expression )
```

atn2

Returns the arctangent of the x and y coordinates specified by "numeric_expression1" and "numeric_expression2", respectively, in radians. The arctangent is the angle whose tangent is "numeric_expression1".

Syntax

```
atn2 ( numeric_expression1, numeric_expression2 )
```

cos

Returns the cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cos ( numeric_expression )
```

cot

Returns the cotangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cot ( numeric_expression )
```

degrees

Returns "numeric_expression" radians converted to degrees.

Syntax

```
degrees ( numeric_expression )
```

radians

Returns the number of radians converted from "numeric_expression" degrees.

Syntax

```
radians ( numeric_expression )
```

sin

Returns the sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
sin ( numeric_expression )
```

tan

Returns the tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
tan ( numeric_expression )
```

ascii

Returns a number representing the ascii code value of the leftmost character of "string_expression".

Syntax

```
ascii ( string_expression )
```

Example

```
ascii ( 'A' )
```

Result

65

char

Returns the character that has the ASCII code value specified by "integer_expression". "Integer_expression" should be between 0 and 255.

Syntax

```
char ( integer_expression )
```

Example

```
char ( 65 )
```

Result

A

charindex

Searches "string_expression2" for the first occurrence of "string_expression1" and returns an integer. "Start_location" is the character position to start searching for "string_expression1" in "string_expression2". If "start_location" is not specified, is a negative number, or is zero, the search starts at the beginning of "string_expression2".

Syntax

```
charindex ( string_expression1 , string_expression2 [ ,  
start_location ] )
```

{current_user}

Returns the name of the current user.

Syntax

```
{ current_user }
```

datalength

Returns the length in bytes of "string_expression".

Syntax

```
datalength ( string_expression )
```

dateadd

Returns the date resulting from the addition of "integer_expression" units (indicated by "datepart" (day, month, year)) to "date_expression".

Syntax

```
dateadd ( { datepart } , integer_expression , date_expression )
```

datediff

Returns the number of "datepart" (day, month, year) units between "date_expression1" and "date_expression2".

Syntax

```
datediff ( {datepart} , date_expression1 , date_expression2 )
```

Example

```
datediff ( {yy} , 1984-01-01 , 1997-01-01 )
```

Result

13

datetimeame

Returns "datepart" from "date_expression", which can be a datetime, smalldatetime, date, or time value as an ASCII string. Note that "datepart" must be a keyword representing a datepart or its abbreviation recognized by Microsoft® SQL Server and must be enclosed in curly brackets.

Syntax

```
datetimeame ( ' { ' datepart ' } ' , date_expression )
```

Example

```
datetimeame ( {mm} , 2000-01-01 )
```

Result

January

datepart

Returns part of "date_expression" (for example, the month) as an integer. "date_expression" can be a datetime, smalldatetime, date, or time value. Note that "datepart" must be a keyword representing a datepart or its abbreviation recognized by Microsoft® SQL Server and must be enclosed in curly brackets.

Syntax

```
datepart ( ' { ' datepart ' } ' , date_expression )
```

Example

```
datepart ( {wk} , 2000-01-01 )
```

Result

1 (first week of the year)

day

Returns the day portion of "date_expression". Same as extract (day from date_expression).

Syntax

```
day ( date_expression )
```

difference

Returns an integer value representing the difference between the values returned by the data source-specific soundex function for "string_expression1" and "string_expression2". The value returned ranges from 0 to 4, with 4 indicating the best match. Note that 4 does not mean that the strings are equal.

Syntax

```
difference ( string_expression1 , string_expression2 )
```

Example 1

```
difference ([Sales target (query)].[Sales Staff].[First name],[Sales (query)].[Retailers].[Contact first name])
```

Result

0

Example 2

```
difference ([Sales target (query)].[Sales Staff].[First name],[Sales target (query)].[Sales Staff].[First name])
```

Result

4

getdate

Returns a datetime value representing the current date and time of the computer that the database software runs on.

Syntax

getdate ()

isnull

Returns the first non-null argument (or null if both arguments are null). It is recommended to use the sql standard COALESCE function instead.

Syntax

isnull (expression , expression)

Example

```
isnull ( [Sales (query)].[Sales Fact].[Sales quantity] , 0 )
```

Result

Returns the sales quantity if it's not null, otherwise returns 0.

left

Returns the leftmost "integer_expression" characters of "string_expression".

Syntax

left (string_expression , integer_expression)

Example

```
left ( [Sales (query)].[Sales staff].[Last name] , 3 )
```

Result

Returns the first three characters of each last name.

ltrim

Returns "string_expression" with leading spaces removed.

Syntax

ltrim (string_expression)

month

Returns the month portion of "date_expression". Same as extract (month from date_expression).

Syntax

month (date_expression)

patindex

Returns an integer that represents the starting position of the first occurrence of "string_expression1" in the "string_expression2". Returns 0 if "string_expression1" is not found. The % wildcard character must precede and follow "string_expression1", except when searching for first or last characters.

Syntax

patindex (string_expression1 , string_expression2)

Example

```
patindex ( '%po%', 'Report' )
```

Result

3

replace

Replaces all occurrences of "string_expression2" in "string_expression1" with "string_expression3".

Syntax

```
replace ( string_expression1 , string_expression2 ,  
         string_expression3 )
```

replicate

Returns a string consisting of "string_expression" repeated "integer_expression" times.

Syntax

```
replicate ( string_expression , integer_expression )
```

reverse

Returns "string_expression" in reverse order.

Syntax

```
reverse ( string_expression )
```

right

Returns the rightmost "integer_expression" characters of "string_expression".

Syntax

```
right ( string_expression , integer_expression )
```

round

Returns "numeric_expression" rounded to the nearest value "integer_expression" places to the right of the decimal point. Rounding takes place before data formatting is applied.

Syntax

```
round ( numeric_expression , integer_expression )
```

Example

```
round (125, -1)
```

Result

130

rtrim

Returns "string_expression" with trailing spaces removed.

Syntax

```
rtrim ( string_expression )
```

Example

```
rtrim ( [Sales (query)].[Sales staff].[Last name] )
```

Result

Returns last names with any spaces at the end of the name removed.

sign

Returns an indicator of the sign "numeric_expression": +1 if "numeric_expression" is positive, 0 if zero or -1 if negative.

Syntax

```
sign ( numeric_expression )
```

soundex

Returns a four character string representing the sound of the words in "string_expression".

Syntax

```
soundex ( string_expression )
```

space

Returns a string consisting of "integer_expression" spaces.

Syntax

```
space ( integer_expression )
```

str

Returns a string representation of "numeric_expression" where "integer_expression1" is the length of the string returned and "integer_expression2" is the number of decimal digits.

Syntax

```
str ( numeric_expression [ , integer_expression1 [ ,  
integer_expression2 ] ] )
```

stuff

Returns a string where "integer_expression2" characters have been deleted from "string_expression1" beginning at "integer_expression1", and where "string_expression2" has been inserted into "string_expression1" at its start. The first character in a string is at position 1.

Syntax

```
stuff ( string_expression1 , integer_expression1 ,  
integer_expression2 , string_expression2 )
```

year

Returns the year portion of "date_expression". Same as extract (year from date_expression).

Syntax

year (date_expression)

Sybase

Sybase Math

log

Returns the natural logarithm of "numeric_expression".

Syntax

log (numeric_expression)

log10

Returns the base ten logarithm of "numeric_expression".

Syntax

log10 (numeric_expression)

pi

Returns the constant value of pi as a floating point value.

Syntax

pi ()

sign

Returns an indicator denoting the sign of "numeric_expression": +1 if "numeric_expression" is positive, 0 if "numeric_expression" is zero, or -1 if "numeric_expression" is negative.

Syntax

sign (numeric_expression)

Sybase Trigonometry

acos

Returns the arccosine of "numeric_expression" in radians. The arccosine is the angle whose cosine is "numeric_expression".

Syntax

acos (numeric_expression)

asin

Returns the arcsine of "numeric_expression" in radians. The arcsine is the angle whose sine is "numeric_expression".

Syntax

asin (numeric_expression)

atan

Returns the arctangent of "numeric_expression" in radians. The arctangent is the angle whose tangent is "numeric_expression".

Syntax

```
atan ( numeric_expression )
```

tan

Returns the tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
tan ( numeric_expression )
```

atan2

Returns the angle, in radians, whose tangent is "numeric_expression1" / "numeric_expression2".

Syntax

```
atan2 ( numeric_expression1, numeric_expression2 )
```

cos

Returns the cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cos ( numeric_expression )
```

cot

Returns the cotangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cot ( numeric_expression )
```

degrees

Returns "numeric_expression" radians converted to degrees.

Syntax

```
degrees ( numeric_expression )
```

radians

Returns the degree equivalent of "numeric_expression". Results are of the same type as "numeric_expression". For numeric or decimal expressions, the results have an internal precision of 77 and a scale equal to that of "numeric_expression". When the money datatype is used, an internal conversion to float may cause some loss of precision.

Syntax

```
radians ( numeric_expression )
```

sin

Returns the sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
sin ( numeric_expression )
```

ascii

Returns a number representing the ascii code value of the leftmost character of "string_expression".

Syntax

```
ascii ( string_expression )
```

Example

```
ascii ( 'A' )
```

Result

65

char

Converts "integer_expression" to a character value. Char is usually used as the inverse of ascii where "integer_expression" must be between 0 and 255. If the resulting value is the first byte of a multibyte character, the character may be undefined.

Syntax

```
char ( integer_expression )
```

charindex

Returns an integer that represents the starting position of "string_expression1" within "string_expression2". If "string_expression1" is not found, zero is returned. If "string_expression1" contains wildcard characters, charindex treats them as literals.

Syntax

```
charindex ( string_expression1 , string_expression2 )
```

datalength

Returns the length in bytes of "string_expression".

Syntax

```
datalength ( string_expression )
```

dateadd

Returns the date resulting from adding "integer_expression" units indicated by datepart (day, month, year) to "date_expression". Note that "datepart" must be enclosed in curly brackets.

Syntax

```
dateadd ( ' { ' datepart ' } ' , integer_expression ,  
date_expression )
```

Example

```
dateadd ( {dd} , 16 , 1997-06-16 )
```

Result

Jul 2, 1997

datediff

Returns the number of units indicated by "datepart" (day, month, year) between "date_expression1" and "date_expression2". Note that "datepart" must be enclosed in curly brackets.

Syntax

```
datediff ( ' { ' datepart ' } ' , date_expression1 ,  
          date_expression2 )
```

Example

```
datediff ( {yy} , 1984-01-01 , 1997-01-01 )
```

Result

13

datetimeame

Returns "datepart" of "date_expression" as an ASCII string. "Date_expression" can be a datetime, smalldatetime, date, or time value. Note that "datepart" must be enclosed in curly brackets.

Syntax

```
datetimeame ( ' { ' datepart ' } ' , date_expression )
```

Example

```
datetimeame ( {mm} , 1999-05-01 )
```

Result

May

datepart

Returns "datepart" of "date_expression" as an integer. "Date_expression" can be a datetime, smalldatetime, date, or time value. Note that the datepart argument must be enclosed in curly brackets.

Syntax

```
datepart ( ' { ' datepart ' } ' , date_expression )
```

Example

```
datepart ( {mm} , 1999-05-01 )
```

Result

5

day

Returns the day of the month (1-31) from "date_expression".

Syntax

```
day ( date_expression )
```

difference

Returns an integer value representing the difference between the values returned by the data source-specific soundex function for "string_expression1" and "string_expression2". The value that is returned ranges from 0 to 4, with 4 indicating the best match. Note that 4 does not mean that the strings are equal.

Syntax

```
difference ( string_expression1 , string_expression2 )
```

Example 1

```
difference ([Sales target (query)].[Sales staff].[First name],[Sales (query)].[Retailers].[Contact first name])
```

Result

0

Example 2

```
difference ([Sales target (query)].[Sales staff].[First name],[Sales target (query)].[Sales staff].[First name])
```

Result

4

getdate

Returns current system date and time.

Syntax

```
getdate ()
```

left

Returns the leftmost "integer_expression" characters of "string_expression".

Syntax

```
left ( string_expression , integer_expression )
```

Example

```
left ( [Sales (query)].[Sales staff].[Last name] , 3 )
```

Result

Returns the first three characters of each last name.

ltrim

Returns "string_expression" with any leading spaces removed.

Syntax

```
ltrim ( string_expression )
```

month

Returns the month number (1-12) from "date_expression".

Syntax

```
month ( date_expression )
```

patindex

Returns an integer representing the starting position of the first occurrence of "string_expression1" in "string_expression2" or returns 0 if "string_expression1" is not found. By default, patindex returns the offset in characters. The offset can be returned in bytes by setting the return type to bytes. The % wildcard character must precede and follow the pattern in "string_expression1", except when searching for first or last characters.

Syntax

```
patindex ( string_expression1 , string_expression2 [ using  
{bytes|chars|characters} ] )
```

rand

Returns a random float value between 0 and 1, using the optional "integer_expression" as a seed value.

Syntax

```
rand ( integer_expression )
```

replicate

Returns a string consisting of "string_expression" repeated "integer_expression" times.

Syntax

```
replicate ( string_expression , integer_expression )
```

reverse

Returns the reverse of "string_expression".

Syntax

```
reverse ( string_expression )
```

right

Returns the rightmost "integer_expression" characters of "string_expression".

Syntax

```
right ( string_expression , integer_expression )
```

round

Returns "numeric_expression" rounded to the nearest value "integer_expression" places to the right of the decimal point. Rounding takes place before data formatting is applied.

Syntax

```
round ( numeric_expression, integer_expression )
```

Example

```
round (125, -1)
```

Result

130

rtrim

Returns "string_expression" with trailing spaces removed.

Syntax

```
rtrim ( string_expression )
```

Example

```
rtrim ( [Sales (query)].[Sales staff].[Last name] )
```

Result

Returns last names with any spaces at the end of the name removed.

soundex

Returns a four-character soundex code for character strings that are composed of a contiguous sequence of valid single- or double-byte Roman letter.

Syntax

```
soundex ( string_expression )
```

space

Returns a string with "integer_expression" single-byte spacing.

Syntax

```
space ( integer_expression )
```

str

Returns a string representation of "numeric_expression". "Integer_expression1" is the length of the returned string and has a default setting of 10. "Integer_expression2" is the number of decimal digits and has a default setting of 0. Both are optional values.

Syntax

```
str ( numeric_expression [ , integer_expression1 [ ,  
integer_expression2 ] ] )
```

stuff

Deletes "integer_expression2" characters from "string_expression1" starting at "integer_expression1", and inserts "string_expression2" into "string_expression1" at that position. To delete characters without inserting other characters, "string_expression2" should be null and not " ", which indicates a single space.

Syntax

```
stuff ( string_expression1 , integer_expression1 ,  
integer_expression2 , string_expression2 )
```


substring

Returns the substring of "string_expression" that starts at position "integer_expression1". "Integer_expression2" specifies the number of characters in the substring.

Syntax

```
substring ( string_expression , integer_expression1 ,  
           integer_expression2 )
```

Example

```
substring ( [Sales (query)].[Sales staff].[Position code], 3 , 5 )
```

Result

Returns characters 3 to 7 of the position codes.

to_unichar

Returns a unichar expression with the value "integer_expression". If "integer_expression" is in the range 0xD800..0xDFFF, the operation is aborted. If the "integer_expression" is in the range 0..0xFFFF, a single Unicode value is returned. If "integer_expression" is in the range 0x10000..0x10FFFF, a surrogate pair is returned.

Syntax

```
to_unichar ( integer_expression )
```

uhighsurr

Returns 1 if the Unicode value at "integer_expression" is the high half of a surrogate pair (which should appear first in the pair). Otherwise, it returns 0. This function allows you to write explicit code for surrogate handling. Particularly, if a substring starts on a Unicode character where uhighsurr () is true, extract a substring of at least 2 Unicode values, as substr() does not extract just 1. Substr () does not extract half of a surrogate pair.

Syntax

```
uhighsurr ( string_expression , integer_expression )
```

ulowsurr

Returns 1 if the Unicode value at "integer_expression" is the low half of a surrogate pair (which should appear second in the pair). Otherwise, it returns 0. This function allows you to explicitly code around the adjustments performed by substr (), stuff (), and right (). Particularly, if a substring ends on a Unicode value where ulowsurr () is true, extract a substring of 1 less characters (or 1 more), since substr () does not extract a string that contains an unmatched surrogate pair.

Syntax

```
ulowsurr ( string_expression , integer_expression )
```

uscalar

Returns the Unicode scalar value for the first Unicode character in "string_expression". If the first character is not the high-order half of a surrogate pair, then the value is in the range 0..0xFFFF. If the first character is the high-order half of a surrogate pair, a second value must be a low-order half, and the return

value is in the range 0x10000..0x10FFFF. If this function is called on a Unicode character expression containing an unmatched surrogate half, the operation is aborted.

Syntax

```
uscalar ( string_expression )
```

year

Returns the year from date_expression.

Syntax

```
year ( date_expression )
```

Teradata

Teradata Trigonometry

acos

Returns the arccosine of "numeric_expression" in radians. The arccosine is the angle whose cosine is "numeric_expression". "Numeric_expression" must be between -1 and 1, inclusive.

Syntax

```
acos ( numeric_expression )
```

acosh

Returns the inverse hyperbolic cosine of "numeric_expression" where "numeric_expression" can be any real number equal to or greater than 1.

Syntax

```
acosh ( numeric_expression )
```

asin

Returns the arcsine of "numeric_expression" in radians. The arcsine is the angle whose sine is "numeric_expression". "Numeric_expression" must be between -1 and 1, inclusive.

Syntax

```
asin ( numeric_expression )
```

asinh

Returns the inverse hyperbolic sine of "numeric_expression" where "numeric_expression" can be any real number.

Syntax

```
asinh ( numeric_expression )
```

atan

Returns the arctangent of "numeric_expression" in radians where the arctangent is the angle whose tangent is "numeric_expression".

Syntax

```
atan ( numeric_expression )
```

atan2

Returns the arctangent of the x and y coordinates specified by "numeric_expression1" and "numeric_expression2", respectively, in radians. The returned angle will be between - and π radians, excluding π .

Syntax

```
atan2 ( numeric_expression1, numeric_expression2 )
```

atanh

Returns the inverse hyperbolic tangent of "numeric_expression" where "numeric_expression" can be any real number between 1 and -1, excluding 1 and -1.

Syntax

```
atanh ( numeric_expression )
```

cos

Returns the cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cos ( numeric_expression )
```

cosh

Returns the hyperbolic cosine of "numeric_expression" where "numeric_expression" can be any real number.

Syntax

```
cosh ( numeric_expression )
```

sin

Returns the sine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
sin ( numeric_expression )
```

sinh

Returns the hyperbolic sine of "numeric_expression" where "numeric_expression" can be any real number.

Syntax

```
sinh ( numeric_expression )
```

tan

Returns the tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
tan ( numeric_expression )
```

tanh

Returns the hyperbolic tangent of "numeric_expression" where "numeric_expression" can be any real number.

Syntax

tanh (numeric_expression)

account

Returns the account string for the current user.

Syntax

{account}

add_months

Returns the date or the datetime resulting from adding "integer_expression" months to "date_expression" or "datetime_expression".

Syntax

add_months (date_expression|datetime_expression ,
integer_expression)

bytes

Returns the number of bytes contained in "byte_expression". "Byte_expression" is restricted to BYTE or VARBYTE.

Syntax

bytes (byte_expression)

case_n

Evaluates "condition_expression_list" and returns the position of the first true condition, provided that no prior condition in the list evaluates to unknown. The keywords must be enclosed in curly brackets. No case is an optional condition that evaluates to true if every expression in the list evaluates to false. No case or unknown is an optional condition that evaluates to true if every expression in the list evaluates to false, or if an expression evaluates to unknown and all prior conditions in the list evaluate to false. Unknown is an optional condition that evaluates to true if an expression evaluates to unknown and all prior conditions in the list evaluate to false.

Syntax

case_n (condition_expression_list [, NO CASE|UNKNOWN|NO CASE OR
UNKNOWN [, UNKNOWN]])

char2hexint

Returns the hexadecimal representation for "string_expression".

Syntax

char2hexint (string_expression)

characters

Returns an integer value representing the number of logical characters or bytes contained in "string_expression".

Syntax

characters (string_expression)

database

Returns the name of the default database for the current user.

Syntax

```
{database}
```

date

Returns the current date.

Syntax

```
{date}
```

format

Returns the declared format for "expression" as a variable character string of up to 30 characters.

Syntax

```
format ( expression )
```

index

Returns the starting position of "string_expression2" in "string_expression1".

Syntax

```
index ( string_expression1 , string_expression2 )
```

log

Computes the base 10 logarithm of "numeric_expression". "Numeric_expression" must be a non-zero, positive, numeric expression.

Syntax

```
log ( numeric_expression )
```

nullif

Returns null if "scalar_expression1" and "scalar_expression2" are equal. Otherwise, it returns "scalar_expression1". "Scalar_expression1" and "scalar_expression2" can be any data type.

Syntax

```
nullif ( scalar_expression1 , scalar_expression2 )
```

nullifzero

If "numeric_expression" is zero, converts it to null to avoid division by zero.

Syntax

```
nullifzero ( numeric_expression )
```

profile

Returns the current profile for the session or null if none.

Syntax

```
{profile}
```

random

Returns a random integer number for each row of the results table. "Lower_bound" and "upper_bound" are integer constants. The limits for "lower_bound" and "upper_bound" range from -2147483648 to 2147483647 inclusive. "Upper_bound" must be greater than or equal to "lower_bound".

Syntax

```
random ( lower_bound , upper_bound )
```

role

Returns the current role for the session or null if none.

Syntax

```
{role}
```

session

Returns the number of the session for the current user.

Syntax

```
{session}
```

soundex

Returns a character string that represents the Soundex code for "string_expression".

Syntax

```
soundex ( string_expression )
```

substr

Returns the substring of "string_expression" that starts at position "integer_expression1" for "integer_expression2" characters. The first character in "string_expression" is at position 1. If "integer_expression2" is omitted, returns the substring of "string_expression" that starts at position "integer_expression1" and ends at the end of "string_expression".

Syntax

```
substr ( string_expression , integer_expression1 [ ,  
integer_expression2 ] )
```

Example

```
substr ( [Sales (query)].[Sales staff].[Position code], 3 , 5 )
```

Result

Returns characters 3 to 7 of the position codes.

time

Returns the current time based on a 24-hour day. According to Teradata documentation, the system function TIME is deprecated. Use CURRENT_TIME function instead. Please note that in Compatible Mode TIME returns time data type, while in Dynamic Query Mode time returns a value of type FLOAT.

Syntax

{time}

type

Returns the data type defined for "expression".

Syntax

type (expression)

user

Returns the user name of the current user.

Syntax

{user}

vargraphic

Returns a character string that represents the vargraphic code for "string_expression".

Syntax

vargraphic (string_expression)

zeroifnull

Converts data from null to 0 to avoid errors created by a null value. If "numeric_expression" is not null, returns the value of "numeric_expression". If "numeric_expression" is a character string, it is converted to a numeric value of float data type. If "numeric_expression" is null or zero, it returns zero.

Syntax

zeroifnull (numeric_expression)

Vectorwise**Vectorwise String****lpad**

Returns "string_exp1" padded to length "integer_exp" with occurrences of "string_exp2". If "string_exp1" is longer than "integer_exp", the appropriate portion of "string_exp1" is returned.

Syntax

lpad (string_exp1, integer_exp [, string_exp2])

ltrim

Returns "string_exp1", with leading blank characters removed.

Syntax

ltrim (string_exp1)

rtrim

Returns "string_exp1", with trailing blank characters removed.

Syntax

```
rtrim ( string_exp1 )
```

shift

Returns "string_exp1" shifted by numeric_exp character. If "numeric_exp" is greater than zero shift to the right else shift to the left.

Syntax

```
shift ( string_exp1, numeric_exp )
```

soundex

Returns a four character code for the "string_exp1".

Syntax

```
soundex ( string_exp1 )
```

squeeze

Returns "string_exp1" with multiple whitespace characters collapsed into a single whitespace character.

Syntax

```
squeeze ( string_exp1 )
```

Vectorwise Math

log

Returns the base 10 logarithm of "numeric_exp1".

Syntax

```
log ( numeric_exp1 )
```

ln

Returns the natural logarithm of "numeric_exp1".

Syntax

```
ln ( numeric_exp )
```

pi

Returns the constant of pi.

Syntax

```
pi ( )
```

Vectorwise Trigonometry

acos

Returns the arccosine of "numeric_exp" in radians. The arccosine is the angle whose cosine is "numeric_exp".

Syntax

```
acos ( numeric_exp )
```

asin

Returns the arcsine of "numeric_exp" in radians. The arcsine is the angle whose sine is "numeric_exp".

Syntax

```
asin ( numeric_exp )
```

atan

Returns the arctangent of "numeric_exp" in radians. The arctangent is the angle whose tangent is "numeric_exp".

Syntax

```
atan ( numeric_exp )
```

atan2

Returns the arctangent of the x and y coordinates specified by "numeric_exp1" and "numeric_exp2", respectively, in radians. The arctangent is the angle whose tangent is "numeric_exp2" / "numeric_exp1".

Syntax

```
atan2 ( numeric_exp1 ,numeric_exp2 )
```

cos

Returns the cosine of "numeric_exp" where "numeric_exp" is an angle expressed in radians.

Syntax

```
cos ( numeric_exp )
```

sin

Returns the sine of "numeric_exp" where "numeric_exp" is an angle expressed in radians.

Syntax

```
sin ( numeric_exp )
```

tan

Returns the tangent of "numeric_exp" where "numeric_exp" is an angle expressed in radians.

Syntax

```
tan ( numeric_exp )
```

{initial_user}

Returns the initial username.

Syntax

```
{ initial_user }
```

{session_user}

Returns the session username.

Syntax

```
{ session_user }
```

numeric_trunc

Returns the numeric_exp1 truncated at the decimal place or numeric_exp2 digits to the left or right of the decimal place.

Syntax

`trunc (numeric_exp1 , numeric_exp2)`

Vertica

Vertica String

overlay

Returns the "string_expression1", replacing "string_expression2" from character position numeric_expression.

Syntax

`overlay (string_expression1 , string_expression2 ,
numeric_expression1 [, numeric_expression2])`

btrim

Returns string_expression1 after removing the longest string of characters in string_expression2.

Syntax

`btrim (string_expression1 [, string_expression2])`

initcap

Returns "string_expression", with the first letter of each word in uppercase and all other letters in lowercase. Words are delimited by white space or characters that are not alphanumeric.

Syntax

`initcap (string_expression)`

lpad

Returns "string_expression1" padded to length "integer_expression" with occurrences of "string_expression2". If "string_expression1" is longer than "integer_expression", the appropriate portion of "string_expression1" is returned.

Syntax

`lpad (string_expression1 , integer_expression [, string_expression2
])`

ltrim

Returns "string_expression1", with leading characters removed up to the first character not in "string_expression2"; for example, `ltrim ('yxXxyAB' , 'xy')` returns XxyAB.

Syntax

`ltrim (string_expression1 [, string_expression2])`

to_hex

Returns the hexadecimal string representation of "numeric_exp1".

Syntax

`to_hex (numeric_expression1)`

repeat

Returns the "string_expression" repeated "numeric_expression1" times.

Syntax

```
repeat ( string_expression , numeric_expression1 )
```

replace

Returns "string_expression" having replaced "string_expression2" with "string_expression3".

Syntax

```
replace ( string_expression , string_expression2 , string_expression3 )
```

rpad

Returns "string_expression1" right-padded to length "integer_expression" with occurrences of "string_expression2". If "string_expression1" is longer than "integer_expression", the appropriate portion of "string_expression1" is returned. If "string_expression2" is not specified, then spaces are used.

Syntax

```
rpad ( string_expression1 , integer_expression [ , string_expression2 ] )
```

rtrim

Returns "string_expression1", with final characters removed after the last character not in "string_expression2"; for example, rtrim ('ABxXxyx' , 'xy') returns ABxX. If "string_expression2" is not specified, the final space characters are removed.

Syntax

```
rtrim ( string_expression1 [ , string_expression2 ] )
```

Vertica Data type formatting

to_char

Returns the string representation of "expression" with the format of "string_expression". "Expression" can be either a date value or a numeric value.

Syntax

```
to_char ( expression , string_expression )
```

to_date

Converts "string_expression1" to a date value as specified by the format "string_expression2".

Syntax

```
to_date ( string_expression1 , string_expression2 )
```

to_number

Converts "string_expression1" to a numeric value as specified by the format "string_expression2".

Syntax

```
to_number ( string_expression1 , string_expression2 )
```

to_timestamp

Converts "string_expression1" to a timestamp value as specified by the format "string_expression2".

Syntax

`to_timestamp (string_expression1, string_expression2)`

Vertica Math

log

Returns the base 10 logarithm of "numeric_expression1" or logarithm to the base "numeric_expression2".

Syntax

`log (numeric_expression1 [, numeric_expression2])`

ln

Returns the natural logarithm of "numeric_expression1".

Syntax

`ln (numeric_expression)`

cbrt

Returns the cube root of "numeric_expression1".

Syntax

`cbrt (numeric_expression)`

pi

Returns the constant of pi.

Syntax

`pi ()`

Vertica Trigonometry

acos

Returns the arccosine of "numeric_expression" in radians. The arccosine is the angle whose cosine is "numeric_expression".

Syntax

`acos (numeric_expression)`

asin

Returns the arcsine of "numeric_expression" in radians. The arcsine is the angle whose sine is "numeric_expression".

Syntax

`asin (numeric_expression)`

atan

Returns the arctangent of "numeric_expression" in radians. The arctangent is the angle whose tangent is "numeric_expression".

Syntax

`atan (numeric_expression)`

atan2

Returns the arctangent of the x and y coordinates specified by "numeric_expression1" and "numeric_expression2", respectively, in radians. The arctangent is the angle whose tangent is "numeric_expression2" / "numeric_expression1".

Syntax

```
atan2 ( numeric_expression1 , numeric_expression2 )
```

cos

Returns the cosine of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cos ( numeric_expression )
```

cot

Returns the cotangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
cot ( numeric_expression )
```

degrees

Returns the degrees where "numeric_expression" is an angle expressed in radians.

Syntax

```
degrees ( numeric_expression )
```

radians

Returns the radians where "numeric_expression" is an angle expressed in degrees.

Syntax

```
radians ( numeric_expression )
```

sin

Returns the sine of "numeric_exp" where "numeric_expression" is an angle expressed in radians.

Syntax

```
sin ( numeric_expression )
```

tan

Returns the tangent of "numeric_expression" where "numeric_expression" is an angle expressed in radians.

Syntax

```
tan ( numeric_expression )
```

ascii

Returns a number representing the ASCII code value of the leftmost character of "string_expression"; for example, `ascii ('A')` is 65.

Syntax

`ascii (string_expression)`

chr

Returns the character that has the ASCII code value specified by "integer_expression". "Integer_expression" should be between 0 and 255.

Syntax

`chr (integer_expression)`

current_database

Returns the name of the current database.

Syntax

`current_database ()`

current_schema

Returns the name of the current schema

Syntax

`current_schema ()`

{current_user}**Syntax**

`{current_user}`

{session_user}**Syntax**

`{session_user}`

translate

Returns "string_expression1", with each occurrence of each character in "string_expression2" replaced by its corresponding character in "string_expression3".

Syntax

`translate (string_expression1 , string_expression2 , string_expression3)`

date_trunc

Returns the timestamp to the specified precision.

Syntax

`date_trunc (string_expression , timestamp_expression)`

version

Returns the string value of the database version.

Syntax

`version ()`

Macro Functions

This list contains functions that can be used within a macro. A macro may contain one or more macro functions. A macro is delimited by a number sign (#) at the beginning and at the end. Everything between the number signs is treated as a macro expression and is executed at run time. For macro functions that accept expressions of datatype timestamp with time zone as arguments, the accepted format is 'yyyy-mm-dd hh:mm:ss[.ff]+hh:mm' where fractional seconds are optional and can be represented by 1 to 9 digits. In lieu of a space separating the date portion to the time portion, the character 'T' is also accepted. Also, in lieu of the time zone '+hh:mm', the character 'Z' is accepted and will be processed internally as '+00:00'. The macro functions that return expressions of datatype timestamp with time zone return 9 digits by default for their fractional seconds. The macro function timestampMask () can be used to trim the output if required.

+

Concatenates two strings.

Syntax

```
value1 + value2
```

Example

```
# '{ ' + $runLocale + ' }' #
```

Result

```
{en-us}
```

_add_seconds

Returns the timestamp with time zone (as a string) that results from adding "integer_expression" number of seconds to "string_expression", where "string_expression" represents a timestamp with time zone.

Syntax

```
_add_seconds ( string_expression , integer_expression )
```

Example 1

```
# _add_seconds ( '2005-11-01 12:00:00.000-05:00' , -1 ) #
```

Result

```
2005-11-01 11:59:59.000-05:00
```

Example 2

```
# _add_seconds ( $current_timestamp , 1 ) #
```

Result

```
2005-11-01 12:00:01.000000000-05:00
```

Example 3

```
# timestampMask ( _add_seconds ( $current_timestamp , 1 ) ,  
'hh:mm:ss' ) #
```

Result

12:00:01

_add_minutes

Returns the timestamp with time zone (as a string) that results from adding "integer_expression" number of minutes to "string_expression", where "string_expression" represents a timestamp with time zone.

Syntax

```
_add_minutes ( string_expression , integer_expression )
```

Example 1

```
# _add_minutes ( '2005-11-01 12:00:00.000-05:00' , -1 ) #
```

Result

2005-11-01 11:59:00.000-05:00

Example 2

```
# _add_minutes ( $current_timestamp , 1 ) #
```

Result

2005-11-01 12:01:00.000000000-05:00

Example 3

```
# timestampMask ( _add_minutes ( $current_timestamp , 1 ) ,  
  'hh:mm:ss' ) #
```

Result

12:01:00

_add_hours

Returns the timestamp with time zone (as a string) that results from adding "integer_expression" number of hours to "string_expression", where "string_expression" represents a timestamp with time zone.

Syntax

```
_add_hours ( string_expression , integer_expression )
```

Example 1

```
# _add_hours ( '2005-11-01 12:00:00.000-05:00' , -1 ) #
```

Result

2005-11-01 13:00:00.000-05:00

Example 2

```
# _add_hours ( $current_timestamp , 1 ) #
```

Result

2005-11-01 13:00:00.000000000-05:00

Example 3

```
# timestampMask ( _add_hours ( $current_timestamp , 1 ) ,  
  'hh:mm:ss' ) #
```

Result

13:00:00

_add_days

Returns the timestamp with time zone (as a string) that results from adding "integer_expression" number of days to "string_expression", where "string_expression" represents a timestamp with time zone.

Syntax

```
_add_days ( string_expression , integer_expression )
```

Example 1

```
# _add_days ( '2005-11-01 12:00:00.000-05:00' , -1 ) #
```

Result

2005-10-31 12:00:00.000000000-05:00

Example 2

```
# _add_days ( $current_timestamp , 1 ) #
```

Result

2005-11-02 12:00:00.000000000-05:00

Example 3

```
# timestampMask ( _add_days ( $current_timestamp , 1 ) ,  
  'yyyy-mm-dd' ) #
```

Result

2005-11-02

_add_months

Returns the timestamp with time zone (as a string) that results from adding "integer_expression" number of months to "string_expression", where "string_expression" represents a timestamp with time zone.

Syntax

```
_add_months ( string_expression , integer_expression )
```

Example 1

```
# _add_months ( '2005-11-01 12:00:00.000-05:00' , -1 ) #
```

Result

2005-10-01 12:00:00.000000000-05:00

Example 2

```
# _add_months ( $current_timestamp , 1 ) #
```

Result

```
2005-12-01 12:00:00.000000000-05:00
```

Example 3

```
# timestampMask ( _add_months ( $current_timestamp , 1 ) ,  
'yyyy-mm-dd' ) #
```

Result

```
2005-12-01
```

_add_years

Returns the timestamp with time zone (as a string) that results from adding "integer_expression" number of years to "string_expression", where "string_expression" represents a timestamp with time zone.

Syntax

```
_add_years ( string_expression , integer_expression )
```

Example 1

```
# _add_years ( '2005-11-01 12:00:00.000-05:00' , -1 ) #
```

Result

```
2004-11-01 12:00:00.000000000-05:00
```

Example 2

```
# _add_years ( $current_timestamp , 1 ) #
```

Result

```
2006-11-01 12:00:00.000000000-05:00
```

Example 3

```
# timestampMask ( _add_years ( $current_timestamp , 1 ) ,  
'yyyy-mm-dd' ) #
```

Result

```
2006-11-01
```

array

Constructs an array out of the list of parameters.

Syntax

```
array ( string_expression|array_expression { ,  
string_expression|array_expression } )
```

Example

```
# csv ( array ( 'a1' , array ( 'x1' , 'x2' ) , 'a2' ) ) #
```

Result

```
'a1' , 'x1' , 'x2' , 'a2'
```

CSV

Constructs a string from the elements of the array where the values are separated by commas. Optionally, the separator and quote strings can be specified. The default separator is a comma (,) and the default quote character is a single quote (').

Syntax

```
csv ( array_expression [ , separator_string [ , quote_string ] ] )
```

Example

```
# csv ( array ( 'a1' , 'a2' ) ) #
```

Result

```
'a1', 'a2'
```

dq

Surrounds "string_expression" with double quotes.

Syntax

```
dq ( string_expression )
```

Example

```
# dq ( 'zero' ) #
```

Result

```
"zero"
```

getConfigurationEntry

Get an entry from the IBM® Cognos® configuration file. The force_decode_flag is optional and must be one of: 'true', '1', 1, 'false', '0', 0. The default is 'true'. When true, the value of the configuration entry will be decrypted into plain text if it is encrypted.

Syntax

```
getConfigurationEntry ( entry_string , force_decode_flag )
```

Example

```
# getConfigurationEntry ( 'serverLocale' ) #
```

Result

```
en
```

grep

Searches for and returns elements of an array that match the pattern specified in "pattern_string".

Syntax

```
grep ( pattern_string , array_expression )
```

Example

```
# csv ( grep ( 's' , array ( 'as', 'an', 'arts' ) ) ) #
```

Result

```
'as', 'arts'
```

_first_of_month

Returns a timestamp with time zone (as a string) by converting the day value in "string_expression" to 1, where "string_expression" is a timestamp with time zone.

Syntax

```
_first_of_month ( string_expression )
```

Example 1

```
# _first_of_month ( '2005-11-11 12:00:00.000-05:00' ) #
```

Result

```
2005-11-01 12:00:00.000000000-05:00
```

Example 2

```
# timestampMask ( _first_of_month ( '2005-11-11 12:00:00.000-05:00' ) , 'yyyymmdd' ) #
```

Result

```
20051101
```

_last_of_month

Returns a timestamp with time zone (as a string) that is the last day of the month represented by "string_expression", where "string_expression" is a timestamp with time zone.

Syntax

```
_last_of_month ( string_expression )
```

Example 1

```
# _last_of_month ( '2005-11-11 12:00:00.000-05:00' ) #
```

Result

```
2005-11-30 12:00:00.000000000-05:00
```

Example 2

```
# timestampMask ( _last_of_month ( '2005-11-11 12:00:00.000-05:00' ) ,  
  'yyyy-mm-dd' ) #
```

Result

2005-11-30

join

Joins the elements of an array using "separator_string".

Syntax

```
join ( separator_string , array_expression )
```

Example

```
# sq ( join ( ' | | ' , array ( 'as', 'an', 'arts' ) ) ) #
```

Result

'as | | an | | arts'

lstrip

Strips the leading characters from the first argument. The optional second argument defines the set of characters to strip. By default, this function strips white space (ie. space, tab, carriage return and line feed).

Note: Supported only in dynamic query mode.

Syntax

```
lstrip ( string_expression [ , set_of_characters ] )
```

Example 1

```
# sq( lstrip ( '   abc ' ) ) #
```

Result

'abc '

Example 2

```
' ) #
```

Result

53.2100

prompt

Prompts the user for a single value or member. Only "prompt_name" is required. The datatype defaults to 'string' when it is not specified. The prompt is optional when "defaultText" is specified. "Text", when specified, will precede the value. "QueryItem" can be specified to take advantage of the prompt information properties of "queryItem". "Trailing_text", when specified, will be appended to the value. When the data type is 'memberuniquename', a single select member prompt is created. It is good practice to provide a default value, as 3rd argument. The

default value must be a valid member unique name; it can also be an alias that references a member unique name as done in Report Studio.

Syntax

```
prompt ( prompt_name , datatype , defaultText , text , queryItem ,  
        trailing_text )
```

Example 1

```
select . . . where COUNTRY_MULTILINGUAL.COUNTRY_CODE > #prompt ( 'Starting CountryCode' , 'integer' , '10' ) #
```

Result

```
select . . . where COUNTRY_MULTILINGUAL.COUNTRY_CODE > 10
```

Example 2

```
[gosales].[COUNTRY].[COUNTRY] = # prompt ( 'countryPrompt' ,  
      'string' , '''Canada''' ) #
```

Result

```
[gosales].[COUNTRY].[COUNTRY] = 'Canada'
```

Example 3

```
set ( #prompt ('myProduct', 'memberuniqueName', '[Camping  
Equipment]', '', '[Sales].[Product].[Product].[Product line]')#)
```

Result

```
set([Sales].[Product].[Product].[Product line]->[all].[1])
```

Notes

- The "defaultText" parameter must be specified such that it is literally valid in the context of the macro since no formatting takes place on this value. The default string "'Canada'" in Example 2 is specified as a string using single quotes, in which the embedded single quotes are doubled up, thus 3 quotes. This results in the string being properly displayed within single quotes in the expression. As a general rule for the string datatype, "defaultText" should always be specified like this, except in the context of a stored procedure parameter. For "defaultText" of types 'date' or 'datetime', a special format should be used in the context of SQL. Examples of these formats are 'DATE "2001-12-25"' and 'DATETIME "2001-12-25 12:00:00"'. In all other contexts, use the date/datetime without the keyword and escaped single quotes (e.g., '2001-12-25').

promptmany

Prompts the user for one or more values or members. Only "prompt_name" is required. The datatype defaults to 'string' when it is not specified. The prompt is optional when "defaultText" is specified. "Text", when specified, will precede the list of values. "QueryItem" can be specified to take advantage of the prompt information properties of "queryItem". "Trailing_text", when specified, will be appended to the list of values. When the data type is 'memberuniqueName', a multi select member prompt is created. It is good practice to provide a default value, as 3rd argument. The default value must be a valid member unique name; it can also be an alias that references a member unique name as done in Report Studio.

Syntax

```
promptmany ( prompt_name , datatype , defaultText , text , queryItem ,  
trailing_text )
```

Example 1

```
select . . . where COUNTRY_MULTILINGUAL.COUNTRY in ( # promptmany ( 'CountryName' ) # )
```

Result

```
select . . . where COUNTRY_MULTILINGUAL.COUNTRY_CODE in ( 'Canada' , 'The Netherlands' , 'Russia' )
```

Example 2

```
select . . . from gosales.gosales.dbo.COUNTRY_MULTILINGUAL  
COUNTRY_MULTILINGUAL , gosales.gosales.dbo.COUNTRY XX where  
COUNTRY_MULTILINGUAL.COUNTRY_CODE = XX.COUNTRY_CODE # promptmany ( 'Selected CountryCodes' , 'integer' , ' ' , 'and  
COUNTRY_MULTILINGUAL.COUNTRY_CODE in ( ' , ' , ' ) ' ) #
```

Result

```
select . . . from gosales.gosales.dbo.COUNTRY_MULTILINGUAL  
COUNTRY_MULTILINGUAL , gosales.gosales.dbo.COUNTRY XX where  
COUNTRY_MULTILINGUAL.COUNTRY_CODE = XX.COUNTRY_CODE and  
COUNTRY_MULTILINGUAL.COUNTRY_CODE in ( 'Canada' , 'The  
Netherlands' , 'Russia' )
```

Example 3

```
set ( #promptmany ('myProduct', 'memberuniquename', '[Camping  
Equipment]', ' ', '[Sales].[Product].[Product].[Product line]')#)
```

Result

```
set([Sales].[Product].[Product].[Product line]->[all].[1];  
[Sales].[Product].[Product].[Product line]->[all].[2])
```

rstrip

Strips the trailing characters from the first argument. The optional second argument defines the set of characters to strip. By default, this function strips white space (ie. space, tab, carriage return and line feed).

Note: Supported only in dynamic query mode.

Syntax

```
rstrip ( string_expression [ , set_of_characters ] )
```

Example 1

```
# sq( rstrip ( ' abc ' ) ) #
```

Result

```
' abc'
```

Example 2

```
' ) #
```

Result

```
0053.21
```

sb

Surrounds "string_expression" with square brackets.

Syntax

```
sb ( string_expression )
```

Example

```
# sb ( 'abc' ) #
```

Result

```
[abc]
```

sq

Surrounds "string_expression" with single quotes.

Syntax

```
sq ( string_expression )
```

Example

```
# sq ( 'zero' ) #
```

Result

```
'zero'
```

sort

Sorts the elements of the array in alphabetical order. Duplicates are retained.

Syntax

```
sort ( array_expression )
```

Example

```
# csv ( sort ( array ( 's3', 'a', 'x' ) ) ) #
```

Result

```
'a', 's3', 'x'
```

split

Splits a string or string elements of the array into separate elements.

Syntax

```
split ( pattern_string, string_expression|array_expression )
```


Example 1

```
# csv ( split ( '::', 'ab=c::de=f::gh=i' ) ) #
```

Result

```
'ab=c', 'de=f', 'gh=i'
```

Example 2

```
# csv ( split ( '=', split ( '::', 'ab=c::de=f::gh=i' ) ) ) #
```

Result

```
'ab', 'c', 'de', 'f', 'gh', 'i'
```

strip

Strips the leading and trailing characters from the first argument. The optional second argument defines the set of characters to strip. By default, this function strips white space (ie. space, tab, carriage return and line feed).

Note: Supported only in dynamic query mode.

Syntax

```
strip ( string_expression [ , set_of_characters ] )
```

Example 1

```
# sq( strip ( ' abc ' ) ) #
```

Result

```
'abc'
```

Example 2

```
' ) #
```

Result

```
53.21
```

substitute

Searches for a pattern in a string or in the string elements of an array and substitutes the first occurrence of "pattern_string" with "replacement_string".

Syntax

```
substitute ( pattern_string, replacement_string,  
string_expression|array_expression )
```

Example 1

```
#sq ( substitute ( '^cn=', '***', 'cn=help' ) )#
```

Result

```
'***help'
```

Example 2

```
# csv ( substitute ( '^cn=', '***', array ( 'cn=help' , 'acn=5' ) ) )  
#
```

Result

```
'***help', 'acn=5'
```

Example 3

```
# csv ( substitute ( 'cn=', '', array ( 'cn=help' , 'acn=5' ) ) ) #
```

Result

```
'help', 'a5'
```

timestampMask

Returns "string_expression1", representing a timestamp with time zone, trimmed to the format specified in "string_expression2". The format in "string_expression2" must be one of the following: 'yyyy', 'mm', 'dd', 'yyyy-mm', 'yyyymm', 'yyyy-mm-dd', 'yyyymmdd', 'yyyy-mm-dd hh:mm:ss', 'yyyy-mm-dd hh:mm:ss+hh:mm', 'yyyy-mm-dd hh:mm:ss.ff3', 'yyyy-mm-dd hh:mm:ss.ff3+hh:mm', 'yyyy-mm-ddThh:mm:ss', 'yyyy-mm-ddThh:mm:ss+hh:mm', 'yyyy-mm-ddThh:mm:ss.ff3+hh:mm', or 'yyyy-mm-ddThh:mm:ss.ff3+hh:mm'. The macro functions that return a string representation of a timestamp with time zone show a precision of 9 digits for the fractional part of the seconds by default. The format options allow this to be trimmed down to a precision of 3 or 0.

Syntax

```
timestampMask ( string_expression1 , string_expression2 )
```

Example 1

```
# timestampMask ( $current_timestamp , 'yyyy-dd-mm' ) #
```

Result

```
2005-11-01
```

Example 2

```
# timestampMask ( '2005-11-01 12:00:00.000-05:00' , 'yyyy-mm-dd  
hh:mm:ss+hh:mm' ) #
```

Result

```
2005-11-01 12:00:00-05:00
```

Example 3

```
# timestampMask ( '2005-11-01 12:00:00.123456789-05:00' ,  
'yyyy-mm-ddThh:mm:ss+hh:mm.ff3+hh:mm' ) #
```

Result

```
2005-11-01T12:00:00.123-05:00
```

toLocal

Returns the string representing a timestamp with time zone resulting from adjusting "string_expression" to the time zone of the operating system. Note that the macro function timestampMask () can be used to trim the output.

Syntax

```
toLocal ( string_expression )
```

Example 1

```
# toLocal ( '2005-11-01 17:00:00.000-00:00' ) # where OS local time  
zone is -05:00
```

Result

```
2005-11-01 12:00:00.000000000-05:00
```

Example 2

```
# timestampMask ( toLocal ( '2005-11-01 17:00:00.000-00:00' ) ,  
'yyyy-mm-dd hh:mm:ss+hh:mm' ) # where OS local time zone is -05:00
```

Result

```
2005-11-01 12:00:00-05:00
```

Example 3

```
# toLocal ( '2005-11-01 13:30:00.000-03:30' ) # where OS local time  
zone is -05:00
```

Result

```
2005-11-01 12:00:00.000000000-05:00
```

tolower

Returns the string "string_expression" with all the characters converted to lower case using the rules of the locale "locale_string". If no locale is specified, the locale 'en' is used.

Note: Supported only in dynamic query mode.

Syntax

```
tolower ( string_expression [ , locale_string ] )
```

Example 1

```
# tolower ( 'ABC' ) #
```

Result

```
abc
```

Example 2

```
# tolower ( 'ABC' , 'fr' ) #
```

Result

abc

toupper

Returns the string "string_expression" with all the characters converted to upper case using the rules of the locale defined in "locale_string". If "locale_string" is not specified, the locale 'en' is used.

Note: Supported only in dynamic query mode.

Syntax

```
toupper ( string_expression [ , locale_string ] )
```

Example 1

```
# toupper ( 'abc' ) #
```

Result

ABC

Example 2

```
# toupper ( 'abc' , 'fr' ) #
```

Result

ABC

toUTC

Returns the string representing a timestamp with time zone resulting from adjusting "string_expression" to the zero-point reference UTC time zone, also known as GMT time. Note that the macro function timestampMask () can be used to trim the output.

Syntax

```
toUTC ( string_expression )
```

Example 1

```
# toUTC ( '2005-11-01 12:00:00.000-05:00' ) #
```

Result

2005-11-01 17:00:00.000000000-00:00

Example 2

```
# timestampMask( toUTC ( '2005-11-01 12:00:00.000-05:00' ) ,  
'yyyy-mm-dd hh:mm:ss.ff3+hh:mm' ) #
```

Result

2005-11-01 17:00:00.000-00:00

Example 3

```
# toUTC ( $current_timestamp ) #
```

Result

unique

Removes duplicate entries from the array. The order of the elements is retained.

Syntax

```
unique ( array_expression )
```

Example

```
# csv ( unique ( array ( 's3', 'a', 's3', 'x' ) ) ) #
```

Result

```
's3', 'a', 'x'
```

urlencode

URL-encodes the passed argument. This function is useful when specifying XML connection strings.

Syntax

```
urlencode ( prompt ( 'userValue' ) )
```

Example

```
urlencode ( prompt ( 'some_val' ) )
```

Result

```
%27testValue%27
```

CSVIdentityName

Uses the identity information of the current authenticated user to look up values in the specified parameter map. Each individual piece of the user's identity (account name, group names, role names) is used as a key into the map. The unique list of values that is retrieved from the parameter map is then returned as a string, where each value is surrounded by single quotes and where multiple values are separated by commas.

Syntax

```
CSVIdentityName ( %parameter_map_name [ , separator_string ] )
```

Example

```
# CSVIdentityName ( %security_clearance_level_map ) #
```

Result

```
'level_500', 'level_501', 'level_700'
```

CSVIdentityNameList

Returns the pieces of the user's identity (account name, group names, role names) as a list of strings. The unique list of values is returned as a string, where each value is surrounded by single quotes and where multiple values are separated by commas.

Syntax

```
CSVIdentityNameList ( [ separator_string ] )
```

Example

```
# CSVIdentityNameList ( ) #
```

Result

```
'Everyone', 'Report Administrators', 'Query User'
```

CAMPassport

Returns the Cognos® Access Manager passport.

Syntax

```
CAMPassport ( )
```

Example

```
# CAMPassport ( ) #
```

Result

```
111:98812d62-4fd4-037b-4354-26414cf7ebef:3677162321
```

CAMIDList

Returns the pieces of the user's Cognos® Access Manager ID (CAMID), such as account name, group names, or role names, as a list of values separated by commas.

Syntax

```
CAMIDList ( [ separator_string ] )
```

Example

```
#CAMIDList ( ) #
```

Result

```
CAMID ( "::Everyone" ) , CAMID ( ":Authors" ) , CAMID ( ":Query  
Users" ) , CAMID ( ":Consumers" ) , CAMID ( ":Metrics Authors" )
```

CAMIDListForType

Returns an array of the user's Cognos® Access Manager IDs (CAMIDs) based on the identity type (account, group, or role). CAMIDListForType can be used with the macro functions csv or join.

Syntax

```
CAMIDListForType ( identity type )
```

Example

```
[qs].[userRole] in ( # csv ( CAMIDListForType ( 'role' ) ) # )
```

Result

```
[qs].[userRole] in ( 'CAMID ( "::System Administrators" ) ' , 'CAMID  
( "::Authors" ) ' )
```

simple case

This macro construct is the template for a simple case, including the case, when, then, else, and end functions. Note that this macro construct is only supported in DQM mode.

Syntax

```
CASE <expression> WHEN <literal> THEN <expression> [ELSE  
<expression>] END
```

Example

```
#CASE prompt('pDateRange','token') WHEN 'Current Week' THEN '[PR  
Current Week]' ELSE '[PR Prior Week]' END#
```

Result

```
[PR Current Week]
```

Common Functions

abs

Returns the absolute value of "numeric_expression". Negative values are returned as positive values.

Syntax

```
abs ( numeric_expression )
```

Example 1

```
abs ( 15 )
```

Result

```
15
```

Example 2

```
abs ( -15 )
```

Result

```
15
```

cast

Converts "expression" to a specified data type. Some data types allow for a length and precision to be specified. Make sure that the target is of the appropriate type and size. The following can be used for "datatype_specification": character, varchar, char, numeric, decimal, integer, bigint, smallint, real, float, date, time, timestamp, time with time zone, timestamp with time zone, and interval. When type casting to an interval type, one of the following interval qualifiers must be specified: year, month, or year to month for the year-to-month interval datatype; day, hour, minute, second, day to hour, day to minute, day to second, hour to minute, hour to second, or minute to second for the day-to-second interval datatype. Notes:

When you convert a value of type timestamp to type date, the time portion of the timestamp value is ignored. When you convert a value of type timestamp to type time, the date portion of the timestamp is ignored. When you convert a value of type date to type timestamp, the time components of the timestamp are set to zero. When you convert a value of type time to type timestamp, the date component is set to the current system date. It is invalid to convert one interval datatype to the other (for instance because the number of days in a month is variable). Note that you can specify the number of digits for the leading qualifier only, i.e. YEAR(4) TO MONTH, DAY(5). Errors will be reported if the target type and size are not compatible with the source type and size.

Syntax

```
cast ( expression , datatype_specification )
```

Example 1

```
cast ( '123' , integer )
```

Result

123

Example 2

```
cast ( 12345 , varchar ( 10 ) )
```

Result

a string containing 12345

ceil

Returns the smallest integer that is greater than or equal to "numeric_expression".

Syntax

```
ceil ( numeric_expression )
```

ceiling

Returns the smallest integer that is greater than or equal to "numeric_expression".

Syntax

```
ceiling ( numeric_expression )
```

Example 1

```
ceiling ( 4.22 )
```

Result

5

Example 2

```
ceiling ( -1.23 )
```

Result

-1

char_length

Returns the number of logical characters in "string_expression". The number of logical characters can be distinct from the number of bytes in some East Asian locales.

Syntax

```
char_length ( string_expression )
```

Example

```
char_length ( 'Canada' )
```

Result

6

character_length

Returns the number of characters in "string_expression".

Syntax

```
character_length ( string_expression )
```

Example

```
character_length ( 'Canada' )
```

Result

6

coalesce

Returns the first non-null argument (or null if all arguments are null). Requires two or more arguments in "expression_list".

Syntax

```
coalesce ( expression_list )
```

Example

```
coalesce ( [Unit price], [Unit sale price] )
```

Result

Returns the unit price, or the unit sale price if the unit price is null.

current_date

Returns a date value representing the current date of the computer that the database software runs on.

Syntax

```
current_date
```

Example

```
current_date
```

Result

2003-03-04

current_time

Returns a time with time zone value, representing the current time of the computer that runs the database software if the database supports this function. Otherwise, it represents the current time of the computer that runs IBM® Cognos® BI software.

Syntax

`current_time`

Example

`current_time`

Result

16:33:11.354+05:00

current_timestamp

Returns a datetime with time zone value, representing the current time of the computer that runs the database software if the database supports this function. Otherwise, it represents the current time of the computer that runs IBM® Cognos® BI software.

Syntax

`current_timestamp`

Example

`current_timestamp`

Result

2003-03-03 16:40:15.535+05:00

exp

Returns 'e' raised to the power of "numeric_expression". The constant 'e' is the base of the natural logarithm.

Syntax

`exp (numeric_expression)`

Example

`exp (2)`

Result

7.389056

extract

Returns an integer representing the value of datepart (year, month, day, hour, minute, second) in "datetime_expression".

Syntax

`extract (datepart , datetime_expression)`

Example 1

```
extract ( year , 2003-03-03 16:40:15.535 )
```

Result

2003

Example 2

```
extract ( hour , 2003-03-03 16:40:15.535 )
```

Result

16

floor

Returns the largest integer that is less than or equal to "numeric_expression".

Syntax

```
floor ( numeric_expression )
```

Example 1

```
floor ( 3.22 )
```

Result

3

Example 2

```
floor ( -1.23 )
```

Result

-2

ln

Returns the natural logarithm of "numeric_expression".

Syntax

```
ln ( numeric_expression )
```

Example

```
ln ( 4 )
```

Result

1.38629

localtime

Returns a time value, representing the current time of the computer that runs the database software.

Syntax

```
localtime
```

Example

```
localtime
```

Result

```
16:33:11
```

localtimestamp

Returns a datetime value, representing the current timestamp of the computer that runs the database software.

Syntax

```
localtimestamp
```

Example

```
localtimestamp
```

Result

```
2003-03-03 16:40:15
```

lower

Returns "string_expression" with all uppercase characters shifted to lowercase.

Syntax

```
lower ( string_expression )
```

Example

```
lower ( 'ABCDEF' )
```

Result

```
abcdef
```

mod

Returns the remainder (modulus) of "integer_expression1" divided by "integer_expression2". "Integer_expression2" must not be zero or an exception condition is raised.

Syntax

```
mod ( integer_expression1, integer_expression2 )
```

Example

```
mod ( 20 , 3 )
```

Result

```
2
```

nullif

Returns null if "expression1" equals "expression2", otherwise returns "expression1".

Syntax

`nullif (expression1, expression2)`

octet_length

Returns the number of bytes in "string_expression".

Syntax

`octet_length (string_expression)`

Example 1

`octet_length ('ABCDEF')`

Result

6

Example 2

`octet_length ('')`

Result

0

position

Returns the integer value representing the starting position of "string_expression1" in "string_expression2" or 0 when the "string_expression1" is not found.

Syntax

`position (string_expression1 , string_expression2)`

Example 1

`position ('C' , 'ABCDEF')`

Result

3

Example 2

`position ('H' , 'ABCDEF')`

Result

0

power

Returns "numeric_expression1" raised to the power "numeric_expression2". If "numeric_expression1" is negative, then "numeric_expression2" must result in an integer value.

Syntax

`power (numeric_expression1 , numeric_expression2)`

Example

```
power ( 3 , 2 )
```

Result

9

_round

Returns "numeric_expression" rounded to "integer_expression" places to the right of the decimal point. Notes: "integer_expression" must be a non-negative integer. Rounding takes place before data formatting is applied.

Syntax

```
_round ( numeric_expression , integer_expression )
```

Example

```
_round ( 1220.42369, 2 )
```

Result

1220.42

row

The row constructor represents a collection of values organized as a row of data. It can be used in conditional expressions (i.e. IF-THEN-ELSE) and filter expressions (i.e. IN clause).

Note: Supported only in dynamic query mode.

Syntax

```
row ( expression_list )
```

Example 1

```
if ( row([RetailerName],[OrderMethodCode]) = row('ActiForme',4) )  
then ('A')  
else ('B')
```

Result

Returns 'A' if the Retailer Name is 'ActiForme' and the order method code is 4. Otherwise, the value 'B' is returned.

Example 2

```
case row([RetailerName],[OrderMethodCode])  
when row('Advanced  
Climbing Ltd',3) then 1  
when row('ActiForme',5) then 2  
else 3  
end
```

Result

Returns 1 if the Retailer Name is 'Advanced Climbing Ltd' and the order method code is 3. Returns 2 if the Retailer Name is 'ActiForme' and the order method code is 5. Otherwise, the value 3 is returned.

Example 3

```
row ( [OrderMethodCode], [Year] ) in ( [Query].[OMC], [Query].[YR] )
```

Result

The returned data is filtered on the following two conditions: 1) [OrderMethodCode] in ([Query].[OMC]) 2) [Year] in ([Query].[YR])

sqrt

Returns the square root of "numeric_expression". "Numeric_expression" must be non-negative.

Syntax

```
sqrt ( numeric_expression )
```

Example

```
sqrt ( 9 )
```

Result

3

substring

Returns the substring of "string_expression" that starts at position "integer_expression1" for "integer_expression2" characters or to the end of "string_expression" if "integer_expression2" is omitted. The first character in "string_expression" is at position 1.

Syntax

```
substring ( string_expression , integer_expression1 [ ,  
integer_expression2 ] )
```

Example

```
substring ( 'abcdefg' , 3 , 2 )
```

Result

cd

trim

Returns "string_expression" trimmed of leading and trailing blanks or trimmed of a certain character specified in "match_character_expression". "Both" is implicit when the first argument is not stated and blank is implicit when the second argument is not stated.

Syntax

```
trim ( [ [ trailing|leading|both ] [ match_character_expression ] , ]  
string_expression )
```

Example 1

```
trim ( trailing 'A' , 'ABCDEFA' )
```

Result

ABCDEF

Example 2

```
trim ( both , ' ABCDEF ' )
```

Result

ABCDEF

upper

Returns "string_expression" with all lowercase characters converted to uppercase.

Syntax

```
upper ( string_expression )
```

Example

```
upper ( 'abcdef' )
```

Result

ABCDEF

width-bucket

For a given expression, this function returns the bucket number into which the value of this expression would fall after being evaluated.

Note: Supported only in dynamic query mode.

Syntax

```
width-bucket ( numeric_expression , min_value , max_value ,  
num_of_buckets )
```

Example

```
width-bucket ( Quantity , 100 , 5000 , 10 )
```

Result

For each row, returns the bucket number (from 0 to 11) for the current Quantity value.

Result data

Quantity	width-bucket (Quantity)
50	0
450	1
1400	3
3600	8
4900	10
5000	11

Trigonometric functions

arccos

This inverse trigonometric function returns the arc cosine of the argument, where the argument is in the range of -1 to 1 and the result is a value expressed in radians.

Note: Supported only in dynamic query mode.

Syntax

```
arccos ( numeric_expression )
```

Example

```
arccos ( -1 )
```

Result

3.1415

arcsin

This inverse trigonometric function returns the arc sine of the argument, where the argument is in the range of -1 to 1 and the result is a value expressed in radians.

Note: Supported only in dynamic query mode.

Syntax

```
arcsin ( numeric_expression )
```

Example

```
arcsin ( 0 )
```

Result

3.1415

arctan

This inverse trigonometric function returns the arc tangent of the argument, where the argument is in the range of -1 to 1 and the result is a value expressed in radians.

Note: Supported only in dynamic query mode.

Syntax

```
arctan ( numeric_expression )
```

Example

```
arctan ( 0 )
```

Result

3.1415

cos

This trigonometric function returns the cosine of the argument, where the argument is an angle expressed in radians.

Note: Supported only in dynamic query mode.

Syntax

```
cos ( numeric_expression )
```

Example

```
cos ( 0.3333 * 3.1415 )
```

Result

0.5

coshyp

This trigonometric function returns the hyperbolic cosine of the argument, where the argument is an angle expressed in radians.

Note: Supported only in dynamic query mode.

Syntax

```
coshyp ( numeric_expression )
```

Example

```
coshyp ( 0 )
```

Result

1

sin

This trigonometric function returns the sine of the argument, where the argument is an angle expressed in radians.

Note: Supported only in dynamic query mode.

Syntax

```
sin ( numeric_expression )
```

Example

```
sin ( 0.1667 * 3.1415 )
```

Result

0.5

sinhyp

This trigonometric function returns the hyperbolic sine of the argument, where the argument is an angle expressed in radians.

Note: Supported only in dynamic query mode.

Syntax

```
sinhyp ( numeric_expression )
```

Example

```
sinhyp ( 0 )
```

Result

0

tan

This trigonometric function returns the tangent of the argument, where the argument is an angle expressed in radians.

Note: Supported only in dynamic query mode.

Syntax

```
tan ( numeric_expression )
```

Example

```
tan ( 0.25 * 3.1415 )
```

Result

1

tanhyp

This trigonometric function returns the hyperbolic tangent of the argument, where the argument is an angle expressed in radians.

Note: Supported only in dynamic query mode.

Syntax

```
tanhyp ( numeric_expression )
```

Example

```
tanhyp ( 0 )
```

Result

0

Dimensional Functions

ancestor

Returns the ancestor of "member" at "level" or at "integer" number of levels above "member". Note: The result is not guaranteed to be consistent when there is more than one such ancestor.

Syntax

```
ancestor ( member, level|integer )
```

Example 1

```
ancestor ( [TrailChef Water Bag] , 1 )
```

Result

Cooking Gear

Example 2

```
ancestor ( [TrailChef Water Bag] , 2 )
```

Result

Camping Equipment

Example 3

```
ancestor ( [TrailChef Water Bag] , [great_outdoors_company].  
[Products].[Products].[Product type] )
```

Result

Cooking Gear

ancestors

Returns all the ancestors of "member" at "level" or "index" distance above the member. (Most data sources support only one ancestor at a specified level. If the data source supports more than one ancestor, the result is a member set.)

Syntax

```
ancestors ( member , level|index )
```

Example 1

```
ancestors ( [TrailChef Water Bag] , 1 )
```

Result

Cooking Gear

Example 2

```
ancestors ( [TrailChef Water Bag] , 2 )
```

Result

Camping Equipment

Example 3

```
ancestors ( [TrailChef Water Bag] , [great_outdoors_company].  
[Products].[Products].[Product type] )
```

Result

Cooking Gear

bottomCount

Sorts a set according to the value of "numeric_expression" evaluated at each of the members of "set_expression" and returns the bottom "index_expression" members.

Syntax

```
bottomCount ( set_expression , index_expression , numeric_expression )
```

Example

```
bottomCount ( [great_outdoors_company].[Products].[Products].[Product  
line] , 2 , [Revenue] )
```

Result

Returns the bottom two members of the set sorted by revenue.

Result data

Prod line	Revenue
Camping	\$3,171,114.92
Personal	\$20,891,350.60

bottomPercent

Sorts the set specified in "set_expression" in ascending order and returns the bottommost elements from the sorted set whose cumulative percentage of the total is greater than or equal to "percentage".

Syntax

```
bottomPercent ( set_expression , percentage , numeric_expression )
```

Example

```
bottomPercent ( set ( [Camping Equipment] , [Golf Equipment] ,  
[Mountaineering Equipment] ) , 40 , [2006] )
```

Result

For the set of Camping Equipment, Golf Equipment, and Mountaineering Equipment, returns the members with the smallest Gross profit whose total for the year 2006 is at least 40% of the overall total.

bottomSum

Sorts the set specified in "set_expression" in ascending order and returns the bottommost elements from the sorted set whose cumulative total is greater than or equal to "value".

Syntax

```
bottomSum ( set_expression , value , numeric_expression )
```

Example

```
bottomSum ( members ( [great_outdoors_company].[Products].[Products].  
[Product line] ) , 6000000 , tuple ( [2006] ,  
[great_outdoors_company].[Measures].[Gross profit] ) )
```

Result

For the Product line members, returns the members with the smallest Gross profit whose total for the year 2006 is at least \$6,000,000.

caption

Returns the caption values of "level", "member", or "set_expression". The caption is the string display name for an element and does not necessarily match the unique identifier used to generate the business key or member unique name (MUN) for

the element. The caption is not necessarily unique; for example, the caption for a month may return the month name without further year details to make the value unique.

Syntax

```
caption ( level|member|set_expression )
```

Example 1

```
caption ( [TrailChef Water Bag] )
```

Result

TrailChef Water Bag

Example 2

```
caption ( [great_outdoors_company].[Products].[Products].[Product  
line] )
```

Result

Returns the caption values of the Product line set.

Result data

Camping Equipment
Mountaineering Equipment
Personal Accessories
Outdoor Protection
Golf Equipment

children

Returns the set of children of a specified member.

Syntax

```
children ( member )
```

Example

```
children ( [Camping Equipment] )
```

Result

Returns the set of children for Camping Equipment.

Result data

Cooking Gear
Tents
Sleeping Bags
Packs
Lanterns

closingPeriod

Returns the last sibling member among the descendants of a member at "level". This function is typically used with a time dimension.

Syntax

```
closingPeriod ( level [ , member ] )
```

Example 1

```
closingPeriod ( [great_outdoors_company].[Years].[Years].[Month] )
```

Result

2006/Dec

Example 2

```
closingPeriod ( [great_outdoors_company].[Years].[Years].[Year] )
```

Result

2006

Example 3

```
closingPeriod ( [great_outdoors_company].[Years].[Years].[Month] ,  
[2006 Q 4] )
```

Result

2006/Dec

cousin

Returns the child member of "member2" with the same relative position as "member1" to its parent. This function appears in the Revenue by GO Subsidiary 2005 sample report in the GO Data Warehouse (analysis) package.

Syntax

```
cousin ( member1 , member2 )
```

Example 1

```
cousin ( [Irons] , [Camping Equipment] )
```

Result

Cooking Gear

Example 2

```
cousin ( [Putters] , [Camping Equipment] )
```

Result

Sleeping Bags

completeTuple

Identifies a cell location (intersection) based on the specified members, each of which must be from a different dimension. However, `completeTuple ()` implicitly includes the default member from all dimensions not otherwise specified in the arguments, rather than the current member. `CompleteTuple` will use the default measure rather than the `currentMeasure` in the query if the measure is not defined in the `completetuple` function. This function appears in the Planned Headcount sample report in the GO Data Warehouse (analysis) package.

Syntax

```
completeTuple ( member { , member } )
```

Example 1

```
completeTuple ( [Mountaineering Equipment] , [Fax] )
```

Result

The completeTuple does not pick up the currentMember by default as the tuple function does. The values in the first column are identical across each year because the default member of the Years dimension, the root member, is used rather than the current member. Likewise, the first column displays Revenue rather than Quantity Sold because the Revenue measure is the default from the Measures dimension. CompleteTuple will use the default measure rather than the currentMeasure in the query if the measure is not defined in the completetuple function.

Result data

Qty Sold	Mountaineering Sales by Fax
2004	\$1,220,329.38
2005	\$1,220,329.38
2006	\$1,220,329.38

Example 2

```
completeTuple ( [Mountaineering Equipment] , [Fax] , [Quantity sold] ,  
currentMember ( [great_outdoors_company].[Years].[Years] ) )
```

Result

The completeTuple function uses the currentMember of the Years dimension and the Quantity sold measure.

Result data

Qty Sold	Mountaineering Sales by Fax
2004	0
2005	8,746
2006	7,860

currentMember

Returns the current member of the hierarchy during an iteration. If "hierarchy" is not present in the context in which the expression is being evaluated, its default member is assumed. This function appears in the Rolling and Moving Averages interactive sample report.

Syntax

```
currentMember ( hierarchy )
```

defaultMember

Returns the default member of "hierarchy".

Syntax

```
defaultMember ( hierarchy )
```

Example 1

```
defaultMember ( [great_outdoors_company].[Products].[Products] )
```

Result

Products

Example 2

```
defaultMember ( [great_outdoors_company].[Years].[Years] )
```

Result

Year

Example 3

```
defaultMember ( hierarchy ( [great_outdoors_company].[Measures].  
[Quantity sold] ) )
```

Result

Revenue

descendants

Returns the set of descendants of "member" or "set_expression" at "level" (qualified name) or "distance" (integer 0..n) from the root. Multiple options may be specified (separated by a space) to determine which members are returned. self: Only the members at the specified level are included in the final set (this is the default behaviour in the absence of any options). before: If there are any intermediate levels between the member's level and the one specified, members from those levels are included. If the level specified is the same as the member upon which the function is applied, the member is included in the final set. beforewithmember: If there are any intermediate levels between the member's level and the one specified, members from those levels are included. The member upon which the function is applied is also included in the final set. after: If other levels exist after the specified level, members from those levels are included in the final set. This function appears in the Sales Commissions for Central Europe sample report in the GO Data Warehouse (analysis) package.

Syntax

```
descendants ( member|set_expression , level|distance [ ,  
{ self|before|beforewithmember|after } ] )
```

Example 1

```
descendants ( [great_outdoors_company].[Products].[Products].  
[Products] , [great_outdoors_company].[Products].[Products].[Product  
type] )
```

Result

Returns the set of descendants of the Products set at the Product type level. Note: [great_outdoors_company].[Products].[Products].[Products] is the root member of the Products hierarchy.

Result data

Cooking Gear
Sleeping Bags
Packs
Tents
...
Eyewear
Knives
Watches

Example 2

```
descendants ( [great_outdoors_company].[Products].[Products].  
[Products] , 1 )
```

Result

Returns the set of descendants of the Products set at the first level.

Result data

Camping Equipment
Golf Equipment
Mountaineering Equipment
Outdoor Protection
Personal Accessories

Example 3

```
descendants ( [great_outdoors_company].[Products].[Products].  
[Products] , 3 , before )
```

Result

Returns the descendants of the Products set before the third level.

Result data

Camping Equipment
Cooking Gear
Sleeping Bags
Packs
Tents
...
Eyewear
Knives
Watches

Example 4

```
descendants ( [great_outdoors_company].[Products].[Products].  
[Products] , 2 , self before )
```

Result

Returns the set of descendants of the Products set before and including the second level.

Result data

Camping Equipment
Cooking Gear
Sleeping Bags
Packs
Tents

```
...  
Eyewear  
Knives  
Watches
```

except

Returns the members of "set_expression1" that are not also in "set_expression2". Duplicates are retained only if the optional keyword "all" is supplied as the third argument.

Syntax

```
except ( set_expression1 , set_expression2 [ , all ] )
```

Example

```
except ( set ( [Camping Equipment] , [Mountaineering Equipment] ) ,  
        set ( [Camping Equipment] , [Golf Equipment] ) )
```

Result

Mountaineering Equipment

filter

Returns the set resulting from filtering a specified set based on the Boolean condition. Each member is included in the result if and only if the corresponding value of "Boolean_expression" is true.

Syntax

```
filter ( set_expression , Boolean_expression )
```

Example

```
filter ( [Product line] , [Gross margin] > .30 )
```

Result

Mountaineering Equipment

firstChild

Returns the first child of "member".

Syntax

```
firstChild ( member )
```

Example 1

```
firstChild ( [By Product Lines] )
```

Result

Camping Equipment

Example 2

```
firstChild ( [Camping Equipment] )
```

Result

Cooking Gear

firstSibling

Returns the first child of the parent of "member".

Syntax

```
firstSibling ( member )
```

Example 1

```
firstSibling ( [Outdoor Protection] )
```

Result

Camping Equipment

Example 2

```
firstSibling ( [Camping Equipment] )
```

Result

Camping Equipment

_format

Associates a format with the expression. The `format_keyword` can be `PERCENTAGE_0`, `PERCENTAGE_1`, or `PERCENTAGE_2`. `PERCENTAGE_1` returns a percentage with one digit to the right of the decimal point, `PERCENTAGE_2` returns a percentage with two digits to the right of the decimal point, and `PERCENTAGE_3` returns a percentage value out of one with three digits to the right of the decimal point (for example, 0.965).

Syntax

```
_format ( expression , format_keyword )
```

Example

```
_format ( [Unit Sale Price] / [Unit Price] , PERCENTAGE_2 )
```

Result

75.12%

emptySet

Returns an empty member set for "hierarchy". This is most often used as a placeholder during development or with dynamic report design (either with the IBM® Cognos® Software Development Kit or via report design). By creating a data item that contains the emptyset function, it is possible to build complex expressions that can later be revised by redefining the emptyset data item.

Syntax

```
emptySet ( hierarchy )
```

Example

```
except ( [great_outdoors_company].[Products].[Products].[Product  
line] , emptySet ( [great_outdoors_company].[Products].[Products] ) )
```

Result

Returns the Product line set and an empty set for the Products set.

Result data

Camping Equipment
Golf Equipment
Mountaineering Equipment
Outdoor Protection
Personal Accessories

generate

Evaluates "set_expression2" for each member of "set_expression1" and joins the resulting sets by union. The result retains duplicates only when the optional keyword "all" is supplied as the third argument.

Syntax

```
generate ( set_expression1 , set_expression2 [ , all ] )
```

Example

```
generate ( [Product line] , topCount ( descendants ( currentMember (
  [great_outdoors_company].[Products].[Products] ) ,
  [great_outdoors_company].[Products].[Products].[Product name] ) , 2 ,
  [Revenue] ) )
```

Result

Returns the top two products by revenue for each product line.

head

Returns the first "index_expression" elements of "set_expression". The default for "index_expression" is 1.

Syntax

```
head ( set_expression [ , index_expression ] )
```

Example 1

```
head ( members ( [great_outdoors_company].[Products].[Products].
  [Product line] ) )
```

Result

Camping Equipment

Example 2

```
head ( members ( [great_outdoors_company].[Products].[Products].
  [Product line] ) , 2 )
```

Result

Returns the top two members of the Product line set.

Result data

Camping Equipment
Mountaineering Equipment

hierarchize

Orders the members of "set_expression" in a hierarchy. Members in a level are sorted in their natural order. This is the default ordering of the members along a dimension when no other sort conditions are specified.

Syntax

```
hierarchize ( set_expression )
```

Example

```
hierarchize ( set ( [Golf Equipment] , [Mountaineering Equipment] ,  
[Camping Equipment] ) )
```

Result

Returns Camping Equipment, Golf Equipment, Mountaineering Equipment.

hierarchy

Returns the hierarchy that contains "level", "member", or "set_expression".

Syntax

```
hierarchy ( level|member|set_expression )
```

Example 1

```
hierarchy ( [Cooking Gear] )
```

Result

Returns every member in the hierarchy that contains Cooking Gear.

Result data

```
Products  
Camping Equipment  
Cooking Gear  
TrailChef Water Bag  
TrailChef Canteen  
...  
Mountain Man Extreme  
Mountain Man Deluxe
```

Example 2

```
hierarchy ( [great_outdoors_company].[Products].[Products].[Product  
line] )
```

Result

Returns every member in the hierarchy that contains the Product line.

Result data

```
Products  
Camping Equipment  
Cooking Gear  
TrailChef Water Bag  
TrailChef Canteen  
...  
Mountain Man Extreme  
Mountain Man Deluxe
```

item

Returns a member from the "index" location within "set_expression". The index into the set is zero based.

Syntax

```
item ( set_expression , index )
```

Example

```
item ( children ( [Camping Equipment] ) , 2 )
```

Result

Sleeping Bags

intersect

Returns the intersection of "set_expression1" and "set_expression2". The result retains duplicates only when the optional keyword "all" is supplied as the third argument.

Syntax

```
intersect ( set_expression1 , set_expression2 [ , all ] )
```

Example

```
intersect ( set ( [Camping Equipment] , [Mountaineering Equipment] ) ,  
set ( [Camping Equipment] , [Outdoor Protection] , ) , all )
```

Result

Camping Equipment

lag

Returns the sibling member that is "index_expression" number of positions prior to "member".

Syntax

```
lag ( member , index_expression )
```

Example 1

```
lag ( [Tents] , 1 )
```

Result

Cooking Gear

Example 2

```
lag ( [Tents] , -2 )
```

Result

Packs

lastChild

Returns the last child of a specified member.

Syntax

```
lastChild ( member )
```

Example 1

```
lastChild ( Cooking Gear )
```

Result

TrailChef Utensils

Example 2

```
lastChild ( [By Product Line] )
```

Result

Golf Equipment

lastPeriods

Returns the set of members from the same level that ends with "member". The number of members returned is the absolute value of "integer_expression". If "integer_expression" is negative, members following and including the specified member are returned. Typically used with a time dimension. This function appears in the Rolling and Moving Averages interactive sample report.

Syntax

```
lastPeriods ( integer_expression , member )
```

Example 1

```
lastPeriods ( 2 , [2006 Q 4] )
```

Result

Returns the last two members from the level that ends with 2006 Q 4.

Result data

```
2006 Q 3  
2006 Q 4
```

Example 2

```
lastPeriods ( -3 , [2006 Q 4] )
```

Result

Returns the last three members from the level that starts with 2006 Q 4.

Result data

```
2006 Q 4  
2007 Q 1  
2007 Q 2
```

lastSibling

Returns the last child of the parent of a specified member.

Syntax

lastSibling (member)

Example

lastSibling ([Camping Equipment])

Result

Golf Equipment

lead

Returns the sibling member that is "index_expression" number of positions after "member". If "index_expression" is negative, returns the sibling member that is "index_expression" number of positions before "member".

Syntax

lead (member , index_expression)

Example 1

lead ([Outdoor Protection] , 1)

Result

Personal Accessories

Example 2

lead ([Outdoor Protection] , -2)

Result

Golf Equipment

level

Returns the level of "member".

Syntax

level (member)

Example

level ([Golf Equipment])

Result

Returns the members on the Golf Equipment level.

Result data

Camping Equipment
Mountaineering Equipment
Personal Accessories
Outdoor Protection
Golf Equipment

levels

Returns the level in "hierarchy" whose distance from the root is specified by "index".

Syntax

```
levels ( hierarchy , index )
```

Example 1

```
levels ( [great_outdoors_company].[Products].[Products] , 2 )
```

Result

Returns the members two levels from the root Products hierarchy.

Result data

```
Cooking Gear  
Sleeping Bags  
Packs  
Tents  
...  
Irons  
Putters  
Woods  
Golf Accessories
```

Example 2

```
levels ( [great_outdoors_company].[Products].[Products] , 1 )
```

Result

Returns the members one level from the root Products hierarchy.

Result data

```
Camping Equipment  
Mountaineering Equipment  
Personal Accessories  
Outdoor Protection  
Golf Equipment
```

linkMember

Returns the corresponding member in "level" or "hierarchy" (of the same dimension). For level-based hierarchies, a level must be specified as the second argument, and for parent-child hierarchies, a hierarchy must be specified. An exception is thrown when the second parameter does not resolve to a hierarchy of the member's dimension. Note that calculated members are not supported as the first argument.

Syntax

```
linkMember ( member , level|hierarchy )
```

members

Returns the set of members in "hierarchy" or "level". In the case of a hierarchy, the order of the members in the result is not guaranteed. If a predictable order is required, an explicit ordering function (such as hierarchize) must be used.

Syntax

members (hierarchy|level)

Example 1

members ([great_outdoors_company].[Years].[Years])

Result

Returns the members in Years.

Example 2

members ([great_outdoors_company].[Products].[Products].[Product line])

Result

Returns the members in Product line.

nextMember

Returns the next member in the "member" level.

Syntax

nextMember (member)

Example

nextMember ([Outdoor Protection])

Result

Golf Equipment

openingPeriod

Returns the first sibling member among the descendants of a member at "level". This function is typically used with a time dimension.

Syntax

openingPeriod (level [, member])

Example 1

openingPeriod ([great_outdoors_company].[Years].[Years].[Month])

Result

2004/Jan

Example 2

openingPeriod ([great_outdoors_company].[Years].[Years].[Year])

Result

2004

Example 3

```
openingPeriod ( [great_outdoors_company].[Years].[Years].[Month] ,  
                [2006 Q 4] )
```

Result

2006/Oct

order

Arranges the members of "set_expression" according to their "value_expression" and the third parameter. ASC and DESC arrange members in ascending or descending order, respectively, according to their position in the set hierarchy. Then the children of each member are arranged according to "value_expression". BASC and BDESC arrange members in the set without regard to the hierarchy. In the absence of an explicit specification, ASC is the default.

Syntax

```
order ( set_expression , value_expression [ , ASC|DESC|BASC|BDESC ] )
```

Example 1

```
order ( members ( [Great Outdoors Company].[Product].[Product].  
                [Product type] ) , [Quantity sold] , BASC )
```

Result

Returns the quantity sold for each product type in no particular order.

Result data

ProdLine	Quantity
Woods	13,924
Irons	14,244
Safety	22,332
...	...
Sun	215,432
Repellent	270,04
Lanterns	345,096

Example 2

```
order ( members ( [Great Outdoors Company].[Product].[Product].  
                [Product type] ) , [Quantity sold] , ASC )
```

Result

Returns the quantity sold for each product type in ascending order.

Result data

ProdLine	Quantity
Woods	13,924
Irons	14,244
Putters	23,244
...	...
Tents	130,664
Cooking	198,676

ProdLine
Lanterns

Quantity
345,096

ordinal

Returns the zero-based ordinal value (distance from the root level) of "level".

Syntax

```
ordinal ( level )
```

Example 1

```
ordinal ( [great_outdoors_company].[Products].[Products].[Product  
line] )
```

Result

1

Example 2

```
ordinal ( [great_outdoors_company].[Products].[Products].[Product  
type] )
```

Result

2

parallelPeriod

Returns a member from a prior period in the same relative position as "member". This function is similar to the cousin function, but is more closely related to time series. It takes the ancestor of "member" at "level" (called "ancestor") and the sibling of "ancestor" that lags by "integer_expression" positions, and returns the parallel period of "member" among the descendants of that sibling. When unspecified, "integer_expression" defaults to 1 and "member" defaults to the current member.

Syntax

```
parallelPeriod ( level [ , integer_expression [ , member ] ] )
```

Example 1

```
parallelPeriod ( [great_outdoors_company].[Years].[Years].[Quarter] ,  
-1 , [2006/Aug] )
```

Result

2006/Nov

Example 2

```
parallelPeriod ( [great_outdoors_company].[Years].[Years].[Quarter] ,  
1 , [2006/Aug] )
```

Result

2006/May

Example 3

```
parallelPeriod ( [great_outdoors_company].[Years].[Years].[Year] , 2 ,  
[2006/Aug] )
```

Result

2004/Aug

parent

Returns the member that is the parent of "member" or "measure".

Syntax

```
parent ( member|measure )
```

Example

```
parent ( [Cooking Gear] )
```

Result

Camping Equipment

periodsToDate

Returns a set of sibling members from the same level as "member", as constrained by "level". It locates the ancestor of "member" at "level" and returns that ancestor's descendants at the same level as "member" (up to and including "member"). Typically used with a time dimension. This function appears in the Rolling and Moving Averages interactive sample report.

Syntax

```
periodsToDate ( level , member )
```

Example

```
periodsToDate ( [great_outdoors_company].[Years].[Years].[Year] ,  
[2004/Mar] )
```

Result

Returns values for [2004/Jan], [2004/Feb], [2004/Mar]

prevMember

Returns the member that immediately precedes "member" in the same level. This function appears in the Sales Growth Year Over Year sample report in the GO Data Warehouse (analysis) package.

Syntax

```
prevMember ( member )
```

Example 1

```
prevMember ( [Outdoor Protection] )
```

Result

Personal Accessories

Example 2

```
prevMember ( [2005] )
```

Result

2004

member

Defines a member based on "value_expression" in "hierarchy". "String1" identifies the member created by this function. It must be unique in the query and different from any other member in the same hierarchy. "String2" is the caption of the member; if it is absent, the caption is empty. To ensure predictable results, it is recommended that you supply the "hierarchy". Note: All calculations used as grouping items whose sibling items are other calculations or member sets should be explicitly assigned to a hierarchy using this function. The results are not predictable otherwise. The only exception is where the calculation involves only members of the same hierarchy as the siblings. In this case, the calculation is assumed to belong to that hierarchy.

Syntax

```
member ( value_expression [ , string1 [ , string2 [ ,  
  hierarchy ] ] ] )
```

Example

```
member ( total ( currentMeasure within set filter ( [great_outdoors_company].[Products].[Products].[Product name] ,  
  caption ( [great_outdoors_company].[Products].[Products].[Product name] ) starts with 'B' ) ) , 'BProducts' , 'B Products' ,  
  [great_outdoors_company].[Products].[Products] )
```

Result

Returns the quantity sold and revenue for all products that start with the letter B.

nestedSet

This function is intended for use only by Analysis Studio

Syntax

```
nestedSet ( set_expression1 , set_expression2 )
```

set

Returns the list of members defined in the expression. The members must belong to the same hierarchy.

Syntax

```
set ( member { , member } )
```

Example

```
set ( [Golf Equipment] , [Irons] , [TrailChef Cup] )
```

Result

Returns Golf Equipment, Irons, and TrailChef Cup.

siblings

Returns the children of the parent of the specified member.

Syntax

```
siblings ( member )
```

Example

```
siblings ( [Golf Equipment] )
```

Result

Returns the siblings of Golf Equipment.

Result data

```
Camping Equipment  
Golf Equipment  
Mountaineering Equipment  
Outdoor Protection  
Personal Accessories
```

tail

Returns the last "index_expression" elements of "set expression". The default for "index_expression" is 1.

Syntax

```
tail ( set_expression [ , index_expression ] )
```

Example 1

```
tail ( members ( [great_outdoors_company].[Products].[Products].  
[Product line] ) )
```

Result

Returns the last member of the Product line set.

Result data

```
Personal Accessories
```

Example 2

```
tail ( members ( [great_outdoors_company].[Products].[Products].  
[Product line] ) , 2 )
```

Result

Returns the last two members of the Product line set.

Result data

```
Outdoor Protection  
Personal Accessories
```

topCount

Sorts a set according to the values of "numeric_expression" evaluated at each of the members of "set_expression" and returns the top "index_expression" members.

Syntax

```
topCount ( set_expression , index_expression , numeric_expression )
```

Example

```
topCount ( [great_outdoors_company].[Products].[Products].[Product  
line] , 2 , [Revenue] )
```

Result

Returns the top two revenues for the Product line set.

Result data

Prod line	Revenue
Camping	\$89,713,990.92
Personal	\$31,894,465.86

topPercent

Sorts the set specified in "set_expression" in descending order and returns the topmost elements from the sorted set whose cumulative percentage of the total is greater than or equal to "percentage".

Syntax

```
topPercent ( set_expression , percentage , numeric_expression2 )
```

Example

```
topPercent ( set ( [Camping Equipment] , [Golf Equipment] ,  
[Mountaineering Equipment] ) , 40 , [2006] )
```

Result

For the set of Camping Equipment, Golf Equipment, and Mountaineering Equipment, returns the members with the largest Gross profit whose total for the year 2006 is at least 40% of the overall total.

topSum

Sorts the set specified in "set_expression" in descending order and returns the topmost elements from the sorted set whose cumulative total is greater than or equal to "value".

Syntax

```
topSum ( set_expression , value , numeric_expression2 )
```

Example

```
topSum ( children ( [Products] ) , 16000000 , tuple ( [2006] ,  
[great_outdoors_company].[Measures].[Gross profit] ) )
```

Result

For the Product line members, returns the members with the largest Gross profit whose total for the year 2006 is at least \$6,000,000.

tuple

Identifies a cell location (intersection) based on the specified members, each of which must be from a different dimension. This function implicitly includes the current member from all dimensions that are not otherwise specified in the arguments. The current member of any dimension not specified in the evaluating context is assumed to be the default member of that dimension. The value of this cell can be obtained with the "value" function.

Syntax

```
tuple ( member { , member } )
```

Example

```
tuple ( [Mountaineering Equipment] , [Fax] )
```

Result

Returns the Mountaineering Equipment sales by fax.

union

Returns data for "set_expression1" and "set_expression2". The result retains duplicates only when the optional keyword "all" is supplied as the third argument.

Syntax

```
union ( set_expression1 , set_expression2 [ , all ] )
```

Example 1

```
union ( set ( [Camping Equipment] , [Golf Equipment] ) , set ( [Golf  
Equipment] , [Mountaineering Equipment] ) )
```

Result

Returns data for both sets as one new set, showing the Golf Equipment column only once.

Example 2

```
union ( set ( [Camping Equipment] , [Golf Equipment] ) , set ( [Golf  
Equipment] , [Mountaineering Equipment] ) , all )
```

Result

Returns data for both sets as one new set, showing the Golf Equipment column twice.

roleValue

Returns the value of the attribute that is associated with the role whose name is specified by "string" within the specified context. "Member" or "set_expression" is optional only in a number of limited circumstances, where it can be derived from another context. Applications can be made portable across different data sources and models by accessing attributes by role rather than by query item ID. For dimensionally-modeled relational (DMR) data sources, assignment of roles is the modeler's responsibility. Intrinsic roles that are defined for members of all data source types include: '_businessKey', '_memberCaption', '_memberDescription', '_memberUniqueName'. Additional roles can be defined in Framework Manager for each level in a hierarchy. For example, a Product type level may have an

attribute column called "Type Shipping Container", and the Product level may have a "Product Shipping Container" attribute. Each of these could be assigned a custom role in Framework Manager called "Container". The property could then be referenced independently of the actual column name by using the `roleValue` function.

Syntax

```
roleValue ( string [ , member|set_expression ] )
```

Example 1

```
roleValue ( 'memberCaption' , [Sales].[Product].[Product].[Product  
line] -> [all].[1] )
```

Result

Camping Equipment

Example 2

```
roleValue ( '_businessKey' , [great_outdoors_company].[Years].[Years].  
[Year] )
```

Result

Returns the value of the attribute that is associated with the business key role.

Result data

```
("2004-01-01","2004-12-31")  
("2005-01-01","2005-12-31")  
("2006-01-01","2006-12-31")
```

Example 3

```
roleValue ( 'memberUniqueName' , [great_outdoors_company].[Years].  
[Years].[Year] )
```

Result

Returns the value of the attribute that is associated with the MUN role.

Result data

```
[great_outdoors_company].[Years].[Years].[Year] ->:[PC].[Years (Root)].[20040101-20041231]  
[great_outdoors_company].[Years].[Years].[Year] ->:[PC].[Years (Root)].[20050101-20051231]  
[great_outdoors_company].[Years].[Years].[Year] ->:[PC].[Years (Root)].[20060101-20061231]
```

rootMember

Returns the root member of a single-root hierarchy. This function appears in the Promotion Success sample report in the GO Data Warehouse (analysis) package.

Syntax

```
rootMember ( hierarchy )
```

rootMembers

Returns the root members of a hierarchy.

Syntax

```
rootMembers ( hierarchy )
```

Example

```
rootMembers ( [great_outdoors_company].[Years].[Years] )
```

Result

By Time

subset

Returns a subset of members in "set_expression" starting at "index_expression1" from the beginning. If the count "index_expression2" is specified, that many members are returned (if available). Otherwise, all remaining members are returned.

Syntax

```
subset ( set_expression, index_expression1 [ , index_expression2 ] )
```

Example 1

```
subset ( members ( [great_outdoors_company].[Products].[Products].  
[Product line] ) , 2 )
```

Result

Returns the members of the Product line set starting at the second member.

Result data

```
Mountaineering Equipment  
Outdoor Protection  
Personal Accessories
```

Example 2

```
subset ( members ( [great_outdoors_company].[Products].[Products].  
[Product line] ) , 2 , 2 )
```

Result

Returns two members of the Product line set starting at the second member.

Result data

```
Mountaineering Equipment  
Outdoor Protection
```

unique

Removes all duplicates from "set_expression". The remaining members retain their original order.

Syntax

```
unique ( set_expression )
```

value

Returns the value of the cell identified by "tuple". Note that the default member of the Measures dimension is the Default Measure.

Syntax

value (tuple)

Example 1

```
value ( tuple ( [great_outdoors_company].[Years].[Years].[Year]
->:[PC].[Years (Root)].[20040101-20041231] , [great_outdoors_company].
[Measures].[Revenue] ) )
```

Result

\$34,750,563.50

Example 2

```
value ( tuple ( [2004] , [Camping Equipment] , [Revenue] ) )
```

Result

\$20,471,328.88

Report Functions

Today

Returns the current system date.

Syntax

Today ()

Now

Returns the current system time.

Syntax

Now ()

AsOfDate

Returns the date value of the AsOfDate expression, if it is defined. Otherwise, AsOfDate returns the report execution date.

Syntax

AsOfDate ()

AsOfTime

Returns the time value of the AsOfTime expression, if it is defined. Otherwise, AsOfTime returns the report execution time.

Syntax

AsOfTime ()

ReportDate

Returns the report execution date and time.

Syntax

ReportDate ()

ReportName

Returns the report name. This function works only when the report is run from IBM® Cognos® Connection. If a saved report view is run, returns the report view name.

Syntax

ReportName ()

ReportPath

Returns the report path. This function works only when the report is run from IBM® Cognos® Connection.

Syntax

ReportPath ()

ReportDescription

Returns the report description. This function works only when the report is run from IBM® Cognos® Connection.

Syntax

ReportDescription ()

ReportLocale

Returns the run locale.

Syntax

ReportLocale ()

GetLocale

Returns the run locale (deprecated).

Syntax

GetLocale ()

Locale

Returns the run locale.

Syntax

Locale ()

ReportProductLocale

Returns the product locale.

Syntax

ReportProductLocale ()

ReportAuthorLocale

Returns the author locale.

Syntax

ReportAuthorLocale ()

ReportSaveDate

Returns the date when the report was last saved.

Syntax

ReportSaveDate ()

ReportCreateDate

Returns the date when the report was created.

Syntax

ReportCreateDate ()

ReportID

Returns the report ID.

Syntax

ReportID ()

ReportOutput

Returns the name of the output format, such as CSV, HTML, HTMLFragment, layoutDataXML, MHT, PDF, rawXML, spreadsheetML (Excel 2007 format), XHTML, xlsxData (Excel 2007 Data format), XLWA (Excel 2002 format), XML, singleXLS (deprecated), XLS (deprecated).

Syntax

ReportOutput ()

ReportOption

Returns the value of the run option variable identified by "optionName", such as attachmentEncoding, burst, cssURL, email, emailAsAttachment, emailAsURL, emailBody, emailSubject, emailTo, emailToAddress, metadataModel, outputEncapsulation, outputFormat, outputLocale, outputPageDefinition, outputPageOrientation, primaryWaitThreshold, print, printer, printerAddress, prompt, promptFormat, saveAs, saveOutput, secondaryWaitThreshold, verticalElements, or xslURL.

Syntax

ReportOption ('optionName')

ServerName

Returns the name of the web server where the run request originated from. The value may be empty if the request is executed from the scheduler.

Syntax

ServerName ()

ServerLocale

Returns the locale of the server that runs the report.

Syntax

ServerLocale ()

ModelPath

Returns the model path.

Syntax

ModelPath ()

BurstKey

Returns the burst key.

Syntax

BurstKey ()

BurstRecipients

Returns the distribution list of burst recipients.

Syntax

BurstRecipients ()

IsBursting

Returns Boolean 1 (true) when the report will be distributed to the recipient; otherwise, returns Boolean 0 (false).

Syntax

IsBursting ('recipientName')

ParamNames

Returns all parameter names.

Syntax

ParamNames ()

ParamName

Returns the parameter name of "parameterName".

Syntax

ParamName ('parameterName')

ParamDisplayValue

Returns a string that is the parameter display value of "parameterName". This function appears in the Recruitment Report sample report in the GO Data Warehouse (analysis) package.

Syntax

ParamDisplayValue ('parameterName')

ParamValue

Returns the parameter value of "parameterName".

Syntax

ParamValue ('parameterName')

ParamCount

Returns the parameter count of "parameterName".

Syntax

```
ParamCount ('parameterName')
```

RowNumber

Returns the current row.

Syntax

```
RowNumber ()
```

PageNumber

Returns the current page number.

Syntax

```
PageNumber ()
```

PageCount

Returns the current page count. This function works only when the report output is Adobe® PDF or Microsoft® Excel. If you save the report output, this function works for all formats.

Syntax

```
PageCount ()
```

IsPageCountAvailable

Returns Boolean 1 (true) if the page count is available for the current execution of the report; otherwise, returns Boolean 0 (false).

Syntax

```
IsPageCountAvailable ()
```

HorizontalPageNumber

Returns the current horizontal page number.

Syntax

```
HorizontalPageNumber ()
```

HorizontalPageCount

Returns the current horizontal page count.

Syntax

```
HorizontalPageCount ()
```

PageName

Returns the current page name.

Syntax

```
PageName ()
```

URLEncode

Returns the URL encoded value of the input text.

Syntax

```
URLEncode ('text')
```

TOCHeadingCount

Returns the table of contents heading count for a specified heading level.

Syntax

```
TOCHeadingCount ( headingLevel )
```

IsAccessible

Returns Boolean 1 (true) if the report is run with the accessibility features enabled. Use this function as a variable expression with a conditional block to make your reports accessible. For example, you can add a list or crosstab equivalent to a chart in reports that are run with accessibility features enabled.

Syntax

```
IsAccessible()
```

IsBooklet

Returns Boolean 1 (true) if the report is a child report of a booklet; otherwise, returns Boolean 0 (false).

Syntax

```
IsBooklet()
```

ColumnNumber

Returns the current column number.

Syntax

```
ColumnNumber ()
```

IsCrosstabRowNodeMember

Returns Boolean 1 (true) if the current node is a crosstab row node member.

Syntax

```
IsCrosstabRowNodeMember ()
```

IsCrosstabColumnNodeMember

Returns Boolean 1 (true) if the current node is a crosstab column node member.

Syntax

```
IsCrosstabColumnNodeMember ()
```

IsInnerMostCrosstabRowNodeMember

Returns Boolean 1 (true) if the current node is an innermost crosstab row node member.

Syntax

`IsInnerMostCrosstabRowNodeMember ()`

IsInnerMostCrosstabColumnNodeMember

Returns Boolean 1 (true) if the current node is an innermost crosstab column node member.

Syntax

`IsInnerMostCrosstabColumnNodeMember ()`

IsOuterMostCrosstabRowNodeMember

Returns Boolean 1 (true) if the current node is an outermost crosstab row node member.

Syntax

`IsOuterMostCrosstabRowNodeMember ()`

IsOuterMostCrosstabColumnNodeMember

Returns Boolean 1 (true) if the current node is an outermost crosstab column node member.

Syntax

`IsOuterMostCrosstabColumnNodeMember ()`

IsFirstColumn

Returns Boolean 1 (true) if the current column is the first column.

Syntax

`IsFirstColumn ()`

IsLastColumn

Returns Boolean 1 (true) if the current column is the last column.

Syntax

`IsLastColumn ()`

IsLastInnerMostCrosstabColumnNodeMember

Returns Boolean 1 (true) if the current node is the last innermost crosstab column node member.

Syntax

`IsLastInnerMostCrosstabColumnNodeMember ()`

IsLastInnerMostCrosstabRowNodeMember

Returns Boolean 1 (true) if the current node is the last innermost crosstab row node member.

Syntax

`IsLastInnerMostCrosstabRowNodeMember ()`

CubeName

Returns the name of the cube. "Dimension" specifies from which cube to retrieve the metadata.

Syntax

CubeName (dimension)

CubeDescription

Returns the description of the cube. "Dimension" specifies from which cube to retrieve the metadata.

Syntax

CubeDescription (dimension)

CubeCreatedOn

Returns the date and time when the cube was created. "Dimension" specifies from which cube to retrieve the metadata. If the dimension source is an IBM® Cognos® PowerCube (.mdc), the function returns a blank string because the initial creation date of a PowerCube is not maintained.

Syntax

CubeCreatedOn (dimension)

CubeDataUpdatedOn

Returns the date time that data in the cube was last updated. "Dimension" specifies from which cube to retrieve the metadata.

Syntax

CubeDataUpdatedOn (dimension)

CubeSchemaUpdatedOn

Returns the date time that the cube schema was last updated. "Dimension" specifies from which cube to retrieve the metadata.

Syntax

CubeSchemaUpdatedOn (dimension)

CubelsOptimized

Returns "true" if the cube is optimized. "Dimension" specifies from which cube to retrieve the metadata.

Syntax

CubeIsOptimized (dimension)

CubeDefaultMeasure

Returns the name of the default measure for the cube. "Dimension" specifies from which cube to retrieve the metadata.

Syntax

CubeDefaultMeasure (dimension)

CubeCurrentPeriod

Returns the current period for the cube. "Dimension" specifies from which cube to retrieve the metadata.

Syntax

```
CubeCurrentPeriod ( dimension )
```

CellValue

Returns the value of the current crosstab cell.

Syntax

```
CellValue ( )
```

InScope

Returns Boolean 1 (true) when the cell is in the scope of the data items and MUNs; otherwise, returns Boolean 0 (false).

Syntax

```
InScope ( dataItem , MUN, ... )
```

Data Type Casting Functions

_add_days

Returns the datetime resulting from adding "integer_expression" days to "timestamp_expression".

Syntax

```
_add_days ( timestamp_expression , integer_expression )
```

Example

```
_add_days ( 2007-01-14 00:00:00.000 , 3 )
```

Result

```
2007-01-17 00:00:00.000
```

_add_months

Returns the datetime resulting from adding "integer_expression" months to "timestamp_expression".

Syntax

```
_add_months ( timestamp_expression , integer_expression )
```

_add_years

Returns the datetime resulting from adding "integer_expression" years to "timestamp_expression".

Syntax

```
_add_years ( timestamp_expression , integer_expression )
```

_age

Returns a number by subtracting "timestamp_expression" from today's date.

Syntax

```
_age ( timestamp_expression )
```

Example

```
_age ([Query1].[Date]), where [Query1].[Date] is March 2, 2004, and  
today is July 8, 2009
```

Result

50,406, where 5 is the number of years, 04 is the number of months, and 06 is the number of days.

_day_of_week

Returns the day of the week (between 1 and 7) for "timestamp_expression" where "integer_expression" indicates which day of that week is day 1. To determine "integer_expression", choose the day of the week and count from Monday; for example, if you choose Wednesday, "integer_expression" would be 3 because Wednesday is the third day from Monday.

Syntax

```
_day_of_week ( timestamp_expression , integer_expression )
```

Example

```
_day_of_week ( 2009-01-01 , 7 ), where 7 means that Sunday is the  
first day of the week.
```

Result

5

_day_of_year

Returns the ordinal for the day of the year in "timestamp_expression" (1 to 366). Also known as Julian day.

Syntax

```
_day_of_year ( timestamp_expression )
```

_days_between

Returns a positive or negative number representing the number of days between "timestamp_expression1" and "timestamp_expression2". If "timestamp_expression1" < "timestamp_expression2", the result will be a negative number.

Syntax

```
_days_between ( timestamp_expression1 , timestamp_expression2 )
```

_days_to_end_of_month

Returns a number representing the number of days remaining in the month represented by "timestamp_expression".

Syntax

`_days_to_end_of_month (timestamp_expression)`

_first_of_month

Returns a datetime that is the first day of the month represented by "timestamp_expression".

Syntax

`_first_of_month (timestamp_expression)`

Example 1

`_first_of_month (2009-05-04 00:00:00.000)`

Result

Returns 2009-05-01 00:00:00.000

Example 2

`_first_of_month (current_date)`

Result

Returns Jul 1, 2009 if the current date is July 30, 2009.

_last_of_month

Returns a datetime that is the last day of the month represented by "timestamp_expression".

Syntax

`_last_of_month (timestamp_expression)`

_make_timestamp

Returns a timestamp constructed from "integer_expression1" (the year), "integer_expression2" (the month), and "integer_expression3" (the day). The time portion defaults to 00:00:00.000 .

Syntax

`_make_timestamp (integer_expression1 , integer_expression2 , integer_expression3)`

_months_between

Returns a positive or negative number representing the number of months between "timestamp_expression1" and "timestamp_expression2". If "timestamp_expression1" < "timestamp_expression2", the result will be a negative number.

Syntax

`_months_between (timestamp_expression1 , timestamp_expression2)`

`_week_of_year`

Returns the week number (1-53) of the year for "timestamp_expression". According to the ISO 8601, week 1 of the year is the first week to contain a Thursday, which is equivalent to the first week containing January 4th. A week starts on a Monday (day 1) and ends on a Sunday (day 7).

Syntax

```
_week_of_year ( timestamp_expression )
```

`_years_between`

Returns a positive or negative integer representing the number of years between "timestamp_expression1" and "timestamp_expression2". If "timestamp_expression1" < "timestamp_expression2", a negative value is returned.

Syntax

```
_years_between ( timestamp_expression1 , timestamp_expression2 )
```

`_ymdint_between`

Returns a number representing the difference between "timestamp_expression1" and "timestamp_expression2". This value has the form YYMMDD, where YY represents the number of years, MM represents the number of months, and DD represents the number of days.

Syntax

```
_ymdint_between ( timestamp_expression1 , timestamp_expression2 )
```

Example

```
_ymdint_between ( [Query1].[Date (close date)] , [Query1].[Date (ship date)] ), where [Query1].[Date (close date)] is February 20, 2004, and [Query1].[Date (ship date)] is January 19, 2004.
```

Result

101, where 1 is the number of months and 01 is the number of days.

`abs`

Returns the absolute value of "numeric_expression". If "numeric_expression" is negative, a positive value is returned.

Syntax

```
abs ( numeric_expression )
```

`ceiling`

Returns the smallest integer that is greater than or equal to "numeric_expression".

Syntax

```
ceiling ( numeric_expression )
```

`character_length`

Returns the number of characters in "string_expression".

Syntax

`character_length (string_expression)`

date2string

Returns a date as a string in YYYY-MM-DD format.

Syntax

`date2string (date_expression)`

date2timestamp

Converts "date_expression" to a timestamp. The time part of the timestamp will equal zero.

Syntax

`date2timestamp (date_expression)`

date2timestampTZ

Converts "date_expression" to a timestamp with a time zone. The time and time zone parts of the timestamp will equal zero.

Syntax

`date2timestampTZ (date_expression)`

DTinterval2string

Returns a date time interval as a string in DDDD HH:MM:SS.FFFFFFFF or -DDDD HH:MM:SS.FFF format.

Syntax

`DTinterval2string (date_time_interval_expression)`

DTinterval2stringAsTime

Returns a date time interval as a string in HHHH:MM:SS.FFFFFFFF or HH:MM:SS.FFF format. Days are converted to hours.

Syntax

`DTinterval2stringAsTime (date_time_interval_expression)`

exp

Returns the constant 'e' raised to the power of "numeric_expression". The constant 'e' is the base of the natural logarithm.

Syntax

`exp (numeric_expression)`

Example

`exp (2)`

Result

7.389056

extract

Returns an integer representing the value of "date_part_expression" in "datetime_expression". "Date_part_expression" could be the year, month, day, hour, minute, or second.

Syntax

```
extract ( date_part_expression , datetime_expression )
```

Example 1

```
extract ( year , 2003-03-03 16:40:15.535 )
```

Result

2003

Example 2

```
extract ( hour , 2003-03-03 16:40:15.535 )
```

Result

16

floor

Returns the largest integer that is less than or equal to "numeric_expression".

Syntax

```
floor ( numeric_expression )
```

int2DTInterval

Converts an integer to a date time interval. "String_expression" specifies what "integer_expression" represents: "ns" = nanoseconds, "s" = seconds (default), "m" = minutes, "h" = hours, "d" = days.

Syntax

```
int2DTInterval ( integer_expression , string_expression )
```

Example 1

```
int2DTInterval (1020,"h")
```

Result

42 days 12 hours

Example 2

```
int2DTInterval (1020,"s")
```

Result

17 minutes

int2YMInterval

Converts "integer_expression" to a year month interval. "String_expression" specifies what "integer_expression" represents: "y" = years, "m" = months (default).

Syntax

```
int2YMininterval ( integer_expression , string_expression )
```

ln

Returns the natural logarithm of "numeric_expression".

Syntax

```
ln ( numeric_expression )
```

lower

Returns "string_expression" with all uppercase characters converted to lowercase. This function appears in the Bursted Sales Performance Report sample report in the GO Data Warehouse (query) package.

Syntax

```
lower ( string_expression )
```

mapNumberToLetter

Adds "integer_expression" to "string_expression".

Syntax

```
mapNumberToLetter ( string_expression , integer_expression )
```

Example

```
mapNumberToLetter ( 'a' , 1 )
```

Result

b

mod

Returns an integer value representing the remainder (modulo) of "integer_expression1" / "integer_expression2".

Syntax

```
mod ( integer_expression1 , integer_expression2 )
```

nullif

Returns null if "string_expression1" equals "string_expression2" (case-insensitive), otherwise returns "string_expression1".

Syntax

```
nullif ( string_expression1 , string_expression2 )
```

number2string

Converts "numeric_expression" to a string, using the %g format specifier (C/C++ syntax).

Syntax

```
number2string ( numeric_expression )
```

octet_length

Returns the number of bytes in "string_expression".

Syntax

```
octet_length ( string_expression )
```

position

Returns the integer value representing the starting position of "string_expression1" in "string_expression2". Returns 0 if "string_expression1" is not found.

Syntax

```
position ( string_expression1 , string_expression2 )
```

power

Returns "numeric_expression1" raised to the power of "numeric_expression2".

Syntax

```
power ( numeric_expression1 , numeric_expression2 )
```

Example

```
power ( 3 , 2 )
```

Result

9

round

Returns "numeric_expression" rounded to the nearest value with "integer_expression" significant digits to the right of the decimal point. If "integer_expression" is negative, "numeric_expression" is rounded to the nearest absolute value with "integer_expression" significant digits to the left of the decimal point. Rounding takes place before data formatting is applied.

Syntax

```
round ( numeric_expression , integer_expression )
```

Example

```
round (125, -1)
```

Result

130

sqrt

Returns the square root of "numeric_expression". "Numeric_expression" must not be a negative value.

Syntax

```
sqrt ( numeric_expression )
```

status

Returns the status of "expression". Possible values are: 0 - OK, 1 - null, 2 - not available, 4 - divide by zero, 8 - overflow, 16 - security, 32 - error, 64 - new, 128 - sample, 256 - pending.

Syntax

```
status ( expression )
```

string2date

Returns "string_expression" as a date in YYYY-MM-DD format.

Syntax

```
string2date ( string_expression )
```

string2double

Returns a floating point number. "String_expression" has the following form: "[whitespace] [sign] [digits] [digits] [{d|D|e|E }[sign]digits]"

Syntax

```
string2double ( string_expression )
```

string2DTinterval

Returns "string_expression" as a date time interval in [-]DD HH:MM[:SS[.FFF]] format.

Syntax

```
string2DTinterval ( string_expression )
```

string2int32

Returns an integer. "String_expression" has the following form: "[whitespace] [{+|-}] [digits]"

Syntax

```
string2int32 ( string_expression )
```

string2int64

Returns a long integer. "String_expression" has the following form: "[whitespace] [{+|-}] [digits]"

Syntax

```
string2int64 ( string_expression )
```

string2time

Returns "string_expression" as a time in HH:MM:SS.FFFFFFFF format.

Syntax

```
string2time ( string_expression )
```

string2timestamp

Returns "string_expression" as a timestamp in YYYY-MM-DD [T|t|[white space]+] HH:MM:SS.FFFFFFFF format.

Syntax

`string2timestamp (string_expression)`

string2timestampTZ

Returns "string_expression" in YYYY-MM-DD HH:MM:SS.FFFFFFFF +HHMM or YYYY-MM-DD [T|t] HH:MM:SS.FFF -HHMM format.

Syntax

`string2timestampTZ (string_expression)`

string2YMinterval

Returns "string_expression" as a Year Month Interval in [-]YY MM format.

Syntax

`string2YMinterval (string_expression)`

substring

Returns the substring of "string_expression" that starts at position "integer_expression1" for "integer_expression2" characters or to the end of "string_expression" if "integer_expression2" is -1. The first character in "string_expression" is at position 1.

Syntax

`substring (string_expression , integer_expression1 , integer_expression2)`

Example

```
substring ( [Sales (analysis)].[Sales staff].[Sales staff].[Sales staff].[Position code], 3 , 5 )
```

Result

Returns characters 3 to 7 of the position codes.

time2string

Returns a time as a string in HH:MM:SS.FFF format.

Syntax

`time2string (time_expression)`

timestamp2date

Converts "timestamp_expression" to a date. The time part of the timestamp will be ignored.

Syntax

`timestamp2date (timestamp_expression)`

timestamp2string

Returns a timestamp as a string in YYYY-MM-DD HH:MM:SS.FFFFFFFF format.

Syntax

`timestamp2string (timestamp_expression)`

timestamp2timestampTZ

Converts "timestamp_expression" to a timestamp with a time zone. The displacement part of the timestamp with the time zone will be zero.

Syntax

```
timestamp2timestampTZ ( timestamp_expression )
```

timestampTZ2date

Converts "timestamp_time_zone_expression" to a date. The time and time zone parts of the timestamp will be ignored.

Syntax

```
timestampTZ2date ( timestamp_time_zone_expression )
```

timestampTZ2string

Returns a timestamp with the time zone as a string in YYYY-MM-DD HH:MM:SS.FFFFFFFF +HHMM or YYYY-MM-DD HH:MM:SS.FFF -HHMM format.

Syntax

```
timestampTZ2string ( timestamp_time_zone_expression )
```

timestampTZ2timestamp

Converts "timestamp_time_zone_expression" to a timestamp. The displacement part of the timestamp with the time zone will be ignored.

Syntax

```
timestampTZ2timestamp ( timestamp_time_zone_expression )
```

timeTZ2string

Returns a time with the time zone as a string in HH:MM:SS.FFF +HHMM or HH:MM:SS.FFFFFFFF -HHMM format. For example, -05:30 means a timezone of GMT minus 5 hours and 30 minutes

Syntax

```
timeTZ2string ( timeTZ_expression )
```

trim

Returns "string_expression" trimmed of any leading and trailing blanks or trimmed of the character specified by "match_character_expression". "Trim_what_expression" may be "leading", "trailing", or "both" (default). "Match_character_expression" can be an empty string to trim blanks or can specify a character to be trimmed.

Syntax

```
trim ( trim_what_expression , match_character_expression ,  
      string_expression )
```

upper

Returns "string_expression" with all lowercase characters converted to uppercase.

Syntax

```
upper ( string_expression )
```

YMinterval2string

Returns "year_month_interval_expression" as a string in (YY MM) or -(YY MM) format.

Syntax

`YMinterval2string (year_month_interval_expression)`

Appendix G. Report Studio Object and Property Reference

This appendix contains definitions of the objects and properties found in IBM Cognos Report Studio. They are available contextually, by pressing F1 when an object or property is active in the Report Studio authoring environment.

Objects

Objects are visible in the Report Studio work area. They can be inserted from the

Toolbox tab  .

Properties

Properties can be set on Report Studio objects. They are available in the lower-left pane of Report Studio.

Data formatting properties

Data formatting properties can be set on data values by selecting **Default Data Format** from the **Data** menu, or by editing the **Data Format** property for Report Studio objects.

Report Studio Objects

The following is a list of objects available in IBM® Cognos® Report Studio.

3-D Area

A chart in which members of a data series are represented by three-dimensional areas of varying size and color. The three-dimensional area chart is one of three chart types that can be included in a three-dimensional combination chart.

Properties of 3-D Area

“Border Color” on page 884, “Borders” on page 885, “Chart Type” on page 891, “Values” on page 994

3-D Bar

A chart in which members of a data series are represented by three-dimensional bars of varying length and color. The three-dimensional bar chart is one of three chart types that can be included in a three-dimensional combination chart.

Properties of 3-D Bar

“Border Color” on page 884, “Borders” on page 885, “Chart Type” on page 891, “Values” on page 994

3-D Combination Chart

A chart that includes any number and combination of three-dimensional bar charts, line charts, and area charts. This chart plots any number of data series against one common measure on the vertical numeric axis and one or two common data series on ordinal axes.

Properties of 3-D Combination Chart

"3-D Viewing Angle" on page 872, "Alternate Text" on page 875, "Application Drill-Through" on page 876, "Background Color" on page 881, "Background Effects" on page 881, "Baselines" on page 883, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Clickable Regions" on page 893, "Conditional Palette" on page 895, "Container Selection" on page 897, "Display for Orientation" on page 908, "Drill-Through Definitions" on page 910, "Margin" on page 932, "Master Detail Relationships" on page 935, "Maximum Hotspots" on page 936, "Name" on page 942, "No Data Contents" on page 945, "Notes" on page 945, "Numerical Axis" on page 947, "Padding" on page 949, "Pagination" on page 950, "Palette" on page 950, "Query" on page 957, "Relative Alignment" on page 959, "Render Page when Empty" on page 960, "Render Variable" on page 961, "Series Color" on page 969, "Set Variable Values" on page 970, "Show Hover" on page 971, "Show Pointer Cursor" on page 972, "Size & Overflow" on page 975, "Suppression" on page 981, "Title" on page 985, "Tooltips" on page 986, "Visible" on page 996, "X Axis" on page 997, "Y Axis" on page 998

3-D Line

A chart in which members of a data series are represented by three-dimensional lines of varying colors. The three-dimensional line chart is one of three chart types that can be included in a three-dimensional combination chart.

Properties of 3-D Line

"Border Color" on page 884, "Borders" on page 885, "Chart Type" on page 891, "Values" on page 994

3-D Scatter Chart

A chart that plots three measures against one or more data series on a three-dimensional X-Y-Z graph.

Properties of 3-D Scatter Chart

"3-D Viewing Angle" on page 872, "Alternate Text" on page 875, "Application Drill-Through" on page 876, "Background Color" on page 881, "Background Effects" on page 881, "Baselines" on page 883, "Border" on page 884, "Border Color" on page 884, "Borders" on page 885, "Box Type" on page 886, "Classes" on page 891, "Clickable Regions" on page 893, "Conditional Palette" on page 895, "Container Selection" on page 897, "Display for Orientation" on page 908, "Drill-Through Definitions" on page 910, "Legend" on page 928, "Margin" on page 932, "Marker Size (pt)" on page 934, "Master Detail Relationships" on page 935, "Maximum Hotspots" on page 936, "Name" on page 942, "No Data Contents" on page 945, "Notes" on page 945, "Padding" on page 949, "Pagination" on page 950, "Palette" on page 950, "Point Shape" on page 953, "Query" on page 957, "Relative Alignment" on page 959, "Render Page when Empty" on page 960, "Render Variable" on page 961, "Set Variable Values" on page 970, "Show Feelers" on page 971, "Show Hover" on page 971, "Show Pointer Cursor" on page 972, "Size &

“Overflow” on page 975, “Suppression” on page 981, “Title” on page 985, “Tooltips” on page 986, “Values” on page 994, “Visible” on page 996

Angular Axis

The angular numeric axis for a polar chart, including labels, titles, range, and scale.

Properties of Angular Axis

“Axis Labels” on page 879, “Axis Line” on page 879, “Axis Title” on page 880, “Axis Title” on page 880, “Classes” on page 891, “Data Format” on page 900, “Gridlines” on page 919, “Include Zero For Auto Scale” on page 923, “Maximum Value” on page 938, “Minimum Value” on page 940, “Minor Gridlines” on page 940, “Scale” on page 967, “Scale Interval” on page 967, “Use Same Range For All Instances” on page 992

Angular Measure

The measure that determines the angular position of each data marker on a polar chart.

Properties of Angular Measure

“Conditional Styles” on page 895, “Custom Label” on page 900, “Data Format” on page 900, “Style Variable” on page 979

Area

The data marker used to represent data series in an area chart.

Properties of Area

“Aggregate Function” on page 873, “Area Shape” on page 877, “Border Color” on page 884, “Borders” on page 885, “Chart Type” on page 890, “Conditional Palette” on page 895, “Expression” on page 913, “Extend Width” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Level” on page 930, “Level Unique Name” on page 930, “Member” on page 938, “Member Unique Name” on page 939, “Palette” on page 951, “Property Unique Name” on page 956, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, “Series Type” on page 969, Set Definition, “Set Sorting” on page 970, “Show Values” on page 973

Area

The data marker used to represent data series in an area chart. This object applies only to legacy charts.

Properties of Area

“Axis Assignment” on page 878, “Border Color” on page 884, “Borders” on page 885, “Chart Type” on page 890, “Grouping Type” on page 920, “Value Location:” on page 993, “Values” on page 994, “Value Type” on page 995

As of Time Expression

An expression that produces a Date-Time value. This expression can be used to show report results for a specific time period that is defined by an expression that you create.

Properties of As of Time Expression

“Report Expression” on page 963

Axis Labels

The labels that appear on an axis.

Properties of Axis Labels

“Auto Font Size” on page 877, “Classes” on page 891, “Conditional Styles” on page 895, “Data Format” on page 900, “Drill-Through Definitions” on page 910, “Font” on page 916, “Foreground Color” on page 917, “Nested Label Display” on page 944, “Render Variable” on page 961, “Text Truncation” on page 984

Axis Title

The title for an axis of the chart. This object applies only to legacy charts.

Properties of Axis Title

“Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Default Title” on page 905, “Master Detail Relationships” on page 935, “Properties” on page 956, “Query” on page 957, “Style Variable” on page 979

Axis Title

The title for an axis of the chart.

Properties of Axis Title

“Auto Font Size” on page 877, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Default Title” on page 905, “Master Detail Relationships” on page 935, “Properties” on page 956, “Query” on page 957, “Render Variable” on page 961

Bar

A chart in which members of a data series are represented by bars of varying length and color.

Properties of Bar

“Aggregate Function” on page 873, “Bar Shape” on page 883, “Bar Width” on page 883, “Bevel” on page 883, “Border Color” on page 884, “Borders” on page 885, “Chart Type” on page 890, “Conditional Palette” on page 895, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Level” on page 930, “Level Unique Name” on page 930, “Member” on page 938, “Member Unique Name” on page 939, “Palette” on page 951, “Property Unique Name” on page 956, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, “Series Type” on page 969, Set Definition, “Set Sorting” on page 970, “Show Values” on page 973

Bar

A chart in which members of a data series are represented by bars of varying length and color. This object applies only to legacy charts.

Properties of Bar

"Axis Assignment" on page 878, *"Border Color"* on page 884, *"Borders"* on page 885, *"Chart Type"* on page 890, *"Connecting Lines"* on page 896, *"Grouping Type"* on page 920, *"Value Location:"* on page 993, *"Values"* on page 994, *"Value Type"* on page 995

Baseline

A baseline to be rendered on a chart.

Properties of Baseline

"Axis Assignment" on page 878, *"Bar, Line, or Area Index"* on page 882, *"Box Type"* on page 886, *"Data Item Value"* on page 903, *"Label"* on page 926, *"Legend Label"* on page 929, *"Line Styles"* on page 931, *"Master Detail Relationships"* on page 935, *"Member Offset (%)"* on page 938, *"Numeric Value"* on page 948, *"Percentile"* on page 952, *"Percent of Axis"* on page 952, *"Position type"* on page 954, *"Properties"* on page 956, *"Query"* on page 957, *"Report Expression"* on page 962, *"Report Expression"* on page 962, *"Standard Deviations"* on page 978

Baseline

A baseline for a polar chart, scatter chart, or bubble chart.

Properties of Baseline

"Axis Assignment" on page 878, *"Data Item Value"* on page 903, *"Label"* on page 926, *"Legend Label"* on page 929, *"Line Styles"* on page 931, *"Master Detail Relationships"* on page 935, *"Numeric Value"* on page 948, *"Percentile"* on page 952, *"Percent of Axis"* on page 952, *"Position type"* on page 954, *"Properties"* on page 956, *"Query"* on page 957, *"Report Expression"* on page 962, *"Standard Deviations"* on page 978

Baseline

A baseline for a three-dimensional combination chart.

Properties of Baseline

"Bar, Line, or Area Index" on page 882, *"Box Type"* on page 886, *"Data Item Value"* on page 903, *"Line Styles"* on page 931, *"Master Detail Relationships"* on page 935, *"Numeric Value"* on page 948, *"Percentile"* on page 952, *"Percent of Axis"* on page 952, *"Position type"* on page 954, *"Properties"* on page 956, *"Query"* on page 957, *"Report Expression"* on page 962, *"Standard Deviations"* on page 978

Baseline

A baseline for a three-dimensional scatter chart.

Properties of Baseline

"Box Type" on page 886, *"Data Item Value"* on page 903, *"Line Styles"* on page 931, *"Master Detail Relationships"* on page 935, *"Numeric Value"* on page 948, *"Percentile"* on page 952, *"Percent of Axis"* on page 952, *"Position type"* on page 954, *"Properties"* on page 956, *"Query"* on page 957, *"Report Expression"* on page 962, *"Standard Deviations"* on page 978

Block

A container into which you can insert other objects.

Properties of Block

“Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Margin” on page 932, “Name” on page 942, “Padding” on page 949, “Render Variable” on page 961, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Visible” on page 996, “White Space” on page 996

Bookmark

A link to another area within the same report. The link can be defined as a static value, a query item, or as the result of a report expression.

Properties of Bookmark

“Data Item Label” on page 902, “Data Item Value” on page 903, “Label” on page 925, “Report Expression” on page 962, “Source Type” on page 977

Bubble Chart

A point chart that plots one or more data series against three measures: a Y-value, an X-value, and a bubble whose relative size represents the third measure. Multiple points are plotted for each category. This object applies only to legacy charts.

To help distinguish values, set the Tooltips property of this object to Yes.

Properties of Bubble Chart

“Alternate Text” on page 875, “Application Drill-Through” on page 876, “Background Color” on page 881, “Background Effects” on page 881, “Baselines” on page 883, “Border” on page 884, “Border Color” on page 884, “Borders” on page 885, “Box Type” on page 886, “Bubble Size” on page 887, “Classes” on page 891, “Clickable Regions” on page 893, “Conditional Palette” on page 895, “Container Selection” on page 897, “Display for Orientation” on page 908, “Drill-Through Definitions” on page 910, “Legend” on page 928, “Margin” on page 932, “Markers” on page 933, “Marker Text Location” on page 935, “Master Detail Relationships” on page 935, “Maximum Hotspots” on page 936, “Name” on page 942, “No Data Contents” on page 945, “Notes” on page 945, “Padding” on page 949, “Pagination” on page 950, “Palette” on page 950, “Point Shape” on page 953, “Query” on page 957, “Regression Line” on page 959, “Relative Alignment” on page 959, “Render Page when Empty” on page 960, “Render Variable” on page 961, “Set Variable Values” on page 970, “Show Hover” on page 971, “Show Pointer Cursor” on page 972, “Size & Overflow” on page 975, “Suppression” on page 981, “Title” on page 985, “Tooltips” on page 986, “Value Location:” on page 993, “Values” on page 994, “Visible” on page 996, “X Axis” on page 997, “Y Axis” on page 998

Bubble Chart

A point chart that plots one or more data series against three measures: a Y-value, an X-value, and a bubble whose relative size represents the third measure. Multiple points are plotted for each category.

To help distinguish values, set the `Tooltips` property of this object to `Yes`.

Properties of Bubble Chart

"Alternate Text" on page 875, *"Application Drill-Through"* on page 876, *"Background Effects"* on page 881, *"Border"* on page 884, *"Box Type"* on page 886, *"Bubble Size"* on page 887, *"Classes"* on page 891, *"Clickable Regions"* on page 893, *"Color by Value"* on page 893, *"Colored Regions"* on page 893, *"Conditional Palette"* on page 895, *"Contained Text Direction"* on page 897, *"Container Selection"* on page 897, *"Direction & Justification"* on page 907, *"Display for Orientation"* on page 908, *"Drill-Through Definitions"* on page 910, *"Drop Shadow"* on page 911, *"Legend"* on page 929, *"Margin"* on page 932, *"Markers"* on page 934, *"Master Detail Relationships"* on page 935, *"Material Effects"* on page 935, *"Matrix Rows and Columns"* on page 936, *"Maximum Hotspots"* on page 936, *"Name"* on page 942, *"No Data Contents"* on page 945, *"Notes"* on page 946, *"Numeric Baselines"* on page 948, *"Padding"* on page 949, *"Pagination"* on page 950, *"Palette"* on page 951, *"Plot Area Fill"* on page 953, *"Query"* on page 957, *"Relative Alignment"* on page 959, *"Render Page when Empty"* on page 960, *"Render Variable"* on page 961, *"Set Variable Values"* on page 970, *"Show Hover"* on page 971, *"Show Pointer Cursor"* on page 972, *"Show Values"* on page 974, *"Size & Overflow"* on page 975, *"Suppression"* on page 981, *"Title"* on page 985, *"Tooltips"* on page 986, *"Trendlines"* on page 988, *"Visible"* on page 996

Bubble Measure

The measure that determines the size of each bubble on a bubble chart.

Properties of Bubble Measure

"Conditional Styles" on page 895, *"Custom Label"* on page 900, *"Data Format"* on page 900

Bubble Measure

The measure that determines the size of each bubble on a bubble chart. This object applies only to legacy charts.

Properties of Bubble Measure

"Conditional Styles" on page 895, *"Custom Label"* on page 900, *"Data Format"* on page 900, *"Style Variable"* on page 979

Bullet Chart

A chart that compares a measure to a target. Use the `Colored Regions` property to relate the compared measures against additional qualitative measurements, such as colored regions for good, satisfactory, and poor.

Properties of Bullet Chart

"Alternate Text" on page 875, *"Application Drill-Through"* on page 876, *"Background Effects"* on page 881, *"Bevel"* on page 883, *"Border"* on page 884,

“Box Type” on page 886, “Bullet Indicators” on page 887, “Chart Orientation” on page 890, “Classes” on page 891, “Clickable Regions” on page 893, “Colored Regions” on page 893, “Contained Text Direction” on page 897, “Container Selection” on page 897, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Drill-Through Definitions” on page 910, “Drop Shadow” on page 911, “Legend” on page 929, “Margin” on page 932, “Master Detail Relationships” on page 935, “Matrix Rows and Columns” on page 936, “Maximum Hotspots” on page 936, “Name” on page 942, “No Data Contents” on page 945, “Notes” on page 946, “Padding” on page 949, “Pagination” on page 950, “Query” on page 957, “Relative Alignment” on page 959, “Render Page when Empty” on page 960, “Render Variable” on page 961, “Set Variable Values” on page 970, “Show Hover” on page 971, “Show Pointer Cursor” on page 972, “Size & Overflow” on page 975, “Suppression” on page 981, “Title” on page 985, “Tooltips” on page 986, “Visible” on page 996

Bullet Measure

The measure that determines the size of the bullet for a bullet chart.

Properties of Bullet Measure

“Custom Label” on page 900, “Data Format” on page 900

Button

A button in a static button bar control.

Properties of Button

“Icon” on page 923, “Label” on page 926

Button

A single static button control. The button requires a row in the data table of the control.

Properties of Button

“Application Drill-Through” on page 876, “Button Definition” on page 887, “Contained Text Direction” on page 897, “Control Enable” on page 899, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Icon” on page 923, “Label” on page 926, “Name” on page 942, “Render Variable” on page 961, “Set Variable Values” on page 970, “Size” on page 974

Button Bar

A static button bar control. Each button requires a corresponding row in the data table of the control.

Properties of Button Bar

“Application Drill-Through” on page 876, “Button Gap” on page 887, “Buttons Definition” on page 887, “Button Width” on page 888, “Contained Text Direction” on page 897, “Container Selection” on page 897, “Control Enable” on page 899, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Name” on page 942, “Orientation” on page 948, “Render Variable” on page 961, “Set Variable Values” on page 970

Button Label

The label used to identify each button in a data button bar control. Each label is determined by the data items inserted into the control.

Properties of Button Label

“Data Format” on page 900

Calculated Measure

A data item that is a calculated member.

Properties of Calculated Measure

“Calculation Intersection” on page 888, “Dimension” on page 907, “Expression” on page 913, “Label” on page 926, “Name” on page 941, “Solve Order” on page 976, “Type” on page 989

Calculated Member

An item, within a dimension, that represents an occurrence of schema data defined as a calculation of two or more members.

Properties of Calculated Member

“Caption” on page 888, “Data Item” on page 902, “Name” on page 944

Calculated Member

A data item that is a calculated member.

Properties of Calculated Member

“Calculation Intersection” on page 888, “Detail” on page 906, “Dimension” on page 907, “Expression” on page 913, “Hierarchy” on page 921, “Label” on page 926, “Name” on page 941, “Solve Order” on page 976, “Type” on page 989

Caption

The caption on a Field Set object.

Properties of Caption

“Background Color” on page 881, “Border” on page 884, “Classes” on page 891, “Conditional Styles” on page 895, “Font” on page 916, “Foreground Color” on page 917, “Margin” on page 932, “Padding” on page 949, “Style Variable” on page 979

Card

A card in a static deck control.

Properties of Card

“Current Card” on page 900

Category

A category that is used to plot data in a visualization.

Properties of Category

“Category Range” on page 890, *“Empty Item Label”* on page 911, *“Label”* on page 926

Category Axis

The axis line for an ordinal, or non-numeric, axis. This object applies only to legacy charts.

Properties of Category Axis

“Allow 45° Rotation” on page 874, *“Allow 90° Rotation”* on page 874, *“Allow Skip”* on page 874, *“Allow Stagger”* on page 874, *“Axis Labels”* on page 879, *“Axis Line”* on page 879, *“Axis Title”* on page 880, *“Axis Title”* on page 880, *“Classes”* on page 891, *“Display Frequency”* on page 909, *“Drill-Through Definitions”* on page 910, *“First Label Index”* on page 915, *“Gridlines”* on page 919, *“Label Control”* on page 927, *“Maximum Truncation Characters”* on page 937, *“Minor Gridlines”* on page 940, *“Truncation”* on page 988, *“Truncation Text”* on page 988

Category axis

The axis line for an ordinal, or non-numeric, axis.

Properties of Category axis

“Axis Labels” on page 879, *“Axis Line”* on page 879, *“Axis Title”* on page 880, *“Axis Title”* on page 880, *“Display Frequency”* on page 909, *“First Label Index”* on page 915, *“Gridlines”* on page 919, *“Label Control”* on page 927, *“Minor Gridlines”* on page 940, *“Number of Minor Intervals”* on page 946, *“Number of Stagger Levels”* on page 947, *“Reverse Category Order”* on page 964, *“Rotation Angle”* on page 966

Category Baseline

A baseline for the category in a chart.

Properties of Category Baseline

“Aggregate Function” on page 873, *“Category Baselines”* on page 889, *“Expression”* on page 913, *“Hierarchy”* on page 921, *“Hierarchy Unique Name”* on page 921, *“Level”* on page 930, *“Level Unique Name”* on page 930, *“Line Style”* on page 931, *“Master Detail Relationships”* on page 935, *“Member”* on page 938, *“Member Offset (%)”* on page 938, *“Member Unique Name”* on page 939, *“Properties”* on page 956, *“Property Unique Name”* on page 956, *“Query”* on page 957, *“Render Variable”* on page 961, *“Rollup Aggregate Function”* on page 965, *“Root Members Only”* on page 966, *Set Definition*, *“Set Sorting”* on page 970

Chart Body

Defines the body style of the chart itself. The style of the body can be set independently of the chart itself. This object applies only to legacy charts.

Properties of Chart Body

“Background Color” on page 881, “Conditional Styles” on page 895, “Fill Effects” on page 914, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Style Variable” on page 979

Chart Body

Defines the body style of the chart itself. The style of the body can be set independently of the chart itself.

Properties of Chart Body

“Background Color” on page 881, “Background Effects” on page 881, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922

Chart Footer

A footer for the chart. This object applies only to legacy charts.

Properties of Chart Footer

“Background Effects” on page 881, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Horizontal Alignment” on page 922, “Master Detail Relationships” on page 935, “Properties” on page 956, “Query” on page 957, “Style Variable” on page 979

Chart Footer

A footer for the chart.

Properties of Chart Footer

“Background Effects” on page 881, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Horizontal Alignment” on page 922, “Master Detail Relationships” on page 935, “Properties” on page 956, “Query” on page 957, “Render Variable” on page 961

Chart Measure

The measure for the chart.

Properties of Chart Measure

“Conditional Styles” on page 895, “Custom Label” on page 900, “Data Format” on page 900

Chart Node Member

A data item, and its accompanying text, to render on the chart.

Properties of Chart Node Member

“Aggregate Function” on page 873, “Custom Label” on page 900, “Data Format” on page 900, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Level” on page 930, “Level Unique Name” on page 930, “Member” on page 938, “Member Unique Name” on page 939, “Properties” on page 956, “Property Unique Name” on page 956, “Rollup Aggregate Function” on page 965

on page 962, “Root Members Only” on page 966, Set Definition, “Set Sorting” on page 970, “Sorting” on page 976

Chart Subtitle

The subtitle for a chart. This object applies only to legacy charts.

Properties of Chart Subtitle

“Background Effects” on page 881, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Horizontal Alignment” on page 922, “Master Detail Relationships” on page 935, “Properties” on page 956, “Query” on page 957, “Style Variable” on page 979

Chart Subtitle

The subtitle for a chart.

Properties of Chart Subtitle

“Background Effects” on page 881, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Horizontal Alignment” on page 922, “Master Detail Relationships” on page 935, “Properties” on page 956, “Query” on page 957, “Render Variable” on page 961

Chart Text Item

The data source and format for a text item, such as a legend item, legend title, axis label, or axis title. This object applies only to legacy charts.

Properties of Chart Text Item

“Aggregate Function” on page 873, “Conditional Styles” on page 895, “Control Data Item Value” on page 898, “Data Format” on page 900, “Data Item Label” on page 902, “Data Item Value” on page 902, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Level” on page 930, “Level Unique Name” on page 930, “Member” on page 938, “Member Unique Name” on page 939, “Property Unique Name” on page 956, “Report Expression” on page 962, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, Set Definition, “Set Sorting” on page 970, “Source Type” on page 976, “Style Variable” on page 979, “Text” on page 983, “Text Source Variable” on page 984

Chart Text Item

The data source and format for a text item, such as a legend item, legend title, axis label, or axis title.

Properties of Chart Text Item

“Aggregate Function” on page 873, “Conditional Styles” on page 895, “Control Data Item Value” on page 898, “Data Format” on page 900, “Data Item Label” on page 902, “Data Item Value” on page 902, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Level” on page 930, “Level Unique Name” on page 930, “Member” on page 938, “Member Unique Name” on page 939, “Property Unique Name” on page 956, “Render Variable” on page 961, “Report Expression” on page 962, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, Set Definition, “Set Sorting” on page 970, “Source Type” on page 976, “Text” on page 983, “Text Source Variable” on page 984

Chart Title

The title text that appears at the top of the chart. This object applies only to legacy charts.

Properties of Chart Title

“Background Effects” on page 881, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Horizontal Alignment” on page 922, “Master Detail Relationships” on page 935, “Properties” on page 956, “Query” on page 957, “Style Variable” on page 979

Chart Title

The title text that appears at the top of the chart.

Properties of Chart Title

“Background Effects” on page 881, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Horizontal Alignment” on page 922, “Master Detail Relationships” on page 935, “Properties” on page 956, “Query” on page 957, “Render Variable” on page 961

Check Box

A check box in a static check box group control.

Properties of Check Box

“Icon” on page 923, “Label” on page 926

Check Box Group

A static check box group control. Each check box requires a corresponding row in the data table of the control.

Properties of Check Box Group

“Application Drill-Through” on page 876, “Check Boxes Definition” on page 891, “Contained Text Direction” on page 897, “Container Filter” on page 897, “Container Selection” on page 897, “Control Enable” on page 899, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Name” on page 942, “Orientation” on page 948, “Render Variable” on page 961, “Set Variable Values” on page 970, “Text Color” on page 983

Check Box Label

The label used to identify a check box in a data check box group control. The label is determined by the data items inserted into the control.

Properties of Check Box Label

“Data Format” on page 900

Class

The HTML class name for a layout object. Use this attribute to indicate the type of styling to apply to the object when the report is rendered.

Properties of Class

“Background Effects” on page 881, “Description” on page 906, “Inherited Style” on page 924, “Label” on page 925, “Label” on page 925

Color by Value Measure

The measure or value used to determine the color of the points in a scatter or bubble chart. The points are colored according to the range of the data item instead of using the palette.

Properties of Color by Value Measure

“Color by Value” on page 893, “Conditional Styles” on page 895, “Custom Label” on page 900, “Data Format” on page 900

Colored Region

Defines a collection of colored regions, which are rectangles drawn in the chart body to highlight parts of the chart. The regions are drawn behind the data markers and in the same order that they appear in this element. The first region is drawn first, on the bottom, and the last region is drawn on top of the other regions.

Properties of Colored Region

“Aggregate Function” on page 873, “End Position” on page 912, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Level” on page 930, “Level Unique Name” on page 930, “Master Detail Relationships” on page 935, “Member” on page 938, “Member Unique Name” on page 939, “Properties” on page 956, “Property Unique Name” on page 956, “Query” on page 957, “Render Variable” on page 961, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, Set Definition, “Set Sorting” on page 970, “Start Position” on page 979

Colored Region

Defines a collection of colored regions, which are rectangles drawn in the chart body to highlight parts of the chart. The regions are drawn behind the data markers and in the same order that they appear in this element. The first region is drawn first, on the bottom, and the last region is drawn on top of the other regions.

Properties of Colored Region

“Aggregate Function” on page 873, “Bottom Position” on page 885, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Left Position” on page 928, “Level” on page 930, “Level Unique Name” on page 930, “Master Detail Relationships” on page 935, “Member” on page 938, “Member Unique Name” on page 939, “Properties” on page 956, “Property Unique Name” on page 956, “Query” on page 957, “Render Variable” on page 961, “Right Position” on page 964, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, Set Definition, “Set Sorting” on page 970, “Top Position” on page 987

Combination Chart

A chart that uses combinations of column charts, area charts, and line charts as data markers to plot multiple data series. This object applies only to legacy charts.

Properties of Combination Chart

"Alternate Text" on page 875, *"Application Drill-Through"* on page 876, *"Background Color"* on page 881, *"Background Effects"* on page 881, *"Baselines"* on page 883, *"Border"* on page 884, *"Box Type"* on page 886, *"Category Axis"* on page 889, *"Chart Orientation"* on page 890, *"Classes"* on page 891, *"Clickable Regions"* on page 893, *"Conditional Palette"* on page 895, *"Container Selection"* on page 897, *"Depth"* on page 906, *"Display for Orientation"* on page 908, *"Drill-Through Definitions"* on page 910, *"Legend"* on page 928, *"Margin"* on page 932, *"Markers"* on page 933, *"Marker Text Location"* on page 935, *"Master Detail Relationships"* on page 935, *"Maximum Hotspots"* on page 936, *"Name"* on page 942, *"No Data Contents"* on page 945, *"Notes"* on page 945, *"Padding"* on page 949, *"Pagination"* on page 950, *"Palette"* on page 950, *"Query"* on page 957, *"Relative Alignment"* on page 959, *"Render Page when Empty"* on page 960, *"Render Variable"* on page 961, *"Rotate Values"* on page 966, *"Series Color"* on page 969, *"Set Variable Values"* on page 970, *"Show Hover"* on page 971, *"Show Pointer Cursor"* on page 972, *"Size & Overflow"* on page 975, *"Suppression"* on page 981, *"Title"* on page 985, *"Tooltips"* on page 986, *"Value Location:"* on page 993, *"Visible"* on page 996, *"Visual Angle"* on page 996, *"Y1 Axis"* on page 998, *"Y2 Axis"* on page 998, *"Y2 Axis Position"* on page 998

Combination Chart

A chart that uses combinations of column charts, area charts, and line charts as data markers to plot multiple data series.

Properties of Combination Chart

"Alternate Text" on page 875, *"Application Drill-Through"* on page 876, *"Background Effects"* on page 881, *"Border"* on page 884, *"Box Type"* on page 886, *"Category Baselines"* on page 889, *"Chart Orientation"* on page 890, *"Classes"* on page 891, *"Clickable Regions"* on page 893, *"Colored Regions"* on page 893, *"Combinations"* on page 895, *"Contained Text Direction"* on page 897, *"Container Selection"* on page 897, *"Depth"* on page 906, *"Direction & Justification"* on page 907, *"Display for Orientation"* on page 908, *"Drill-Through Definitions"* on page 910, *"Drop Shadow"* on page 911, *"Legend"* on page 929, *"Margin"* on page 932, *"Markers"* on page 934, *"Master Detail Relationships"* on page 935, *"Material Effects"* on page 935, *"Matrix Rows and Columns"* on page 936, *"Maximum Hotspots"* on page 936, *"Name"* on page 942, *"No Data Contents"* on page 945, *"Notes"* on page 946, *"Numeric Baselines"* on page 948, *"Padding"* on page 949, *"Pagination"* on page 950, *"Plot Area Fill"* on page 953, *"Query"* on page 957, *"Relative Alignment"* on page 959, *"Render Page when Empty"* on page 960, *"Render Variable"* on page 961, *"Series Color"* on page 969, *"Set Variable Values"* on page 970, *"Show Hover"* on page 971, *"Show Pointer Cursor"* on page 972, *"Size & Overflow"* on page 975, *"Summarize Small Items"* on page 980, *"Suppression"* on page 981, *"Title"* on page 985, *"Tooltips"* on page 986, *"Trendlines"* on page 988, *"Visible"* on page 996

Component Override

Overrides a child object of the Layout Component Reference object.

Properties of Component Override

“Component Reference” on page 895

Conditional Block

A block that can be used for conditional display.

Properties of Conditional Block

“Background Color” on page 881, “Background Effects” on page 881, “Block Variable” on page 883, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Current Block” on page 900, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Margin” on page 932, “Padding” on page 949, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Visible” on page 996, “White Space” on page 996

Conditional Block

Contains the default set of layout objects to render based on a report variable.

Properties of Conditional Block

“Background Color” on page 881, “Background Effects” on page 881, “Block Variable” on page 883, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Current Block” on page 900, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Margin” on page 932, “Padding” on page 949, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Visible” on page 996, “White Space” on page 996

Context Item Text

The text associated with a context area item.

Properties of Context Item Text

“Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Font” on page 916, “Foreground Color” on page 917, “Margin” on page 932, “Padding” on page 949, “Relative Alignment” on page 959, “Render Variable” on page 961, “Separator” on page 969, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Visible” on page 996

Continuous Values Slider

A slider control that allows users to slide through numeric values between minimum and maximum values that you define, such as 0 and 100.

Properties of Continuous Values Slider

“Animate” on page 875, “Application Drill-Through” on page 876, “Contained Text Direction” on page 897, “Control Enable” on page 899, “Data Format” on page 901, “Direction & Justification” on page 907, “Display for Orientation” on page 908,

“Label Color” on page 927, “Maximum Value” on page 938, “Minimum Value” on page 940, “Name” on page 942, “Orientation” on page 948, “Range Type” on page 959, “Render Variable” on page 961, “Reverse” on page 964, “Set Variable Values” on page 970, “Show Tooltip” on page 973, “Step” on page 979, “Tick Interval” on page 984, “Tick Label Skip Interval” on page 985, “Tick Type” on page 985, “Track Length” on page 988, “Update Variables Live” on page 989, “Variable” on page 995, “Variable for Maximum” on page 995, “Variable for Minimum” on page 995

Crosstab

A layout object used to render the results of a query that aggregates data, and then arranges it in a two-dimensional grid.

Properties of Crosstab

“Application Drill-Through” on page 876, “Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Clickable Regions” on page 893, “Conditional Styles” on page 895, “Container Filter” on page 897, “Container Selection” on page 897, “Default Measure” on page 905, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Drop Shadow” on page 911, “Fact Cells Precedence” on page 914, “Font” on page 916, “Foreground Color” on page 917, “Has Fact Cells” on page 920, “Horizontal Alignment” on page 922, “Layout Table” on page 928, “Margin” on page 932, “Master Detail Relationships” on page 935, “Name” on page 942, “No Data Contents” on page 945, “Pagination” on page 950, “Query” on page 957, “Relative Alignment” on page 959, “Render Page when Empty” on page 960, “Render Variable” on page 961, “Rows Per Page” on page 967, “Set Variable Values” on page 970, “Show Hover” on page 971, “Show Pointer Cursor” on page 972, “Size & Overflow” on page 974, “Style Variable” on page 979, “Summary Text” on page 981, “Suppression” on page 981, “Table Properties” on page 982, “Visible” on page 996

Crosstab Columns

Overrides the style for Crosstab Column Member objects that is defined in the GlobalReportStyles.css file.

Properties of Crosstab Columns

“Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Padding” on page 949, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Vertical Alignment” on page 995, “White Space” on page 996

Crosstab Columns

A list of columns in a crosstab.

Properties of Crosstab Columns

“Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Padding” on page 949

on page 947, "Size & Overflow" on page 974, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Vertical Alignment" on page 995, "White Space" on page 996

Crosstab Corner

The top-left corner of a crosstab, on top of the row labels and to the left of the column labels. It is generally used to represent crosstab members.

Properties of Crosstab Corner

"Aggregate Function" on page 873, "Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Conditional Styles" on page 895, "Data Format" on page 900, "Direction & Justification" on page 907, "Expression" on page 913, "Font" on page 916, "Foreground Color" on page 917, "Hierarchy" on page 921, "Hierarchy Unique Name" on page 921, "Horizontal Alignment" on page 922, "Level" on page 930, "Level Unique Name" on page 930, "Member" on page 938, "Member Unique Name" on page 939, "Padding" on page 949, "Property Unique Name" on page 956, "Rollup Aggregate Function" on page 965, "Root Members Only" on page 966, Set Definition, "Set Sorting" on page 970, "Size & Overflow" on page 974, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Vertical Alignment" on page 995, "White Space" on page 996

Crosstab Fact Cells

The contents of the fact cells of the crosstab. There is only one fact cell definition for the crosstab, regardless of the number of measures.

Properties of Crosstab Fact Cells

"Aggregate Function" on page 873, "Apply Single Class" on page 876, "Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Clickable Region" on page 892, "Conditional Styles" on page 895, "Data Format" on page 900, "Direction & Justification" on page 907, "Drill-Through Definitions" on page 910, "Expression" on page 913, "Font" on page 916, "Foreground Color" on page 917, "Hierarchy" on page 921, "Hierarchy Unique Name" on page 921, "Horizontal Alignment" on page 922, "Level" on page 930, "Level Unique Name" on page 930, "Member" on page 938, "Member Unique Name" on page 939, "Padding" on page 949, "Property Unique Name" on page 956, "Rollup Aggregate Function" on page 965, "Root Members Only" on page 966, Set Definition, "Set Sorting" on page 970, "Size & Overflow" on page 974, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Vertical Alignment" on page 995, "White Space" on page 996

Crosstab Intersection

An intersection in a crosstab. The cell contents of a specific intersection can be overridden and the style defined.

Properties of Crosstab Intersection

"Aggregate Function" on page 873, "Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Clickable Region" on page 892, "Column Coordinate" on page 894, "Conditional Styles" on page 895, "Data Format" on page 900, "Define Contents" on page 905

on page 902, "Direction & Justification" on page 907, "Drill-Through Definitions" on page 910, "Expression" on page 913, "Font" on page 916, "Foreground Color" on page 917, "Hierarchy" on page 921, "Hierarchy Unique Name" on page 921, "Horizontal Alignment" on page 922, "Level" on page 930, "Level Unique Name" on page 930, "Member" on page 938, "Member Unique Name" on page 939, "Padding" on page 949, "Property Unique Name" on page 956, "Rollup Aggregate Function" on page 965, "Root Members Only" on page 966, "Row Coordinate" on page 966, Set Definition, "Set Sorting" on page 970, "Size & Overflow" on page 974, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Vertical Alignment" on page 995, "White Space" on page 996

Crosstab Member Fact Cells

The contents of the fact cells of a crosstab node member.

Properties of Crosstab Member Fact Cells

"Aggregate Function" on page 873, "Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Clickable Region" on page 892, "Conditional Styles" on page 895, "Data Format" on page 900, "Define Contents" on page 905, "Direction & Justification" on page 907, "Drill-Through Definitions" on page 910, "Expression" on page 913, "Font" on page 916, "Foreground Color" on page 917, "Hierarchy" on page 921, "Hierarchy Unique Name" on page 921, "Horizontal Alignment" on page 922, "Level" on page 930, "Level Unique Name" on page 930, "Member" on page 938, "Member Unique Name" on page 939, "Padding" on page 949, "Property Unique Name" on page 956, "Rollup Aggregate Function" on page 965, "Root Members Only" on page 966, Set Definition, "Set Sorting" on page 970, "Size & Overflow" on page 974, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Vertical Alignment" on page 995, "White Space" on page 996

Crosstab Node Member

A member in the crosstab node.

Properties of Crosstab Node Member

"Aggregate Function" on page 873, "Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Clickable Region" on page 892, "Conditional Styles" on page 895, "Data Format" on page 900, "Direction & Justification" on page 907, "Drill-Through Definitions" on page 910, "Expression" on page 913, "Font" on page 916, "Foreground Color" on page 917, "Hierarchy" on page 921, "Hierarchy Unique Name" on page 921, "Horizontal Alignment" on page 922, "Level" on page 930, "Level Indentation" on page 930, "Level Unique Name" on page 930, "Member" on page 938, "Member Unique Name" on page 939, "Node Coordinate" on page 945, "Padding" on page 949, "Pagination" on page 950, "Properties" on page 956, "Property Unique Name" on page 956, "Rollup Aggregate Function" on page 965, "Root Members Only" on page 966, Set Definition, "Set Sorting" on page 970, "Size & Overflow" on page 974, "Sorting" on page 976, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Vertical Alignment" on page 995, "Visible" on page 995, "White Space" on page 996

Crosstab Rows

Overrides the style for Crosstab Row Member objects that is defined in the GlobalReportStyles.css file.

Properties of Crosstab Rows

"Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Conditional Styles" on page 895, "Data Format" on page 900, "Direction & Justification" on page 907, "Font" on page 916, "Foreground Color" on page 917, "Horizontal Alignment" on page 922, "Padding" on page 949, "Size & Overflow" on page 974, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Vertical Alignment" on page 995, "White Space" on page 996

Crosstab Rows

A list of rows in a crosstab.

Properties of Crosstab Rows

"Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Conditional Styles" on page 895, "Data Format" on page 900, "Direction & Justification" on page 907, "Font" on page 916, "Foreground Color" on page 917, "Horizontal Alignment" on page 922, "Padding" on page 949, "Size & Overflow" on page 974, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Vertical Alignment" on page 995, "White Space" on page 996

Crosstab Space

Inserts an empty cell on a crosstab edge. Allows for the insertion of non-data cells on an edge.

Properties of Crosstab Space

"Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Clickable Region" on page 892, "Conditional Styles" on page 895, "Data Format" on page 900, "Direction & Justification" on page 907, "Drill-Through Definitions" on page 910, "Font" on page 916, "Foreground Color" on page 917, "Horizontal Alignment" on page 922, "Node Coordinate" on page 945, "Padding" on page 949, "Pagination" on page 950, "Render Fact Cells" on page 960, "Size & Overflow" on page 974, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Vertical Alignment" on page 995, "Visible" on page 995, "White Space" on page 996

Crosstab Summary

The crosstab summary that appears in executed active reports.

Properties of Crosstab Summary

"Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Clickable Region" on page 892, "Conditional Styles" on page 895, "Data Format" on page 900, "Data Item" on page 901, "Direction & Justification" on page 907, "Font" on page 916, "Foreground Color" on page 917, "Horizontal Alignment" on page 922, "Node Coordinate" on page 945, "Output Aggregation Method" on page 949, "Padding" on page 949, "Size & Overflow" on page 974, "Solve Order" on page 976, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Vertical Alignment" on page 995, "Visible" on page 995, "White Space" on page 996

Cumulation Label

A label that is rendered for the cumulation line in a Pareto chart.

Properties of Cumulation Label

“Conditional Styles” on page 895, *“Data Format”* on page 900, *“Properties”* on page 956, *“Query”* on page 957

Cumulation Line

The cumulation line in a Pareto chart.

Properties of Cumulation Line

“Axis Labels” on page 879, *“Axis Line”* on page 879, *“Axis Range”* on page 880, *“Axis Title”* on page 880, *“Axis Title”* on page 880, *“Gridlines”* on page 919, *“Minor Gridlines”* on page 940, *“Number of Minor Intervals”* on page 946

Cumulation Line

A line that shows the cumulative effect of multiple series members on a measure in a Pareto chart. This object applies only to legacy charts.

Properties of Cumulation Line

“Cumulation Axis” on page 899, *“Cumulation Label”* on page 899, *“Line Styles”* on page 931, *“Marker Shape”* on page 934, *“Marker Size (pt)”* on page 934, *“Properties”* on page 956, *“Value Location:”* on page 993, *“Values”* on page 994

Cumulation Line

A line that shows the cumulative effect of multiple series members on a measure in a Pareto chart.

Properties of Cumulation Line

“Cumulation Label” on page 899, *“Data Points”* on page 904, *“Line Style”* on page 931, *“Show Values”* on page 974

Cumulation Line Axis

The axis for the cumulation line in a Pareto chart.

Properties of Cumulation Line Axis

“Axis Labels” on page 879, *“Axis Line”* on page 879, *“Axis Title”* on page 880, *“Classes”* on page 891, *“Conditional Styles”* on page 895, *“Data Format”* on page 900, *“Font”* on page 916, *“Foreground Color”* on page 917, *“Gridlines”* on page 919, *“Minor Gridlines”* on page 940, *“Scale Interval”* on page 967, *“Style Variable”* on page 979, *“Visible”* on page 996

Cumulation Line Label

A label that is rendered with the cumulation line in a Pareto chart. This object applies only to legacy charts.

Properties of Cumulation Line Label

"Aggregate Function" on page 873, "Control Data Item Value" on page 898, "Data Item Label" on page 902, "Data Item Value" on page 902, "Expression" on page 913, "Hierarchy" on page 921, "Hierarchy Unique Name" on page 921, "Level" on page 930, "Level Unique Name" on page 930, "Member" on page 938, "Member Unique Name" on page 939, "Property Unique Name" on page 956, "Report Expression" on page 962, "Rollup Aggregate Function" on page 965, "Root Members Only" on page 966, Set Definition, "Set Sorting" on page 970, "Source Type" on page 976, "Text" on page 983, "Text Source Variable" on page 984

Custom Groups

A group of data items defined by the report author.

Properties of Custom Groups

"Define Custom Grouping" on page 905, "Label" on page 926, "Name" on page 941, "Type" on page 989

Data Button Bar

A data-driven button bar control. Each button label is determined by the data items inserted into the control.

Properties of Data Button Bar

"Application Drill-Through" on page 876, "Button Gap" on page 887, "Button Width" on page 888, "Contained Text Direction" on page 897, "Container Selection" on page 897, "Control Enable" on page 899, "Direction & Justification" on page 907, "Display for Orientation" on page 908, "Master Detail Relationships" on page 935, "Name" on page 942, "Orientation" on page 948, "Query" on page 957, "Render Variable" on page 961, "Set Variable Values" on page 970, "Sorting" on page 976, "Suppression" on page 981

Data Check Box Group

A data-driven check box group control. Each check box label is determined by the data items inserted into the control.

Properties of Data Check Box Group

"Application Drill-Through" on page 876, "Contained Text Direction" on page 897, "Container Filter" on page 897, "Container Selection" on page 897, "Control Enable" on page 899, "Direction & Justification" on page 907, "Display for Orientation" on page 908, "Master Detail Relationships" on page 935, "Name" on page 942, "Orientation" on page 948, "Query" on page 957, "Render Variable" on page 961, "Set Variable Values" on page 970, "Sorting" on page 976, "Suppression" on page 981, "Text Color" on page 983

Data Container

A set of data that is used to populate a visualization.

Properties of Data Container

"Application Drill-Through" on page 876, "Container Filter" on page 897, "Container Selection" on page 897, "Drill-Through Definitions" on page 910,

"Master Detail Relationships" on page 935, *"Maximum Hotspots"* on page 936, *"Name"* on page 942, *"Nesting Order"* on page 944, *"Query"* on page 957, *"Set Variable Values"* on page 970, *"Show Hover"* on page 972, *"Tooltips"* on page 986

Data Deck

A data-driven deck control. Each card in the deck is determined by the data items inserted into the control.

Properties of Data Deck

"Application Drill-Through" on page 876, *"Container Filter"* on page 897, *"Container Selection"* on page 897, *"Default Card"* on page 904, *"Direction & Justification"* on page 907, *"Display for Orientation"* on page 908, *"Master Detail Relationships"* on page 935, *"Name"* on page 942, *"Query"* on page 957, *"Render Variable"* on page 961, *"Set Variable Values"* on page 970, *"Size"* on page 974, *"Slide Animation Direction"* on page 975, *"Sorting"* on page 976, *"Suppression"* on page 981

Data Discrete Values Slider

A slider control that allows users to slide through discrete values. The values on the slider are determined by the data items inserted in the control.

Properties of Data Discrete Values Slider

"Animate" on page 875, *"Application Drill-Through"* on page 876, *"Contained Text Direction"* on page 897, *"Container Filter"* on page 897, *"Container Selection"* on page 897, *"Control Enable"* on page 899, *"Direction & Justification"* on page 907, *"Display for Orientation"* on page 908, *"Label Color"* on page 927, *"Master Detail Relationships"* on page 935, *"Name"* on page 942, *"Orientation"* on page 948, *"Query"* on page 957, *"Range Type"* on page 959, *"Render Variable"* on page 961, *"Reverse"* on page 964, *"Set Variable Values"* on page 970, *"Show Tooltip"* on page 973, *"Sorting"* on page 976, *"Suppression"* on page 981, *"Tick Interval"* on page 984, *"Tick Label Skip Interval"* on page 985, *"Tick Type"* on page 985, *"Track Length"* on page 988, *"Update Variables Live"* on page 989

Data Drop-Down List

A data-driven drop-down list control. The items that appear in the list are determined by the data items inserted into the control.

Properties of Data Drop-Down List

"Application Drill-Through" on page 876, *"Auto Select"* on page 877, *"Contained Text Direction"* on page 897, *"Container Filter"* on page 897, *"Container Selection"* on page 897, *"Control Enable"* on page 899, *"Direction & Justification"* on page 907, *"Display for Orientation"* on page 908, *"Master Detail Relationships"* on page 935, *"Name"* on page 942, *"No Value List Item"* on page 946, *"Query"* on page 957, *"Render Variable"* on page 961, *"Set Variable Values"* on page 970, *"Show Icon"* on page 972, *"Size"* on page 974, *"Sorting"* on page 976, *"Suppression"* on page 981

Data Item

A set of data values or members.

Properties of Data Item

“Aggregate Function” on page 873, “Calculation Intersection” on page 888, “Detail” on page 906, “Expression” on page 913, “Pre-Sort” on page 955, “Rollup Aggregate Function” on page 965, “Solve Order” on page 976

Data Iterator

A data-driven iterator control that allows users to navigate through values by using buttons such as previous and next. The values on the iterator are determined by the data items inserted in the control.

Properties of Data Iterator

“Application Drill-Through” on page 876, “Contained Text Direction” on page 897, “Container Filter” on page 897, “Container Selection” on page 897, “Control Enable” on page 899, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Iterator First” on page 924, “Iterator Label Area” on page 924, “Iterator Last” on page 924, “Iterator Next” on page 924, “Iterator Previous” on page 925, “Master Detail Relationships” on page 935, “Name” on page 942, “Orientation” on page 948, “Query” on page 957, “Render Variable” on page 961, “Set Variable Values” on page 970, “Sorting” on page 976, “Suppression” on page 981

Data List Box

A data-driven list box control. The items that appear in the list are determined by the data items inserted into the control.

Properties of Data List Box

“Application Drill-Through” on page 876, “Auto Select” on page 877, “Contained Text Direction” on page 897, “Container Filter” on page 897, “Container Selection” on page 897, “Control Enable” on page 899, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Master Detail Relationships” on page 935, “Multi-Select” on page 941, “Name” on page 942, “No Value List Item” on page 946, “Query” on page 957, “Render Variable” on page 961, “Set Variable Values” on page 970, “Size” on page 974, “Sorting” on page 976, “Suppression” on page 981

Data Radio Button Group

A data-driven radio button group control. Each radio button label is determined by the data items inserted into the control.

Properties of Data Radio Button Group

“Application Drill-Through” on page 876, “Auto Select” on page 877, “Contained Text Direction” on page 897, “Container Filter” on page 897, “Container Selection” on page 897, “Control Enable” on page 899, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Master Detail Relationships” on page 935, “Name” on page 942, “Orientation” on page 948, “Query” on page 957, “Render Variable” on page 961, “Set Variable Values” on page 970, “Sorting” on page 976, “Suppression” on page 981, “Text Color” on page 983

Data Tab Control

A data-driven tab control. The label of each tab is determined by the data items inserted into the control.

Properties of Data Tab Control

"Application Drill-Through" on page 876, *"Contained Text Direction"* on page 897, *"Container Selection"* on page 897, *"Direction & Justification"* on page 907, *"Display for Orientation"* on page 908, *"Master Detail Relationships"* on page 935, *"Name"* on page 942, *"Query"* on page 957, *"Render Variable"* on page 961, *"Set Variable Values"* on page 970, *"Size"* on page 974, *"Sorting"* on page 976, *"Suppression"* on page 981, *"Tab Orientation"* on page 982, *"Tab Width"* on page 982

Data Toggle Button Bar

A data-driven toggle button bar control. Each toggle button label is determined by the data items inserted into the control.

Properties of Data Toggle Button Bar

"Application Drill-Through" on page 876, *"Button Gap"* on page 887, *"Button Width"* on page 888, *"Contained Text Direction"* on page 897, *"Container Selection"* on page 897, *"Control Enable"* on page 899, *"Direction & Justification"* on page 907, *"Display for Orientation"* on page 908, *"Master Detail Relationships"* on page 935, *"Name"* on page 942, *"Orientation"* on page 948, *"Query"* on page 957, *"Render Variable"* on page 961, *"Set Variable Values"* on page 970, *"Sorting"* on page 976, *"Suppression"* on page 981

Date

The date when the report runs.

Properties of Date

"Background Color" on page 881, *"Classes"* on page 891, *"Data Format"* on page 900, *"Display for Orientation"* on page 908, *"Font"* on page 916, *"Foreground Color"* on page 917, *"Margin"* on page 932, *"Relative Alignment"* on page 959

Date & Time Prompt

A prompt control with which you can select a date and time value.

Properties of Date & Time Prompt

"Box Type" on page 886, *"Calendar Type"* on page 888, *"Choices Deselect All Text"* on page 891, *"Choices Select All Text"* on page 891, *"Choices Text"* on page 891, *"Clock Mode"* on page 893, *"Conditional Styles"* on page 895, *"Contained Text Direction"* on page 897, *"Default Selections"* on page 905, *"Deselect Text"* on page 906, *"Direction & Justification"* on page 907, *"Display Milliseconds"* on page 909, *"Display Seconds"* on page 909, *"First Date"* on page 915, *"From Text"* on page 917, *"Hide Adornments"* on page 921, *"Highest Value Text"* on page 922, *"Insert Text"* on page 924, *"Last Date"* on page 928, *"Lowest Value Text"* on page 932, *"Multi-Select"* on page 941, *"Name"* on page 942, *"Parameter"* on page 951, *"Range"* on page 958, *"Remove Text"* on page 960, *"Render Variable"* on page 961, *"Required"* on page 963, *"Select UI"* on page 969, *"Style Variable"* on page 979, *"To Text"* on page 987, *"Visible"* on page 996

Date Prompt

A prompt control that allows you to select a date value.

Properties of Date Prompt

"Box Type" on page 886, "Calendar Type" on page 888, "Choices Deselect All Text" on page 891, "Choices Select All Text" on page 891, "Choices Text" on page 891, "Conditional Styles" on page 895, "Contained Text Direction" on page 897, "Default Selections" on page 905, "Deselect Text" on page 906, "Direction & Justification" on page 907, "First Date" on page 915, "From Text" on page 917, "Hide Adornments" on page 921, "Highest Value Text" on page 922, "Insert Text" on page 924, "Last Date" on page 928, "Lowest Value Text" on page 932, "Multi-Select" on page 941, "Name" on page 942, "Parameter" on page 951, "Range" on page 958, "Relative Alignment" on page 959, "Remove Text" on page 960, "Render Variable" on page 961, "Required" on page 963, "Select UI" on page 968, "Style Variable" on page 979, "To Text" on page 987, "Visible" on page 996

Deck

A static deck control. Each card in the deck requires a corresponding row in the data table of the control.

Properties of Deck

"Application Drill-Through" on page 876, "Container Filter" on page 897, "Container Selection" on page 897, "Current Card" on page 900, "Deck Cards Definition" on page 904, "Default Card" on page 904, "Direction & Justification" on page 907, "Display for Orientation" on page 908, "Name" on page 942, "Render Variable" on page 961, "Set Variable Values" on page 970, "Size" on page 974, "Slide Animation Direction" on page 975

Default Measure

A default measure for the chart. If the chart measure cannot be determined by the data series rendered on the chart edges, the default measure is used. This object applies only to legacy charts.

Properties of Default Measure

"Conditional Styles" on page 895, "Custom Label" on page 900, "Data Format" on page 900, "Style Variable" on page 979

Default Measure

A default measure for the chart. If the chart measure cannot be determined by the data series rendered on the chart edges, the default measure is used.

Properties of Default Measure

"Conditional Styles" on page 895, "Custom Label" on page 900, "Data Format" on page 900

Default Measure

When using a dimensional data source, the default measure for the visualization. If the visualization measure cannot be determined by the data series that is rendered on the visualization edges, the default measure is used.

Detail Filter

A set of conditions in a query that narrow the scope of the data returned. A detail filter is applied before aggregation is complete.

Properties of Detail Filter

“Application” on page 875, “Definition” on page 906, “Usage” on page 990

Dimension

A grouping of descriptive information about an aspect of a business. Dimensions contain levels, whose order defines the hierarchy of organizational structures and data. Dimensions and levels are values by which measures can be viewed, filtered, or aggregated.

Properties of Dimension

“Name” on page 943

Dimensional Edge Summary

A summary that appears on the edge of a crosstab. For more information about creating summaries, see the topic Summarizing Data Dimensionally.

Properties of Dimensional Edge Summary

“Aggregate Data Item” on page 873, “Aggregation Method” on page 874, “Calculation Intersection” on page 888, “Dimension” on page 907, “Hierarchy” on page 921, “Label” on page 926, “Name” on page 941, “Solve Order” on page 976, “Type” on page 989, “Use Set Aggregation” on page 992

Discrete Values Slider

A static slider control that allows users to slide through discrete values. Each value in the slider comes from a row in the data table of the control.

Properties of Discrete Values Slider

“Animate” on page 875, “Application Drill-Through” on page 876, “Contained Text Direction” on page 897, “Container Filter” on page 897, “Container Selection” on page 897, “Control Enable” on page 899, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Label Color” on page 927, “Name” on page 942, “Orientation” on page 948, “Range Type” on page 959, “Render Variable” on page 961, “Reverse” on page 964, “Set Variable Values” on page 970, “Show Tooltip” on page 973, “Slider Values Definition” on page 976, “Tick Interval” on page 984, “Tick Label Skip Interval” on page 985, “Tick Type” on page 985, “Track Length” on page 988, “Update Variables Live” on page 989

Display Layer

A map layer that is there for appearance only. Display layers do not correspond to data series or measures.

Properties of Display Layer

“Border Color” on page 884, “Borders” on page 885, “Conditional Styles” on page 895, “Fill Effects” on page 914, “Show Labels” on page 972, “Style Variable” on page 979

Drop-Down List

A static drop-down list control. Each item in the list requires a corresponding row in the data table of the control.

Properties of Drop-Down List

“Application Drill-Through” on page 876, “Auto Select” on page 877, “Contained Text Direction” on page 897, “Container Filter” on page 897, “Container Selection” on page 897, “Control Enable” on page 899, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “List Items Definition” on page 932, “Name” on page 942, “No Value List Item” on page 946, “Render Variable” on page 961, “Set Variable Values” on page 970, “Show Icon” on page 972, “Size” on page 974

Edge Summary

A summary that appears on the edge of a crosstab. For more information about creating summaries, see the topic Summarizing Data Relationally.

Properties of Edge Summary

“Aggregate Data Item” on page 873, “Aggregation Method” on page 874, “Calculation Intersection” on page 888, “Label” on page 926, “Name” on page 941, “Solve Order” on page 976, “Type” on page 989, “Use Set Aggregation” on page 992

Equation Label

An equation label for a trendline that is displayed on a chart.

Properties of Equation Label

“Conditional Styles” on page 895, “Data Format” on page 900

Equation Label

An equation label for a trendline displayed on a chart.

Properties of Equation Label

“Background Effects” on page 881, “Conditional Styles” on page 895, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Position” on page 953

Explicit Member Set

A set of data items that define an explicit set of members.

Properties of Explicit Member Set

“Detail” on page 906, “Dimension” on page 907, “Hierarchy” on page 921, “Label” on page 926, “Members” on page 939, “Name” on page 941, “Set Sorting” on page 970, “Type” on page 989

Extra Category

A data item that is used for filtering or setting variables. The item is not visible in the visualization.

Extra Value

A measure or single value that is used for filtering or setting variables. The item is not visible in the visualization.

Properties of Extra Value

“Use Decimal” on page 990

Fact

The central values that are aggregated and analyzed. Also known as measures, they are special business measurement values, such as sales or inventory levels.

Properties of Fact

“Data Item” on page 902, “Name” on page 943

Field Set

A container with a caption, into which you can insert other objects. It is similar to a block object, except that it also has a caption.

Properties of Field Set

“Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Display for Orientation” on page 908, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Margin” on page 932, “Name” on page 942, “Relative Alignment” on page 959, “Render Variable” on page 961, “Show Caption” on page 971, “Size & Overflow” on page 974, “Style Variable” on page 979, “Visible” on page 996

Gauge Axis

The axis on the face of the gauge that contains gauge indicators, such as data ranges, color ranges, and interval markers.

Properties of Gauge Axis

“Aggregate Function” on page 873, “Axis Angles” on page 878, “Axis Justification” on page 878, “Axis Labels” on page 879, “Axis Line” on page 879, “Axis Range” on page 880, “Axis Title” on page 880, “Conditional Palette” on page 895, “Expression” on page 913, “Gauge Axis Colors” on page 918, “Gauge Axis Inner Radius” on page 918, “Gauge Axis Outer Radius” on page 918, “Gauge Needle” on page 918, “Gridlines” on page 919, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Level” on page 930, “Level Unique Name” on page 930,

"Member" on page 938, *"Member Unique Name"* on page 939, *"Minor Gridlines"* on page 940, *"Number of Minor Intervals"* on page 946, *"Palette"* on page 951, *"Property Unique Name"* on page 956, *"Rollup Aggregate Function"* on page 965, *"Root Members Only"* on page 966, *Set Definition*, *"Set Sorting"* on page 970, *"Text Orientation"* on page 984

Gauge Chart

A chart that plots a data series against a measure using a dial or gauge for the measure, and needles or indicators for the series members.

Properties of Gauge Chart

"Alternate Text" on page 875, *"Application Drill-Through"* on page 876, *"Background Effects"* on page 881, *"Border"* on page 884, *"Box Type"* on page 886, *"Classes"* on page 891, *"Clickable Regions"* on page 893, *"Contained Text Direction"* on page 897, *"Container Selection"* on page 897, *"Dial Face Fill"* on page 907, *"Direction & Justification"* on page 907, *"Display for Orientation"* on page 908, *"Drill-Through Definitions"* on page 910, *"Drop Shadow"* on page 911, *"Gauge Axes"* on page 917, *"Gauge Border"* on page 918, *"Gauge Pivot"* on page 919, *"Legend"* on page 929, *"Margin"* on page 932, *"Master Detail Relationships"* on page 935, *"Matrix Rows and Columns"* on page 936, *"Maximum Hotspots"* on page 936, *"Name"* on page 942, *"No Data Contents"* on page 945, *"Notes"* on page 946, *"Padding"* on page 949, *"Pagination"* on page 950, *"Query"* on page 957, *"Relative Alignment"* on page 959, *"Render Page when Empty"* on page 960, *"Render Variable"* on page 961, *"Set Variable Values"* on page 970, *"Show Hover"* on page 971, *"Show Pointer Cursor"* on page 972, *"Size & Overflow"* on page 975, *"Suppression"* on page 981, *"Title"* on page 985, *"Tooltips"* on page 986, *"Visible"* on page 996

Gauge Chart

A chart that plots a data series against a measure using a dial or gauge for the measure, and needles or indicators for the series members. This object applies only to legacy charts.

Properties of Gauge Chart

"Alternate Text" on page 875, *"Application Drill-Through"* on page 876, *"Axis Title"* on page 880, *"Background Color"* on page 881, *"Background Effects"* on page 881, *"Border"* on page 884, *"Border Color"* on page 884, *"Borders"* on page 885, *"Box Type"* on page 886, *"Classes"* on page 891, *"Clickable Regions"* on page 893, *"Conditional Palette"* on page 895, *"Container Selection"* on page 897, *"Dial Outline Color"* on page 907, *"Display for Orientation"* on page 908, *"Drill-Through Definitions"* on page 910, *"Face Color"* on page 914, *"Gauge Labels"* on page 918, *"Gauge Palette"* on page 918, *"Legend"* on page 928, *"Margin"* on page 932, *"Master Detail Relationships"* on page 935, *"Maximum Hotspots"* on page 936, *"Name"* on page 942, *"No Data Contents"* on page 945, *"Notes"* on page 945, *"Numerical Axis"* on page 947, *"Padding"* on page 949, *"Pagination"* on page 950, *"Palette"* on page 950, *"Query"* on page 957, *"Relative Alignment"* on page 959, *"Render Page when Empty"* on page 960, *"Render Variable"* on page 961, *"Set Variable Values"* on page 970, *"Show Hover"* on page 971, *"Show Pointer Cursor"* on page 972, *"Size & Overflow"* on page 975, *"Suppression"* on page 981, *"Title"* on page 985, *"Tooltips"* on page 986, *"Visible"* on page 996

Gauge Labels

A label for each gauge in a multiple gauge chart.

Properties of Gauge Labels

“Classes” on page 891, “Conditional Styles” on page 895, “Drill-Through Definitions” on page 910, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Maximum Truncation Characters” on page 937, “Style Variable” on page 979, “Truncation” on page 988, “Truncation Text” on page 988, “Visible” on page 996

Gauge Numerical Axis

The numeric axis for the gauge chart, including labels, titles, range, and scale.

Properties of Gauge Numerical Axis

“Conditional Styles” on page 895, “Data Format” on page 900, “Font” on page 916, “Foreground Color” on page 917, “Gridlines” on page 919, “Include Zero For Auto Scale” on page 923, “Maximum Value” on page 938, “Minimum Value” on page 940, “Minor Gridlines” on page 940, “Scale” on page 967, “Scale Interval” on page 967, “Style Variable” on page 979, “Use Same Range For All Instances” on page 992, “Visible” on page 996

Generated Prompt

A control that acts as a placeholder. The report server will replace this control with an appropriate generated prompt control, as if it was on a generated prompt page.

Properties of Generated Prompt

“Hide Adornments” on page 921, “Name” on page 942, “Parameter” on page 951, “Render Variable” on page 961, “Required” on page 963

Hierarchy Set

A set of data items that define the members of a hierarchy.

Properties of Hierarchy Set

“Detail” on page 906, “Dimension” on page 907, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Label” on page 926, “Name” on page 941, “Root Members Only” on page 966, “Set Sorting” on page 970, “Type” on page 989

HTML Item

A container into which you can add HTML, such as a link to a multimedia file. HTML items will only appear when you run the report in HTML format.

When you upgrade to the next version of IBM® Cognos® Business Intelligence, the report upgrade processes do not account for the use of undocumented and unsupported mechanisms or features such as JavaScript that refers to IBM Cognos HTML items.

Properties of HTML Item

“Aggregate Function” on page 873, “Control Data Item Value” on page 898, “Data Item Label” on page 902, “Data Item Value” on page 903, “Description” on page 906, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “HTML” on page 923, “HTML Source Variable” on page 923, “Level” on page 930, “Level Unique Name” on page 930, “Member” on page 938, “Member Unique Name” on page 939, “Name” on page 942, “Property Unique Name” on page 956, “Render Variable” on page 961, “Report Expression” on page 962, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, Set Definition, “Set Sorting” on page 970, “Source Type” on page 977

Hyperlink

A hyperlink that can be defined as a static value, a query item, or as the result of a report expression. If a report expression is used, then the other values are ignored.

Properties of Hyperlink

“Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Control Data Item Value” on page 898, “Control Data Item Value” on page 898, “Data Item Label” on page 902, “Data Item Label” on page 902, “Data Item Value” on page 903, “Data Item Value” on page 902, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Font” on page 916, “Foreground Color” on page 917, “Margin” on page 932, “Name” on page 942, “Padding” on page 949, “Relative Alignment” on page 959, “Render Variable” on page 961, “Report Expression” on page 962, “Report Expression” on page 962, “Size & Overflow” on page 974, “Source Type” on page 977, “Source Type” on page 976, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Text” on page 983, “Text Source Variable” on page 984, “URL” on page 990, “URL Source Variable” on page 990, “Visible” on page 996

Hyperlink Button

A hyperlink that is formatted as a button. The hyperlink can be defined as a static value, a query item, or as the result of a report expression. If a report expression is used, then the other values are ignored.

Properties of Hyperlink Button

“Background Color” on page 881, “Border” on page 884, “Classes” on page 891, “Conditional Styles” on page 895, “Control Data Item Value” on page 898, “Control Data Item Value” on page 898, “Data Item Label” on page 902, “Data Item Label” on page 902, “Data Item Value” on page 903, “Data Item Value” on page 902, “Display for Orientation” on page 908, “Foreground Color” on page 917, “Margin” on page 932, “Name” on page 942, “Padding” on page 949, “Relative Alignment” on page 959, “Render Variable” on page 961, “Report Expression” on page 962, “Report Expression” on page 962, “Size & Overflow” on page 974, “Source Type” on page 977, “Source Type” on page 976, “Style Variable” on page 979, “Text” on page 983, “Text Source Variable” on page 984, “URL” on page 990, “URL Source Variable” on page 990

Image

A link to an image file. The link can be a static value, or it can come from a report expression or query item. Use the URL source properties of the image object to define the link.

Properties of Image

“Aggregate Function” on page 873, “Alternate Text” on page 875, “Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Control Data Item Value” on page 898, “Data Item Label” on page 902, “Data Item Value” on page 903, “Display for Orientation” on page 908, “Drill-Through Definitions” on page 910, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Level” on page 930, “Level Unique Name” on page 930, “Margin” on page 932, “Member” on page 938, “Member Unique Name” on page 939, “Name” on page 942, “Property Unique Name” on page 956, “Relative Alignment” on page 959, “Render Variable” on page 961, “Report Expression” on page 962, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, Set Definition, “Set Sorting” on page 970, “Size & Overflow” on page 974, “Source Type” on page 977, “Style Variable” on page 979, “URL” on page 990, “URL Source Variable” on page 990, “Visible” on page 996

Intersection (Tuple)

A data item obtained from the combination of two or more members that you specify. An intersection appears as a single, unified member instead of its component members. Each member must be from a different dimension.

Properties of Intersection (Tuple)

“Dimension” on page 907, “Hierarchy” on page 921, “Label” on page 926, “Members” on page 939, “Name” on page 941, “Type” on page 989

Interval Prompt

An advanced prompt control that allows you to enter time duration values.

Properties of Interval Prompt

“Box Type” on page 886, “Choices Deselect All Text” on page 891, “Choices Select All Text” on page 891, “Choices Text” on page 891, “Conditional Styles” on page 895, “Contained Text Direction” on page 897, “Days Text” on page 904, “Default Selections” on page 905, “Deselect Text” on page 906, “Direction & Justification” on page 907, “Display Milliseconds” on page 909, “Display Seconds” on page 909, “From Text” on page 917, “Hide Adornments” on page 921, “Highest Value Text” on page 922, “Hours Text” on page 923, “Insert Text” on page 924, “Lowest Value Text” on page 932, “Milliseconds Text” on page 939, “Minutes Text” on page 941, “Multi-Select” on page 941, “Name” on page 942, “Parameter” on page 951, “Range” on page 958, “Remove Text” on page 960, “Render Variable” on page 961, “Required” on page 963, “Seconds Text” on page 968, “Style Variable” on page 979, “To Text” on page 987, “Visible” on page 996

Iterator

A static iterator control that allows users to navigate through values by using buttons such as previous and next. Each value in the iterator comes from a row in the data table of the control.

Properties of Iterator

“Application Drill-Through” on page 876, “Contained Text Direction” on page 897, “Container Filter” on page 897, “Container Selection” on page 897, “Control Enable” on page 899, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Iterator First” on page 924, “Iterator Label Area” on page 924, “Iterator Last” on page 924, “Iterator Next” on page 924, “Iterator Previous” on page 925, “Iterator Values Definition” on page 925, “Name” on page 942, “Orientation” on page 948, “Render Variable” on page 961, “Set Variable Values” on page 970

Iterator First

The button in the iterator that moves the control to the first value.

Properties of Iterator First

“Button Width” on page 888, “Label” on page 926, “Select UI” on page 968, “Text Color” on page 984

Iterator Label Area

The area in the iterator that shows the label of the current value.

Properties of Iterator Label Area

“Active Dot Color” on page 873, “Dot Color” on page 910, “Drop-Down Width” on page 911, “Number Style” on page 947, “Select UI” on page 968, “Show Icon” on page 972, “Text Color” on page 984

Iterator Last

The button in the iterator that moves the control to the last value.

Properties of Iterator Last

“Button Width” on page 888, “Label” on page 926, “Select UI” on page 968, “Text Color” on page 984

Iterator Next

The button in the iterator that moves the control to the next value.

Properties of Iterator Next

“Button Width” on page 888, “Label” on page 926, “Select UI” on page 968, “Text Color” on page 984

Iterator Previous

The button in the iterator that moves the control to the previous value.

Properties of Iterator Previous

“Button Width” on page 888, “Label” on page 926, “Select UI” on page 968, “Text Color” on page 984

Iterator Value Label

The label used to identify each value in a data iterator control. Each label is determined by the data items inserted into the control.

Properties of Iterator Value Label

“Data Format” on page 900

Join

A relationship between a field in one table or query and a field of the same data type in another table or query.

Properties of Join

“Filter Type” on page 914, “Join Relationships” on page 925

Key

An object that uniquely identifies members of a level.

If the unique identifier is a primary or alternate key, you need only one key object. If the unique identifier is a composite key, you need one key object for every data item that participates in making the members of a level unique.

Properties of Key

“Data Item” on page 902, “Name” on page 944

Label

Specifies the text, or label, for the object in a chart.

Properties of Label

“Conditional Styles” on page 895, “Data Format” on page 900, “Master Detail Relationships” on page 935, “Properties” on page 956, “Query” on page 957, “Render Variable” on page 961

Layout Component Reference

A reference to another layout object. Before you can reference an object, its Name property must be set.

Properties of Layout Component Reference

“Component Reference” on page 895, “Embed” on page 911, “Overrides” on page 949

Legend

A key to the patterns or colors assigned to the data series in a chart. This object applies only to legacy charts.

Properties of Legend

“Absolute Position” on page 872, “Auto Truncation” on page 878, “Background Color” on page 881, “Border Color” on page 884, “Borders” on page 885, “Bottom

Position (px)" on page 885, "Box Type" on page 886, "Classes" on page 891, "Conditional Styles" on page 895, "Drill-Through Definitions" on page 910, "Fill Effects" on page 914, "Font" on page 916, "Font Auto-Sizing" on page 916, "Foreground Color" on page 917, "Horizontal Alignment" on page 922, "Left Position (px)" on page 928, "Legend Title" on page 929, "Legend Title" on page 929, "Maximum Characters" on page 936, "Position" on page 953, "Right Position (px)" on page 965, "Separator" on page 969, "Show Legend Values" on page 972, "Style Variable" on page 979, "Top Position (px)" on page 987, "Truncation Text" on page 988, "Visible" on page 996

Legend

A key to the patterns or colors assigned to the data series in a chart.

Properties of Legend

"Auto Font Size" on page 877, "Background Effects" on page 881, "Classes" on page 891, "Conditional Styles" on page 895, "Drill-Through Definitions" on page 910, "Font" on page 916, "Foreground Color" on page 917, "Horizontal Alignment" on page 922, "Legend Separator" on page 929, "Legend Title" on page 929, "Legend Title" on page 929, "Render Variable" on page 961, "Show Values" on page 973, "Text Truncation" on page 984

Legend Title

The title for the legend, including the title text and text style. If this object is empty, a default title is rendered, if available. This object applies only to legacy charts.

Properties of Legend Title

"Box Type" on page 886, "Classes" on page 891, "Conditional Styles" on page 895, "Default Title" on page 905, "Horizontal Alignment" on page 922, "Master Detail Relationships" on page 935, "Properties" on page 956, "Query" on page 957, "Style Variable" on page 979

Legend Title

The title for the legend, including the title text and text style. If this object is empty, a default title is rendered, if available.

Properties of Legend Title

"Auto Font Size" on page 877, "Box Type" on page 886, "Classes" on page 891, "Conditional Styles" on page 895, "Default Title" on page 905, "Horizontal Alignment" on page 922, "Master Detail Relationships" on page 935, "Properties" on page 956, "Query" on page 957, "Render Variable" on page 961

Level

A set of members with a predefined set of similar characteristics. For example, the members Year 2011 and Year 2012 in the Time dimension form a year level, while the corresponding quarters form a quarter level.

Properties of Level

"Caption" on page 888, "Name" on page 943, "Sorting" on page 976

Level Hierarchy

Specifies how the levels in a dimension are logically ordered.

Properties of Level Hierarchy

“Name” on page 944

Level Set

A set of data items that define the members of a level.

Properties of Level Set

“Detail” on page 906, “Dimension” on page 907, “Hierarchy” on page 921, “Label” on page 926, “Level” on page 930, “Level Unique Name” on page 930, “Name” on page 941, “Set Sorting” on page 970, “Type” on page 989

Line

The data marker used to represent a data series in a line chart.

Properties of Line

“Aggregate Function” on page 873, “Chart Type” on page 890, “Conditional Palette” on page 895, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Level” on page 930, “Level Unique Name” on page 930, “Line and Markers” on page 930, “Line Shape” on page 931, “Member” on page 938, “Member Unique Name” on page 939, “Palette” on page 951, “Property Unique Name” on page 956, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, “Series Type” on page 969, “Set Definition, “Set Sorting” on page 970, “Show Values” on page 973, “Value Markers” on page 993

Line

The data marker used to represent a data series in a line chart. This object applies only to legacy charts.

Properties of Line

“Axis Assignment” on page 878, “Border Color” on page 884, “Borders” on page 885, “Chart Type” on page 890, “Grouping Type” on page 920, “Line Style” on page 931, “Line Type” on page 931, “Line Weight (pt)” on page 931, “Show Data Points” on page 971, “Show line” on page 972, “Value Location:” on page 993, “Values” on page 994, “Value Type” on page 995

List

A layout object that is used to present query results in a list fashion.

Properties of List

“Application Drill-Through” on page 876, “Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Clickable Regions” on page 893, “Column Titles” on page 894, “Conditional Styles” on page 895, “Container Filter” on page 897, “Container Selection” on page 897, “Contents Height” on page 898, “Direction & Justification” on page 907, “Display for

Orientation" on page 908, "Drop Shadow" on page 911, "Font" on page 916, "Foreground Color" on page 917, "Grouping & Sorting" on page 919, "Horizontal Alignment" on page 922, "Layout Table" on page 928, "Margin" on page 932, "Master Detail Relationships" on page 935, "Name" on page 942, "No Data Contents" on page 945, "Pagination" on page 950, "Properties" on page 956, "Query" on page 957, "Relative Alignment" on page 959, "Render Page when Empty" on page 960, "Render Variable" on page 961, "Rows Per Page" on page 967, "Set Variable Values" on page 970, "Share Result Set" on page 970, "Show Hover" on page 971, "Show Pointer Cursor" on page 972, "Size & Overflow" on page 974, "Style Variable" on page 979, "Summary Text" on page 981, "Suppression" on page 981, "Table Properties" on page 982, "Visible" on page 996

List Box

A static list box control. Each item in the list requires a corresponding row in the data table of the control.

Properties of List Box

"Application Drill-Through" on page 876, "Auto Select" on page 877, "Contained Text Direction" on page 897, "Container Filter" on page 897, "Container Selection" on page 897, "Control Enable" on page 899, "Direction & Justification" on page 907, "Display for Orientation" on page 908, "List Items Definition" on page 932, "Multi-Select" on page 941, "Name" on page 942, "No Value List Item" on page 946, "Render Variable" on page 961, "Set Variable Values" on page 970, "Size" on page 974

List Cell

A cell in a row, you can use for a list header or footer.

Properties of List Cell

"Aggregate Function" on page 873, "Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Conditional Styles" on page 895, "Data Format" on page 900, "Direction & Justification" on page 907, "Expression" on page 913, "Font" on page 916, "Foreground Color" on page 917, "Hierarchy" on page 921, "Hierarchy Unique Name" on page 921, "Horizontal Alignment" on page 922, "Level" on page 930, "Level Unique Name" on page 930, "Member" on page 938, "Member Unique Name" on page 939, "Output Aggregation Method" on page 949, "Padding" on page 949, "Property Unique Name" on page 956, "Rollup Aggregate Function" on page 965, "Root Members Only" on page 966, "Set Definition", "Set Sorting" on page 970, "Size & Overflow" on page 974, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Table Header" on page 981, "Vertical Alignment" on page 995, "White Space" on page 996

List Column

A column in a list. Generally, the column will contain a query item, but it may also contain any number of layout objects. For example, the To column in a statement list may present the address in a table format. If the column only contains a query items, then the column will automatically span the group if the query item is grouped.

Properties of List Column

“Allow Sorting” on page 874, “Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Clickable Region” on page 892, “Column Visibility” on page 894, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Padding” on page 949, “Pagination” on page 950, “Render” on page 960, “Render Variable” on page 961, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Vertical Alignment” on page 995, “White Space” on page 996

List Column Body

The contents of a column in a list report.

Properties of List Column Body

“Aggregate Function” on page 873, “Allow Sorting” on page 874, “Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Clickable Region” on page 892, “Column Visibility” on page 894, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Drill-Through Definitions” on page 910, “Expression” on page 913, “Font” on page 916, “Foreground Color” on page 917, “Group Span” on page 920, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Horizontal Alignment” on page 922, “Level” on page 930, “Level Unique Name” on page 930, “Member” on page 938, “Member Unique Name” on page 939, “Padding” on page 949, “Property Unique Name” on page 956, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, Set Definition, “Set Sorting” on page 970, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Vertical Alignment” on page 995, “White Space” on page 996

List Columns

A set of columns in a list.

Properties of List Columns

“Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Padding” on page 949, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Vertical Alignment” on page 995, “White Space” on page 996

List Columns

Overrides the style for List Column objects that is defined in the GlobalReportStyles.css file.

Properties of List Columns

“Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Font” on page 916,

“Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Padding” on page 949, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Vertical Alignment” on page 995, “White Space” on page 996

List Columns Body Style

Overrides the style for List Column Body objects that is defined in the GlobalReportStyles.css file.

Properties of List Columns Body Style

“Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Padding” on page 949, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Vertical Alignment” on page 995, “White Space” on page 996

List Columns Title Style

Overrides the style for List Column Title objects that is defined in the GlobalReportStyles.css file.

Properties of List Columns Title Style

“Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Padding” on page 949, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Vertical Alignment” on page 995, “White Space” on page 996

List Column Title

The title of a list column.

Properties of List Column Title

“Aggregate Function” on page 873, “Allow Sorting” on page 874, “Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Clickable Region” on page 892, “Column Visibility” on page 894, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Drill-Through Definitions” on page 910, “Expression” on page 913, “Font” on page 916, “Foreground Color” on page 917, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Horizontal Alignment” on page 922, “Level” on page 930, “Level Unique Name” on page 930, “Member” on page 938, “Member Unique Name” on page 939, “Padding” on page 949, “Property Unique Name” on page 956, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, “Set Definition”, “Set Sorting” on page 970, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Vertical Alignment” on page 995, “White Space” on page 996

List Footer

Overall footer that appears once at the end of lists. Footers are containers in which you can insert text, images, data items, and report expressions such as the page number.

Properties of List Footer

“Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Padding” on page 949, “Properties” on page 956, “Push To Bottom” on page 957, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Vertical Alignment” on page 995, “White Space” on page 996

List Header

Overall header that appears once at the top of lists. Headers are containers in which you can insert text, images, data items, and report expressions such as the current date.

Properties of List Header

“Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Padding” on page 949, “Pagination” on page 950, “Properties” on page 956, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Vertical Alignment” on page 995, “White Space” on page 996

List Item

A list item in a static list box control.

Properties of List Item

“Icon” on page 923, “Label” on page 926

List Item Label

The label used to identify each item in a data list box control. Each label is determined by the data items inserted into the control.

Properties of List Item Label

“Data Format” on page 900

List Page Footer

The footer that appears at the bottom of every page of a list report. This object is rendered after the list details and other list footers. It is useful for presenting page totals.

Properties of List Page Footer

“Push To Bottom” on page 957

List Page Header

The header in the list that will appear on every page rendered. It occurs after the column titles and before the overall group header of the list. It is useful for presenting carry forward totals.

Properties of List Page Header

“Display After Overall Header” on page 908

List Row

A row in a list.

Properties of List Row

“Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Clickable Region” on page 892, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Padding” on page 949, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Vertical Alignment” on page 995, “White Space” on page 996

List Row Cells Style

Overrides the style for Row Cells Style objects that is defined in the GlobalReportStyles.css file.

Properties of List Row Cells Style

“Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Conditional Styles” on page 895, “Data Format” on page 900, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Padding” on page 949, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Vertical Alignment” on page 995, “White Space” on page 996

List Summary

A summary that is automatically added as the footer row in a list.

Properties of List Summary

“Aggregate Data Item” on page 873, “Aggregation Method” on page 874, “Label” on page 926, “Name” on page 941, “Type” on page 989

List Summary

The list summary that appears in executed active reports.

Properties of List Summary

“Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Data Format” on page 900, “Data Item” on page 901, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Font” on page 916, “Foreground Color” on page 917,

"Margin" on page 932, *"Output Aggregation Method"* on page 949, *"Padding"* on page 949, *"Relative Alignment"* on page 959, *"Render Variable"* on page 961, *"Size & Overflow"* on page 974, *"Spacing & Breaking"* on page 977, *"Style Variable"* on page 979, *"Visible"* on page 996

Map

A chart that uses a map to show data.

Properties of Map

"Alternate Text" on page 875, *"Application Drill-Through"* on page 876, *"Axis Title"* on page 880, *"Background Color"* on page 881, *"Background Effects"* on page 881, *"Border"* on page 884, *"Box Type"* on page 886, *"Classes"* on page 891, *"Clickable Regions"* on page 893, *"Contained Text Direction"* on page 897, *"Container Selection"* on page 897, *"Data Language"* on page 904, *"Dictionary"* on page 907, *"Direction & Justification"* on page 907, *"Display for Orientation"* on page 908, *"Drill-Through Definitions"* on page 910, *"Expand Features"* on page 912, *"Ignore Data with No Features"* on page 923, *"Ignore Hover when No Data"* on page 923, *"Legend"* on page 928, *"Map & Layers"* on page 932, *"Margin"* on page 932, *"Master Detail Relationships"* on page 935, *"Maximum Hotspots"* on page 936, *"Name"* on page 942, *"No Data Contents"* on page 945, *"No Data Features Size (pt)"* on page 945, *"Notes"* on page 945, *"Padding"* on page 949, *"Pagination"* on page 950, *"Query"* on page 957, *"Relative Alignment"* on page 959, *"Render Page when Empty"* on page 960, *"Render Variable"* on page 961, *"Set Variable Values"* on page 970, *"Show Hover"* on page 971, *"Show Pointer Cursor"* on page 972, *"Size & Overflow"* on page 975, *"Suppression"* on page 981, *"Title"* on page 985, *"Tooltips"* on page 986, *"Visible"* on page 996

Map Location

Associates a data series with regions on the region layer of the map.

Properties of Map Location

"Aggregate Function" on page 873, *"Expression"* on page 913, *"Hierarchy"* on page 921, *"Hierarchy Unique Name"* on page 921, *"Level"* on page 930, *"Level Unique Name"* on page 930, *"Member"* on page 938, *"Member Unique Name"* on page 939, *"Property Unique Name"* on page 956, *"Rollup Aggregate Function"* on page 965, *"Root Members Only"* on page 966, *Set Definition*, *"Set Sorting"* on page 970

Map Location

Associates a data series with points on the point layer of the map.

Properties of Map Location

"Aggregate Function" on page 873, *"Expression"* on page 913, *"Hierarchy"* on page 921, *"Hierarchy Unique Name"* on page 921, *"Level"* on page 930, *"Level Unique Name"* on page 930, *"Member"* on page 938, *"Member Unique Name"* on page 939, *"Property Unique Name"* on page 956, *"Rollup Aggregate Function"* on page 965, *"Root Members Only"* on page 966, *Set Definition*, *"Set Sorting"* on page 970

Map Refinement Location

Qualifies the data series members that are associated with regions on the map.

Properties of Map Refinement Location

“Aggregate Function” on page 873, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Level” on page 930, “Level Unique Name” on page 930, “Member” on page 938, “Member Unique Name” on page 939, “Property Unique Name” on page 956, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, Set Definition, “Set Sorting” on page 970

Map Refinement Location

Qualifies the data series members that are associated with points on the map.

Properties of Map Refinement Location

“Aggregate Function” on page 873, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Level” on page 930, “Level Unique Name” on page 930, “Member” on page 938, “Member Unique Name” on page 939, “Property Unique Name” on page 956, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, Set Definition, “Set Sorting” on page 970

Marimekko Chart

A type of bar chart that can show three levels of data.

Properties of Marimekko Chart

“Alternate Text” on page 875, “Application Drill-Through” on page 876, “Background Color” on page 881, “Background Effects” on page 881, “Baselines” on page 883, “Border” on page 884, “Border Color” on page 884, “Borders” on page 885, “Box Type” on page 886, “Category Axis” on page 889, “Classes” on page 891, “Clickable Regions” on page 893, “Conditional Palette” on page 895, “Container Selection” on page 897, “Depth” on page 906, “Display for Orientation” on page 908, “Drill-Through Definitions” on page 910, “Legend” on page 928, “Margin” on page 932, “Marimekko Totals” on page 933, “Markers” on page 933, “Marker Text Location” on page 935, “Master Detail Relationships” on page 935, “Maximum Hotspots” on page 936, “Name” on page 942, “No Data Contents” on page 945, “Notes” on page 945, “Padding” on page 949, “Pagination” on page 950, “Palette” on page 950, “Query” on page 957, “Relative Alignment” on page 959, “Render Page when Empty” on page 960, “Render Variable” on page 961, “Set Variable Values” on page 970, “Show Hover” on page 971, “Show Pointer Cursor” on page 972, “Size & Overflow” on page 975, “Suppression” on page 981, “Title” on page 985, “Tooltips” on page 986, “Values” on page 994, “Visible” on page 996, “Visual Angle” on page 996, “Y Axis” on page 998

Marker

A marker, or symbol, that you can place at a static place in a chart. Markers can designate a point of significance that may help you analyze or understand the data.

Properties of Marker

“Aggregate Function” on page 873, “Data Item Value” on page 903, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Label Location” on page 927, “Level” on page 930, “Level Unique Name” on page 930, “Marker Shape” on page 934, “Marker Size (pt)” on page 934, “Marker Style” on page 934, “Master Detail Relationships” on page 935, “Member” on page 938,

"Member Offset (%)" on page 938, *"Member Unique Name"* on page 939, *"Properties"* on page 956, *"Property Unique Name"* on page 956, *"Query"* on page 957, *"Render Variable"* on page 961, *"Rollup Aggregate Function"* on page 965, *"Root Members Only"* on page 966, *Set Definition*, *"Set Sorting"* on page 970

Marker

A marker, or symbol, that you can place at a static place in a chart. Markers can designate a point of significance that may help you analyze or understand the data. This object applies only to legacy charts.

Properties of Marker

"Axis Assignment" on page 878, *"Bar, Line, or Area Index"* on page 882, *"Box Type"* on page 886, *"Data Item Value"* on page 903, *"Label"* on page 926, *"Marker Color"* on page 933, *"Marker Shape"* on page 934, *"Marker Size (pt)"* on page 934, *"Master Detail Relationships"* on page 935, *"Numeric Value"* on page 948, *"Percentile"* on page 952, *"Percent of Axis"* on page 952, *"Position type"* on page 954, *"Properties"* on page 956, *"Query"* on page 957, *"Report Expression"* on page 962, *"Report Expression"* on page 962, *"Standard Deviations"* on page 978

Marker

A marker on a point chart. Point charts include scatter charts, polar charts, radar charts, and bubble charts. This object applies only to legacy charts.

Properties of Marker

"Box Type" on page 886, *"Data Item Value"* on page 903, *"Data Item Value"* on page 903, *"Expression"* on page 913, *"Expression"* on page 913, *"Label"* on page 926, *"Marker Color"* on page 933, *"Marker Shape"* on page 934, *"Marker Size (pt)"* on page 934, *"Master Detail Relationships"* on page 935, *"Numeric Value"* on page 948, *"Numeric Value"* on page 948, *"Percentile"* on page 952, *"Percentile"* on page 952, *"Percent of Axis"* on page 952, *"Percent of Axis"* on page 952, *"Position type"* on page 954, *"Position type"* on page 954, *"Properties"* on page 956, *"Query"* on page 957, *"Report Expression"* on page 963, *"Report Expression"* on page 963, *"Standard Deviations"* on page 978, *"Standard Deviations"* on page 978

MDX

A multidimensional expression (MDX) query against an OLAP data source.

Properties of MDX

"Catalog" on page 889, *"Data Source"* on page 904, *"MDX"* on page 938, *"Name"* on page 943

Measure

A data item that defines a measure.

Properties of Measure

"Dimension" on page 907, *"Label"* on page 926, *"Member"* on page 938, *"Member Unique Name"* on page 939, *"Name"* on page 941, *"Type"* on page 989

Member

A data item that defines a member.

Properties of Member

"Detail" on page 906, "Dimension" on page 907, "Hierarchy" on page 921, "Label" on page 926, "Member" on page 938, "Member Unique Name" on page 939, "Name" on page 941, "Type" on page 989

Member Children Set

A set of data items that define the children set of a member.

Properties of Member Children Set

"Detail" on page 906, "Dimension" on page 907, "Hierarchy" on page 921, "Label" on page 926, "Member" on page 938, "Member Unique Name" on page 939, "Name" on page 941, "Set Sorting" on page 970, "Type" on page 989

Member Hierarchy

The organization of a dimension's members into a logical tree structure, with each member having one or more "parent" members and an arbitrary number of "child" members.

Properties of Member Hierarchy

"Name" on page 944

Member Property

A property that is associated with members of a level. Attributes can be used to refine a search within level members, or to provide additional information about members.

Properties of Member Property

"Data Item" on page 902, "Name" on page 944

Member Property

A member property from either a level or a hierarchy.

Properties of Member Property

"Dimension" on page 907, "Hierarchy" on page 921, "Label" on page 926, "Level" on page 930, "Name" on page 941, "Property" on page 956, "Property Unique Name" on page 956, "Type" on page 989

Member Set

A data item that represents a named set. Member sets supply the context for expressions that require evaluation for multiple dimensions. For example, they determine the contexts for which you can apply analytical functions such as rank.

Properties of Member Set

"Data Item" on page 901, "Name" on page 944

Metrics Range Chart

A chart that superimposes target value markers, target range markers, and tolerance range markers over any number or combination of bar, line, and area charts.

Properties of Metrics Range Chart

“Alternate Text” on page 875, “Application Drill-Through” on page 876, “Background Color” on page 881, “Background Effects” on page 881, “Baselines” on page 883, “Border” on page 884, “Box Type” on page 886, “Category Axis” on page 889, “Classes” on page 891, “Clickable Regions” on page 893, “Conditional Palette” on page 895, “Container Selection” on page 897, “Depth” on page 906, “Display for Orientation” on page 908, “Drill-Through Definitions” on page 910, “Legend” on page 928, “Margin” on page 932, “Marker Color” on page 933, “Marker Label” on page 933, “Markers” on page 933, “Marker Text Location” on page 935, “Master Detail Relationships” on page 935, “Maximum Hotspots” on page 936, “Name” on page 942, “No Data Contents” on page 945, “Notes” on page 945, “Padding” on page 949, “Pagination” on page 950, “Palette” on page 950, “Performance Pattern” on page 953, “Query” on page 957, “Range Label” on page 958, “Relative Alignment” on page 959, “Render Page when Empty” on page 960, “Render Variable” on page 961, “Set Variable Values” on page 970, “Show Hover” on page 971, “Show Pointer Cursor” on page 972, “Size & Overflow” on page 975, “Suppression” on page 981, “Target Color” on page 983, “Target Marker” on page 983, “Target Marker Border Color” on page 983, “Target Marker Position” on page 983, “Target Range (%)” on page 983, “Title” on page 985, “Tolerance Color” on page 985, “Tolerance Label” on page 986, “Tooltips” on page 986, “Upper Range Skew (%)” on page 989, “Value Location:” on page 993, “Visible” on page 996, “Visual Angle” on page 996, “Y1 Axis” on page 998

Metric Studio Diagram

A Metric Studio diagram rendered as a static image.

Properties of Metric Studio Diagram

“Alternate Text” on page 875, “Description” on page 906, “Diagram Identifier” on page 907

Named Set

A reference to a named set from the model.

Properties of Named Set

“Detail” on page 906, “Dimension” on page 907, “Hierarchy” on page 921, “Label” on page 926, “Name” on page 941, “Set Sorting” on page 970, “Type” on page 989

Node

Data item that represents categorical data in the visualization. For example, the bubbles in a packed bubble visualization.

Properties of Node

“Category Range” on page 890, “Data Format” on page 900, “Fact Cell Data Format” on page 914, “Sorting” on page 976

Note

A note on a chart. The source of the note text can be static text, a query item, or a report expression.

Properties of Note

"Background Effects" on page 881, "Conditional Styles" on page 895, "Font" on page 916, "Foreground Color" on page 917, "Horizontal Alignment" on page 922, "Master Detail Relationships" on page 935, "Note Text" on page 946, "Position" on page 953, "Properties" on page 956, "Render Variable" on page 961, "Size & Overflow" on page 974

Note

A note on a chart. The source of the note text can be static text, a query item, or a report expression. This object applies only to legacy charts.

Properties of Note

"Bottom Position (px)" on page 885, "Height (px)" on page 920, "Left Position (px)" on page 928, "Note Border" on page 945, "Note Text" on page 946, "Width (px)" on page 997

Note Content

The content and style of a note.

Properties of Note Content

"Background Color" on page 881, "Box Type" on page 886, "Classes" on page 891, "Conditional Styles" on page 895, "Horizontal Alignment" on page 922, "Master Detail Relationships" on page 935, "Properties" on page 956, "Query" on page 957, "Style Variable" on page 979

No Value List Item

The default item in a list control. When the default item is selected when the report is run, it sets the value of the data item in the control to null. By default, the no value item is the first item in the list.

Properties of No Value List Item

"Label" on page 926, "Position in List" on page 954

Numerical Axis

The numeric axis for a progressive chart, including labels, titles, range, scale, and gridlines. This object applies only to legacy charts.

Properties of Numerical Axis

"Axis Labels" on page 879, "Axis Line" on page 879, "Axis Title" on page 880, "Axis Title" on page 880, "Classes" on page 891, "Data Format" on page 900, "Gridlines" on page 919, "Include Zero For Auto Scale" on page 923, "Maximum Value" on page 938, "Minimum Value" on page 940, "Minor Gridlines" on page 940, "Scale" on page 967, "Scale Interval" on page 967, "Use Same Range For All Instances" on page 992

Numerical Axis

The numeric axis for a Pareto chart, including labels, titles, and gridlines. This object applies only to legacy charts.

Properties of Numerical Axis

"Axis Labels" on page 879, *"Axis Line"* on page 879, *"Axis Title"* on page 880, *"Axis Title"* on page 880, *"Classes"* on page 891, *"Data Format"* on page 900, *"Gridlines"* on page 919, *"Include Zero For Auto Scale"* on page 923, *"Maximum Value"* on page 938, *"Minimum Value"* on page 940, *"Minor Gridlines"* on page 940, *"Scale"* on page 967, *"Scale Interval"* on page 967, *"Use Same Range For All Instances"* on page 992

Numeric Axis

The axis that displays numbers.

Properties of Numeric Axis

"Axis Labels" on page 879, *"Axis Line"* on page 879, *"Axis Range"* on page 880, *"Axis Title"* on page 880, *"Axis Title"* on page 880, *"Gridlines"* on page 919, *"Minor Gridlines"* on page 940, *"Number of Minor Intervals"* on page 946

Numeric Baseline

The baseline on a numeric axis.

Properties of Numeric Baseline

"Aggregate Function" on page 873, *"Data Item Value"* on page 903, *"Expression"* on page 913, *"Hierarchy"* on page 921, *"Hierarchy Unique Name"* on page 921, *"Level"* on page 930, *"Level Unique Name"* on page 930, *"Line Style"* on page 931, *"Master Detail Relationships"* on page 935, *"Member"* on page 938, *"Member Unique Name"* on page 939, *"Numeric Baselines"* on page 948, *"Properties"* on page 956, *"Property Unique Name"* on page 956, *"Query"* on page 957, *"Render Variable"* on page 961, *"Rollup Aggregate Function"* on page 965, *"Root Members Only"* on page 966, *Set Definition*, *"Set Sorting"* on page 970

Page

A page in a layout.

Properties of Page

"Background Color" on page 881, *"Border"* on page 884, *"Classes"* on page 891, *"Conditional Styles"* on page 895, *"Direction & Justification"* on page 907, *"Font"* on page 916, *"Foreground Color"* on page 917, *"Gradient"* on page 919, *"Horizontal Alignment"* on page 922, *"Margin"* on page 932, *"Master Detail Relationships"* on page 935, *"Name"* on page 942, *"Pagination"* on page 950, *"PDF Page Setup"* on page 951, *"Properties"* on page 956, *"Query"* on page 957, *"Render Variable"* on page 961, *"Size & Overflow"* on page 974, *"Style Variable"* on page 979

Page Body

The main body of a page.

Properties of Page Body

“Classes” on page 891, “Size & Overflow” on page 974

Page Break Text

The text associated with a page break.

Properties of Page Break Text

“Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Font” on page 916, “Foreground Color” on page 917, “Margin” on page 932, “Padding” on page 949, “Relative Alignment” on page 959, “Render Variable” on page 961, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Visible” on page 996

Page Footer

The footer of a page.

Properties of Page Footer

“Classes” on page 891, “Size & Overflow” on page 974

Page Header

The header of a page.

Properties of Page Header

“Classes” on page 891, “Size & Overflow” on page 974

Page Number

The number of a page.

Properties of Page Number

“Background Color” on page 881, “Classes” on page 891, “Display for Orientation” on page 908, “Font” on page 916, “Foreground Color” on page 917, “Margin” on page 932, “Number Style” on page 947, “Relative Alignment” on page 959

Page Set

The set of pages to render according to a grouping structure.

Properties of Page Set

“Grouping & Sorting” on page 919, “Master Detail Relationships” on page 935, “Name” on page 942, “Pagination” on page 950, “Properties” on page 956, “Query” on page 957

Pareto Bars

The bars in a Pareto chart.

Properties of Pareto Bars

“Axis Labels” on page 879, *“Axis Line”* on page 879, *“Axis Range”* on page 880, *“Axis Title”* on page 880, *“Axis Title”* on page 880, *“Gridlines”* on page 919, *“Minor Gridlines”* on page 940, *“Number of Minor Intervals”* on page 946

Pareto Chart

A chart in which data series appear as colored sections stacked in columns or bars. The maximum of each column or bar represents the series total as a percentage of the overall total of all data series in the chart.

Negative values are not supported in Pareto charts.

Properties of Pareto Chart

“Alternate Text” on page 875, *“Application Drill-Through”* on page 876, *“Background Effects”* on page 881, *“Bar Width”* on page 883, *“Bevel”* on page 883, *“Border”* on page 884, *“Border Color”* on page 884, *“Borders”* on page 885, *“Box Type”* on page 886, *“Category Baselines”* on page 889, *“Chart Orientation”* on page 890, *“Classes”* on page 891, *“Clickable Regions”* on page 893, *“Colored Regions”* on page 893, *“Conditional Palette”* on page 895, *“Contained Text Direction”* on page 897, *“Container Selection”* on page 897, *“Cumulative Line”* on page 900, *“Depth”* on page 906, *“Direction & Justification”* on page 907, *“Display for Orientation”* on page 908, *“Drill-Through Definitions”* on page 910, *“Drop Shadow”* on page 911, *“Legend”* on page 929, *“Margin”* on page 932, *“Markers”* on page 934, *“Master Detail Relationships”* on page 935, *“Material Effects”* on page 935, *“Matrix Rows and Columns”* on page 936, *“Maximum Hotspots”* on page 936, *“Name”* on page 942, *“No Data Contents”* on page 945, *“Notes”* on page 946, *“Numeric Baselines”* on page 948, *“Padding”* on page 949, *“Pagination”* on page 950, *“Palette”* on page 951, *“Plot Area Fill”* on page 953, *“Query”* on page 957, *“Relative Alignment”* on page 959, *“Render Page when Empty”* on page 960, *“Render Variable”* on page 961, *“Set Variable Values”* on page 970, *“Show Hover”* on page 971, *“Show Pointer Cursor”* on page 972, *“Show Values”* on page 973, *“Size & Overflow”* on page 975, *“Summarize Small Items”* on page 980, *“Suppression”* on page 981, *“Title”* on page 985, *“Tooltips”* on page 986, *“Visible”* on page 996

Pareto Chart

A chart in which data series appear as colored sections stacked in columns or bars. The maximum of each column or bar represents the series total as a percentage of the overall total of all data series in the chart. This object applies only to legacy charts.

Negative values are not supported in Pareto charts.

Properties of Pareto Chart

“Alternate Text” on page 875, *“Application Drill-Through”* on page 876, *“Background Color”* on page 881, *“Background Effects”* on page 881, *“Baselines”* on page 883, *“Border”* on page 884, *“Border Color”* on page 884, *“Borders”* on page 885, *“Box Type”* on page 886, *“Category Axis”* on page 889, *“Chart Orientation”* on page 890, *“Classes”* on page 891, *“Clickable Regions”* on page 893, *“Conditional Palette”* on page 895, *“Connecting Lines”* on page 896, *“Container Selection”* on page 897, *“Cumulative Line”* on page 899, *“Depth”* on page 906, *“Display for Orientation”* on page 908, *“Drill-Through Definitions”* on page 910,

"Legend" on page 928, "Margin" on page 932, "Markers" on page 933, "Marker Text Location" on page 935, "Master Detail Relationships" on page 935, "Maximum Hotspots" on page 936, "Name" on page 942, "No Data Contents" on page 945, "Notes" on page 945, "Padding" on page 949, "Pagination" on page 950, "Palette" on page 950, "Pareto Axis" on page 951, "Query" on page 957, "Relative Alignment" on page 959, "Render Page when Empty" on page 960, "Render Variable" on page 961, "Rotate Values" on page 966, "Set Variable Values" on page 970, "Show Hover" on page 971, "Show Pointer Cursor" on page 972, "Size & Overflow" on page 975, "Suppression" on page 981, "Title" on page 985, "Tooltips" on page 986, "Value Location:" on page 993, "Values" on page 994, "Visible" on page 996, "Visual Angle" on page 996

Percentaged Measure

A measure that shows values as a percentage of a summary.

Properties of Percentaged Measure

"Actual Measure" on page 873, "Dimension" on page 907, "Label" on page 926, "Name" on page 941, "Percentage Based On" on page 951, "Type" on page 989

Pie Chart

A chart that uses sections of a circle as data markers to plot one or more data series. The size of each section is proportional to the value of each data series for a given category value. Each pie corresponds to a category value. This object applies only to legacy charts.

Properties of Pie Chart

"Alternate Text" on page 875, "Application Drill-Through" on page 876, "Avoid Label Collision" on page 878, "Axis Title" on page 880, "Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Border Color" on page 884, "Borders" on page 885, "Box Type" on page 886, "Classes" on page 891, "Clickable Regions" on page 893, "Conditional Palette" on page 895, "Container Selection" on page 897, "Depth" on page 906, "Display for Orientation" on page 908, "Drill-Through Definitions" on page 910, "Hole Size (%)" on page 922, "Labels" on page 928, "Legend" on page 928, "Margin" on page 932, "Master Detail Relationships" on page 935, "Maximum Hotspots" on page 936, "Name" on page 942, "No Data Contents" on page 945, "Notes" on page 945, "Padding" on page 949, "Pagination" on page 950, "Palette" on page 950, "Pie Labels" on page 953, "Query" on page 957, "Relative Alignment" on page 959, "Render Page when Empty" on page 960, "Render Variable" on page 961, "Set Variable Values" on page 970, "Show Hover" on page 971, "Show Pointer Cursor" on page 972, "Size & Overflow" on page 975, "Suppression" on page 981, "Title" on page 985, "Tooltips" on page 986, "Value Representation" on page 994, "Values" on page 994, "Visible" on page 996

Pie Chart

A chart that uses sections of a circle as data markers to plot one or more data series. The size of each section is proportional to the value of each data series for a given category value. Each pie corresponds to a category value.

Properties of Pie Chart

“Alternate Text” on page 875, “Application Drill-Through” on page 876, “Axis Title” on page 880, “Background Effects” on page 881, “Bevel” on page 883, “Border” on page 884, “Border Color” on page 884, “Borders” on page 885, “Box Type” on page 886, “Classes” on page 891, “Clickable Regions” on page 893, “Conditional Palette” on page 895, “Contained Text Direction” on page 897, “Container Selection” on page 897, “Depth” on page 906, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Drill-Through Definitions” on page 910, “Drop Shadow” on page 911, “Exploded Slices” on page 912, “First Slice Angle” on page 915, “Hole Size (%)” on page 922, “Legend” on page 929, “Margin” on page 932, “Master Detail Relationships” on page 935, “Material Effects” on page 935, “Matrix Rows and Columns” on page 936, “Maximum Hotspots” on page 936, “Name” on page 942, “No Data Contents” on page 945, “Notes” on page 946, “Padding” on page 949, “Pagination” on page 950, “Palette” on page 951, “Query” on page 957, “Relative Alignment” on page 959, “Render Page when Empty” on page 960, “Render Variable” on page 961, “Set Variable Values” on page 970, “Show Hover” on page 971, “Show Pointer Cursor” on page 972, “Show Values” on page 974, “Size & Overflow” on page 975, “Slice Direction” on page 975, “Summarize Small Slices” on page 980, “Suppression” on page 981, “Title” on page 985, “Tooltips” on page 986, “Visible” on page 996

Pie Labels

The labels that will be drawn if multiple pie charts are rendered. If this object does not exist, no labels will be rendered.

Properties of Pie Labels

“Classes” on page 891, “Conditional Styles” on page 895, “Drill-Through Definitions” on page 910, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Maximum Truncation Characters” on page 937, “Style Variable” on page 979, “Truncation” on page 988, “Truncation Text” on page 988, “Visible” on page 996

Point Color Legend Title

The title for the point color legend. If this object is empty, a default title is rendered, if available.

Properties of Point Color Legend Title

“Master Detail Relationships” on page 935, “Properties” on page 956, “Query” on page 957

Point Layer

A map layer that includes points, such as cities. The color and size of each point is determined by their respective measure.

Properties of Point Layer

“Border Color” on page 884, “Borders” on page 885, “Color Legend Title” on page 894, “Conditional Palette” on page 895, “Conditional Styles” on page 895, “Fill Effects” on page 914, “Map Drills” on page 932, “Palette” on page 951, “Show Data Range in Legend” on page 971, “Show Features with No Data” on page 971,

“Show Values” on page 973, “Size Legend Title” on page 975, “Style Variable” on page 979

Point Measure

The measure that determines the colors of points on a map chart.

Properties of Point Measure

“Conditional Styles” on page 895, “Custom Label” on page 900, “Data Format” on page 900, “Style Variable” on page 979

Point Size Legend Title

The title for the point size legend. If this object is empty, a default title is rendered, if available.

Properties of Point Size Legend Title

“Master Detail Relationships” on page 935, “Properties” on page 956, “Query” on page 957

Point Size Measure

The measure that determines the size of the points on a map chart.

Properties of Point Size Measure

“Conditional Styles” on page 895, “Custom Label” on page 900, “Data Format” on page 900, “Maximum Size (pt)” on page 937, “Minimum Size (pt)” on page 939, “Style Variable” on page 979

Polar Chart

A point chart that plots one or more data series against two measures. The radius of a data series is determined by one measure and the arc is determined by the other measure. Multiple points are plotted for each category. They can be distinguished with the help of tool tips if the Tool Tip property is set to Yes.

Properties of Polar Chart

“Alternate Text” on page 875, “Angular Axis” on page 875, “Application Drill-Through” on page 876, “Background Color” on page 881, “Background Effects” on page 881, “Baselines” on page 883, “Border” on page 884, “Border Color” on page 884, “Borders” on page 885, “Box Type” on page 886, “Classes” on page 891, “Clickable Regions” on page 893, “Conditional Palette” on page 895, “Container Selection” on page 897, “Display for Orientation” on page 908, “Drill-Through Definitions” on page 910, “Legend” on page 928, “Margin” on page 932, “Markers” on page 933, “Marker Size (pt)” on page 934, “Marker Text Location” on page 935, “Master Detail Relationships” on page 935, “Maximum Hotspots” on page 936, “Name” on page 942, “No Data Contents” on page 945, “Notes” on page 945, “Padding” on page 949, “Pagination” on page 950, “Palette” on page 950, “Point Shape” on page 953, “Query” on page 957, “Radial Axis” on page 958, “Relative Alignment” on page 959, “Render Page when Empty” on page 960, “Render Variable” on page 961, “Set Variable Values” on page 970, “Show Hover” on page 971, “Show Pointer Cursor” on page 972, “Size & Overflow” on page 975, “Spider Effects” on page 977, “Suppression” on page 981, “Title” on page 985

982, "Tooltips" on page 986, "Value Location:" on page 993, "Values" on page 994, "Visible" on page 996

Primary Axis

The generic numeric axis for the combination chart. This axis is normally shown as the top-left axis but can be in a different position depending on the chart orientation, as specified in the Chart Orientation property of the chart.

Properties of Primary Axis

"Axis Labels" on page 879, "Axis Line" on page 879, "Axis Range" on page 880, "Axis Title" on page 880, "Axis Title" on page 880, "Gridlines" on page 919, "Minor Gridlines" on page 940, "Number of Minor Intervals" on page 946

Primary Bottom Axis

The numeric axis for a combination chart. This axis is normally rendered as the bottom-left axis, but can change depending on the orientation of the chart, as specified in the Chart Orientation property of the chart.

Properties of Primary Bottom Axis

"Axis Labels" on page 879, "Axis Line" on page 879, "Axis Range" on page 880, "Axis Title" on page 880, "Axis Title" on page 880, "Gridlines" on page 919, "Minor Gridlines" on page 940, "Number of Minor Intervals" on page 946

Progressive Chart

A chart that uses columns as data markers to plot one category across a single measure. The top of the first column represents the starting value for the second column. This chart emphasizes the positive or negative contribution of each value to the total.

Properties of Progressive Chart

"Alternate Text" on page 875, "Application Drill-Through" on page 876, "Background Effects" on page 881, "Bar Width" on page 883, "Bevel" on page 883, "Border" on page 884, "Border Color" on page 884, "Borders" on page 885, "Box Type" on page 886, "Category Baselines" on page 889, "Chart Orientation" on page 890, "Classes" on page 891, "Clickable Regions" on page 893, "Colored Regions" on page 893, "Conditional Palette" on page 895, "Connecting Lines" on page 896, "Contained Text Direction" on page 897, "Container Selection" on page 897, "Depth" on page 906, "Direction & Justification" on page 907, "Display for Orientation" on page 908, "Drill-Through Definitions" on page 910, "Drop Shadow" on page 911, "Legend" on page 929, "Margin" on page 932, "Markers" on page 934, "Master Detail Relationships" on page 935, "Material Effects" on page 935, "Matrix Rows and Columns" on page 936, "Maximum Hotspots" on page 936, "Name" on page 942, "No Data Contents" on page 945, "Notes" on page 946, "Numeric Baselines" on page 948, "Padding" on page 949, "Pagination" on page 950, "Plot Area Fill" on page 953, "Progressive Palette" on page 955, "Query" on page 957, "Relative Alignment" on page 959, "Render Page when Empty" on page 960, "Render Variable" on page 961, "Set Variable Values" on page 970, "Show Hover" on page 971, "Show Pointer Cursor" on page 972, "Show Values" on page 973, "Size & Overflow" on page 975, "Suppression" on page 981, "Title" on page 985, "Tooltips" on page 986, "Total Column" on page 987, "Visible" on page 996

Progressive Chart

A chart that uses columns as data markers to plot one category across a single measure. The top of the first column represents the starting value for the second column. This chart emphasizes the positive or negative contribution of each value to the total. This object applies only to legacy charts.

Properties of Progressive Chart

"Alternate Text" on page 875, *"Application Drill-Through"* on page 876, *"Background Color"* on page 881, *"Background Effects"* on page 881, *"Baselines"* on page 883, *"Border"* on page 884, *"Border Color"* on page 884, *"Borders"* on page 885, *"Box Type"* on page 886, *"Category Axis"* on page 889, *"Chart Orientation"* on page 890, *"Classes"* on page 891, *"Clickable Regions"* on page 893, *"Conditional Palette"* on page 895, *"Connecting Lines"* on page 896, *"Container Selection"* on page 897, *"Depth"* on page 906, *"Display for Orientation"* on page 908, *"Drill-Through Definitions"* on page 910, *"First Column Color"* on page 914, *"Margin"* on page 932, *"Markers"* on page 933, *"Marker Text Location"* on page 935, *"Master Detail Relationships"* on page 935, *"Maximum Hotspots"* on page 936, *"Name"* on page 942, *"Negative Column Color"* on page 944, *"No Data Contents"* on page 945, *"Notes"* on page 945, *"Padding"* on page 949, *"Pagination"* on page 950, *"Palette"* on page 950, *"Positive Column Color"* on page 954, *"Progressive Axis"* on page 955, *"Query"* on page 957, *"Relative Alignment"* on page 959, *"Render Page when Empty"* on page 960, *"Render Variable"* on page 961, *"Rotate Values"* on page 966, *"Set Variable Values"* on page 970, *"Show Hover"* on page 971, *"Show Pointer Cursor"* on page 972, *"Size & Overflow"* on page 975, *"Suppression"* on page 981, *"Title"* on page 985, *"Tooltips"* on page 986, *"Total Column"* on page 987, *"Value Location:"* on page 993, *"Values"* on page 994, *"Visible"* on page 996, *"Visual Angle"* on page 996

Prompt Button

A predefined button used in prompt pages. Its usage changes according to its Type property, which can be set to Cancel, Back, Next, Finish, or Reprompt.

Properties of Prompt Button

"Background Color" on page 881, *"Border"* on page 884, *"Classes"* on page 891, *"Conditional Styles"* on page 895, *"Font"* on page 916, *"Foreground Color"* on page 917, *"Margin"* on page 932, *"Name"* on page 942, *"Padding"* on page 949, *"Relative Alignment"* on page 959, *"Size & Overflow"* on page 974, *"Style Variable"* on page 979, *"Type"* on page 989

Queries

The queries that are defined in a report.

Query

The data that is to be retrieved from the database. The query consists of a source, a selection, detailed and summary filters, and dimension information.

Properties of Query

"Auto Group & Summarize" on page 877, *"Auto-Sort"* on page 877, *"Avoid Division by Zero"* on page 878, *"Cross Product Allowed"* on page 899, *"Define Member Sets"* on page 905, *"Execution Method"* on page 912, *"Execution Optimization"* on page 912, *"Generated SQL"* on page 919, *"Maximum Execution*

Time" on page 936, "Maximum Rows Retrieved" on page 937, "Maximum Tables" on page 937, "Maximum Text Blob Characters" on page 937, "Name" on page 943, "Outer Join Allowed" on page 949, "Override Dimension Info" on page 949, "Processing" on page 955, "Rollup Processing" on page 965, "SQL Join Syntax" on page 978, "Suppress" on page 981, "Use 1.x Behavior" on page 990, "Use Aggregate Cache" on page 990, "Use for Parameter Info" on page 991, "Use Local Cache" on page 991, "User SAP Member Cache" on page 991, "Use SAP MUN as Business Key" on page 992, "Use SQL Parameters" on page 992, "Use SQL With Clause" on page 993

Query Operation

Union, Intersect, Except (minus) operations on one or more queries that result in a projection list upon which other queries can be based.

Properties of Query Operation

"Duplicates" on page 911, "Name" on page 943, "Projection List" on page 956, "Set Operation" on page 969

Query Reference

A reference to another query defined in the same query set.

Properties of Query Reference

"Cardinality" on page 889

Radar Chart

A chart that integrates multiple axes into a single radial figure as lines or stacked areas.

Properties of Radar Chart

"Alternate Text" on page 875, "Application Drill-Through" on page 876, "Background Color" on page 881, "Background Effects" on page 881, "Baselines" on page 883, "Border" on page 884, "Border Color" on page 884, "Borders" on page 885, "Box Type" on page 886, "Category Axis" on page 889, "Classes" on page 891, "Clickable Regions" on page 893, "Conditional Palette" on page 895, "Container Selection" on page 897, "Display for Orientation" on page 908, "Drill-Through Definitions" on page 910, "Legend" on page 928, "Margin" on page 932, "Markers" on page 933, "Marker Size (pt)" on page 934, "Marker Text Location" on page 935, "Master Detail Relationships" on page 935, "Maximum Hotspots" on page 936, "Name" on page 942, "No Data Contents" on page 945, "Notes" on page 945, "Padding" on page 949, "Pagination" on page 950, "Palette" on page 950, "Point Shape" on page 953, "Query" on page 957, "Radar Type" on page 958, "Radial Axis" on page 958, "Relative Alignment" on page 959, "Render Page when Empty" on page 960, "Render Variable" on page 961, "Set Variable Values" on page 970, "Show Hover" on page 971, "Show Pointer Cursor" on page 972, "Size & Overflow" on page 975, "Spider Effects" on page 977, "Suppression" on page 981, "Title" on page 985, "Tooltips" on page 986, "Value Location:" on page 993, "Values" on page 994, "Visible" on page 996

Radial Axis

The radial numeric axis for a polar chart or radar chart, including labels, titles, range, and scale.

Properties of Radial Axis

“Axis Labels” on page 879, “Axis Line” on page 879, “Axis Title” on page 880, “Axis Title” on page 880, “Classes” on page 891, “Data Format” on page 900, “Gridlines” on page 919, “Include Zero For Auto Scale” on page 923, “Maximum Value” on page 938, “Minimum Value” on page 940, “Minor Gridlines” on page 940, “Scale” on page 967, “Scale Interval” on page 967, “Use Same Range For All Instances” on page 992

Radial Measure

The measure that determines the distance between the center of the chart and each data marker.

Properties of Radial Measure

“Conditional Styles” on page 895, “Custom Label” on page 900, “Data Format” on page 900, “Style Variable” on page 979

Radio Button

A radio button in a static radio button group control.

Properties of Radio Button

“Icon” on page 923, “Label” on page 926

Radio Button Group

A static radio button group control. Each radio button requires a corresponding row in the data table of the control.

Properties of Radio Button Group

“Application Drill-Through” on page 876, “Auto Select” on page 877, “Contained Text Direction” on page 897, “Container Filter” on page 897, “Container Selection” on page 897, “Control Enable” on page 899, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Name” on page 942, “Orientation” on page 948, “Radio Buttons Definition” on page 958, “Render Variable” on page 961, “Set Variable Values” on page 970, “Text Color” on page 983

Radio Button Label

The label used to identify each radio button in a data radio button group control. Each label is determined by the data items inserted into the control.

Properties of Radio Button Label

“Data Format” on page 900

Region Color Legend Title

The title for the region color legend. If this object is empty, a default title is rendered, if available.

Properties of Region Color Legend Title

“Master Detail Relationships” on page 935, “Properties” on page 956, “Query” on page 957

Region Layer

A map layer that includes regions, such as provinces.

Properties of Region Layer

“Border Color” on page 884, “Borders” on page 885, “Color Legend Title” on page 894, “Conditional Palette” on page 895, “Conditional Styles” on page 895, “Fill Effects” on page 914, “Map Drills” on page 932, “Palette” on page 951, “Show Data Range in Legend” on page 971, “Show Features with No Data” on page 971, “Show Values” on page 973, “Style Variable” on page 979

Region Measure

The measure that determines the colors of regions on a map chart.

Properties of Region Measure

“Conditional Styles” on page 895, “Custom Label” on page 900, “Data Format” on page 900, “Style Variable” on page 979

Regression Line

A regression line for a bubble chart or scatter chart.

Properties of Regression Line

“Box Type” on page 886, “Line Styles” on page 931, “Number of Regression Lines” on page 947, “Polynomial Exponent” on page 953, “Properties” on page 956, “Regression Type” on page 959

Regression Line Label

A label that will be shown in the legend for the regression line.

Repeater

A container that repeats items across a single row without a particular structure.

Properties of Repeater

“Grouping & Sorting” on page 919, “Master Detail Relationships” on page 935, “Name” on page 942, “No Data Contents” on page 945, “Pagination” on page 950, “Properties” on page 956, “Query” on page 957, “Render Page when Empty” on page 960, “Render Variable” on page 961, “Rows Per Page” on page 967, “Share Result Set” on page 970, “Suppression” on page 981

Repeater Table

A table into which you can insert items that will be repeated.

Properties of Repeater Table

"Across" on page 872, "Application Drill-Through" on page 876, "Background Color" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Clickable Regions" on page 893, "Conditional Styles" on page 895, "Container Filter" on page 897, "Container Selection" on page 897, "Direction & Justification" on page 907, "Display for Orientation" on page 908, "Down" on page 910, "Drop Shadow" on page 911, "Font" on page 916, "Foreground Color" on page 917, "Grouping & Sorting" on page 919, "Horizontal Alignment" on page 922, "Layout Table" on page 928, "Margin" on page 932, "Master Detail Relationships" on page 935, "Name" on page 942, "No Data Contents" on page 945, "Pagination" on page 950, "Properties" on page 956, "Query" on page 957, "Relative Alignment" on page 959, "Render Page when Empty" on page 960, "Render Variable" on page 961, "Repeater Direction" on page 961, "Set Variable Values" on page 970, "Share Result Set" on page 970, "Show Hover" on page 971, "Show Pointer Cursor" on page 972, "Size & Overflow" on page 974, "Style Variable" on page 979, "Summary Text" on page 981, "Suppression" on page 981, "Table Properties" on page 982, "Visible" on page 996

Repeater Table Cell

The contents of a repeater table object.

Properties of Repeater Table Cell

"Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Conditional Styles" on page 895, "Direction & Justification" on page 907, "Font" on page 916, "Foreground Color" on page 917, "Horizontal Alignment" on page 922, "Padding" on page 949, "Render Variable" on page 961, "Size & Overflow" on page 974, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Vertical Alignment" on page 995, "White Space" on page 996

Repeater Table Cell

A cell in an active report repeater table.

Properties of Repeater Table Cell

"Background Color" on page 881, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Conditional Styles" on page 895, "Direction & Justification" on page 907, "Font" on page 916, "Foreground Color" on page 917, "Horizontal Alignment" on page 922, "Padding" on page 949, "Size & Overflow" on page 974, "Spacing & Breaking" on page 977, "Style Variable" on page 979, "Vertical Alignment" on page 995, "White Space" on page 996

Report Reference

A reference to a report, a report view, or another booklet in a report booklet.

Properties of Report Reference

"Name" on page 942, "Pagination" on page 950, "Referenced Report" on page 959, "Roll Up Table of Contents" on page 965, "Saved Parameter Values" on page 967, "Show Prompt Pages" on page 973, "Start Heading Level" on page 979, "Table of Contents Entry" on page 982

Rich Text Item

Inserts an object that is used to render a subset of HTML in the layout. The HTML may come from either a static or dynamic source, and the object will also render in PDF output. For information about what elements are allowed in rich text items, see Elements Supported in Rich Text Items.

Properties of Rich Text Item

“Aggregate Function” on page 873, *“Control Data Item Value”* on page 898, *“Data Item Label”* on page 902, *“Data Item Value”* on page 903, *“Description”* on page 906, *“Expression”* on page 913, *“Hierarchy”* on page 921, *“Hierarchy Unique Name”* on page 921, *“HTML”* on page 923, *“HTML Source Variable”* on page 923, *“Level”* on page 930, *“Level Unique Name”* on page 930, *“Member”* on page 938, *“Member Unique Name”* on page 939, *“Name”* on page 942, *“Property Unique Name”* on page 956, *“Render Variable”* on page 961, *“Report Expression”* on page 962, *“Rollup Aggregate Function”* on page 965, *“Root Members Only”* on page 966, *Set Definition*, *“Set Sorting”* on page 970, *“Source Type”* on page 977

Row Number

Shows the row numbers in a column.

Properties of Row Number

“Background Color” on page 881, *“Classes”* on page 891, *“Data Format”* on page 900, *“Display for Orientation”* on page 908, *“Font”* on page 916, *“Foreground Color”* on page 917, *“Margin”* on page 932, *“Relative Alignment”* on page 959

Row Number

Shows the row numbers in a column in an active report. The active report row number object will always reflect the visible row number in the report. The report row number object reflects the server calculated row number.

Properties of Row Number

“Background Color” on page 881, *“Classes”* on page 891, *“Data Format”* on page 900, *“Direction & Justification”* on page 907, *“Display for Orientation”* on page 908, *“Font”* on page 916, *“Foreground Color”* on page 917, *“Margin”* on page 932, *“Relative Alignment”* on page 959

Scatter Chart

A point chart that plots one or more data series against two measures. Multiple points are plotted for each category. This object applies only to legacy charts.

Properties of Scatter Chart

“Alternate Text” on page 875, *“Application Drill-Through”* on page 876, *“Background Color”* on page 881, *“Background Effects”* on page 881, *“Baselines”* on page 883, *“Border”* on page 884, *“Border Color”* on page 884, *“Borders”* on page 885, *“Box Type”* on page 886, *“Classes”* on page 891, *“Clickable Regions”* on page 893, *“Conditional Palette”* on page 895, *“Container Selection”* on page 897, *“Display for Orientation”* on page 908, *“Drill-Through Definitions”* on page 910, *“Legend”* on page 928, *“Margin”* on page 932, *“Markers”* on page 933, *“Marker Size (pt)”* on page 934, *“Marker Text Location”* on page 935, *“Master Detail Relationships”* on page 935, *“Maximum Hotspots”* on page 936, *“Name”* on page 942

939, "No Data Contents" on page 945, "Notes" on page 945, "Padding" on page 949, "Pagination" on page 950, "Palette" on page 950, "Point Shape" on page 953, "Query" on page 957, "Regression Line" on page 959, "Relative Alignment" on page 959, "Render Page when Empty" on page 960, "Render Variable" on page 961, "Set Variable Values" on page 970, "Show Hover" on page 971, "Show Pointer Cursor" on page 972, "Size & Overflow" on page 975, "Suppression" on page 981, "Title" on page 985, "Tooltips" on page 986, "Value Location:" on page 993, "Values" on page 994, "Visible" on page 996, "X Axis" on page 997, "Y Axis" on page 998

Scatter Chart

A point chart that plots one or more data series against two measures. Multiple points are plotted for each category.

Properties of Scatter Chart

"Alternate Text" on page 875, "Application Drill-Through" on page 876, "Background Effects" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Clickable Regions" on page 893, "Color by Value" on page 893, "Colored Regions" on page 893, "Conditional Palette" on page 895, "Contained Text Direction" on page 897, "Container Selection" on page 897, "Direction & Justification" on page 907, "Display for Orientation" on page 908, "Drill-Through Definitions" on page 910, "Drop Shadow" on page 911, "Legend" on page 929, "Margin" on page 932, "Markers" on page 934, "Master Detail Relationships" on page 935, "Material Effects" on page 935, "Matrix Rows and Columns" on page 936, "Maximum Hotspots" on page 936, "Name" on page 942, "No Data Contents" on page 945, "Notes" on page 946, "Numeric Baselines" on page 948, "Padding" on page 949, "Pagination" on page 950, "Palette" on page 951, "Plot Area Fill" on page 953, "Query" on page 957, "Relative Alignment" on page 959, "Render Page when Empty" on page 960, "Render Variable" on page 961, "Set Variable Values" on page 970, "Show Hover" on page 971, "Show Pointer Cursor" on page 972, "Show Values" on page 974, "Size & Overflow" on page 975, "Suppression" on page 981, "Title" on page 985, "Tooltips" on page 986, "Trendlines" on page 988, "Visible" on page 996

Scatter Marker

A marker, or symbol, that you can place at a static place in a chart. Markers can designate a point of significance that may help you analyze or understand the data.

Properties of Scatter Marker

"Aggregate Function" on page 873, "Expression" on page 913, "Hierarchy" on page 921, "Hierarchy Unique Name" on page 921, "Label Location" on page 927, "Level" on page 930, "Level Unique Name" on page 930, "Marker Shape" on page 934, "Marker Size (pt)" on page 934, "Marker Style" on page 934, "Master Detail Relationships" on page 935, "Member" on page 938, "Member Unique Name" on page 939, "Properties" on page 956, "Property Unique Name" on page 956, "Query" on page 957, "Render Variable" on page 961, "Rollup Aggregate Function" on page 965, "Root Members Only" on page 966, "Set Definition", "Set Sorting" on page 970, "X-Axis Data Item Value" on page 998, "Y-Axis Data Item Value" on page 999

Secondary Axis

The generic numeric axis for the combination chart. This axis is normally shown as the top-right axis but can be in a different position depending on the chart orientation, as specified in the Chart Orientation property of the chart.

Properties of Secondary Axis

“Axis Labels” on page 879, “Axis Line” on page 879, “Axis Range” on page 880, “Axis Title” on page 880, “Axis Title” on page 880, “Gridlines” on page 919, “Minor Gridlines” on page 940, “Number of Minor Intervals” on page 946

Secondary Bottom Axis

The numeric axis for a combination chart. This axis is normally shown as the bottom-right axis, but can change depending on the orientation of the chart, as specified in the Chart Orientation property of the chart.

Properties of Secondary Bottom Axis

“Axis Labels” on page 879, “Axis Line” on page 879, “Axis Range” on page 880, “Axis Title” on page 880, “Axis Title” on page 880, “Gridlines” on page 919, “Minor Gridlines” on page 940, “Number of Minor Intervals” on page 946

Select & Search Prompt

An advanced prompt control that allows you to search for values. You cannot use this prompt control with SAP BW data sources.

Properties of Select & Search Prompt

“Box Type” on page 886, “Cascade Source” on page 889, “Case Insensitive” on page 889, “Choices Deselect All Text” on page 891, “Choices Select All Text” on page 891, “Choices Text” on page 891, “Conditional Styles” on page 895, “Contained Text Direction” on page 897, “Data Format” on page 900, “Deselect Text” on page 906, “Direction & Justification” on page 907, “Display Value” on page 909, “Hide Adornments” on page 921, “Insert Text” on page 924, “Keywords Text” on page 925, “Multi-Select” on page 941, “Name” on page 942, “Options Text” on page 948, “Parameter” on page 951, “Properties” on page 956, “Query” on page 957, “Remove Text” on page 960, “Render Variable” on page 961, “Required” on page 963, “Results Deselect All Text” on page 964, “Results Select All Text” on page 964, “Results Text” on page 964, “Rows Per Page” on page 967, “Search Instructions Text” on page 968, “Search Text” on page 968, “Sorting” on page 976, “Static Choices” on page 979, “Style Variable” on page 979, “Use Value” on page 993, “Visible” on page 996

Set Expression

A set of members.

Properties of Set Expression

“Detail” on page 906, “Dimension” on page 907, “Expression” on page 913, “Hierarchy” on page 921, “Label” on page 926, “Name” on page 941, “Set Sorting” on page 970, “Type” on page 989

Singleton

A query item that you can insert anywhere in the layout of your report where there is no query associated. When the report is run, the singleton object retrieves only the first row value for that query. Singletons are useful for adding boilerplate text to a report, such as a company name or address, to add overall calculations in a report, or to add multidimensional cell calculations in a report.

Properties of Singleton

“Name” on page 942, “Properties” on page 956, “Query” on page 957, “Render Variable” on page 961

Slicer Member Set

A set expression that returns members from a single hierarchy of a single dimension.

Properties of Slicer Member Set

“Expression” on page 913

Slider Value Label

The label used to identify each value in a data discrete values slider control. Each label is determined by the data items inserted into the control

Properties of Slider Value Label

“Data Format” on page 900

SQL

An SQL query against a relational data source.

Properties of SQL

“Data Source” on page 904, “Name” on page 943, “SQL” on page 977, “SQL Syntax” on page 978

Static Repeater Table

An active report layout object that is used to present data in a repeating structure. Repeater table controls allow you to create button bars or grids of custom content that control the content that appears in other controls.

Properties of Static Repeater Table

“Across” on page 872, “Application Drill-Through” on page 876, “Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Clickable Regions” on page 893, “Conditional Styles” on page 895, “Container Filter” on page 897, “Container Selection” on page 897, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Down” on page 910, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Margin” on page 932, “Name” on page 942, “Relative Alignment” on page 959, “Render Variable” on page 961, “Repeater Direction” on page 961, “Repeater Table Values Definition” on page 962, “Set Variable Values” on page 970, “Show Hover” on page 971, “Show Pointer Cursor” on page 972, “Size &

“Overflow” on page 974, “Style Variable” on page 979, “Table Properties” on page 982, “Visible” on page 996

Summary Filter

A set of conditions in a query that narrow the scope of the data returned. A summary filter is applied after aggregation is complete.

Properties of Summary Filter

“Definition” on page 906, “Scope” on page 967, “Usage” on page 990

Tab

A tab in a static tab control.

Properties of Tab

“Icon” on page 923, “Label” on page 926

Tab Control

A static tab control. Each tab requires a corresponding row in the data table of the control.

Properties of Tab Control

“Application Drill-Through” on page 876, “Contained Text Direction” on page 897, “Container Selection” on page 897, “Current Tab” on page 900, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Name” on page 942, “Render Variable” on page 961, “Set Variable Values” on page 970, “Size” on page 974, “Tab Orientation” on page 982, “Tabs Definition” on page 982, “Tab Width” on page 982

Table

A collection of cells in which objects can be organized in a grid fashion.

Properties of Table

“Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Drop Shadow” on page 911, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Margin” on page 932, “Name” on page 942, “Pagination” on page 950, “Relative Alignment” on page 959, “Render Variable” on page 961, “Size & Overflow” on page 974, “Style Variable” on page 979, “Summary Text” on page 981, “Table Properties” on page 982, “Visible” on page 996

Table Cell

The cells within a row.

Properties of Table Cell

“Background Color” on page 881, “Background Effects” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Direction & Justification” on page 907, “Font” on page 916,

“Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Padding” on page 949, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Table Header” on page 981, “Vertical Alignment” on page 995, “White Space” on page 996

Table of Contents

A collection of Table of Contents Entry objects that refer the same table of contents. The table of contents is generated in the rendered output.

Properties of Table of Contents

“Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Margin” on page 932, “No Data Contents” on page 945, “Padding” on page 949, “Render Page when Empty” on page 960, “Render Variable” on page 961, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Table of Contents Name” on page 982, “Visible” on page 996, “White Space” on page 996

Table of Contents Entry

An entry in the table of contents.

Properties of Table of Contents Entry

“Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “Heading Level” on page 920, “Horizontal Alignment” on page 922, “Margin” on page 932, “Padding” on page 949, “Render Variable” on page 961, “Size & Overflow” on page 974, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Table of Contents” on page 982, “Visible” on page 996, “White Space” on page 996

Table Row

The rows in a table.

Properties of Table Row

“Background Color” on page 881, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Font” on page 916, “Foreground Color” on page 917, “Horizontal Alignment” on page 922, “Style Variable” on page 979, “Vertical Alignment” on page 995

Target Measure

The target measure for a bullet chart.

Properties of Target Measure

“Custom Label” on page 900, “Data Format” on page 900

Target Measure

The target measure for a metrics range chart.

Properties of Target Measure

“Conditional Styles” on page 895, “Custom Label” on page 900, “Data Format” on page 900, “Style Variable” on page 979

Text Box Prompt

A prompt control that allows you to type in a value.

Properties of Text Box Prompt

“Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Choices Deselect All Text” on page 891, “Choices Select All Text” on page 891, “Choices Text” on page 891, “Conditional Styles” on page 895, “Contained Text Direction” on page 897, “Default Selections” on page 905, “Deselect Text” on page 906, “Direction & Justification” on page 907, “Font” on page 916, “Foreground Color” on page 917, “From Text” on page 917, “Hide Adornments” on page 921, “Hide Text” on page 921, “Highest Value Text” on page 922, “Insert Text” on page 924, “Lowest Value Text” on page 932, “Multi-Line” on page 941, “Multi-Select” on page 941, “Name” on page 942, “Numbers Only” on page 947, “Parameter” on page 951, “Range” on page 958, “Relative Alignment” on page 959, “Remove Text” on page 960, “Render Variable” on page 961, “Required” on page 963, “Size & Overflow” on page 974, “Style Variable” on page 979, “To Text” on page 987, “Use Thousands Separator” on page 993, “Visible” on page 996

Text Item

A text item in a report. The content can be static text, or it can come from a query item or report expression.

Properties of Text Item

“Aggregate Function” on page 873, “Background Color” on page 881, “Border” on page 884, “Box Type” on page 886, “Classes” on page 891, “Conditional Styles” on page 895, “Control Data Item Value” on page 898, “Data Format” on page 900, “Data Item Label” on page 902, “Data Item Value” on page 902, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Drill-Through Definitions” on page 910, “Expression” on page 913, “Font” on page 916, “Foreground Color” on page 917, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Label For” on page 927, “Level” on page 930, “Level Unique Name” on page 930, “Margin” on page 932, “Maximum Characters” on page 936, “Member” on page 938, “Member Unique Name” on page 939, “Name” on page 942, “Padding” on page 949, “Property Unique Name” on page 956, “Relative Alignment” on page 959, “Render Variable” on page 961, “Report Expression” on page 962, “Rollup Aggregate Function” on page 965, “Root Members Only” on page 966, Set Definition, “Set Sorting” on page 970, “Size & Overflow” on page 974, “Source Type” on page 976, “Spacing & Breaking” on page 977, “Style Variable” on page 979, “Text” on page 983, “Text Source Variable” on page 984, “Use Detail Value on Page” on page 991, “Visible” on page 996

Time

Returns the time on the report server when the report server started rendering the report.

Properties of Time

“Background Color” on page 881, “Classes” on page 891, “Data Format” on page 900, “Display for Orientation” on page 908, “Font” on page 916, “Foreground Color” on page 917, “Margin” on page 932, “Relative Alignment” on page 959

Time Prompt

An advanced prompt control that allows you to select a time value.

Properties of Time Prompt

“Box Type” on page 886, “Choices Deselect All Text” on page 891, “Choices Select All Text” on page 891, “Choices Text” on page 891, “Clock Mode” on page 893, “Conditional Styles” on page 895, “Contained Text Direction” on page 897, “Default Selections” on page 905, “Deselect Text” on page 906, “Direction & Justification” on page 907, “Display Milliseconds” on page 909, “Display Seconds” on page 909, “From Text” on page 917, “Hide Adornments” on page 921, “Highest Value Text” on page 922, “Insert Text” on page 924, “Lowest Value Text” on page 932, “Multi-Select” on page 941, “Name” on page 942, “Parameter” on page 951, “Range” on page 958, “Remove Text” on page 960, “Render Variable” on page 961, “Required” on page 963, “Select UI” on page 969, “Style Variable” on page 979, “To Text” on page 987, “Visible” on page 996

Toggle Button Bar

A static toggle button bar control. Each toggle button requires a corresponding row in the data table of the control.

Properties of Toggle Button Bar

“Application Drill-Through” on page 876, “Button Gap” on page 887, “Buttons Definition” on page 887, “Button Width” on page 888, “Contained Text Direction” on page 897, “Container Selection” on page 897, “Control Enable” on page 899, “Direction & Justification” on page 907, “Display for Orientation” on page 908, “Name” on page 942, “Orientation” on page 948, “Render Variable” on page 961, “Set Variable Values” on page 970

Tolerance Measure

The tolerance measure for a metrics chart.

Properties of Tolerance Measure

“Conditional Styles” on page 895, “Custom Label” on page 900, “Data Format” on page 900, “Style Variable” on page 979

Total Column

A column or bar representing the total cumulative value of all other columns or bars in a progressive chart.

Properties of Total Column

“Aggregate Function” on page 873, “Data Format” on page 900, “Data Item Value” on page 902, “Expression” on page 913, “Hierarchy” on page 921, “Hierarchy Unique Name” on page 921, “Level” on page 930, “Level Unique Name” on page 930, “Member” on page 938, “Member Unique Name” on page 939, “Properties” on page 956

on page 953, "Property Unique Name" on page 956, "Report Expression" on page 962, "Rollup Aggregate Function" on page 965, "Root Members Only" on page 966, Set Definition, "Set Sorting" on page 970, "Text" on page 983, "Total Column Color" on page 987

Total Column Label

The label to be rendered for the total column.

Properties of Total Column Label

"Properties" on page 956

Tree Prompt

A data-driven prompt control that shows hierarchical information and allows you to select one or more members.

Properties of Tree Prompt

"Cascade Source" on page 889, "Conditional Styles" on page 895, "Contained Text Direction" on page 897, "Default Selections" on page 905, "Deselect Text" on page 906, "Direction & Justification" on page 907, "Hide Adornments" on page 921, "Multi-Select" on page 941, "Name" on page 942, "Parameter" on page 951, "Pre-populate" on page 954, "Pre-populate Levels" on page 954, "Query" on page 957, "Render Variable" on page 961, "Required" on page 963, "Results Deselect All Text" on page 964, "Results Select All Text" on page 964, "Rows Per Page" on page 967, "Size & Overflow" on page 974, "Sorting" on page 976, "Style Variable" on page 979, "Use Value" on page 993, "Visible" on page 996

Trendline

A line or curve that indicates the general direction of the data over time.

Properties of Trendline

"Based on" on page 883, "Line Style" on page 931, "Render Variable" on page 961, "Trendline Label" on page 988, "Type" on page 989

Trendline Label

A label that will be shown in the legend for the trend line.

Properties of Trendline Label

"Conditional Styles" on page 895, "Data Format" on page 900, "Properties" on page 956, "Query" on page 957

Value

The return value from the evaluation of the report variable.

Value

A group of two or more variable values.

Value

A measure or single value that is used to plot data in a visualization.

Properties of Value

"Data Format" on page 901, "Label" on page 926, "Rollup Method" on page 965, "Use Decimal" on page 990, "Value Range" on page 994

Value Prompt

A prompt control that allows you to select one or more values from a list.

Properties of Value Prompt

"Auto-Submit" on page 877, "Background Color" on page 881, "Box Type" on page 886, "Cascade Source" on page 889, "Choices Deselect All Text" on page 891, "Choices Select All Text" on page 891, "Choices Text" on page 891, "Conditional Styles" on page 895, "Contained Text Direction" on page 897, "Data Format" on page 900, "Default Selections" on page 905, "Deselect Text" on page 906, "Direction & Justification" on page 907, "Display Value" on page 909, "Font" on page 916, "Foreground Color" on page 917, "From Text" on page 917, "Header Text" on page 920, "Hide Adornments" on page 921, "Highest Value Text" on page 922, "Insert Text" on page 924, "Lowest Value Text" on page 932, "Multi-Select" on page 941, "Name" on page 942, "Parameter" on page 951, "Pre-populate" on page 954, "Properties" on page 956, "Query" on page 957, "Range" on page 958, "Relative Alignment" on page 959, "Remove Text" on page 960, "Render Variable" on page 961, "Required" on page 963, "Results Deselect All Text" on page 964, "Results Select All Text" on page 964, "Rows Per Page" on page 967, "Select UI" on page 968, "Size & Overflow" on page 974, "Sorting" on page 976, "Static Choices" on page 979, "Style Variable" on page 979, "To Text" on page 987, "Use Value" on page 993, "Visible" on page 996

Variable

A report variable.

Properties of Variable

"Name" on page 944, "Report Expression" on page 963, "Type" on page 988

Variable Text Item

A text item that renders the value of an active report variable.

Properties of Variable Text Item

"Active Report Variable" on page 873, "Background Color" on page 881, "Border" on page 884, "Box Type" on page 886, "Classes" on page 891, "Data Format" on page 900, "Direction & Justification" on page 907, "Display for Orientation" on page 908, "Display Values" on page 910, "Font" on page 916, "Foreground Color" on page 917, "Margin" on page 932, "Padding" on page 949, "Relative Alignment" on page 959, "Render Variable" on page 961, "Size & Overflow" on page 974, "Spacing & Breaking" on page 977, "Visible" on page 996

Visualization

A visual representation of data.

Properties of Visualization

“Alternate Text” on page 875, *“Clickable Regions”* on page 893, *“Data Format”* on page 901, *“Display for Orientation”* on page 908, *“Name”* on page 942, *“Render Method”* on page 960, *“Render Variable”* on page 961, *“Set Variable Values”* on page 970, *“Type”* on page 989, *“Use Embedded Data”* on page 991

Win-Loss Chart

A microchart in which the value of each column is either 1 or -1, often denoting a win or a loss.

Properties of Win-Loss Chart

“Allow Ties” on page 875, *“Axis Line”* on page 879, *“Background Color”* on page 881, *“Background Effects”* on page 881, *“Border”* on page 884, *“Border Color”* on page 884, *“Borders”* on page 885, *“Box Type”* on page 886, *“Chart Orientation”* on page 890, *“Classes”* on page 891, *“Conditional Styles”* on page 895, *“Drill-Through Definitions”* on page 910, *“Font”* on page 916, *“Footer”* on page 916, *“Foreground Color”* on page 917, *“Loss Color”* on page 932, *“Margin”* on page 932, *“Master Detail Relationships”* on page 935, *“Maximum Hotspots”* on page 936, *“Name”* on page 942, *“No Data Contents”* on page 945, *“Padding”* on page 949, *“Pagination”* on page 950, *“Query”* on page 957, *“Relative Alignment”* on page 959, *“Render Page when Empty”* on page 960, *“Render Variable”* on page 961, *“Size & Overflow”* on page 974, *“Style Variable”* on page 979, *“Subtitle”* on page 980, *“Suppression”* on page 981, *“Title”* on page 985, *“Tooltips”* on page 986, *“Visible”* on page 996, *“Win Color”* on page 997, *“Win-Loss Threshold”* on page 997

Win-Loss Measure

The measure for a win-loss chart.

Properties of Win-Loss Measure

“Aggregate Function” on page 873, *“Custom Label”* on page 900, *“Data Format”* on page 900, *“Expression”* on page 913, *“Hierarchy”* on page 921, *“Hierarchy Unique Name”* on page 921, *“Level”* on page 930, *“Level Unique Name”* on page 930, *“Member”* on page 938, *“Member Unique Name”* on page 939, *“Property Unique Name”* on page 956, *“Rollup Aggregate Function”* on page 965, *“Root Members Only”* on page 966, *Set Definition*, *“Set Sorting”* on page 970

X Axis

The horizontal numeric axis for the chart, including labels, titles, range, and scale.

Properties of X Axis

“Axis Labels” on page 879, *“Axis Line”* on page 879, *“Axis Title”* on page 880, *“Axis Title”* on page 880, *“Classes”* on page 891, *“Data Format”* on page 900, *“Gridlines”* on page 919, *“Include Zero For Auto Scale”* on page 923, *“Maximum Value”* on page 938, *“Minimum Value”* on page 940, *“Minor Gridlines”* on page 940, *“Scale”* on page 967, *“Scale Interval”* on page 967, *“Use Same Range For All Instances”* on page 992

X Axis

The x-axis on a scatter or bubble chart.

Properties of X Axis

"Axis Labels" on page 879, "Axis Line" on page 879, "Axis Range" on page 880, "Axis Title" on page 880, "Axis Title" on page 880, "Gridlines" on page 919, "Minor Gridlines" on page 940, "Number of Minor Intervals" on page 946

X Axis

The axis line for an ordinal, or non-numeric, axis.

Properties of X Axis

"Allow 45° Rotation" on page 874, "Allow 90° Rotation" on page 874, "Allow Skip" on page 874, "Allow Stagger" on page 874, "Axis Labels" on page 879, "Axis Line" on page 879, "Axis Title" on page 880, "Axis Title" on page 880, "Classes" on page 891, "Display Frequency" on page 909, "Drill-Through Definitions" on page 910, "First Label Index" on page 915, "Gridlines" on page 919, "Label Control" on page 927, "Maximum Truncation Characters" on page 937, "Minor Gridlines" on page 940, "Truncation" on page 988, "Truncation Text" on page 988

X Axis Measure

The measure for the horizontal axis of a scatter chart or bubble chart.

Properties of X Axis Measure

"Conditional Styles" on page 895, "Custom Label" on page 900, "Data Format" on page 900, "Style Variable" on page 979

Y1 Axis

The numeric axis of a metrics chart, or the primary numeric axis of a combination chart.

Properties of Y1 Axis

"Axis Labels" on page 879, "Axis Line" on page 879, "Axis Title" on page 880, "Axis Title" on page 880, "Classes" on page 891, "Data Format" on page 900, "Gridlines" on page 919, "Include Zero For Auto Scale" on page 923, "Maximum Value" on page 938, "Minimum Value" on page 940, "Minor Gridlines" on page 940, "Scale" on page 967, "Scale Interval" on page 967, "Use Same Range For All Instances" on page 992

Y2 Axis

The secondary numeric axis of a combination chart.

Properties of Y2 Axis

"Axis Labels" on page 879, "Axis Line" on page 879, "Axis Title" on page 880, "Axis Title" on page 880, "Classes" on page 891, "Data Format" on page 900, "Gridlines" on page 919, "Include Zero For Auto Scale" on page 923, "Maximum Value" on page 938, "Minimum Value" on page 940, "Minor Gridlines" on page 940, "Scale" on page 967, "Scale Interval" on page 967, "Use Same Range For All Instances" on page 992

Y Axis

The vertical numeric axis for the chart, including labels, titles, range, and scale.

Properties of Y Axis

"Axis Labels" on page 879, *"Axis Line"* on page 879, *"Axis Title"* on page 880, *"Axis Title"* on page 880, *"Classes"* on page 891, *"Data Format"* on page 900, *"Gridlines"* on page 919, *"Include Zero For Auto Scale"* on page 923, *"Maximum Value"* on page 938, *"Minimum Value"* on page 940, *"Minor Gridlines"* on page 940, *"Scale"* on page 967, *"Scale Interval"* on page 967, *"Use Same Range For All Instances"* on page 992

Y Axis

The y-axis on a scatter or bubble chart.

Properties of Y Axis

"Axis Labels" on page 879, *"Axis Line"* on page 879, *"Axis Range"* on page 880, *"Axis Title"* on page 880, *"Axis Title"* on page 880, *"Gridlines"* on page 919, *"Minor Gridlines"* on page 940, *"Number of Minor Intervals"* on page 946

Y Axis

The axis line for an ordinal, or non-numeric, axis.

Properties of Y Axis

"Allow 45° Rotation" on page 874, *"Allow 90° Rotation"* on page 874, *"Allow Skip"* on page 874, *"Allow Stagger"* on page 874, *"Axis Labels"* on page 879, *"Axis Line"* on page 879, *"Axis Title"* on page 880, *"Axis Title"* on page 880, *"Classes"* on page 891, *"Display Frequency"* on page 909, *"Drill-Through Definitions"* on page 910, *"First Label Index"* on page 915, *"Gridlines"* on page 919, *"Label Control"* on page 927, *"Maximum Truncation Characters"* on page 937, *"Minor Gridlines"* on page 940, *"Truncation"* on page 988, *"Truncation Text"* on page 988

Y Axis Measure

The measure for the vertical axis of a scatter chart or bubble chart.

Properties of Y Axis Measure

"Conditional Styles" on page 895, *"Custom Label"* on page 900, *"Data Format"* on page 900, *"Style Variable"* on page 979

Z Axis

The third numeric axis for a three-dimensional scatter chart, including labels, titles, range, and scale.

Properties of Z Axis

"Axis Labels" on page 879, *"Axis Line"* on page 879, *"Axis Title"* on page 880, *"Axis Title"* on page 880, *"Classes"* on page 891, *"Data Format"* on page 900, *"Gridlines"* on page 919, *"Include Zero For Auto Scale"* on page 923, *"Maximum Value"* on page 938, *"Minimum Value"* on page 940, *"Minor Gridlines"* on page 940

937, "Scale" on page 967, "Scale Interval" on page 967, "Use Same Range For All Instances" on page 992

Z Axis

The vertical numeric axis for a three-dimensional combination chart, including labels, titles, range, and scale.

Properties of Z Axis

"Axis Labels" on page 879, "Axis Line" on page 879, "Axis Title" on page 880, "Axis Title" on page 880, "Classes" on page 891, "Data Format" on page 900, "Gridlines" on page 919, "Include Zero For Auto Scale" on page 923, "Maximum Value" on page 938, "Minimum Value" on page 940, "Minor Gridlines" on page 940, "Scale" on page 967, "Scale Interval" on page 967, "Use Same Range For All Instances" on page 992

Z Axis Measure

The measure for the third axis of a three-dimensional scatter chart.

Properties of Z Axis Measure

"Conditional Styles" on page 895, "Custom Label" on page 900, "Data Format" on page 900, "Style Variable" on page 979

Report Studio Properties

The following is a list of properties available in the lower left pane of IBM® Cognos® Report Studio.

3-D Viewing Angle

Specifies the 3-D viewing angle of the chart.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800

Absolute Position

Specifies that the legend will be positioned absolutely, by setting its pixel position.

Applies to

"Legend" on page 833

Across

Sets the number of times across, or horizontally, that the contents of the object may be rendered.

The default value depends on the setting of the **Repeater Direction** property. If it is set to **Left to right, top to bottom**, the default is one. If it is set to **Top to bottom, left to right**, the default is 20.

Applies to

“Repeater Table” on page 857, “Static Repeater Table” on page 862

Active Dot Color

Specifies the color of the dot of the selected value in the iterator.

Applies to

“Iterator Label Area” on page 832

Active Report Variable

Specifies the variable to use in the control.

Applies to

“Variable Text Item” on page 868

Actual Measure

The measure that is used to show values as a percentage of a summary.

Applies to

“Percentaged Measure” on page 850

Aggregate Data Item

Specifies the data item that is used to calculate the summary or aggregation.

Applies to

“Dimensional Edge Summary” on page 825, “Edge Summary” on page 826, “List Summary” on page 840

Aggregate Function

Specifies the type of aggregation to apply. The Automatic setting means that the application groups or summarizes based on the data type. The Summarize setting means that any setting found in the model will be used to determine the type of aggregation. The default setting is Automatic.

Applies to

“Area” on page 801, “Bar” on page 802, “Category Baseline” on page 808, “Chart Node Member” on page 809, “Chart Text Item” on page 810, “Chart Text Item” on page 810, “Colored Region” on page 812, “Colored Region” on page 812, “Crosstab Corner” on page 816, “Crosstab Fact Cells” on page 816, “Crosstab Intersection” on page 816, “Crosstab Member Fact Cells” on page 817, “Crosstab Node Member” on page 817, “Cumulation Line Label” on page 819, “Data Item” on page 821, “Gauge Axis” on page 827, “HTML Item” on page 829, “Image” on page 831, “Line” on page 835, “List Cell” on page 836, “List Column Body” on page 837, “List Column Title” on page 838, “Map Location” on page 841, “Map Location” on page 841, “Map Refinement Location” on page 841, “Map Refinement Location” on page 842, “Marker” on page 842, “Numeric Baseline” on page 847, “Rich Text Item” on page 859, “Scatter Marker” on page 860, “Text Item” on page 865, “Total Column” on page 866

page 866, "Win-Loss Measure" on page 869

Aggregation Method

Specifies the type of summary or aggregation that is applied.

Applies to

"Dimensional Edge Summary" on page 825, "Edge Summary" on page 826

Aggregation Method

Specifies the type of summary or aggregation that is applied.

Applies to

"List Summary" on page 840

Allow 45° Rotation

Specifies whether the labels can be rotated 45 degrees if the labels are long.

Applies to

"Category Axis" on page 808, "X Axis" on page 870, "Y Axis" on page 871

Allow 90° Rotation

Specifies whether the labels can be rotated 90 degrees if the labels are long.

Applies to

"Category Axis" on page 808, "X Axis" on page 870, "Y Axis" on page 871

Allow Skip

Specifies whether some labels can be skipped if they are long.

Applies to

"Category Axis" on page 808, "X Axis" on page 870, "Y Axis" on page 871

Allow Sorting

Specifies whether sorting is allowed for the column when the active report is executed. You can set the value of this property for multiple objects simultaneously by first control+clicking the items in the report.

Applies to

"List Column" on page 836, "List Column Body" on page 837, "List Column Title" on page 838

Allow Stagger

Specifies whether the labels can be staggered if they are long.

Applies to

“Category Axis” on page 808, “X Axis” on page 870, “Y Axis” on page 871

Allow Ties

Specifies whether data values that equal the Win Loss Threshold property are converted to zero and mapped on the zero line.

Applies to

“Win-Loss Chart” on page 869

Alternate Text

Specifies a text alternative for non-text objects such as images and charts. Use to make reports accessible for people who use screen readers.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Bubble Chart” on page 805, “Bullet Chart” on page 805, “Combination Chart” on page 813, “Combination Chart” on page 813, “Gauge Chart” on page 828, “Gauge Chart” on page 828, “Image” on page 831, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Metric Studio Diagram” on page 845, “Pareto Chart” on page 849, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Pie Chart” on page 850, “Polar Chart” on page 852, “Progressive Chart” on page 853, “Progressive Chart” on page 854, “Radar Chart” on page 855, “Scatter Chart” on page 859, “Scatter Chart” on page 860, “Visualization” on page 868

Angular Axis

Specifies whether the axis is rendered.

Applies to

“Polar Chart” on page 852

Animate

Specifies whether to animate the movement of the slider.

Applies to

“Continuous Values Slider” on page 814, “Data Discrete Values Slider” on page 821, “Discrete Values Slider” on page 825

Application

Specifies if the condition will be applied before or after aggregation and summarization. When true, the condition will apply to the summarized rows, and a fact, or aggregate, in the expression will be interpreted as the aggregated value of the summarized rows. When false, the condition will apply to the detail database rows from the tabular result set prior to aggregation or summarization, and a fact, or aggregate, in the expression will be interpreted as the individual database value

before it has been summarized. This property has no effect on OLAP data sources, on references to non-aggregate items, or when automatic summarization is disabled.

Applies to

“Detail Filter” on page 825

Application Drill-Through

Specifies active report-to-active report drill-through definitions. This property enables drill-through from one active report to another active report when the reports are viewed in IBM® Cognos® Mobile.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Bubble Chart” on page 805, “Bullet Chart” on page 805, “Button” on page 806, “Button Bar” on page 806, “Check Box Group” on page 811, “Combination Chart” on page 813, “Combination Chart” on page 813, “Continuous Values Slider” on page 814, “Crosstab” on page 815, “Data Button Bar” on page 820, “Data Check Box Group” on page 820, “Data Container” on page 820, “Data Deck” on page 821, “Data Discrete Values Slider” on page 821, “Data Drop-Down List” on page 821, “Data Iterator” on page 822, “Data List Box” on page 822, “Data Radio Button Group” on page 822, “Data Tab Control” on page 823, “Data Toggle Button Bar” on page 823, “Deck” on page 824, “Discrete Values Slider” on page 825, “Drop-Down List” on page 826, “Gauge Chart” on page 828, “Gauge Chart” on page 828, “Iterator” on page 831, “List” on page 835, “List Box” on page 836, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Pie Chart” on page 850, “Polar Chart” on page 852, “Progressive Chart” on page 853, “Progressive Chart” on page 854, “Radar Chart” on page 855, “Radio Button Group” on page 856, “Repeater Table” on page 857, “Scatter Chart” on page 859, “Scatter Chart” on page 860, “Static Repeater Table” on page 862, “Tab Control” on page 863, “Toggle Button Bar” on page 866

Apply Single Class

Specifies whether to apply all of the classes defined or only one class. When set to Yes, the last class that was applied is used.

For example, if you applied a class to a crosstab intersection and another class to the member fact cells of a crosstab row, the class applied to the intersection is the last class applied to the fact cells. For information about the order in which classes are applied, see the topic [Create and Modify Report and Object Styles](#).

This property is set to Yes when you are upgrading a report so that the upgraded report will look the same as the original report. This is because objects in reports created using earlier versions of IBM® Cognos® Business Intelligence support only one class.

Applies to

“Crosstab Fact Cells” on page 816

Area Shape

Specifies the shape of an area in an area chart.

Applies to

“Area” on page 801

Auto Font Size

Specifies whether to automatically resize the font to fit the labels.

The setting for this property, as well as the category axis property Label Control, can impact the number of labels that are displayed.

Applies to

“Axis Labels” on page 802, “Axis Title” on page 802, “Legend” on page 834, “Legend Title” on page 834

Auto Group & Summarize

Specifies whether the application will apply suggested aggregate functions to aggregate data items and group all non-aggregate data items, producing groups and summary rows. If it is set to No, detail rows will be rendered.

Applies to

“Query” on page 854

Auto Select

Specifies to automatically select the first or last item in a control. When a value other than None is selected, any condition that is defined in the Container Selection property is removed.

Applies to

“Data Drop-Down List” on page 821, “Data List Box” on page 822, “Data Radio Button Group” on page 822, “Drop-Down List” on page 826, “List Box” on page 836, “Radio Button Group” on page 856

Auto-Sort

When running the report, specifies whether to automatically sort based on data type.

Applies to

“Query” on page 854

Auto-Submit

Specifies whether the application submits the prompt page automatically, as soon as a value is changed.

Applies to

“Value Prompt” on page 868

Auto Truncation

Specifies whether to allow truncation of text.

Applies to

“Legend” on page 833

Avoid Division by Zero

Specifies whether the application will return a null value when it encounters a division by zero. This property applies only to relational data sources.

Applies to

“Query” on page 854

Avoid Label Collision

Controls how labels are arranged. If set to false, the chart uses the default positions. If set to true, the chart uses a different layout to avoid label collision. To keep existing reports unchanged, set this property to false.

Applies to

“Pie Chart” on page 850

Axis Angles

Specifies the start and end angle and the direction of the gauge axis. All angles are measured in degrees starting from the three o'clock position.

Applies to

“Gauge Axis” on page 827

Axis Assignment

Specifies the numeric axis to use. This property applies only to legacy charts.

Applies to

“Area” on page 801, “Bar” on page 802, “Baseline” on page 803, “Line” on page 835, “Marker” on page 843

Axis Assignment

Specifies which numeric axis to use.

Applies to

“Baseline” on page 803

Axis Justification

Specifies whether the data labels are aligned to the inside or outside of the gauge axis.

Applies to

"Gauge Axis" on page 827

Axis Labels

Specifies whether to show or hide axis labels.

Applies to

"Category axis" on page 808, *"Cumulation Line"* on page 819, *"Gauge Axis"* on page 827, *"Numeric Axis"* on page 847, *"Pareto Bars"* on page 848, *"Primary Axis"* on page 853, *"Primary Bottom Axis"* on page 853, *"Secondary Axis"* on page 861, *"Secondary Bottom Axis"* on page 861, *"X Axis"* on page 869, *"Y Axis"* on page 871

Axis Labels

Specifies whether to show or hide axis labels. This property applies only to legacy charts.

Applies to

"Angular Axis" on page 801, *"Category Axis"* on page 808, *"Cumulation Line Axis"* on page 819, *"Numerical Axis"* on page 846, *"Numerical Axis"* on page 847, *"Radial Axis"* on page 855, *"X Axis"* on page 869, *"X Axis"* on page 870, *"Y1 Axis"* on page 870, *"Y2 Axis"* on page 870, *"Y Axis"* on page 871, *"Y Axis"* on page 871, *"Z Axis"* on page 871, *"Z Axis"* on page 872

Axis Line

Specifies the properties of the axis line in a chart. This property applies only to legacy charts.

Applies to

"Angular Axis" on page 801, *"Category Axis"* on page 808, *"Cumulation Line Axis"* on page 819, *"Numerical Axis"* on page 846, *"Numerical Axis"* on page 847, *"Radial Axis"* on page 855, *"Win-Loss Chart"* on page 869, *"X Axis"* on page 869, *"X Axis"* on page 870, *"Y1 Axis"* on page 870, *"Y2 Axis"* on page 870, *"Y Axis"* on page 871, *"Y Axis"* on page 871, *"Z Axis"* on page 871, *"Z Axis"* on page 872

Axis Line

Specifies the properties of the axis line in a chart.

Applies to

"Category axis" on page 808, *"Cumulation Line"* on page 819, *"Numeric Axis"* on page 847, *"Pareto Bars"* on page 848, *"Primary Axis"* on page 853, *"Primary Bottom Axis"* on page 853, *"Secondary Axis"* on page 861, *"Secondary Bottom Axis"* on page 861, *"X Axis"* on page 869, *"Y Axis"* on page 871

Axis Line

Specifies the properties of the gauge axis line in a gauge chart.

Applies to

"Gauge Axis" on page 827

Axis Range

Specifies the appearance of the range of values on an axis.

Applies to

"Cumulation Line" on page 819, "Gauge Axis" on page 827, "Numeric Axis" on page 847, "Pareto Bars" on page 848, "Primary Axis" on page 853, "Primary Bottom Axis" on page 853, "Secondary Axis" on page 861, "Secondary Bottom Axis" on page 861, "X Axis" on page 869, "Y Axis" on page 871

Axis Title

Specifies whether an axis title is rendered.

Applies to

"Angular Axis" on page 801, "Category Axis" on page 808, "Category axis" on page 808, "Cumulation Line" on page 819, "Numerical Axis" on page 846, "Numerical Axis" on page 847, "Numeric Axis" on page 847, "Pareto Bars" on page 848, "Primary Axis" on page 853, "Primary Bottom Axis" on page 853, "Radial Axis" on page 855, "Secondary Axis" on page 861, "Secondary Bottom Axis" on page 861, "X Axis" on page 869, "X Axis" on page 869, "X Axis" on page 870, "Y1 Axis" on page 870, "Y2 Axis" on page 870, "Y Axis" on page 871, "Y Axis" on page 871, "Y Axis" on page 871, "Z Axis" on page 871, "Z Axis" on page 872

Axis Title

Specifies whether an axis title will be rendered. This property applies only to legacy charts.

Applies to

"Angular Axis" on page 801, "Category Axis" on page 808, "Cumulation Line Axis" on page 819, "Gauge Chart" on page 828, "Map" on page 841, "Numerical Axis" on page 846, "Numerical Axis" on page 847, "Pie Chart" on page 850, "Radial Axis" on page 855, "X Axis" on page 869, "X Axis" on page 870, "Y1 Axis" on page 870, "Y2 Axis" on page 870, "Y Axis" on page 871, "Y Axis" on page 871, "Z Axis" on page 871, "Z Axis" on page 872

Axis Title

Specifies whether to show the axis titles in a chart.

Applies to

"Category axis" on page 808, "Cumulation Line" on page 819, "Gauge Axis" on page 827, "Numeric Axis" on page 847, "Pareto Bars" on page 848, "Pie Chart" on page 850, "Primary Axis" on page 853, "Primary Bottom Axis" on page 853, "Secondary Axis" on page 861, "Secondary Bottom Axis" on page 861, "X Axis" on page 869, "Y Axis" on page 871

Background Color

Specifies the background color for the object.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Block" on page 804, "Bubble Chart" on page 804, "Caption" on page 807, "Chart Body" on page 808, "Chart Body" on page 809, "Combination Chart" on page 813, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Crosstab" on page 815, "Crosstab Columns" on page 815, "Crosstab Columns" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Rows" on page 817, "Crosstab Rows" on page 818, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Date" on page 823, "Field Set" on page 827, "Gauge Chart" on page 828, "Hyperlink" on page 830, "Hyperlink Button" on page 830, "Image" on page 831, "Legend" on page 833, "List" on page 835, "List Cell" on page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838, "List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "List Summary" on page 840, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Note Content" on page 846, "Page" on page 847, "Page Break Text" on page 848, "Page Number" on page 848, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 854, "Prompt Button" on page 854, "Radar Chart" on page 855, "Repeater Table" on page 857, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Row Number" on page 859, "Row Number" on page 859, "Scatter Chart" on page 859, "Static Repeater Table" on page 862, "Table" on page 863, "Table Cell" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Table Row" on page 864, "Text Box Prompt" on page 865, "Text Item" on page 865, "Time" on page 865, "Value Prompt" on page 868, "Variable Text Item" on page 868, "Win-Loss Chart" on page 869

Background Effects

Specifies the characteristics of a background. You can add background effects only to objects that have a fixed height and width; if a percentage size is given, the effects are ignored.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Block" on page 804, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Chart Body" on page 809, "Chart Footer" on page 809, "Chart Footer" on page 809, "Chart Subtitle" on page 810, "Chart Subtitle" on page 810, "Chart Title" on page 811, "Chart Title" on page 811, "Class" on page 811, "Combination Chart" on page 813, "Combination Chart" on page 813, "Conditional Block" on page 814, "Conditional Block" on page 814, "Crosstab Columns" on page 815, "Crosstab Columns" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Rows" on page 817, "Crosstab Rows" on page 818, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Equation Label" on page 826, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Legend" on page 834, "List Cell" on page 836

page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838, "List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Note" on page 846, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Table Cell" on page 863, "Win-Loss Chart" on page 869

Background Image

Specifies an image to be used as the background for the object.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Block" on page 804, "Bubble Chart" on page 804, "Caption" on page 807, "Chart Body" on page 808, "Chart Body" on page 809, "Combination Chart" on page 813, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Crosstab" on page 815, "Crosstab Columns" on page 815, "Crosstab Columns" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Rows" on page 817, "Crosstab Rows" on page 818, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Field Set" on page 827, "Gauge Chart" on page 828, "Hyperlink" on page 830, "Hyperlink Button" on page 830, "Image" on page 831, "Legend" on page 833, "List" on page 835, "List Cell" on page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838, "List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "List Summary" on page 840, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Page" on page 847, "Page Break Text" on page 848, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 854, "Prompt Button" on page 854, "Radar Chart" on page 855, "Repeater Table" on page 857, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Scatter Chart" on page 859, "Static Repeater Table" on page 862, "Table" on page 863, "Table Cell" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Table Row" on page 864, "Text Item" on page 865, "Variable Text Item" on page 868, "Win-Loss Chart" on page 869

Bar, Line, or Area Index

Specifies which combination object to use when calculating the position. When multiple series exist, the index of 0 represents the topmost bar, line, or area in the Series drop zone, the index of 1 represents the second one, and so on.

Applies to

"Baseline" on page 803, "Baseline" on page 803, "Marker" on page 843

Bar Shape

Specifies the shape of the bars in a bar chart.

Applies to

“Bar” on page 802

Bar Width

Specifies the width of the bars as a percentage of the space available. For example, if you specify 50 percent, the bar takes up half of the space available and the bars are separated from each other. If you specify 100 percent, there is no space between the bars. The default value is 80.

Applies to

“Bar” on page 802, “Pareto Chart” on page 849, “Progressive Chart” on page 853

Based on

Specifies the series data item on which the trendline is based.

Applies to

“Trendline” on page 867

Baselines

Adds reference lines to a chart based on numeric or statistical values, calculations, or layout calculations. This property applies only to legacy charts.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Combination Chart” on page 813, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Polar Chart” on page 852, “Progressive Chart” on page 854, “Radar Chart” on page 855, “Scatter Chart” on page 859

Bevel

Specifies whether the chart appears with a beveled edge.

Applies to

“Bar” on page 802, “Bullet Chart” on page 805, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Progressive Chart” on page 853

Block Variable

Specifies a variable based on which the block can be conditionally rendered.

Applies to

“Conditional Block” on page 814, “Conditional Block” on page 814

Border

Specifies the width, style, and color for the border of the object.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Block" on page 804, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Caption" on page 807, "Combination Chart" on page 813, "Combination Chart" on page 813, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Crosstab" on page 815, "Crosstab Columns" on page 815, "Crosstab Columns" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Rows" on page 817, "Crosstab Rows" on page 818, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Field Set" on page 827, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Hyperlink" on page 830, "Hyperlink Button" on page 830, "Image" on page 831, "List" on page 835, "List Cell" on page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838, "List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "List Summary" on page 840, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Page" on page 847, "Page Break Text" on page 848, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Prompt Button" on page 854, "Radar Chart" on page 855, "Repeater Table" on page 857, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Static Repeater Table" on page 862, "Table" on page 863, "Table Cell" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Text Box Prompt" on page 865, "Text Item" on page 865, "Variable Text Item" on page 868, "Win-Loss Chart" on page 869

Border Color

Specifies the color of the border rendered around specific chart elements, such as bars, stacks, areas, points, or pie slices.

Applies to

"3-D Area" on page 799, "3-D Bar" on page 799, "3-D Line" on page 800, "3-D Scatter Chart" on page 800, "Area" on page 801, "Area" on page 801, "Bar" on page 802, "Bar" on page 802, "Bubble Chart" on page 804, "Display Layer" on page 825, "Gauge Chart" on page 828, "Legend" on page 833, "Line" on page 835, "Marimekko Chart" on page 842, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Point Layer" on page 851, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Region Layer" on page 857, "Scatter Chart" on page 859, "Win-Loss Chart" on page 869

Border Color

Specifies the color of the borders around the chart body in a pie chart.

Applies to

"Pie Chart" on page 850

Borders

Specifies whether borders are rendered around specific chart elements, such as bars, stacks, areas, points, or pie slices.

Applies to

"3-D Area" on page 799, "3-D Bar" on page 799, "3-D Line" on page 800, "3-D Scatter Chart" on page 800, "Area" on page 801, "Bar" on page 802, "Bubble Chart" on page 804, "Display Layer" on page 825, "Gauge Chart" on page 828, "Legend" on page 833, "Line" on page 835, "Marimekko Chart" on page 842, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Point Layer" on page 851, "Polar Chart" on page 852, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Region Layer" on page 857, "Scatter Chart" on page 859, "Win-Loss Chart" on page 869

Borders

Specifies whether borders appear around the chart body.

Applies to

"Area" on page 801, "Bar" on page 802, "Pareto Chart" on page 849, "Progressive Chart" on page 853

Borders

Specifies whether borders appear around the chart body in a pie chart.

Applies to

"Pie Chart" on page 850

Bottom Position

Specifies the position of the bottom edge of the colored region.

Applies to

"Colored Region" on page 812

Bottom Position (px)

Specifies the pixel position of the bottom edge of the note measured from the bottom of the chart.

Applies to

"Note" on page 846

Bottom Position (px)

Specifies the pixel position of the bottom edge of the legend measured from the bottom of the chart.

Applies to

"Legend" on page 833

Box Type

Each report object has a container, or box, which can be set to display the contents (the default) or not. This property specifies whether to override the default box type for the object.

When set to None, the object is not rendered and its space is not reserved in the report. You could use this property to remove an object completely from a report when a specific condition is met. When set to Inline, you can insert other objects on the same line as the object. When set to Block, you can insert other objects only on the lines above and below the object.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Block" on page 804, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Combination Chart" on page 813, "Combination Chart" on page 813, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Crosstab" on page 815, "Field Set" on page 827, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Hyperlink" on page 830, "Image" on page 831, "List" on page 835, "List Summary" on page 840, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Page Break Text" on page 848, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Repeater Table" on page 857, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Static Repeater Table" on page 862, "Table" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Text Item" on page 865, "Variable Text Item" on page 868, "Win-Loss Chart" on page 869

Box Type

Each report object has a container, or box, which can be set to display the contents (the default) or not. This property specifies whether to override the default box type for the object. When set to None, the object is not rendered and its space is not reserved in the report.

Applies to

"Axis Title" on page 802, "Axis Title" on page 802, "Baseline" on page 803, "Baseline" on page 803, "Baseline" on page 803, "Chart Footer" on page 809, "Chart Footer" on page 809, "Chart Subtitle" on page 810, "Chart Subtitle" on page 810, "Chart Title" on page 811, "Chart Title" on page 811, "Crosstab Columns" on page 815, "Crosstab Columns" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Rows" on page 817, "Crosstab Rows" on page 818, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Interval Prompt" on page 831, "Legend" on page 833, "Legend Title" on page 834, "Legend Title" on page 834, "List Cell" on page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838,

"List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "Marker" on page 843, "Marker" on page 843, "Note Content" on page 846, "Regression Line" on page 857, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Select & Search Prompt" on page 861, "Table Cell" on page 863, "Table Row" on page 864, "Text Box Prompt" on page 865, "Time Prompt" on page 866, "Value Prompt" on page 868

Bubble Size

Specifies how the bubble size is computed. Minimum-Based assigns the smallest bubble to the minimum data value. Zero-Based computes the bubble size relative to 0. This option is compatible with Excel 2002. Zero-Based with Negatives shows negative bubbles as hollow, and the bubbles get larger as they get further from 0. This option is compatible with Excel 2007.

Applies to

"Bubble Chart" on page 804

Bubble Size

Specifies how bubble sizes are calculated on a bubble chart.

Applies to

"Bubble Chart" on page 805

Bullet Indicators

Specifies the size and shape of the bullet chart data marker that represents the actual value.

Applies to

"Bullet Chart" on page 805

Button Definition

Defines the button in the control.

Applies to

"Button" on page 806

Button Gap

Specifies the gap between buttons in the button bar.

Applies to

"Button Bar" on page 806, "Data Button Bar" on page 820, "Data Toggle Button Bar" on page 823, "Toggle Button Bar" on page 866

Buttons Definition

Defines the buttons in the button bar.

Applies to

“Button Bar” on page 806, “Toggle Button Bar” on page 866

Button Width

Specifies the width of buttons in the button bar.

Applies to

“Button Bar” on page 806, “Data Button Bar” on page 820, “Data Toggle Button Bar” on page 823, “Toggle Button Bar” on page 866

Button Width

Specifies the width of the button.

Applies to

“Iterator First” on page 832, “Iterator Last” on page 832, “Iterator Next” on page 832, “Iterator Previous” on page 832

Calculation Intersection

Specifies whether to suppress calculated values that occur at the intersection of a data source calculated member and a query-defined calculated member. When values are suppressed, the characters specified for the Not Applicable characters data format appear in the cells.

Applies to

“Calculated Measure” on page 807, “Calculated Member” on page 807, “Data Item” on page 821, “Dimensional Edge Summary” on page 825, “Edge Summary” on page 826

Calendar Type

Specifies the type of calendar to show. The date values are mapped to the selected calendar before being formatted. The default value is inherited from the user's content language.

Applies to

“Date & Time Prompt” on page 823, “Date Prompt” on page 824

Caption

Specifies the caption for the level.

Applies to

“Level” on page 834

Caption

Specifies the caption.

Applies to

“Calculated Member” on page 807

Cardinality

Specifies the cardinality for this join operand.

Applies to

“Query Reference” on page 855

Cascade Source

Specifies the parameter whose value is used to filter the values displayed in this control.

Applies to

“Select & Search Prompt” on page 861, “Tree Prompt” on page 867, “Value Prompt” on page 868

Case Insensitive

Specifies whether to perform a case insensitive search by default.

Applies to

“Select & Search Prompt” on page 861

Catalog

Specifies the OLAP catalog.

Applies to

“MDX” on page 843

Category Axis

Specifies whether the axis is rendered.

Applies to

“Combination Chart” on page 813, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Progressive Chart” on page 854, “Radar Chart” on page 855

Category Baselines

Adds reference lines on the category axis of a chart based on numeric or statistical values, calculations, or layout calculations.

Applies to

“Category Baseline” on page 808, “Combination Chart” on page 813, “Pareto Chart” on page 849, “Progressive Chart” on page 853

Category Range

Specifies whether to show the range of all categorical data in the visualization or the filtered range corresponding to selected values in an Active Report control. For example, when all Series data is selected, all legend items are always shown in the visualization, and the color of each legend item stays the same in the visualization. When a category is inserted on an axis, space is reserved on the axis for all data. When filtered data is selected, only the filtered data is shown in the legend and on axes. The color of each legend item can change when users select different values in the control.

Applies to

“Category” on page 808

Category Range

Specifies whether to show the range of all categorical data in the visualization or the filtered range corresponding to selected values in an Active Report control. For example, when all Series data is selected, all legend items are always shown in the visualization, and the color of each legend item stays the same in the visualization. When a category is inserted on an axis, space is reserved on the axis for all data. When filtered data is selected, only the filtered data is shown in the legend and on axes. The color of each legend item can change when users select different values in the control.

Applies to

“Node” on page 845

Chart Orientation

Specifies whether the chart is rendered vertically or horizontally.

Applies to

“Bullet Chart” on page 805, “Combination Chart” on page 813, “Combination Chart” on page 813, “Pareto Chart” on page 849, “Pareto Chart” on page 849, “Progressive Chart” on page 853, “Progressive Chart” on page 854, “Win-Loss Chart” on page 869

Chart Type

Specifies whether the data may be rendered as either a bar, line, or area. This property applies only to legacy charts.

Applies to

“Area” on page 801, “Bar” on page 802, “Line” on page 835

Chart Type

Specifies whether the data may be rendered as either a bar, line, or area.

Applies to

“Area” on page 801, “Bar” on page 802, “Line” on page 835

Chart Type

Specifies whether the data may be rendered as either a bar, line or area.

Applies to

“3-D Area” on page 799, “3-D Bar” on page 799, “3-D Line” on page 800

Check Boxes Definition

Defines the check boxes in the check box group.

Applies to

“Check Box Group” on page 811

Choices Deselect All Text

Specifies the text for the link below the choices box that deselects all the items in the box. This property applies to all prompts with either multiple selections and ranges or multiple selections and search. The default link text is Deselect All.

Applies to

“Date & Time Prompt” on page 823, “Date Prompt” on page 824, “Interval Prompt” on page 831, “Select & Search Prompt” on page 861, “Text Box Prompt” on page 865, “Time Prompt” on page 866, “Value Prompt” on page 868

Choices Select All Text

Specifies the text for the link below the choices box that selects all the items in the box. This property applies to all prompts with either multiple selections and ranges or multiple selections and search. The default link text is Select All.

Applies to

“Date & Time Prompt” on page 823, “Date Prompt” on page 824, “Interval Prompt” on page 831, “Select & Search Prompt” on page 861, “Text Box Prompt” on page 865, “Time Prompt” on page 866, “Value Prompt” on page 868

Choices Text

Specifies the title that appears above the choices box when multiple selections are enabled. This property applies to the following prompt types: value, text box, date, date & time, time, interval, and select & search. The default title text is Choices.

Applies to

“Date & Time Prompt” on page 823, “Date Prompt” on page 824, “Interval Prompt” on page 831, “Select & Search Prompt” on page 861, “Text Box Prompt” on page 865, “Time Prompt” on page 866, “Value Prompt” on page 868

Classes

Specifies a class to apply to the object. The class provides a default style. If you apply more than one class, the style properties from all classes are merged together when they are applied. However, if the classes have style properties in common, the style properties from the last class applied override those from previous classes.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Angular Axis" on page 801, "Axis Labels" on page 802, "Axis Title" on page 802, "Axis Title" on page 802, "Block" on page 804, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Caption" on page 807, "Category Axis" on page 808, "Chart Footer" on page 809, "Chart Footer" on page 809, "Chart Subtitle" on page 810, "Chart Subtitle" on page 810, "Chart Title" on page 811, "Chart Title" on page 811, "Combination Chart" on page 813, "Combination Chart" on page 813, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Crosstab" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Cumulation Line Axis" on page 819, "Date" on page 823, "Field Set" on page 827, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Gauge Labels" on page 829, "Hyperlink" on page 830, "Hyperlink Button" on page 830, "Image" on page 831, "Legend" on page 833, "Legend" on page 834, "Legend Title" on page 834, "Legend Title" on page 834, "List" on page 835, "List Cell" on page 836, "List Column Body" on page 837, "List Column Title" on page 838, "List Summary" on page 840, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Note Content" on page 846, "Numerical Axis" on page 846, "Numerical Axis" on page 847, "Page" on page 847, "Page Body" on page 847, "Page Break Text" on page 848, "Page Footer" on page 848, "Page Header" on page 848, "Page Number" on page 848, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Pie Labels" on page 851, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Prompt Button" on page 854, "Radar Chart" on page 855, "Radial Axis" on page 855, "Repeater Table" on page 857, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Row Number" on page 859, "Row Number" on page 859, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Static Repeater Table" on page 862, "Table" on page 863, "Table Cell" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Table Row" on page 864, "Text Item" on page 865, "Time" on page 865, "Variable Text Item" on page 868, "Win-Loss Chart" on page 869, "X Axis" on page 869, "X Axis" on page 870, "Y1 Axis" on page 870, "Y2 Axis" on page 870, "Y Axis" on page 871, "Y Axis" on page 871, "Z Axis" on page 871, "Z Axis" on page 872

Clickable Region

Specifies whether to make the object clickable when the active report is executed. You can set the value of this property for multiple objects simultaneously by first control+clicking the items in the report.

Applies to

"Crosstab Fact Cells" on page 816, "List Column" on page 836, "List Column Body" on page 837, "List Column Title" on page 838, "List Row" on page 840

Clickable Region

Specifies whether to make the object clickable. When (Default) is selected, the value is inherited from the Clickable Regions property of the parent object.

Applies to

"Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Space" on page 818, "Crosstab Summary" on page 818

Clickable Regions

Specifies which areas of the data container are clickable. For some data containers, if you select to make parts clickable, you can further refine which areas are clickable with the Clickable Region property.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Combination Chart" on page 813, "Combination Chart" on page 813, "Crosstab" on page 815, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "List" on page 835, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Repeater Table" on page 857, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Static Repeater Table" on page 862

Clickable Regions

Specifies which areas of the visualization are clickable. Visualization as a Whole makes the entire visualization the clickable region. Visualization Intersections makes each element in the visualization clickable.

Applies to

"Visualization" on page 868

Clock Mode

Specifies whether the arms of the clock move.

Applies to

"Date & Time Prompt" on page 823, "Time Prompt" on page 866

Color by Value

Specifies how color by value is rendered in a chart.

Applies to

"Bubble Chart" on page 805, "Color by Value Measure" on page 812, "Scatter Chart" on page 860

Colored Regions

Specifies rectangular colored regions drawn in the chart body to highlight parts of the chart. The regions are rendered behind the data markers. The regions are

drawn in the same order that they appear in this property. The first region is drawn first, on the bottom, and the last region is drawn on top of the other regions.

Applies to

“Bubble Chart” on page 805, “Bullet Chart” on page 805, “Combination Chart” on page 813, “Pareto Chart” on page 849, “Progressive Chart” on page 853, “Scatter Chart” on page 860

Color Legend Title

Specifies a title within the legend above the palette for the region color. If this object is not defined, no additional title is drawn. If no legend is drawn, this object is ignored. Styling for this object is inherited from the legend title.

Applies to

“Region Layer” on page 857

Color Legend Title

Specifies a title within the legend above the palette for the point color. If this object is not defined, no additional title is drawn. If no legend is drawn, this object is ignored. Styling for this object is inherited from the legend title.

Applies to

“Point Layer” on page 851

Column Coordinate

Uniquely identifies the column of a node member or spacer on an edge of the crosstab. You cannot modify this value.

Applies to

“Crosstab Intersection” on page 816

Column Titles

Specifies where or whether column titles may be rendered.

Applies to

“List” on page 835

Column Visibility

Specifies whether a column is visible when the active report is executed. You can set column visibility based on a condition.

Applies to

“List Column” on page 836, “List Column Body” on page 837, “List Column Title” on page 838

Combinations

Specifies which axes to show and the chart types to use for the series.

Applies to

“Combination Chart” on page 813

Component Reference

Specifies the layout object that is referenced. An object is a reusable component only if it has a name.

Applies to

“Layout Component Reference” on page 833

Component Reference

Specifies the layout object that is referenced. An object is a reusable component only if it has a name. You cannot modify this value.

Applies to

“Component Override” on page 813

Conditional Palette

Specifies a conditional palette for the chart.

Applies to

“Area” on page 801, “Bar” on page 802, “Bubble Chart” on page 805, “Gauge Axis” on page 827, “Line” on page 835, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Progressive Chart” on page 853, “Scatter Chart” on page 860

Conditional Palette

Specifies a conditional palette for the chart. This property applies only to legacy charts.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Combination Chart” on page 813, “Gauge Chart” on page 828, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Point Layer” on page 851, “Polar Chart” on page 852, “Progressive Chart” on page 854, “Radar Chart” on page 855, “Region Layer” on page 857, “Scatter Chart” on page 859

Conditional Styles

Specifies the conditions and styles used to style the object.

Applies to

“Angular Measure” on page 801, “Axis Labels” on page 802, “Axis Title” on page 802, “Axis Title” on page 802, “Block” on page 804, “Bubble Measure” on page 805, “Bubble Measure” on page 805, “Caption” on page 807, “Chart Body” on page 808,

"Chart Footer" on page 809, "Chart Footer" on page 809, "Chart Measure" on page 809, "Chart Subtitle" on page 810, "Chart Subtitle" on page 810, "Chart Text Item" on page 810, "Chart Text Item" on page 810, "Chart Title" on page 811, "Chart Title" on page 811, "Color by Value Measure" on page 812, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Crosstab" on page 815, "Crosstab Columns" on page 815, "Crosstab Columns" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Rows" on page 817, "Crosstab Rows" on page 818, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Cumulation Label" on page 819, "Cumulation Line Axis" on page 819, "Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Default Measure" on page 824, "Default Measure" on page 824, "Display Layer" on page 825, "Equation Label" on page 826, "Equation Label" on page 826, "Field Set" on page 827, "Gauge Labels" on page 829, "Gauge Numerical Axis" on page 829, "Hyperlink" on page 830, "Hyperlink Button" on page 830, "Image" on page 831, "Interval Prompt" on page 831, "Label" on page 833, "Legend" on page 833, "Legend" on page 834, "Legend Title" on page 834, "Legend Title" on page 834, "List" on page 835, "List Cell" on page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838, "List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "List Summary" on page 840, "Note" on page 846, "Note Content" on page 846, "Page" on page 847, "Page Break Text" on page 848, "Pie Labels" on page 851, "Point Layer" on page 851, "Point Measure" on page 852, "Point Size Measure" on page 852, "Prompt Button" on page 854, "Radial Measure" on page 856, "Region Layer" on page 857, "Region Measure" on page 857, "Repeater Table" on page 857, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Select & Search Prompt" on page 861, "Static Repeater Table" on page 862, "Table" on page 863, "Table Cell" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Table Row" on page 864, "Target Measure" on page 864, "Text Box Prompt" on page 865, "Text Item" on page 865, "Time Prompt" on page 866, "Tolerance Measure" on page 866, "Tree Prompt" on page 867, "Trendline Label" on page 867, "Value Prompt" on page 868, "Win-Loss Chart" on page 869, "X Axis Measure" on page 870, "Y Axis Measure" on page 871, "Z Axis Measure" on page 872

Connecting Lines

Specifies the properties of the lines that connect the segments of a stacked bar. This property is ignored for clustered bars. This property applies only to legacy charts.

Applies to

"Bar" on page 802, "Pareto Chart" on page 849, "Progressive Chart" on page 854

Connecting Lines

Specifies the properties of the lines that connect the segments of a stacked bar in a progressive chart. This property is ignored for clustered bars.

Applies to

"Progressive Chart" on page 853

Contained Text Direction

Specifies the direction of text contained in compound objects. Compound objects include charts, maps, and prompts. Contextual sets the text direction based on the first alphabetic character in the text. If the character belongs to a language that supports bidirectional script, the direction is right to left. Otherwise, the direction is left to right. Numbers and special characters do not influence the text direction. For example, if the text starts with a number followed by an Arabic character, the direction will be right to left. If the text starts with a number followed by a Latin character, the direction will be left to right.

Applies to

"Bubble Chart" on page 805, "Bullet Chart" on page 805, "Button" on page 806, "Button Bar" on page 806, "Check Box Group" on page 811, "Combination Chart" on page 813, "Continuous Values Slider" on page 814, "Data Button Bar" on page 820, "Data Check Box Group" on page 820, "Data Discrete Values Slider" on page 821, "Data Drop-Down List" on page 821, "Data Iterator" on page 822, "Data List Box" on page 822, "Data Radio Button Group" on page 822, "Data Tab Control" on page 823, "Data Toggle Button Bar" on page 823, "Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Discrete Values Slider" on page 825, "Drop-Down List" on page 826, "Gauge Chart" on page 828, "Interval Prompt" on page 831, "Iterator" on page 831, "List Box" on page 836, "Map" on page 841, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Progressive Chart" on page 853, "Radio Button Group" on page 856, "Scatter Chart" on page 860, "Select & Search Prompt" on page 861, "Tab Control" on page 863, "Text Box Prompt" on page 865, "Time Prompt" on page 866, "Toggle Button Bar" on page 866, "Tree Prompt" on page 867, "Value Prompt" on page 868

Container Filter

Defines the condition to use to filter items in a control or container based on the value of a variable.

Applies to

"Check Box Group" on page 811, "Crosstab" on page 815, "Data Check Box Group" on page 820, "Data Container" on page 820, "Data Deck" on page 821, "Data Discrete Values Slider" on page 821, "Data Drop-Down List" on page 821, "Data Iterator" on page 822, "Data List Box" on page 822, "Data Radio Button Group" on page 822, "Deck" on page 824, "Discrete Values Slider" on page 825, "Drop-Down List" on page 826, "Iterator" on page 831, "List" on page 835, "List Box" on page 836, "Radio Button Group" on page 856, "Repeater Table" on page 857, "Static Repeater Table" on page 862

Container Selection

Defines the condition to use to highlight items as selected in a control or container based on the value of a variable. Defining a condition sets the Auto Select property to None.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Button Bar" on page 806, "Check Box Group" on page 811, "Combination Chart" on page 813, "Combination Chart" on page 813, "Crosstab" on page 815, "Data

Button Bar" on page 820, "Data Check Box Group" on page 820, "Data Container" on page 820, "Data Deck" on page 821, "Data Discrete Values Slider" on page 821, "Data Drop-Down List" on page 821, "Data Iterator" on page 822, "Data List Box" on page 822, "Data Radio Button Group" on page 822, "Data Tab Control" on page 823, "Data Toggle Button Bar" on page 823, "Deck" on page 824, "Discrete Values Slider" on page 825, "Drop-Down List" on page 826, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Iterator" on page 831, "List" on page 835, "List Box" on page 836, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Radio Button Group" on page 856, "Repeater Table" on page 857, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Static Repeater Table" on page 862, "Tab Control" on page 863, "Toggle Button Bar" on page 866

Contents Height

Specifies the relative height of list rows. This property is used only when a list has a height defined in the **Size and Overflow** property.

Stretched means that the rows will be evenly sized to fit in the list's height. This is default HTML behavior.

Minimal means that rows will take up only as much space as they need, and be compressed at the top of the list. You can position a footer at the bottom of the list by setting the **Push To Bottom** property to **Yes** on a footer object inside the list.

Applies to

"List" on page 835

Control Data Item Value

Specifies the data item used to populate the text item in the control.

Applies to

"Chart Text Item" on page 810, "Chart Text Item" on page 810, "Cumulation Line Label" on page 819, "Hyperlink" on page 830, "Hyperlink Button" on page 830, "Text Item" on page 865

Control Data Item Value

Specifies the data item used to populate the HTML item in the control.

Applies to

"HTML Item" on page 829, "Rich Text Item" on page 859

Control Data Item Value

Specifies the data item used to populate the image in the control.

Applies to

"Hyperlink" on page 830, "Hyperlink Button" on page 830, "Image" on page 831

Control Enable

Defines the condition to use to enable a control or container based on the value of a variable.

Applies to

"Button" on page 806, "Button Bar" on page 806, "Check Box Group" on page 811, "Continuous Values Slider" on page 814, "Data Button Bar" on page 820, "Data Check Box Group" on page 820, "Data Discrete Values Slider" on page 821, "Data Drop-Down List" on page 821, "Data Iterator" on page 822, "Data List Box" on page 822, "Data Radio Button Group" on page 822, "Data Toggle Button Bar" on page 823, "Discrete Values Slider" on page 825, "Drop-Down List" on page 826, "Iterator" on page 831, "List Box" on page 836, "Radio Button Group" on page 856, "Toggle Button Bar" on page 866

Cross Product Allowed

Specifies whether the query will be allowed to run if there is a cross join between database tables. This type of query generates a result set that includes all possible unique combinations of values from the first and second table. The default value is Deny.

Applies to

"Query" on page 854

Cumulation Axis

Specifies whether the axis for the cumulation line is rendered.

Applies to

"Cumulation Line" on page 819

Cumulation Label

Specifies whether a label for the cumulation line is rendered in the legend.

Applies to

"Cumulation Line" on page 819

Cumulation Label

Specifies the label that is shown with the cumulation line on a Pareto chart.

Applies to

"Cumulation Line" on page 819

Cumulative Line

Specifies whether the cumulation line is rendered.

Applies to

"Pareto Chart" on page 849

Cumulative Line

Specifies whether the cumulation line is rendered in a Pareto chart.

Applies to

"Pareto Chart" on page 849

Current Block

Specifies which block is currently being authored.

Applies to

"Conditional Block" on page 814, "Conditional Block" on page 814

Current Card

Specifies which card to show in the report.

Applies to

"Card" on page 807, "Deck" on page 824

Current Tab

Specifies which tab to show in the report.

Applies to

"Tab Control" on page 863

Custom Label

Overrides the default label for the data item.

Applies to

"Angular Measure" on page 801, "Bubble Measure" on page 805, "Chart Node Member" on page 809, "Default Measure" on page 824, "Point Measure" on page 852, "Point Size Measure" on page 852, "Radial Measure" on page 856, "Region Measure" on page 857, "Target Measure" on page 864, "Tolerance Measure" on page 866, "Win-Loss Measure" on page 869, "X Axis Measure" on page 870, "Y Axis Measure" on page 871, "Z Axis Measure" on page 872

Custom Label

Specifies the data source and format for a text item, such as a legend item, legend title, axis label, or axis title.

Applies to

"Bubble Measure" on page 805, "Bullet Measure" on page 806, "Chart Measure" on page 809, "Color by Value Measure" on page 812, "Default Measure" on page 824, "Target Measure" on page 864

Data Format

Specifies the data format of the object.

Applies to

“Angular Axis” on page 801, “Angular Measure” on page 801, “Axis Labels” on page 802, “Bubble Measure” on page 805, “Bubble Measure” on page 805, “Bullet Measure” on page 806, “Button Label” on page 807, “Chart Measure” on page 809, “Chart Node Member” on page 809, “Chart Text Item” on page 810, “Chart Text Item” on page 810, “Check Box Label” on page 811, “Color by Value Measure” on page 812, “Crosstab Columns” on page 815, “Crosstab Columns” on page 815, “Crosstab Corner” on page 816, “Crosstab Fact Cells” on page 816, “Crosstab Intersection” on page 816, “Crosstab Member Fact Cells” on page 817, “Crosstab Node Member” on page 817, “Crosstab Rows” on page 817, “Crosstab Rows” on page 818, “Crosstab Space” on page 818, “Crosstab Summary” on page 818, “Cumulation Label” on page 819, “Cumulation Line Axis” on page 819, “Date” on page 823, “Default Measure” on page 824, “Default Measure” on page 824, “Equation Label” on page 826, “Gauge Numerical Axis” on page 829, “Iterator Value Label” on page 833, “Label” on page 833, “List Cell” on page 836, “List Column” on page 836, “List Column Body” on page 837, “List Columns” on page 837, “List Columns” on page 837, “List Columns Body Style” on page 838, “List Columns Title Style” on page 838, “List Column Title” on page 838, “List Footer” on page 839, “List Header” on page 839, “List Item Label” on page 839, “List Row” on page 840, “List Row Cells Style” on page 840, “List Summary” on page 840, “Node” on page 845, “Numerical Axis” on page 846, “Numerical Axis” on page 847, “Point Measure” on page 852, “Point Size Measure” on page 852, “Radial Axis” on page 855, “Radial Measure” on page 856, “Radio Button Label” on page 856, “Region Measure” on page 857, “Row Number” on page 859, “Row Number” on page 859, “Select & Search Prompt” on page 861, “Slider Value Label” on page 862, “Target Measure” on page 864, “Target Measure” on page 864, “Text Item” on page 865, “Time” on page 865, “Tolerance Measure” on page 866, “Total Column” on page 866, “Trendline Label” on page 867, “Value Prompt” on page 868, “Variable Text Item” on page 868, “Win-Loss Measure” on page 869, “X Axis” on page 869, “X Axis Measure” on page 870, “Y1 Axis” on page 870, “Y2 Axis” on page 870, “Y Axis” on page 871, “Y Axis Measure” on page 871, “Z Axis” on page 871, “Z Axis” on page 872, “Z Axis Measure” on page 872

Data Format

Specifies the data format of the object. This object supports only numeric formatting.

Applies to

“Value” on page 867, “Visualization” on page 868

Data Format

Specifies the data format of the slider values.

Applies to

“Continuous Values Slider” on page 814

Data Item

Specifies a reference to a data item. You cannot modify this value.

Applies to

“Crosstab Summary” on page 818, “List Summary” on page 840, “Member Set” on page 844

Data Item

Specifies a reference to a data item.

Applies to

“Calculated Member” on page 807, “Fact” on page 827, “Key” on page 833, “Member Property” on page 844

Data Item Label

Specifies the data item label that defines the text to render.

Applies to

“Chart Text Item” on page 810, “Chart Text Item” on page 810, “Cumulation Line Label” on page 819, “Hyperlink” on page 830, “Hyperlink Button” on page 830, “Text Item” on page 865

Data Item Label

Specifies the data item label that defines the HTML to render.

Applies to

“HTML Item” on page 829, “Rich Text Item” on page 859

Data Item Label

Specifies the data item label that defines the URL.

Applies to

“Hyperlink” on page 830, “Hyperlink Button” on page 830, “Image” on page 831

Data Item Label

Specifies the data item label that defines the bookmark. The value used as the bookmark reference must match this value.

Applies to

“Bookmark” on page 804

Data Item Value

Specifies the data item value that defines the text to render.

Applies to

“Chart Text Item” on page 810, “Chart Text Item” on page 810, “Cumulation Line Label” on page 819, “Hyperlink” on page 830, “Hyperlink Button” on page 830, “Text Item” on page 865, “Total Column” on page 866

Data Item Value

Specifies the data item value that defines the HTML to render.

Applies to

“HTML Item” on page 829, “Rich Text Item” on page 859

Data Item Value

Specifies the data item value that defines the URL.

Applies to

“Hyperlink” on page 830, “Hyperlink Button” on page 830, “Image” on page 831

Data Item Value

Specifies the data item value that defines the bookmark. The value used as the bookmark reference must match this value.

Applies to

“Bookmark” on page 804

Data Item Value

Specifies the numeric position by using a data item value.

Applies to

“Baseline” on page 803, “Baseline” on page 803, “Baseline” on page 803, “Baseline” on page 803, “Marker” on page 843

Data Item Value

If the marker or baseline is based on a query calculation, allows you to switch to a different data item.

Applies to

“Marker” on page 842, “Numeric Baseline” on page 847

Data Item Value

Specifies the numeric position of a data item.

Applies to

“Marker” on page 843

Data Item Value

Specifies the numeric position of a data item.

Applies to

“Marker” on page 843

Data Language

Specifies the language of the data.

Applies to

“Map” on page 841

Data Points

Specifies whether to show data points on the chart and how they are formatted.

Applies to

“Cumulation Line” on page 819

Data Source

Specifies the query data source.

Applies to

“MDX” on page 843, “SQL” on page 862

Days Text

Specifies the title that appears above the days box in interval prompts. The default title text is Days.

Applies to

“Interval Prompt” on page 831

Deck Cards Definition

The cards in the deck. Each card must have a corresponding row in the static data table.

Applies to

“Deck” on page 824

Default Card

Card to display when no other card matches the current variable state.

Applies to

“Data Deck” on page 821

Default Card

Card to display when no other card matches the current variable state.

Applies to

“Deck” on page 824

Default Measure

Specifies the default measure to use for a crosstab or chart. If the measures of the crosstab or chart cannot be determined by what is being rendered on the edges, then the default measure will be rendered.

Applies to

“Crosstab” on page 815

Default Selections

Specifies the collection of default selections for a prompt control.

Applies to

“Date & Time Prompt” on page 823, “Date Prompt” on page 824, “Interval Prompt” on page 831, “Text Box Prompt” on page 865, “Time Prompt” on page 866, “Tree Prompt” on page 867, “Value Prompt” on page 868

Default Title

Specifies whether the default title is generated.

Applies to

“Axis Title” on page 802, “Legend Title” on page 834

Default Title

Specifies whether the default title may be generated.

Applies to

“Axis Title” on page 802, “Legend Title” on page 834

Define Contents

Overrides the content of the selected crosstab intersection. Use this property to hide measure values for individual cells or to define custom content.

Applies to

“Crosstab Intersection” on page 816, “Crosstab Member Fact Cells” on page 817

Define Custom Grouping

Specifies the details of the data items in custom groups. Custom groups create groups of data items that are meaningful to you.

Applies to

“Custom Groups” on page 820

Define Member Sets

Specifies the set structure of a query. If it is not defined, it is assumed that each data item defines an unrelated set.

Applies to

"Query" on page 854

Definition

Specifies the expression to evaluate when filtering the data.

Applies to

"Detail Filter" on page 825, "Summary Filter" on page 863

Depth

Specifies the three-dimensional depth effect of the chart. A value of zero indicates a flat chart.

Applies to

"Combination Chart" on page 813, "Combination Chart" on page 813, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Progressive Chart" on page 853, "Progressive Chart" on page 854

Description

Specifies a description for the object, that is used to assist authoring.

Applies to

"Class" on page 811, "HTML Item" on page 829, "Metric Studio Diagram" on page 845, "Rich Text Item" on page 859

Deselect Text

Specifies the text for the link that deselects the items when the selection is optional. This property applies to the following prompt types: text box, date, date & time, time, interval, value, select & search, and tree. The default link text is Deselect.

Applies to

"Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Interval Prompt" on page 831, "Select & Search Prompt" on page 861, "Text Box Prompt" on page 865, "Time Prompt" on page 866, "Tree Prompt" on page 867, "Value Prompt" on page 868

Detail

Specifies whether the data item is to be used for calculating aggregates or not. When set to Yes, the data item is used to aggregate the lowest level details.

Applies to

"Calculated Member" on page 807, "Data Item" on page 821, "Explicit Member Set" on page 826, "Hierarchy Set" on page 829, "Level Set" on page 835, "Member" on page 844, "Member Children Set" on page 844, "Named Set" on page 845, "Set Expression" on page 861

Diagram Identifier

Identifies an impact or custom diagram in IBM® Cognos® Metric Studio. Copy the identifier from Metric Studio (Diagrams tab, View the Diagram Identifier button in the Actions column) and paste it in this property. IBM® Cognos® Report Studio decodes the identifier into an image URL. The diagram is imported as a static image.

Applies to

"Metric Studio Diagram" on page 845

Dial Face Fill

Specifies the fill color and effects for the dial face of a gauge chart.

Applies to

"Gauge Chart" on page 828

Dial Outline Color

Specifies the dial outline color in a gauge chart.

Applies to

"Gauge Chart" on page 828

Dictionary

Specifies the aliases to use when matching data values to feature names in the map.

Applies to

"Map" on page 841

Dimension

Specifies a reference to a dimension. You cannot modify this value.

Applies to

"Calculated Measure" on page 807, "Calculated Member" on page 807, "Dimensional Edge Summary" on page 825, "Explicit Member Set" on page 826, "Hierarchy Set" on page 829, "Intersection (Tuple)" on page 831, "Level Set" on page 835, "Measure" on page 843, "Member" on page 844, "Member Children Set" on page 844, "Member Property" on page 844, "Named Set" on page 845, "Percentaged Measure" on page 850, "Set Expression" on page 861

Direction & Justification

Specifies text flow properties, such as direction, writing mode, and justification.

Applies to

"Block" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Button" on page 806, "Button Bar" on page 806, "Check Box Group" on page 811, "Combination Chart" on page 813, "Conditional Block" on page 814, "Conditional

Block" on page 814, "Context Item Text" on page 814, "Continuous Values Slider" on page 814, "Crosstab" on page 815, "Crosstab Columns" on page 815, "Crosstab Columns" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Rows" on page 817, "Crosstab Rows" on page 818, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Data Button Bar" on page 820, "Data Check Box Group" on page 820, "Data Deck" on page 821, "Data Discrete Values Slider" on page 821, "Data Drop-Down List" on page 821, "Data Iterator" on page 822, "Data List Box" on page 822, "Data Radio Button Group" on page 822, "Data Tab Control" on page 823, "Data Toggle Button Bar" on page 823, "Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Deck" on page 824, "Discrete Values Slider" on page 825, "Drop-Down List" on page 826, "Gauge Chart" on page 828, "Hyperlink" on page 830, "Interval Prompt" on page 831, "Iterator" on page 831, "List" on page 835, "List Box" on page 836, "List Cell" on page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838, "List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "List Summary" on page 840, "Map" on page 841, "Page" on page 847, "Page Break Text" on page 848, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Progressive Chart" on page 853, "Radio Button Group" on page 856, "Repeater Table" on page 857, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Row Number" on page 859, "Scatter Chart" on page 860, "Select & Search Prompt" on page 861, "Static Repeater Table" on page 862, "Tab Control" on page 863, "Table" on page 863, "Table Cell" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Text Box Prompt" on page 865, "Text Item" on page 865, "Time Prompt" on page 866, "Toggle Button Bar" on page 866, "Tree Prompt" on page 867, "Value Prompt" on page 868, "Variable Text Item" on page 868

Display After Overall Header

Specifies whether the list page header is to be rendered after the overall header.

Applies to

"List Page Header" on page 840

Display for Orientation

Specifies the orientation of the mobile device required to display the object when the active report is viewed. For example, if Landscape is selected, the object is displayed only when the mobile device is held in a landscape orientation. The object is not displayed when the mobile device is rotated into a portrait orientation.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Block" on page 804, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Button" on page 806, "Button Bar" on page 806, "Check Box Group" on page 811, "Combination Chart" on page 813, "Combination Chart" on page 813, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Continuous Values Slider" on page 814, "Crosstab" on page 815, "Data Button Bar" on page 820, "Data Check Box Group" on page 820, "Data Deck" on page 821, "Data Discrete Values Slider" on page 821,

"Data Drop-Down List" on page 821, "Data Iterator" on page 822, "Data List Box" on page 822, "Data Radio Button Group" on page 822, "Data Tab Control" on page 823, "Data Toggle Button Bar" on page 823, "Date" on page 823, "Deck" on page 824, "Discrete Values Slider" on page 825, "Drop-Down List" on page 826, "Field Set" on page 827, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Hyperlink" on page 830, "Hyperlink Button" on page 830, "Image" on page 831, "Iterator" on page 831, "List" on page 835, "List Box" on page 836, "List Summary" on page 840, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Page Break Text" on page 848, "Page Number" on page 848, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Radio Button Group" on page 856, "Repeater Table" on page 857, "Row Number" on page 859, "Row Number" on page 859, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Static Repeater Table" on page 862, "Tab Control" on page 863, "Table" on page 863, "Text Item" on page 865, "Time" on page 865, "Toggle Button Bar" on page 866, "Variable Text Item" on page 868, "Visualization" on page 868

Display Frequency

Specifies the frequency for which chart labels are to be rendered. If set to 3, for example, every third label will be rendered.

Applies to

"Category Axis" on page 808, "Category axis" on page 808, "X Axis" on page 870, "Y Axis" on page 871

Display Milliseconds

Specifies whether to show the milliseconds. The format of the milliseconds can be controlled by selecting a specific format. This property is ignored if seconds are not rendered. The default value is inherited from the user's content language.

Applies to

"Date & Time Prompt" on page 823, "Interval Prompt" on page 831, "Time Prompt" on page 866

Display Seconds

Specifies whether to show the seconds. The format of the seconds can be controlled by selecting a specific format. The default value is inherited from the user's content language.

Applies to

"Date & Time Prompt" on page 823, "Interval Prompt" on page 831, "Time Prompt" on page 866

Display Value

Specifies the values rendered to the report user when the prompt is used. These values can be different than the ones that are actually used by the report.

Applies to

“Select & Search Prompt” on page 861, “Value Prompt” on page 868

Display Values

Specifies which value of the variable to show. If the variable returns multiple values, List shows the values separated by commas.

Applies to

“Variable Text Item” on page 868

Dot Color

Specifies the color of the dots of the values that are not selected in the iterator.

Applies to

“Iterator Label Area” on page 832

Down

Specifies the number of times down, or rows, that the frame contents may be rendered.

The default value depends on the setting of the **Repeater Direction** property. If it is set to **Left to right, top to bottom**, the default is 20. If it is set to **Top to bottom, left to right**, the default is one.

Applies to

“Repeater Table” on page 857, “Static Repeater Table” on page 862

Drill-Through Definitions

Specifies report-to-report drill-through definitions, bookmarks, and drill-through text for the object.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Axis Labels” on page 802, “Bubble Chart” on page 804, “Bubble Chart” on page 805, “Bullet Chart” on page 805, “Category Axis” on page 808, “Combination Chart” on page 813, “Combination Chart” on page 813, “Crosstab Fact Cells” on page 816, “Crosstab Intersection” on page 816, “Crosstab Member Fact Cells” on page 817, “Crosstab Node Member” on page 817, “Crosstab Space” on page 818, “Data Container” on page 820, “Gauge Chart” on page 828, “Gauge Chart” on page 828, “Gauge Labels” on page 829, “Image” on page 831, “Legend” on page 833, “Legend” on page 834, “List Column Body” on page 837, “List Column Title” on page 838, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Pie Chart” on page 850, “Pie Labels” on page 851, “Polar Chart” on page 852, “Progressive Chart” on page 853, “Progressive Chart” on page 854, “Radar Chart” on page 855, “Scatter Chart” on page 859, “Scatter Chart” on page 860, “Text Item” on page 865, “Win-Loss Chart” on page 869, “X Axis” on page 870, “Y Axis” on page 871

Drop-Down Width

Specifies the width of the drop-down list box.

Applies to

“Iterator Label Area” on page 832

Drop Shadow

Defines a drop shadow that is rendered around a container.

Applies to

“Crosstab” on page 815, “List” on page 835, “Repeater Table” on page 857, “Table” on page 863

Drop Shadow

Specifies whether a drop shadow appears on a chart and how it appears.

Applies to

“Bubble Chart” on page 805, “Bullet Chart” on page 805, “Combination Chart” on page 813, “Gauge Chart” on page 828, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Progressive Chart” on page 853, “Scatter Chart” on page 860

Duplicates

Specifies whether duplicate rows will be preserved or removed.

Applies to

“Query Operation” on page 855

Embed

Specifies how to embed the reference object. A reference, or pointer, to the object is stored, by default. Alternatively, a copy of the external object can be stored in the report.

Applies to

“Layout Component Reference” on page 833

Empty Item Label

If no data item is specified for the category, defines the label to use for the empty category item. Automatic uses the value label as the label, unless the visualization contains multiple values. When there are multiple values, no text appears for the label. Specified text uses text that you specify as the label. With specified text, you can add translations for the label to support users in multiple languages.

Applies to

“Category” on page 808

End Position

Specifies the position of one edge of the colored region along the numeric axis. The region extends from the position defined in the Start Position to the position defined in this property. The value specified in this property must be greater than the value specified in the Start Position property.

Applies to

“Colored Region” on page 812

Execution Method

Specifies whether the query is a candidate to run concurrently. If set to Concurrent, the query may still execute sequentially based on other factors. If not explicitly set, the query will execute sequentially. Concurrent query execution may improve performance in some cases.

Applies to

“Query” on page 854

Execution Optimization

Specifies how much of the query processing is performed by the client and how much is performed by the database server. If the database server can perform all the query processing, it does.

If **All Rows** is selected, the optimizer adopts a plan that retrieves all rows of the result set in the least amount of time. This value is generally used in a batch environment.

If **First Rows** is selected, the optimizer adopts a plan that retrieves the first row as quickly as possible. This value is generally used in an interactive environment.

If **Incremental** is selected, the optimizer retrieves the first N rows, and then retrieves the next N rows.

Applies to

“Query” on page 854

Expand Features

Specifies whether to center and expand the feature in the map chart. When set to Yes, the map feature is centered and expanded to take up all available space in the chart. When set to No, the map feature is not expanded.

Applies to

“Map” on page 841

Exploded Slices

Specifies the slices that appear pulled out of a pie chart and their appearance.

Applies to

“Pie Chart” on page 850

Expression

Specifies the expression that defines the slicer member set.

Applies to

“Slicer Member Set” on page 862

Expression

Specifies the numeric position for a data marker in a scatter chart.

Applies to

“Marker” on page 843

Expression

Specifies the numeric position for a data marker in a scatter chart.

Applies to

“Marker” on page 843

Expression

Specifies the expression used to populate the data item.

Applies to

“Area” on page 801, “Bar” on page 802, “Calculated Measure” on page 807, “Calculated Member” on page 807, “Category Baseline” on page 808, “Chart Node Member” on page 809, “Chart Text Item” on page 810, “Chart Text Item” on page 810, “Colored Region” on page 812, “Colored Region” on page 812, “Crosstab Corner” on page 816, “Crosstab Fact Cells” on page 816, “Crosstab Intersection” on page 816, “Crosstab Member Fact Cells” on page 817, “Crosstab Node Member” on page 817, “Cumulation Line Label” on page 819, “Data Item” on page 821, “Gauge Axis” on page 827, “HTML Item” on page 829, “Image” on page 831, “Line” on page 835, “List Cell” on page 836, “List Column Body” on page 837, “List Column Title” on page 838, “Map Location” on page 841, “Map Location” on page 841, “Map Refinement Location” on page 841, “Map Refinement Location” on page 842, “Marker” on page 842, “Numeric Baseline” on page 847, “Rich Text Item” on page 859, “Scatter Marker” on page 860, “Set Expression” on page 861, “Text Item” on page 865, “Total Column” on page 866, “Win-Loss Measure” on page 869

Extend Width

Specifies whether the area extends to the width of the chart. This property applies only to defined areas of area charts. When the area chart is converted to a matrix of charts, this property is not supported.

Applies to

“Area” on page 801

Face Color

Specifies the color to show on the face of each gauge in a gauge chart.

Applies to

“Gauge Chart” on page 828

Fact Cell Data Format

Specifies the data format of the object. This object supports only numeric formatting.

Applies to

“Node” on page 845

Fact Cells Precedence

Specifies which style property will override the other style property for intersecting cells in a crosstab, the row's properties, or the column's properties.

This property only applies to style properties that are both set, but to different values. For example, if the row's background color is set to yellow and the column's background color is set to red, you can select which of these properties will override the other. If only the row or the column has a set background color, then that color will be used on the intersecting cell, regardless of this setting.

Applies to

“Crosstab” on page 815

Fill Effects

Specifies the fill effects for the object.

Applies to

“Chart Body” on page 808, “Display Layer” on page 825, “Legend” on page 833, “Point Layer” on page 851, “Region Layer” on page 857

Filter Type

The type of filter to generate for the join relationship. In generates an IN predicate of constant values. Between generates a BETWEEN predicate using the minimum and maximum values of the join keys. Table generates a table row constructor form of the IN predicate. The default value is In. Applies only to dynamic query mode.

Applies to

“Join” on page 833

First Column Color

Specifies the color, gradient, or pattern to be used for the first column in the progressive chart.

Applies to

“Progressive Chart” on page 854

First Date

Specifies the earliest date to render in the control, and the earliest date that can be selected.

Applies to

“Date & Time Prompt” on page 823, “Date Prompt” on page 824

First Label Index

Specifies which label will be rendered first. If set to 5, for example, the fifth label will be the first label rendered. Subsequent labels will be rendered as defined in the Display Frequency property.

Applies to

“Category Axis” on page 808, “Category axis” on page 808, “X Axis” on page 870, “Y Axis” on page 871

First Slice Angle

Specifies the angle at which the first pie slice begins in a pie chart.

Applies to

“Pie Chart” on page 850

Floating

Specifies how objects flow around an object.

Float controls the way the content that follows the selected object will flow around or below it.

Clear controls where the selected object is positioned, relative to other floating objects.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Block” on page 804, “Bubble Chart” on page 804, “Bubble Chart” on page 805, “Bullet Chart” on page 805, “Combination Chart” on page 813, “Combination Chart” on page 813, “Conditional Block” on page 814, “Conditional Block” on page 814, “Context Item Text” on page 814, “Crosstab” on page 815, “Date & Time Prompt” on page 823, “Date Prompt” on page 824, “Field Set” on page 827, “Gauge Chart” on page 828, “Gauge Chart” on page 828, “Hyperlink” on page 830, “Hyperlink Button” on page 830, “Image” on page 831, “Interval Prompt” on page 831, “List” on page 835, “List Summary” on page 840, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Page Break Text” on page 848, “Pareto Chart” on page 849, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Pie Chart” on page 850, “Polar Chart” on page 852, “Progressive Chart” on page 853, “Progressive Chart” on page 854, “Prompt Button” on page 854, “Radar Chart” on page 855, “Repeater Table” on page 857, “Scatter Chart” on page 859

859, "Scatter Chart" on page 860, "Select & Search Prompt" on page 861, "Static Repeater Table" on page 862, "Table" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Text Box Prompt" on page 865, "Text Item" on page 865, "Time Prompt" on page 866, "Tree Prompt" on page 867, "Value Prompt" on page 868, "Variable Text Item" on page 868, "Win-Loss Chart" on page 869

Font

Specifies the font family, size, weight, style, and effects used to display the object's text.

Applies to

"Axis Labels" on page 802, "Block" on page 804, "Caption" on page 807, "Chart Body" on page 808, "Chart Body" on page 809, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Crosstab" on page 815, "Crosstab Columns" on page 815, "Crosstab Columns" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Rows" on page 817, "Crosstab Rows" on page 818, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Cumulation Line Axis" on page 819, "Date" on page 823, "Equation Label" on page 826, "Field Set" on page 827, "Gauge Labels" on page 829, "Gauge Numerical Axis" on page 829, "Hyperlink" on page 830, "Legend" on page 833, "Legend" on page 834, "List" on page 835, "List Cell" on page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838, "List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "List Summary" on page 840, "Note" on page 846, "Page" on page 847, "Page Break Text" on page 848, "Page Number" on page 848, "Pie Labels" on page 851, "Prompt Button" on page 854, "Repeater Table" on page 857, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Row Number" on page 859, "Row Number" on page 859, "Static Repeater Table" on page 862, "Table" on page 863, "Table Cell" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Table Row" on page 864, "Text Box Prompt" on page 865, "Text Item" on page 865, "Time" on page 865, "Value Prompt" on page 868, "Variable Text Item" on page 868, "Win-Loss Chart" on page 869

Font Auto-Sizing

Specifies whether to allow automatic resizing of the font.

Applies to

"Legend" on page 833

Footer

Specifies whether a chart footer is rendered. This property applies only to legacy charts.

Applies to

"Win-Loss Chart" on page 869

Footer

Specifies whether a chart footer is rendered.

Applies to

Foreground Color

Specifies the color of the object's text.

Applies to

"Axis Labels" on page 802, "Block" on page 804, "Caption" on page 807, "Chart Body" on page 808, "Chart Body" on page 809, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Crosstab" on page 815, "Crosstab Columns" on page 815, "Crosstab Columns" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Rows" on page 817, "Crosstab Rows" on page 818, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Cumulation Line Axis" on page 819, "Date" on page 823, "Equation Label" on page 826, "Field Set" on page 827, "Gauge Labels" on page 829, "Gauge Numerical Axis" on page 829, "Hyperlink" on page 830, "Hyperlink Button" on page 830, "Legend" on page 833, "Legend" on page 834, "List" on page 835, "List Cell" on page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838, "List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "List Summary" on page 840, "Note" on page 846, "Page" on page 847, "Page Break Text" on page 848, "Page Number" on page 848, "Pie Labels" on page 851, "Prompt Button" on page 854, "Repeater Table" on page 857, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Row Number" on page 859, "Row Number" on page 859, "Static Repeater Table" on page 862, "Table" on page 863, "Table Cell" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Table Row" on page 864, "Text Box Prompt" on page 865, "Text Item" on page 865, "Time" on page 865, "Value Prompt" on page 868, "Variable Text Item" on page 868, "Win-Loss Chart" on page 869

From Text

Specifies the label that appears beside the beginning of a range. This property applies to the following prompt types: date, date & time, time, and interval. The default label text is From.

Applies to

"Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Interval Prompt" on page 831, "Text Box Prompt" on page 865, "Time Prompt" on page 866, "Value Prompt" on page 868

Gauge Axes

Specifies the start and end angles for the gauge axes.

Applies to

"Gauge Chart" on page 828

Gauge Axis Colors

Specifies the colors of the gauge axis.

Applies to

“Gauge Axis” on page 827

Gauge Axis Inner Radius

Specifies the inner radius of the gauge axis as a percentage of the maximum allowed.

Applies to

“Gauge Axis” on page 827

Gauge Axis Outer Radius

Specifies the outer radius of the gauge axis as a percentage of the maximum allowed.

Applies to

“Gauge Axis” on page 827

Gauge Border

Specifies whether borders appear around the chart body in a gauge chart.

Applies to

“Gauge Chart” on page 828

Gauge Labels

Specifies whether gauge labels are rendered.

Applies to

“Gauge Chart” on page 828

Gauge Needle

Specifies the size and style of the gauge needle. The chart contains one needle for each row in the data series. All needles on a gauge axis use the same specified styles.

Applies to

“Gauge Axis” on page 827

Gauge Palette

Specifies the palette that controls the look of the dial portion of a gauge.

Applies to

“Gauge Chart” on page 828

Gauge Pivot

Specifies whether to show the center pivot point and its color, size, and style.

Applies to

"Gauge Chart" on page 828

Generated SQL

Shows the generated SQL or MDX.

Applies to

"Query" on page 854

Gradient

Specifies a color gradient for the page.

Applies to

"Page" on page 847

Gridlines

Specifies the properties of the major gridlines in the gauge axis of a gauge chart.

Applies to

"Gauge Axis" on page 827

Gridlines

Specifies the properties of the gridlines in a chart.

Applies to

"Angular Axis" on page 801, "Category Axis" on page 808, "Cumulation Line Axis" on page 819, "Gauge Numerical Axis" on page 829, "Numerical Axis" on page 846, "Numerical Axis" on page 847, "Radial Axis" on page 855, "X Axis" on page 869, "X Axis" on page 870, "Y1 Axis" on page 870, "Y2 Axis" on page 870, "Y Axis" on page 871, "Y Axis" on page 871, "Z Axis" on page 871, "Z Axis" on page 872

Gridlines

Specifies the properties of the major gridlines in a chart.

Applies to

"Category axis" on page 808, "Cumulation Line" on page 819, "Numeric Axis" on page 847, "Pareto Bars" on page 848, "Primary Axis" on page 853, "Primary Bottom Axis" on page 853, "Secondary Axis" on page 861, "Secondary Bottom Axis" on page 861, "X Axis" on page 869, "Y Axis" on page 871

Grouping & Sorting

Specifies the grouping and sorting structure.

Applies to

"List" on page 835, "Page Set" on page 848, "Repeater" on page 857, "Repeater Table" on page 857

Grouping Type

Specifies whether the absolute, stacked, or 100 percent stacked data may be drawn.

Applies to

"Area" on page 801, "Bar" on page 802, "Line" on page 835

Group Span

Specifies the group that this cell should visually span.

Applies to

"List Column Body" on page 837

Has Fact Cells

Specifies the contents of the fact cells of the crosstab. There is only one fact cell definition for the crosstab, regardless of the number of measures.

Applies to

"Crosstab" on page 815

Header Text

Specifies the title that appears above the list of choices in a value prompt. The default title text is the name of the level above the data items that are listed as choices; for example, Regions.

Applies to

"Value Prompt" on page 868

Heading Level

Specifies the heading level of the table of contents entry.

Applies to

"Table of Contents Entry" on page 864

Height (px)

Specifies the height of the note, in pixels.

Applies to

"Note" on page 846

Hide Adornments

Specifies whether to hide the asterisk (*) on required prompts and arrow (->) on type-in prompts that are in an error state.

Applies to

"Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Generated Prompt" on page 829, "Interval Prompt" on page 831, "Select & Search Prompt" on page 861, "Text Box Prompt" on page 865, "Time Prompt" on page 866, "Tree Prompt" on page 867, "Value Prompt" on page 868

Hide Text

Specifies whether to replace characters entered in the prompt control with asterisk (*) characters.

Applies to

"Text Box Prompt" on page 865

Hierarchy

Specifies a reference to a hierarchy. You cannot modify this value.

Applies to

"Area" on page 801, "Bar" on page 802, "Calculated Member" on page 807, "Category Baseline" on page 808, "Chart Node Member" on page 809, "Chart Text Item" on page 810, "Chart Text Item" on page 810, "Colored Region" on page 812, "Colored Region" on page 812, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Cumulation Line Label" on page 819, "Dimensional Edge Summary" on page 825, "Explicit Member Set" on page 826, "Gauge Axis" on page 827, "Hierarchy Set" on page 829, "HTML Item" on page 829, "Image" on page 831, "Intersection (Tuple)" on page 831, "Level Set" on page 835, "Line" on page 835, "List Cell" on page 836, "List Column Body" on page 837, "List Column Title" on page 838, "Map Location" on page 841, "Map Location" on page 841, "Map Refinement Location" on page 841, "Map Refinement Location" on page 842, "Marker" on page 842, "Member" on page 844, "Member Children Set" on page 844, "Member Property" on page 844, "Named Set" on page 845, "Numeric Baseline" on page 847, "Rich Text Item" on page 859, "Scatter Marker" on page 860, "Set Expression" on page 861, "Text Item" on page 865, "Total Column" on page 866, "Win-Loss Measure" on page 869

Hierarchy Unique Name

Specifies the Hierarchy Unique Name (HUN) of the hierarchy to which the data item belongs.

Applies to

"Area" on page 801, "Bar" on page 802, "Category Baseline" on page 808, "Chart Node Member" on page 809, "Chart Text Item" on page 810, "Chart Text Item" on page 810, "Colored Region" on page 812, "Colored Region" on page 812, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Cumulation Line Label" on page 819, "Gauge Axis" on page 827,

"Hierarchy Set" on page 829, "HTML Item" on page 829, "Image" on page 831, "Line" on page 835, "List Cell" on page 836, "List Column Body" on page 837, "List Column Title" on page 838, "Map Location" on page 841, "Map Location" on page 841, "Map Refinement Location" on page 841, "Map Refinement Location" on page 842, "Marker" on page 842, "Numeric Baseline" on page 847, "Rich Text Item" on page 859, "Scatter Marker" on page 860, "Text Item" on page 865, "Total Column" on page 866, "Win-Loss Measure" on page 869

Highest Value Text

Specifies the label that appears beside the highest value option when ranges are enabled. This property applies to the following prompt types: date, date & time, time, value, text box, and interval. The default label text is Latest date, Latest time, or Highest interval.

Applies to

"Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Interval Prompt" on page 831, "Text Box Prompt" on page 865, "Time Prompt" on page 866, "Value Prompt" on page 868

Hole Size (%)

Specifies the size of the hole in a donut chart. A value of zero indicates a pie chart.

Applies to

"Pie Chart" on page 850, "Pie Chart" on page 850

Horizontal Alignment

Specifies how the contents of the selected object are aligned horizontally.

Applies to

"Block" on page 804, "Chart Body" on page 808, "Chart Body" on page 809, "Chart Footer" on page 809, "Chart Footer" on page 809, "Chart Subtitle" on page 810, "Chart Subtitle" on page 810, "Chart Title" on page 811, "Chart Title" on page 811, "Conditional Block" on page 814, "Conditional Block" on page 814, "Crosstab" on page 815, "Crosstab Columns" on page 815, "Crosstab Columns" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Rows" on page 817, "Crosstab Rows" on page 818, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Equation Label" on page 826, "Field Set" on page 827, "Gauge Labels" on page 829, "Legend" on page 833, "Legend" on page 834, "Legend Title" on page 834, "Legend Title" on page 834, "List" on page 835, "List Cell" on page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838, "List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "Note" on page 846, "Note Content" on page 846, "Page" on page 847, "Pie Labels" on page 851, "Repeater Table" on page 857, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Static Repeater Table" on page 862, "Table" on page 863, "Table Cell" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Table Row" on page 864

Hours Text

Specifies the title that appears above the hours box in interval prompts. The default title text is Hrs.

Applies to

“Interval Prompt” on page 831

HTML

Specifies the static text used as HTML.

Applies to

“HTML Item” on page 829, “Rich Text Item” on page 859

HTML Source Variable

Specifies a variable based on which the HTML source is chosen.

Applies to

“HTML Item” on page 829, “Rich Text Item” on page 859

Icon

Specifies the image used to identify the object in the control.

Applies to

“Button” on page 806, “Button” on page 806, “Check Box” on page 811, “List Item” on page 839, “Radio Button” on page 856, “Tab” on page 863

Ignore Data with No Features

Specifies whether to allow data that has no corresponding features. When set to Yes, data with no corresponding features will be ignored. When set to No, the map will not run if it contains data with no corresponding features.

Applies to

“Map” on page 841

Ignore Hover when No Data

Specifies whether to highlight areas in the data container that are not clickable, because there is no data for those areas.

Applies to

“Map” on page 841

Include Zero For Auto Scale

Specifies whether the value zero is included in the automatic calculation of the numeric scale. This property applies only to legacy charts.

Applies to

"Angular Axis" on page 801, "Gauge Numerical Axis" on page 829, "Numerical Axis" on page 846, "Numerical Axis" on page 847, "Radial Axis" on page 855, "X Axis" on page 869, "Y1 Axis" on page 870, "Y2 Axis" on page 870, "Y Axis" on page 871, "Z Axis" on page 871, "Z Axis" on page 872

Inherited Style

The report where the styles are referenced from.

Applies to

"Class" on page 811

Insert Text

Specifies the label that appears on the button that is used to add items to the selected items box in all multiple selection prompts. The default label text is Insert.

Applies to

"Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Interval Prompt" on page 831, "Select & Search Prompt" on page 861, "Text Box Prompt" on page 865, "Time Prompt" on page 866, "Value Prompt" on page 868

Iterator First

Specifies whether to show or hide the First button in the iterator.

Applies to

"Data Iterator" on page 822, "Iterator" on page 831

Iterator Label Area

Specifies whether to show or hide the labels of iterator values.

Applies to

"Data Iterator" on page 822, "Iterator" on page 831

Iterator Last

Specifies whether to show or hide the Last button in the iterator.

Applies to

"Data Iterator" on page 822, "Iterator" on page 831

Iterator Next

Specifies whether to show or hide the Next button in the iterator.

Applies to

"Data Iterator" on page 822, "Iterator" on page 831

Iterator Previous

Specifies whether to show or hide the Previous button in the iterator.

Applies to

“Data Iterator” on page 822, “Iterator” on page 831

Iterator Values Definition

Defines the values of the iterator.

Applies to

“Iterator” on page 831

Join Relationships

Specifies how to join the two queries.

Applies to

“Join” on page 833

Keywords Text

Specifies the title that appears above the keyword search box in select & search prompts. The default title text is Keywords.

Applies to

“Select & Search Prompt” on page 861

Label

Specifies the static text that defines the bookmark. The value used as the bookmark reference must match this value.

Applies to

“Bookmark” on page 804

Label

Specifies the class label for a local class.

Applies to

“Class” on page 811

Label

Specifies the class label for a global class. You cannot modify this label.

Applies to

“Class” on page 811

Label

Specifies the name of the no value list item.

Applies to

“No Value List Item” on page 846

Label

Specifies the name of the object in the control.

Applies to

“Button” on page 806, “Button” on page 806, “Check Box” on page 811, “List Item” on page 839, “Radio Button” on page 856, “Tab” on page 863

Label

Specifies whether a label is rendered for the baseline.

Applies to

“Baseline” on page 803, “Baseline” on page 803

Label

Specifies whether a label is rendered for the marker.

Applies to

“Marker” on page 843, “Marker” on page 843

Label

The label for the data item. Automatic text uses the data item name as the label. Specified text uses text that you specify as the label. With specified text, you can add translations for the label to support users in multiple languages.

Applies to

“Category” on page 808, “Value” on page 867

Label

Defines the button label in the iterator.

Applies to

“Iterator First” on page 832, “Iterator Last” on page 832, “Iterator Next” on page 832, “Iterator Previous” on page 832

Label

Specifies the label of the object.

Applies to

“Calculated Measure” on page 807, “Calculated Member” on page 807, “Custom Groups” on page 820, “Dimensional Edge Summary” on page 825, “Edge Summary” on page 826, “Explicit Member Set” on page 826, “Hierarchy Set” on page 829, “Intersection (Tuple)” on page 831, “Level Set” on page 835, “List Summary” on page 840, “Measure” on page 843, “Member” on page 844, “Member Children Set” on page 844, “Member Property” on page 844, “Named Set” on page 845, “Percentaged Measure” on page 850, “Set Expression” on page 861

Label Color

Specifies the color of labels in the slider.

Applies to

“Continuous Values Slider” on page 814, “Data Discrete Values Slider” on page 821, “Discrete Values Slider” on page 825

Label Control

Controls how the labels in a chart are rendered.

Applies to

“Category Axis” on page 808, “X Axis” on page 870, “Y Axis” on page 871

Label Control

Controls how the labels in a chart are rendered.

When you select Manual from the drop-down menu, other properties appear that control how labels are displayed. If you specify values that cause labels to overlap, adjustments are made automatically. For example, Display Frequency is set to show every label. If there is not enough room to show all labels on the axis, some labels are removed. In addition, the axis label property Auto Font Size can also impact the number of labels that are displayed.

Applies to

“Category axis” on page 808

Label For

Specifies the name of the prompt control to associate to the text item. This property is used to make a prompt control accessible by defining a label for the control.

Applies to

“Text Item” on page 865

Label Location

Specifies whether to show the label in the legend or in the chart.

Applies to

“Marker” on page 842, “Scatter Marker” on page 860

Labels

Specifies whether labels are rendered.

Applies to

"Pie Chart" on page 850

Last Date

Specifies the latest date rendered in the control, and the last date that can be selected.

Applies to

"Date & Time Prompt" on page 823, "Date Prompt" on page 824

Layout Table

Specifies whether to render the object as a data table or as a layout table. Applies to lists, crosstabs, and repeater tables. Use this property to make your reports accessible for people who use screen readers. For example, when you create sections in a list, the outer list acts as headings and not as data rows. To correctly identify the outer list as a layout table, set this property for the outer list to Yes.

Applies to

"Crosstab" on page 815, "List" on page 835, "Repeater Table" on page 857

Left Position

Specifies the position of the left edge of the colored region.

Applies to

"Colored Region" on page 812

Left Position (px)

Specifies the pixel position of the bottom edge of the note measured from the left edge of the chart.

Applies to

"Note" on page 846

Left Position (px)

Specifies the pixel position of the left edge of the legend measured from the left edge of the chart.

Applies to

"Legend" on page 833

Legend

Specifies whether the legend is rendered.

Applies to

“3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Combination Chart” on page 813, “Gauge Chart” on page 828, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Polar Chart” on page 852, “Radar Chart” on page 855, “Scatter Chart” on page 859

Legend

Specifies whether a legend is rendered and where the legend is positioned in a chart.

Applies to

“Bubble Chart” on page 805, “Bullet Chart” on page 805, “Combination Chart” on page 813, “Gauge Chart” on page 828, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Progressive Chart” on page 853, “Scatter Chart” on page 860

Legend Label

Specifies whether to render the baseline in the legend.

Applies to

“Baseline” on page 803, “Baseline” on page 803

Legend Separator

Specifies the separator to use between the legend entry and the value when you show values in the legend. The default is a comma (,) followed by a space.

Applies to

“Legend” on page 834

Legend Title

Specifies whether a legend title is rendered. This property applies only to legacy charts.

Applies to

“Legend” on page 833

Legend Title

Specifies whether a legend title is rendered in a chart.

Applies to

“Legend” on page 834

Legend Title

Specifies whether a legend title is rendered in a chart.

Applies to

"Legend" on page 833, "Legend" on page 834

Level

Specifies a reference to a level. You cannot modify this value.

Applies to

"Area" on page 801, "Bar" on page 802, "Category Baseline" on page 808, "Chart Node Member" on page 809, "Chart Text Item" on page 810, "Chart Text Item" on page 810, "Colored Region" on page 812, "Colored Region" on page 812, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Cumulation Line Label" on page 819, "Gauge Axis" on page 827, "HTML Item" on page 829, "Image" on page 831, "Level Set" on page 835, "Line" on page 835, "List Cell" on page 836, "List Column Body" on page 837, "List Column Title" on page 838, "Map Location" on page 841, "Map Location" on page 841, "Map Refinement Location" on page 841, "Map Refinement Location" on page 842, "Marker" on page 842, "Member Property" on page 844, "Numeric Baseline" on page 847, "Rich Text Item" on page 859, "Scatter Marker" on page 860, "Text Item" on page 865, "Total Column" on page 866, "Win-Loss Measure" on page 869

Level Indentation

Controls the indentation of the contents of node members in a crosstab.

Applies to

"Crosstab Node Member" on page 817

Level Unique Name

Specifies the Level Unique Name (LUN) of the level to which the data item belongs.

Applies to

"Area" on page 801, "Bar" on page 802, "Category Baseline" on page 808, "Chart Node Member" on page 809, "Chart Text Item" on page 810, "Chart Text Item" on page 810, "Colored Region" on page 812, "Colored Region" on page 812, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Cumulation Line Label" on page 819, "Gauge Axis" on page 827, "HTML Item" on page 829, "Image" on page 831, "Level Set" on page 835, "Line" on page 835, "List Cell" on page 836, "List Column Body" on page 837, "List Column Title" on page 838, "Map Location" on page 841, "Map Location" on page 841, "Map Refinement Location" on page 841, "Map Refinement Location" on page 842, "Marker" on page 842, "Numeric Baseline" on page 847, "Rich Text Item" on page 859, "Scatter Marker" on page 860, "Text Item" on page 865, "Total Column" on page 866, "Win-Loss Measure" on page 869

Line and Markers

Specifies whether to display a line and whether to display markers.

Applies to

"Line" on page 835

Line Shape

Specifies the shape of a line in a line chart.

Applies to

"Line" on page 835

Line Style

Specifies the style, color, and weight of the line in a Pareto chart.

Applies to

"Cumulation Line" on page 819

Line Style

Specifies the style, color, and weight of the line.

Applies to

"Category Baseline" on page 808, "Numeric Baseline" on page 847, "Trendline" on page 867

Line Style

Specifies the style, color, and weight of the line. This property applies only to legacy charts.

Applies to

"Line" on page 835

Line Styles

Specifies the style, color, and weight of the line.

Applies to

"Baseline" on page 803, "Baseline" on page 803, "Baseline" on page 803, "Baseline" on page 803, "Cumulation Line" on page 819, "Regression Line" on page 857

Line Type

Specifies the type of line used to connect data values.

Applies to

"Line" on page 835

Line Weight (pt)

Specifies the line thickness in points. A value of zero indicates the thinnest possible line.

Applies to

“Line” on page 835

List Items Definition

Defines the list items in the control.

Applies to

“Drop-Down List” on page 826, “List Box” on page 836

Loss Color

Specifies a color, color gradient, or pattern to apply to the loss values.

Applies to

“Win-Loss Chart” on page 869

Lowest Value Text

Specifies the label that appears beside the lowest value option when ranges are enabled. This property applies to the following prompt types: date, date & time, time, value, text box, and interval. The default label text is Earliest date, Earliest time, or Lowest interval.

Applies to

“Date & Time Prompt” on page 823, “Date Prompt” on page 824, “Interval Prompt” on page 831, “Text Box Prompt” on page 865, “Time Prompt” on page 866, “Value Prompt” on page 868

Map & Layers

Sets the map and layers for a map chart.

Applies to

“Map” on page 841

Map Drills

Controls the drill definitions in a map. It is possible to define different drill targets for each region or point.

Applies to

“Point Layer” on page 851, “Region Layer” on page 857

Margin

Specifies the margin properties for the object.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Block” on page 804, “Bubble Chart” on page 804, “Bubble Chart” on page 805, “Bullet Chart” on page 805, “Caption” on page 807, “Combination Chart” on page 813,

"Combination Chart" on page 813, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Crosstab" on page 815, "Date" on page 823, "Field Set" on page 827, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Hyperlink" on page 830, "Hyperlink Button" on page 830, "Image" on page 831, "List" on page 835, "List Summary" on page 840, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Page" on page 847, "Page Break Text" on page 848, "Page Number" on page 848, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Prompt Button" on page 854, "Radar Chart" on page 855, "Repeater Table" on page 857, "Row Number" on page 859, "Row Number" on page 859, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Static Repeater Table" on page 862, "Table" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Text Item" on page 865, "Time" on page 865, "Variable Text Item" on page 868, "Win-Loss Chart" on page 869

Marimekko Totals

Specifies whether to show totals for each column at the top of the chart.

Applies to

"Marimekko Chart" on page 842

Marker Color

Specifies a color for the target value markers in a metrics chart.

Applies to

"Metrics Range Chart" on page 845

Marker Color

Specifies the color of the markers.

Applies to

"Marker" on page 843, "Marker" on page 843

Marker Label

Specifies whether the label for the Target Marker will appear in the legend.

Applies to

"Metrics Range Chart" on page 845

Markers

Adds reference points to a chart based on numeric or statistical values, calculations, or layout calculations. This property applies only to legacy charts.

Applies to

"Bubble Chart" on page 804, "Combination Chart" on page 813, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Pareto Chart" on page 849

849, "Polar Chart" on page 852, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Scatter Chart" on page 859

Markers

Adds reference points to a chart based on numeric or statistical values, calculations, or layout calculations.

Applies to

"Bubble Chart" on page 805, "Combination Chart" on page 813, "Pareto Chart" on page 849, "Progressive Chart" on page 853, "Scatter Chart" on page 860

Marker Shape

Specifies the shape of the markers.

Applies to

"Cumulation Line" on page 819, "Marker" on page 843, "Marker" on page 843

Marker Shape

Specifies the shape of the marker symbol.

Applies to

"Marker" on page 842, "Scatter Marker" on page 860

Marker Size (pt)

Specifies the size of markers in points. A value of zero means do not show markers.

Applies to

"3-D Scatter Chart" on page 800, "Cumulation Line" on page 819, "Marker" on page 843, "Marker" on page 843, "Polar Chart" on page 852, "Radar Chart" on page 855, "Scatter Chart" on page 859

Marker Size (pt)

Specifies the size of markers in points. A value of zero means do not show markers.

Applies to

"Marker" on page 842, "Scatter Marker" on page 860

Marker Style

Specifies the shape, fill type, and color of the markers in the chart.

Applies to

"Marker" on page 842, "Scatter Marker" on page 860

Marker Text Location

Specifies where the text of the marker is rendered.

Applies to

"Bubble Chart" on page 804, "Combination Chart" on page 813, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Pareto Chart" on page 849, "Polar Chart" on page 852, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Scatter Chart" on page 859

Master Detail Relationships

Specifies relationships between the master data container and the detail data container. Specifically, specifies how query items in the master query are linked to query items or parameters in the detail query.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Axis Title" on page 802, "Axis Title" on page 802, "Baseline" on page 803, "Baseline" on page 803, "Baseline" on page 803, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Category Baseline" on page 808, "Chart Footer" on page 809, "Chart Footer" on page 809, "Chart Subtitle" on page 810, "Chart Subtitle" on page 810, "Chart Title" on page 811, "Chart Title" on page 811, "Colored Region" on page 812, "Colored Region" on page 812, "Combination Chart" on page 813, "Combination Chart" on page 813, "Crosstab" on page 815, "Data Button Bar" on page 820, "Data Check Box Group" on page 820, "Data Container" on page 820, "Data Deck" on page 821, "Data Discrete Values Slider" on page 821, "Data Drop-Down List" on page 821, "Data Iterator" on page 822, "Data List Box" on page 822, "Data Radio Button Group" on page 822, "Data Tab Control" on page 823, "Data Toggle Button Bar" on page 823, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Label" on page 833, "Legend Title" on page 834, "Legend Title" on page 834, "List" on page 835, "Map" on page 841, "Marimekko Chart" on page 842, "Marker" on page 842, "Marker" on page 843, "Marker" on page 843, "Metrics Range Chart" on page 845, "Note" on page 846, "Note Content" on page 846, "Numeric Baseline" on page 847, "Page" on page 847, "Page Set" on page 848, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Point Color Legend Title" on page 851, "Point Size Legend Title" on page 852, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Region Color Legend Title" on page 856, "Repeater" on page 857, "Repeater Table" on page 857, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Scatter Marker" on page 860, "Win-Loss Chart" on page 869

Material Effects

Specifies a material effect, such as plastic or metallic.

Applies to

"Bubble Chart" on page 805, "Combination Chart" on page 813, "Pareto Chart" on page 849, "Progressive Chart" on page 853, "Scatter Chart" on page 860

Material Effects

Specifies a material effect, such as plastic or metallic, in a pie chart.

Applies to

"Pie Chart" on page 850

Matrix Rows and Columns

Specifies whether to render a matrix of charts in rows and columns.

Applies to

"Bubble Chart" on page 805, "Bullet Chart" on page 805, "Combination Chart" on page 813, "Gauge Chart" on page 828, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Progressive Chart" on page 853, "Scatter Chart" on page 860

Maximum Characters

Specifies the maximum number of characters to show before the text is truncated.

Applies to

"Legend" on page 833, "Text Item" on page 865

Maximum Execution Time

Specifies the maximum period, in seconds, that the query can spend to open the database cursor and to retrieve the first row of data. An error is returned if the specified time is exceeded. Note that this property is not for the total time required to execute the query. If no value is specified, no error is returned and the query runs until complete.

Applies to

"Query" on page 854

Maximum Hotspots

Specifies the maximum number of hotspots generated in a chart. A hotspot in a chart appears when you pause a pointer over it. For example, a hotspot on a drill-down symbol or a tooltip gives details about the column, line, or pie slice. If specified, this value overrides the hotspot configuration settings in IBM® Cognos® Administration.

For more information, see the topic Changing the number of hotspots in a chart.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Combination Chart" on page 813, "Combination Chart" on page 813, "Data Container" on page 820, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Win-Loss Chart" on page 869

Maximum Rows Retrieved

Specifies the maximum number of database rows that the query can retrieve. An error is returned if the number of database rows returned exceeds the specified value. If no value is specified, no error is returned and the query returns all rows.

Applies to

“Query” on page 854

Maximum Size (pt)

Specifies the maximum size used for map point features that have corresponding data. For example, if the minimum size is 2pt and the maximum size is 12pt, the size of each point is calculated using linear interpolation that is based on its measure value.

Applies to

“Point Size Measure” on page 852

Maximum Tables

Specifies the maximum number of tables that the query can retrieve. An error is returned if the number of tables in the generated IBM® Cognos® SQL exceeds the specified value. If no value is specified, no error is returned and there is no restriction on the number of tables that can be queried.

Applies to

“Query” on page 854

Maximum Text Blob Characters

Specifies the maximum number of characters that the query is allowed to retrieve for each text BLOB. An error is returned if the number of characters retrieved exceeds the specified value. If no value is specified, no error is returned and text BLOBs can be of any size.

Applies to

“Query” on page 854

Maximum Truncation Characters

Specifies the maximum number of characters to show before the label is truncated.

If the **Allow Truncation** property is set to **Yes** and no value is specified in the **Maximum Characters** property, the application automatically determines the optimum number of characters after which to truncate. Use this property only if you want explicit control over the truncation level. Note that regardless of this property's setting, no truncation will occur if there is sufficient space.

Applies to

“Category Axis” on page 808, “Gauge Labels” on page 829, “Pie Labels” on page 851, “X Axis” on page 870, “Y Axis” on page 871

Maximum Value

Specifies the maximum value for the numeric scale. If no value is specified, one will be calculated based on the data.

Applies to

"Angular Axis" on page 801, "Gauge Numerical Axis" on page 829, "Numerical Axis" on page 846, "Numerical Axis" on page 847, "Radial Axis" on page 855, "X Axis" on page 869, "Y1 Axis" on page 870, "Y2 Axis" on page 870, "Y Axis" on page 871, "Z Axis" on page 871, "Z Axis" on page 872

Maximum Value

Specifies the maximum value for the slider.

Applies to

"Continuous Values Slider" on page 814

MDX

The text of the typed-in MDX. It is assumed to be appropriate for the type and data source. If it is not the query may fail or produce unexpected results.

Applies to

"MDX" on page 843

Member

Specifies a reference to a member. You cannot modify this value.

Applies to

"Area" on page 801, "Bar" on page 802, "Category Baseline" on page 808, "Chart Node Member" on page 809, "Chart Text Item" on page 810, "Chart Text Item" on page 810, "Colored Region" on page 812, "Colored Region" on page 812, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Cumulation Line Label" on page 819, "Gauge Axis" on page 827, "HTML Item" on page 829, "Image" on page 831, "Line" on page 835, "List Cell" on page 836, "List Column Body" on page 837, "List Column Title" on page 838, "Map Location" on page 841, "Map Location" on page 841, "Map Refinement Location" on page 841, "Map Refinement Location" on page 842, "Marker" on page 842, "Measure" on page 843, "Member" on page 844, "Member Children Set" on page 844, "Numeric Baseline" on page 847, "Rich Text Item" on page 859, "Scatter Marker" on page 860, "Text Item" on page 865, "Total Column" on page 866, "Win-Loss Measure" on page 869

Member Offset (%)

Specifies a position relative to the next item in the chart. This is a percentage value. Negative values indicate before the member and positive values indicate after the member.

Applies to

“Baseline” on page 803, “Category Baseline” on page 808, “Marker” on page 842

Members

Specifies the members of the intersection (tuple).

Applies to

“Intersection (Tuple)” on page 831

Members

Specifies the members in the member set.

Applies to

“Explicit Member Set” on page 826

Member Unique Name

Specifies the Member Unique Name (MUN) of the member.

Applies to

“Area” on page 801, “Bar” on page 802, “Category Baseline” on page 808, “Chart Node Member” on page 809, “Chart Text Item” on page 810, “Chart Text Item” on page 810, “Colored Region” on page 812, “Colored Region” on page 812, “Crosstab Corner” on page 816, “Crosstab Fact Cells” on page 816, “Crosstab Intersection” on page 816, “Crosstab Member Fact Cells” on page 817, “Crosstab Node Member” on page 817, “Cumulation Line Label” on page 819, “Gauge Axis” on page 827, “HTML Item” on page 829, “Image” on page 831, “Line” on page 835, “List Cell” on page 836, “List Column Body” on page 837, “List Column Title” on page 838, “Map Location” on page 841, “Map Location” on page 841, “Map Refinement Location” on page 841, “Map Refinement Location” on page 842, “Marker” on page 842, “Measure” on page 843, “Member” on page 844, “Member Children Set” on page 844, “Numeric Baseline” on page 847, “Rich Text Item” on page 859, “Scatter Marker” on page 860, “Text Item” on page 865, “Total Column” on page 866, “Win-Loss Measure” on page 869

Milliseconds Text

Specifies the title that appears above the milliseconds box in interval prompts. The default title text is ms.

Applies to

“Interval Prompt” on page 831

Minimum Size (pt)

Specifies the minimum size used for map point features that have corresponding data. For example, if the minimum size is 2pt and the maximum size is 12pt, the size of each point is calculated using linear interpolation that is based on its measure value.

Applies to

"Point Size Measure" on page 852

Minimum Value

Specifies the minimum value for the numeric scale. If no value is specified, one will be calculated based on the data.

Applies to

"Angular Axis" on page 801, "Gauge Numerical Axis" on page 829, "Numerical Axis" on page 846, "Numerical Axis" on page 847, "Radial Axis" on page 855, "X Axis" on page 869, "Y1 Axis" on page 870, "Y2 Axis" on page 870, "Y Axis" on page 871, "Z Axis" on page 871, "Z Axis" on page 872

Minimum Value

Specifies the minimum value for the slider.

Applies to

"Continuous Values Slider" on page 814

Minor Gridlines

Specifies the properties of the minor gridlines in the gauge axis of a gauge chart.

Applies to

"Gauge Axis" on page 827

Minor Gridlines

Specifies the properties of the minor gridlines in a chart. This property applies only to legacy charts.

Applies to

"Angular Axis" on page 801, "Category Axis" on page 808, "Cumulation Line Axis" on page 819, "Gauge Numerical Axis" on page 829, "Numerical Axis" on page 846, "Numerical Axis" on page 847, "Radial Axis" on page 855, "X Axis" on page 869, "X Axis" on page 870, "Y1 Axis" on page 870, "Y2 Axis" on page 870, "Y Axis" on page 871, "Y Axis" on page 871, "Z Axis" on page 871, "Z Axis" on page 872

Minor Gridlines

Specifies the properties of the minor gridlines in a chart.

Applies to

"Category axis" on page 808, "Cumulation Line" on page 819, "Numeric Axis" on page 847, "Pareto Bars" on page 848, "Primary Axis" on page 853, "Primary Bottom Axis" on page 853, "Secondary Axis" on page 861, "Secondary Bottom Axis" on page 861, "X Axis" on page 869, "Y Axis" on page 871

Minutes Text

Specifies the title that appears above the minutes box in interval prompts. The default title text is Mins.

Applies to

“Interval Prompt” on page 831

Multi-Line

Specifies whether to allow multi-line editing in the text control

Applies to

“Text Box Prompt” on page 865

Multi-Select

Specifies whether the control allows the selection of multiple values. Note that an associated parameterized filter expression will override this object's setting. If you edit this property but do not get the expected results, check the associated expression for the presence of an operator that specifies how many items can be selected. Examples of multiple selection operators are "in" and "not in"; examples of single selection operators are equal (=), less than (<) and greater than (>).

For example, if you used the prompt wizard to create a parameterized filter expression and selected one of the operators that specify selection rules, changing the value of this property is not sufficient to change this restriction. You must also edit the filter's expression to remove the offending operator.

To edit a filter expression, you must select the filter, which is accessible from the Query view, using the Explorer bar.

Applies to

“Data List Box” on page 822, “Date & Time Prompt” on page 823, “Date Prompt” on page 824, “Interval Prompt” on page 831, “List Box” on page 836, “Select & Search Prompt” on page 861, “Text Box Prompt” on page 865, “Time Prompt” on page 866, “Tree Prompt” on page 867, “Value Prompt” on page 868

Name

Applies to

“Class” on page 811

Name

Specifies the name of the object.

Applies to

“Calculated Measure” on page 807, “Calculated Member” on page 807, “Custom Groups” on page 820, “Dimensional Edge Summary” on page 825, “Edge Summary” on page 826, “Explicit Member Set” on page 826, “Hierarchy Set” on page 829, “Intersection (Tuple)” on page 831, “Level Set” on page 835, “List Summary” on page 840, “Measure” on page 843, “Member” on page 844, “Member

Children Set” on page 844, “Member Property” on page 844, “Named Set” on page 845, “Percentaged Measure” on page 850, “Set Expression” on page 861

Name

Specifies the name of the object.

Applies to

“Page Set” on page 848

Name

Specifies the name of the object.

Applies to

“Page” on page 847

Name

The name of the booklet item.

Applies to

“Report Reference” on page 858

Name

Specifies a unique name that allows layout objects to be reused, usually to take advantage of any applied styling.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Block” on page 804, “Bubble Chart” on page 804, “Bubble Chart” on page 805, “Bullet Chart” on page 805, “Button” on page 806, “Button Bar” on page 806, “Check Box Group” on page 811, “Combination Chart” on page 813, “Combination Chart” on page 813, “Continuous Values Slider” on page 814, “Crosstab” on page 815, “Data Button Bar” on page 820, “Data Check Box Group” on page 820, “Data Container” on page 820, “Data Deck” on page 821, “Data Discrete Values Slider” on page 821, “Data Drop-Down List” on page 821, “Data Iterator” on page 822, “Data List Box” on page 822, “Data Radio Button Group” on page 822, “Data Tab Control” on page 823, “Data Toggle Button Bar” on page 823, “Date & Time Prompt” on page 823, “Date Prompt” on page 824, “Deck” on page 824, “Discrete Values Slider” on page 825, “Drop-Down List” on page 826, “Field Set” on page 827, “Gauge Chart” on page 828, “Gauge Chart” on page 828, “Generated Prompt” on page 829, “HTML Item” on page 829, “Hyperlink” on page 830, “Hyperlink Button” on page 830, “Image” on page 831, “Interval Prompt” on page 831, “Iterator” on page 831, “List” on page 835, “List Box” on page 836, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Pie Chart” on page 850, “Polar Chart” on page 852, “Progressive Chart” on page 853, “Progressive Chart” on page 854, “Prompt Button” on page 854, “Radar Chart” on page 855, “Radio Button Group” on page 856, “Repeater” on page 857, “Repeater Table” on page 857, “Rich Text Item” on page 859, “Scatter Chart” on page 859, “Scatter Chart” on page 860, “Select & Search Prompt” on page 861, “Singleton” on page 862, “Static Repeater Table” on page 862, “Tab Control” on page 863, “Table” on page 863

page 863, "Text Box Prompt" on page 865, "Text Item" on page 865, "Time Prompt" on page 866, "Toggle Button Bar" on page 866, "Tree Prompt" on page 867, "Value Prompt" on page 868, "Visualization" on page 868, "Win-Loss Chart" on page 869

Name

Specifies the name of the object.

Applies to

"Query" on page 854

Name

Specifies the unique name identifier for a query operation.

Applies to

"Query Operation" on page 855

Name

Specifies the unique name identifier for an SQL object.

Applies to

"SQL" on page 862

Name

Specifies the unique name identifier for an MDX object.

Applies to

"MDX" on page 843

Name

Specifies the name of the object.

Applies to

"Dimension" on page 825

Name

Specifies the name of the object.

Applies to

"Level" on page 834

Name

Specifies the name of the object.

Applies to

"Fact" on page 827

Name

Specifies the name of the object.

Applies to

"Member Set" on page 844

Name

Specifies the name of the object.

Applies to

"Variable" on page 868

Name

Specifies a unique name that allows layout objects to be reused, usually to take advantage of any applied formatting.

Applies to

"Calculated Member" on page 807, "Key" on page 833, "Level Hierarchy" on page 835, "Member Hierarchy" on page 844, "Member Property" on page 844

Negative Column Color

Specifies the color, gradient, or pattern to be used for columns in the progressive chart that represent negative values.

Applies to

"Progressive Chart" on page 854

Nested Label Display

Specifies how to display the axis labels for nested categories. Concatenated separates the labels with a comma.

Applies to

"Axis Labels" on page 802

Nesting Order

Specifies the nesting order of extra categories in the query. Change the nesting order of extra categories when items are from the same dimension. For example, a visualization has Year as categories, and Month and Quarter as extra categories. The order of categories must be Year, Quarter, and Month for the query to run.

Applies to

"Data Container" on page 820

No Data Contents

Specifies what appears in a data container when there is no data available from the database. When set to No Content, shows an empty data container, such as a blank list. When set to Content specified in the No data tab, shows the content that you specified in the No data tab. You can insert any object from the Toolbox tab. When set to Specified text (the default), shows the text that you specify.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Bubble Chart” on page 805, “Bullet Chart” on page 805, “Combination Chart” on page 813, “Combination Chart” on page 813, “Crosstab” on page 815, “Gauge Chart” on page 828, “Gauge Chart” on page 828, “List” on page 835, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Pie Chart” on page 850, “Polar Chart” on page 852, “Progressive Chart” on page 853, “Progressive Chart” on page 854, “Radar Chart” on page 855, “Repeater” on page 857, “Repeater Table” on page 857, “Scatter Chart” on page 859, “Scatter Chart” on page 860, “Table of Contents” on page 864, “Win-Loss Chart” on page 869

No Data Features Size (pt)

Specifies the point size used for map point features that do not have corresponding data.

Applies to

“Map” on page 841

Node Coordinate

Uniquely identifies a node member or spacer on an edge of a crosstab. Used by the Crosstab Intersection object to uniquely identify the intersection of elements from each edge. You cannot modify this value.

Applies to

“Crosstab Node Member” on page 817, “Crosstab Space” on page 818, “Crosstab Summary” on page 818

Note Border

Specifies the properties for the border of a note.

Applies to

“Note” on page 846

Notes

Specifies a block of text that you can position on a chart.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Combination Chart” on page 813, “Gauge Chart” on page 828

828, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Scatter Chart" on page 859

Notes

Specifies whether a note is rendered in a chart.

Applies to

"Bubble Chart" on page 805, "Bullet Chart" on page 805, "Combination Chart" on page 813, "Gauge Chart" on page 828, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Progressive Chart" on page 853, "Scatter Chart" on page 860

Note Text

Specifies the text that appears in a note within a chart. To edit the note text, you must switch to Page Design view (View > Page Design)

Applies to

"Note" on page 846, "Note" on page 846

No Value List Item

Specifies whether to define a default list item. When the default item is selected, sets the value of the data item in the control to null. By default, the no value item is the first item in the list.

Applies to

"Data Drop-Down List" on page 821, "Data List Box" on page 822, "Drop-Down List" on page 826, "List Box" on page 836

Number of Minor Intervals

When minor gridlines are defined for the chart axis, specifies by how many minor intervals to divide the major intervals. The default value is 2, which shows one minor gridline between each major gridline.

Applies to

"Category axis" on page 808, "Gauge Axis" on page 827, "Numeric Axis" on page 847, "X Axis" on page 869, "Y Axis" on page 871

Number of Minor Intervals

When minor gridlines are defined for the chart axis, specifies by how many minor intervals to divide the major intervals. The default value is 2, which shows one minor gridline between each major gridline.

Applies to

"Cumulation Line" on page 819, "Pareto Bars" on page 848, "Primary Axis" on page 853, "Primary Bottom Axis" on page 853, "Secondary Axis" on page 861, "Secondary Bottom Axis" on page 861

Number of Regression Lines

Specifies whether there will be one regression line for all the data or one for each series.

Applies to

“Regression Line” on page 857

Number of Stagger Levels

Specifies the number of stagger levels to use when rendering labels on an axis.

Applies to

“Category axis” on page 808

Numbers Only

Specifies whether the Text Box Prompt allows numbers only.

Applies to

“Text Box Prompt” on page 865

Number Style

Specifies the style to use for page numbers.

Applies to

“Page Number” on page 848

Number Style

Specifies the number style to use for the iterator number.

Applies to

“Iterator Label Area” on page 832

Numerical Axis

Specifies whether the axis is rendered.

Applies to

“3-D Combination Chart” on page 800

Numerical Axis

Specifies whether the numeric axis of a gauge chart is rendered.

Applies to

“Gauge Chart” on page 828

Numeric Baselines

Adds reference lines on the numeric axis of a chart based on numeric or statistical values, calculations, or layout calculations.

Applies to

"Bubble Chart" on page 805, "Combination Chart" on page 813, "Numeric Baseline" on page 847, "Pareto Chart" on page 849, "Progressive Chart" on page 853, "Scatter Chart" on page 860

Numeric Value

Specifies the numeric position by using a number.

Applies to

"Baseline" on page 803, "Baseline" on page 803, "Baseline" on page 803, "Baseline" on page 803, "Marker" on page 843

Numeric Value

Specifies the value of the numeric position.

Applies to

"Marker" on page 843

Numeric Value

Specifies the value of the numeric position.

Applies to

"Marker" on page 843

Options Text

Specifies the text for the additional prompt options link in select & search prompts. The default label text is Options.

Applies to

"Select & Search Prompt" on page 861

Orientation

Specifies the orientation of the control.

Applies to

"Button Bar" on page 806, "Check Box Group" on page 811, "Continuous Values Slider" on page 814, "Data Button Bar" on page 820, "Data Check Box Group" on page 820, "Data Discrete Values Slider" on page 821, "Data Iterator" on page 822, "Data Radio Button Group" on page 822, "Data Toggle Button Bar" on page 823, "Discrete Values Slider" on page 825, "Iterator" on page 831, "Radio Button Group" on page 856, "Toggle Button Bar" on page 866

Outer Join Allowed

Specifies whether outer joins are allowed on the object. This property applies to a single query and overrides the setting in IBM® Cognos® Framework Manager, the modeling tool.

Applies to

“Query” on page 854

Output Aggregation Method

Specifies the aggregation method.

For more information about this property, see the topic Summarizing Data in the Active Report Output.

Applies to

“Crosstab Summary” on page 818, “List Summary” on page 840

Output Aggregation Method

Specifies the aggregation method.

For more information about this property, see the topic Summarizing Data in the Active Report Output.

Applies to

“List Cell” on page 836

Override Dimension Info

Specifies dimension information for a query. Add dimension information when the data source has no dimension information available or when you want to override, extend, or restrict the information.

For more information, see the topic Add Dimension Information to a Query.

Applies to

“Query” on page 854

Overrides

Specifies whether to override child objects. Before you can override child objects, they must have a name.

Applies to

“Layout Component Reference” on page 833

Padding

Specifies the space between the object and the margin. If there is a border then it specifies the space between the object and the border.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Block" on page 804, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Caption" on page 807, "Combination Chart" on page 813, "Combination Chart" on page 813, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Crosstab Columns" on page 815, "Crosstab Columns" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Rows" on page 817, "Crosstab Rows" on page 818, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Hyperlink" on page 830, "Hyperlink Button" on page 830, "List Cell" on page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838, "List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "List Summary" on page 840, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Page Break Text" on page 848, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Prompt Button" on page 854, "Radar Chart" on page 855, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Table Cell" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Text Item" on page 865, "Variable Text Item" on page 868, "Win-Loss Chart" on page 869

Pagination

Specifies pagination rules, such as page breaks, keep-with properties, page counts, and numbering.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Combination Chart" on page 813, "Combination Chart" on page 813, "Crosstab" on page 815, "Crosstab Node Member" on page 817, "Crosstab Space" on page 818, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "List" on page 835, "List Column" on page 836, "List Header" on page 839, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Page" on page 847, "Page Set" on page 848, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Repeater" on page 857, "Repeater Table" on page 857, "Report Reference" on page 858, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Table" on page 863, "Win-Loss Chart" on page 869

Palette

Specifies the palette to use for the chart. This property applies only to legacy charts.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Bubble Chart" on page 804, "Combination Chart" on page 813, "Gauge Chart" on page 828, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Scatter Chart" on page 859

Palette

Specifies the color palette for a chart.

Applies to

"Area" on page 801, "Bar" on page 802, "Bubble Chart" on page 805, "Gauge Axis" on page 827, "Line" on page 835, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Scatter Chart" on page 860

Palette

Map layers use the numeric palette, in which the color of a region or point is based on its numeric value.

Applies to

"Point Layer" on page 851, "Region Layer" on page 857

Parameter

Specifies the parameter that is satisfied by values chosen in the prompt control.

Applies to

"Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Generated Prompt" on page 829, "Interval Prompt" on page 831, "Select & Search Prompt" on page 861, "Text Box Prompt" on page 865, "Time Prompt" on page 866, "Tree Prompt" on page 867, "Value Prompt" on page 868

Pareto Axis

Specifies whether the axis is rendered.

Applies to

"Pareto Chart" on page 849

PDF Page Setup

Specifies the orientation and paper size for PDF documents.

Applies to

"Page" on page 847

Percentage Based On

Specifies the information that is used to calculate the percentage values.

Applies to

“Percentaged Measure” on page 850

Percentile

Specifies a position based on a data percentile value. This value must be greater than zero.

Applies to

“Baseline” on page 803, “Baseline” on page 803, “Baseline” on page 803, “Baseline” on page 803, “Marker” on page 843

Percentile

Specifies a position based on a data percentile value. This value must be greater than zero.

Applies to

“Marker” on page 843

Percentile

Specifies a position based on a data percentile value. This value must be greater than zero.

Applies to

“Marker” on page 843

Percent of Axis

Specifies a position based on a percentage along the numeric axis. This value must be greater than zero.

Applies to

“Baseline” on page 803, “Baseline” on page 803, “Baseline” on page 803, “Baseline” on page 803, “Marker” on page 843

Percent of Axis

Specifies a position based on a percentage along the numeric axis. This value must be greater than zero.

Applies to

“Marker” on page 843

Percent of Axis

Specifies a position based on a percentage along the numeric axis. This value must be greater than zero.

Applies to

“Marker” on page 843

Performance Pattern

Controls what portions of the range markers for tolerance and target ranges are rendered on a metrics chart.

Applies to

“Metrics Range Chart” on page 845

Pie Labels

Specifies whether pie labels are rendered.

Applies to

“Pie Chart” on page 850

Plot Area Fill

Specifies the fill color and effects for the plot area of a chart.

Applies to

“Bubble Chart” on page 805, “Combination Chart” on page 813, “Pareto Chart” on page 849, “Progressive Chart” on page 853, “Scatter Chart” on page 860

Point Shape

Specifies the shape of the markers. If you choose a value of series or category, the marker shape varies accordingly.

Applies to

“3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Polar Chart” on page 852, “Radar Chart” on page 855, “Scatter Chart” on page 859

Polynomial Exponent

Specifies the highest exponential value to use in the regression calculation.

Applies to

“Regression Line” on page 857

Position

Specifies where to position the legend.

Applies to

“Legend” on page 833

Position

Specifies the position of a note in a chart.

Applies to

“Equation Label” on page 826, “Note” on page 846

Position in List

Specifies the position of the no list value item in the list.

Applies to

“No Value List Item” on page 846

Position type

Specifies the source type for the numeric position.

Applies to

“Baseline” on page 803, “Baseline” on page 803, “Baseline” on page 803, “Baseline” on page 803, “Marker” on page 843

Position type

Specifies the type of numeric position on the X-axis. This property applies only to legacy charts.

Applies to

“Marker” on page 843

Position type

Specifies a type of numeric position.

Applies to

“Marker” on page 843

Positive Column Color

Specifies the color, gradient, or pattern to be used for columns in the progressive chart that represent positive values.

Applies to

“Progressive Chart” on page 854

Pre-populate

Specifies whether to pre-populate the control with values, but only if the parent of this prompt control is optional. This only applies to prompt controls that have a parent in a cascade.

Applies to

“Tree Prompt” on page 867, “Value Prompt” on page 868

Pre-populate Levels

Specifies the number of levels to pre-populate the prompt with. The default value is 1, which will pre-populate the prompt with only the root members.

Applies to

“Tree Prompt” on page 867

Pre-Sort

Sorts the data that is used by the query to produce a temporary cube when needed, such as for a crosstab against a relational data source. This property affects the default order of members of a level populated from the data item.

Applies to

“Data Item” on page 821

Processing

Specifies whether the IBM® Cognos® report server picks up a minimal amount of processing. Local processing only occurs if the database cannot handle the load. This property applies only to dimensional or OLAP data sources.

This property overrides the corresponding governor in the model. If unspecified, the value of the governor in the model is used. This property applies only to relational data sources, unless you use the dynamic query mode.

Database only specifies that all query processing is performed on the database, and none is performed and cached by the IBM Cognos report server. The query executes successfully only if all query operations can be performed by the database.

Limited Local specifies that little, or possibly none, of the query processing is performed by the Cognos report server. Local processing only occurs if the database cannot handle the query.

When using the dynamic query mode, this property applies only to SAP BW data sources and the Limited Local option is not supported. Database Only specifies that little, or possibly none, of the query processing is performed and cached by the Cognos report server. Local processing only occurs if the database cannot handle the query. Consider using this option only if your report performance is unacceptable with the default setting, and becomes usable with this setting. Be aware that results may change with this setting; test carefully to confirm that the results are still correct.

Applies to

“Query” on page 854

Progressive Axis

Specifies whether the axis is rendered.

Applies to

“Progressive Chart” on page 854

Progressive Palette

Specifies the color palette in a progressive chart.

Applies to

"Progressive Chart" on page 853

Projection List

Shows the list of projected data items for the set operation. You can automatically generate the list or manually add data items.

Applies to

"Query Operation" on page 855

Properties

Specifies a list of data items from the query in scope to associate to the selected object. This is necessary when you want to reference a data item that is in the associated query, but not used in the layout.

Applies to

"Axis Title" on page 802, "Axis Title" on page 802, "Baseline" on page 803, "Baseline" on page 803, "Baseline" on page 803, "Baseline" on page 803, "Category Baseline" on page 808, "Chart Footer" on page 809, "Chart Footer" on page 809, "Chart Node Member" on page 809, "Chart Subtitle" on page 810, "Chart Subtitle" on page 810, "Chart Title" on page 811, "Chart Title" on page 811, "Colored Region" on page 812, "Colored Region" on page 812, "Crosstab Node Member" on page 817, "Cumulation Label" on page 819, "Cumulation Line" on page 819, "Label" on page 833, "Legend Title" on page 834, "Legend Title" on page 834, "List" on page 835, "List Footer" on page 839, "List Header" on page 839, "Marker" on page 842, "Marker" on page 843, "Marker" on page 843, "Note" on page 846, "Note Content" on page 846, "Numeric Baseline" on page 847, "Page" on page 847, "Page Set" on page 848, "Point Color Legend Title" on page 851, "Point Size Legend Title" on page 852, "Region Color Legend Title" on page 856, "Regression Line" on page 857, "Repeater" on page 857, "Repeater Table" on page 857, "Scatter Marker" on page 860, "Select & Search Prompt" on page 861, "Singleton" on page 862, "Total Column" on page 866, "Total Column Label" on page 867, "Trendline Label" on page 867, "Value Prompt" on page 868

Property

Specifies a reference to a member property. You cannot modify this value.

Applies to

"Member Property" on page 844

Property Unique Name

Specifies the Member Property Unique Name (MPUN) of the member property.

Applies to

"Area" on page 801, "Bar" on page 802, "Category Baseline" on page 808, "Chart Node Member" on page 809, "Chart Text Item" on page 810, "Chart Text Item" on page 810, "Colored Region" on page 812, "Colored Region" on page 812, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817

page 817, "Cumulation Line Label" on page 819, "Gauge Axis" on page 827, "HTML Item" on page 829, "Image" on page 831, "Line" on page 835, "List Cell" on page 836, "List Column Body" on page 837, "List Column Title" on page 838, "Map Location" on page 841, "Map Location" on page 841, "Map Refinement Location" on page 841, "Map Refinement Location" on page 842, "Marker" on page 842, "Member Property" on page 844, "Numeric Baseline" on page 847, "Rich Text Item" on page 859, "Scatter Marker" on page 860, "Text Item" on page 865, "Total Column" on page 866, "Win-Loss Measure" on page 869

Push To Bottom

Specifies whether to position the footer as low as possible inside the parent object.

Applies to

"List Footer" on page 839, "List Page Footer" on page 839

Query

Specifies a reference to a query.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Axis Title" on page 802, "Axis Title" on page 802, "Baseline" on page 803, "Baseline" on page 803, "Baseline" on page 803, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Category Baseline" on page 808, "Chart Footer" on page 809, "Chart Footer" on page 809, "Chart Subtitle" on page 810, "Chart Subtitle" on page 810, "Chart Title" on page 811, "Chart Title" on page 811, "Colored Region" on page 812, "Colored Region" on page 812, "Combination Chart" on page 813, "Combination Chart" on page 813, "Crosstab" on page 815, "Cumulation Label" on page 819, "Data Button Bar" on page 820, "Data Check Box Group" on page 820, "Data Container" on page 820, "Data Deck" on page 821, "Data Discrete Values Slider" on page 821, "Data Drop-Down List" on page 821, "Data Iterator" on page 822, "Data List Box" on page 822, "Data Radio Button Group" on page 822, "Data Tab Control" on page 823, "Data Toggle Button Bar" on page 823, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Label" on page 833, "Legend Title" on page 834, "Legend Title" on page 834, "List" on page 835, "Map" on page 841, "Marimekko Chart" on page 842, "Marker" on page 842, "Marker" on page 843, "Marker" on page 843, "Metrics Range Chart" on page 845, "Note Content" on page 846, "Numeric Baseline" on page 847, "Page Set" on page 848, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Point Color Legend Title" on page 851, "Point Size Legend Title" on page 852, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Region Color Legend Title" on page 856, "Repeater" on page 857, "Repeater Table" on page 857, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Scatter Marker" on page 860, "Singleton" on page 862, "Trendline Label" on page 867, "Win-Loss Chart" on page 869

Query

Specifies a reference to a query.

Applies to

"Page" on page 847, "Select & Search Prompt" on page 861, "Tree Prompt" on page 867, "Value Prompt" on page 868

Radar Type

Specifies how the radar chart is rendered.

Applies to

"Radar Chart" on page 855

Radial Axis

Specifies whether the axis is rendered.

Applies to

"Polar Chart" on page 852, "Radar Chart" on page 855

Radio Buttons Definition

Defines the buttons in the radio button group.

Applies to

"Radio Button Group" on page 856

Range

Specifies whether this control accepts ranges. The setting of the associated parameterized expression for this property will override the setting of this object. If you edit this property but do not get the expected results, check the associated expression for the presence or absence of an `in_range` operator.

For example, if you created this prompt control with the prompt wizard and set up an associated parameterized filter that accepts ranges, changing the value of this property is not sufficient to change this restriction. You must also edit the filter's expression and remove the `in_range` operator.

To edit a filter expression, you must select the filter, which is accessible from the Query view, using the Explorer bar.

Applies to

"Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Interval Prompt" on page 831, "Text Box Prompt" on page 865, "Time Prompt" on page 866, "Value Prompt" on page 868

Range Label

Specifies whether the label for the Target Range will appear in the legend.

Applies to

"Metrics Range Chart" on page 845

Range Type

Specifies whether to show one or two thumbs and what region of the track to highlight.

Applies to

“Continuous Values Slider” on page 814, “Data Discrete Values Slider” on page 821, “Discrete Values Slider” on page 825

Referenced Report

The report that is referenced as the booklet item.

Applies to

“Report Reference” on page 858

Regression Line

Specifies whether a regression line is rendered. A regression line is a straight or curved line that best approximates the data points in the series.

Applies to

“Bubble Chart” on page 804, “Scatter Chart” on page 859

Regression Type

Specifies the type of regression used.

Applies to

“Regression Line” on page 857

Relative Alignment

Specifies how to vertically align this object, relative to its siblings.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Bubble Chart” on page 805, “Bullet Chart” on page 805, “Combination Chart” on page 813, “Combination Chart” on page 813, “Context Item Text” on page 814, “Crosstab” on page 815, “Date” on page 823, “Date Prompt” on page 824, “Field Set” on page 827, “Gauge Chart” on page 828, “Gauge Chart” on page 828, “Hyperlink” on page 830, “Hyperlink Button” on page 830, “Image” on page 831, “List” on page 835, “List Summary” on page 840, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Page Break Text” on page 848, “Page Number” on page 848, “Pareto Chart” on page 849, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Pie Chart” on page 850, “Polar Chart” on page 852, “Progressive Chart” on page 853, “Progressive Chart” on page 854, “Prompt Button” on page 854, “Radar Chart” on page 855, “Repeater Table” on page 857, “Row Number” on page 859, “Row Number” on page 859, “Scatter Chart” on page 859, “Scatter Chart” on page 860, “Static Repeater Table” on page 862, “Table” on page 863, “Text Box Prompt” on page 865, “Text Item” on page 865, “Time” on page 865, “Value Prompt” on page 868, “Variable Text Item” on page 868, “Win-Loss Chart” on page 869

Remove Text

Specifies the label that appears on the button that is used to remove items from the selected items box in all multiple selection prompts. The default label text is Remove.

Applies to

“Date & Time Prompt” on page 823, “Date Prompt” on page 824, “Interval Prompt” on page 831, “Select & Search Prompt” on page 861, “Text Box Prompt” on page 865, “Time Prompt” on page 866, “Value Prompt” on page 868

Render

For list reports, specifies whether to render the column in the report output. Whether set to Yes or No, the query for the column is always executed.

Applies to

“List Column” on page 836

Render Fact Cells

Specifies whether to render values in the fact cells of the spacer on an edge of the crosstab.

Applies to

“Crosstab Space” on page 818

Render Method

Specifies where the visualization is rendered. Visualizations that are rendered on the IBM® Cognos® server are rendered as static images. Some visualization properties apply to only one of the options. Rendering visualizations on the Cognos server or on the client has an impact on performance and on the size of the Active Report. To enable client side filtering, select Client.

Applies to

“Visualization” on page 868

Render Page when Empty

Specifies whether to render a page when data containers on a page contain no data. If all data containers on a page have this property set to No and do not have any data to render, the page is not rendered. If any data container on a page has data or has this property set to Yes, the page is rendered.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Bubble Chart” on page 805, “Bullet Chart” on page 805, “Combination Chart” on page 813, “Combination Chart” on page 813, “Crosstab” on page 815, “Gauge Chart” on page 828, “Gauge Chart” on page 828, “List” on page 835, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Pie Chart” on page 850, “Polar Chart” on page 852,

"Progressive Chart" on page 853, *"Progressive Chart"* on page 854, *"Radar Chart"* on page 855, *"Repeater"* on page 857, *"Repeater Table"* on page 857, *"Scatter Chart"* on page 859, *"Scatter Chart"* on page 860, *"Table of Contents"* on page 864, *"Win-Loss Chart"* on page 869

Render Variable

Specifies a variable based on which the object can be conditionally rendered.

Applies to

"3-D Combination Chart" on page 800, *"3-D Scatter Chart"* on page 800, *"Axis Labels"* on page 802, *"Axis Title"* on page 802, *"Block"* on page 804, *"Bubble Chart"* on page 804, *"Bubble Chart"* on page 805, *"Bullet Chart"* on page 805, *"Button"* on page 806, *"Button Bar"* on page 806, *"Category Baseline"* on page 808, *"Chart Footer"* on page 809, *"Chart Subtitle"* on page 810, *"Chart Text Item"* on page 810, *"Chart Title"* on page 811, *"Check Box Group"* on page 811, *"Colored Region"* on page 812, *"Colored Region"* on page 812, *"Combination Chart"* on page 813, *"Combination Chart"* on page 813, *"Context Item Text"* on page 814, *"Continuous Values Slider"* on page 814, *"Crosstab"* on page 815, *"Data Button Bar"* on page 820, *"Data Check Box Group"* on page 820, *"Data Deck"* on page 821, *"Data Discrete Values Slider"* on page 821, *"Data Drop-Down List"* on page 821, *"Data Iterator"* on page 822, *"Data List Box"* on page 822, *"Data Radio Button Group"* on page 822, *"Data Tab Control"* on page 823, *"Data Toggle Button Bar"* on page 823, *"Date & Time Prompt"* on page 823, *"Date Prompt"* on page 824, *"Deck"* on page 824, *"Discrete Values Slider"* on page 825, *"Drop-Down List"* on page 826, *"Field Set"* on page 827, *"Gauge Chart"* on page 828, *"Gauge Chart"* on page 828, *"Generated Prompt"* on page 829, *"HTML Item"* on page 829, *"Hyperlink"* on page 830, *"Hyperlink Button"* on page 830, *"Image"* on page 831, *"Interval Prompt"* on page 831, *"Iterator"* on page 831, *"Label"* on page 833, *"Legend"* on page 834, *"Legend Title"* on page 834, *"List"* on page 835, *"List Box"* on page 836, *"List Column"* on page 836, *"List Summary"* on page 840, *"Map"* on page 841, *"Marimekko Chart"* on page 842, *"Marker"* on page 842, *"Metrics Range Chart"* on page 845, *"Note"* on page 846, *"Numeric Baseline"* on page 847, *"Page"* on page 847, *"Page Break Text"* on page 848, *"Pareto Chart"* on page 849, *"Pareto Chart"* on page 849, *"Pie Chart"* on page 850, *"Pie Chart"* on page 850, *"Polar Chart"* on page 852, *"Progressive Chart"* on page 853, *"Progressive Chart"* on page 854, *"Radar Chart"* on page 855, *"Radio Button Group"* on page 856, *"Repeater"* on page 857, *"Repeater Table"* on page 857, *"Repeater Table Cell"* on page 858, *"Rich Text Item"* on page 859, *"Scatter Chart"* on page 859, *"Scatter Chart"* on page 860, *"Scatter Marker"* on page 860, *"Select & Search Prompt"* on page 861, *"Singleton"* on page 862, *"Static Repeater Table"* on page 862, *"Tab Control"* on page 863, *"Table"* on page 863, *"Table of Contents"* on page 864, *"Table of Contents Entry"* on page 864, *"Text Box Prompt"* on page 865, *"Text Item"* on page 865, *"Time Prompt"* on page 866, *"Toggle Button Bar"* on page 866, *"Tree Prompt"* on page 867, *"Trendline"* on page 867, *"Value Prompt"* on page 868, *"Variable Text Item"* on page 868, *"Visualization"* on page 868, *"Win-Loss Chart"* on page 869

Repeater Direction

Specifies the direction in which to populate the rendered repeater cells.

Applies to

"Repeater Table" on page 857, *"Static Repeater Table"* on page 862

Repeater Table Values Definition

Defines the data values that can appear in the repeater table. Values are organized by data item. In addition to the default data item (Label) and values provided, you can create your own data items and values.

Applies to

“Static Repeater Table” on page 862

Report Expression

Specifies the report expression that defines the text to render.

Applies to

“Chart Text Item” on page 810, “Chart Text Item” on page 810, “Cumulation Line Label” on page 819, “Hyperlink” on page 830, “Hyperlink Button” on page 830, “Text Item” on page 865, “Total Column” on page 866

Report Expression

Specifies the report expression used to define the HTML to render.

Applies to

“HTML Item” on page 829, “Rich Text Item” on page 859

Report Expression

Specifies the report expression that defines the URL.

Applies to

“Hyperlink” on page 830, “Hyperlink Button” on page 830, “Image” on page 831

Report Expression

Specifies the report expression that defines the bookmark. The value used as the bookmark reference must match this value.

Applies to

“Bookmark” on page 804

Report Expression

Specifies the numeric position by using a report expression.

Applies to

“Baseline” on page 803, “Baseline” on page 803, “Baseline” on page 803, “Baseline” on page 803, “Marker” on page 843

Report Expression

Specifies the report expression for the member position.

Applies to

“Baseline” on page 803, “Marker” on page 843

Report Expression

Specifies a report expression.

Applies to

“As of Time Expression” on page 801

Report Expression

Specifies the expression to evaluate when determining the value for this variable.

Applies to

“Variable” on page 868

Report Expression

Specifies the numeric position from a report expression.

Applies to

“Marker” on page 843

Report Expression

Specifies the numeric position from a report expression.

Applies to

“Marker” on page 843

Required

Specifies whether the prompt is required or optional. If this property is set to required, the prompt must have a value entered before the report can be run. The Usage setting of the associated parameterized filter for this property will override the setting of this object. If you edit this property, but do not get the expected results, verify the **Usage** setting of the associated filter.

For example, if you created this prompt control with the prompt wizard and set the associated parameterized filter to be optional, changing the value of this property is not sufficient to change this setting. You must also edit the filter's **Required** property to match the setting for this object's **Required** property.

To edit a filter expression, you must select the filter, which is accessible from the Query view, using the Explorer bar

Applies to

“Date & Time Prompt” on page 823, “Date Prompt” on page 824, “Generated Prompt” on page 829, “Interval Prompt” on page 831, “Select & Search Prompt” on page 861, “Text Box Prompt” on page 865, “Time Prompt” on page 866, “Tree Prompt” on page 867, “Value Prompt” on page 868

Results Deselect All Text

Specifies the text for the link below the results box that deselects all the items in the box. This property applies to all prompts with multiple selections and search, tree prompts, and value prompts. The default link text is Deselect All.

Applies to

“Select & Search Prompt” on page 861, “Tree Prompt” on page 867, “Value Prompt” on page 868

Results Select All Text

Specifies the text for the link below the results box that selects all the items in the box. This property applies to all prompts with multiple selections and search, tree prompts, and value prompts. The default link text is Select All.

Applies to

“Select & Search Prompt” on page 861, “Tree Prompt” on page 867, “Value Prompt” on page 868

Results Text

Specifies the title that appears above the results box in select & search prompts. The default title text is Results.

Applies to

“Select & Search Prompt” on page 861

Reverse

Specifies whether to reverse the direction of the slider. When set to Yes, horizontal sliders go right-to-left and vertical sliders go bottom-to-top.

Applies to

“Continuous Values Slider” on page 814, “Data Discrete Values Slider” on page 821, “Discrete Values Slider” on page 825

Reverse Category Order

Specifies whether to change the order of the categories, such as the bars in a bar chart. The default is No, which means that for a horizontal bar chart, bars start from the bottom to the top.

Applies to

“Category axis” on page 808

Right Position

Specifies the position of the right edge of the colored region.

Applies to

“Colored Region” on page 812

Right Position (px)

Specifies the pixel position of the right edge of the legend measured from the left edge of the chart.

Applies to

“Legend” on page 833

Rollup Aggregate Function

Specifies the type of aggregation to apply to summarized values. These values appear at the higher levels of lists and crosstabs. For OLAP data sources, a rollup aggregate function of Count Distinct is supported for only levels and member sets.

Applies to

“Area” on page 801, “Bar” on page 802, “Category Baseline” on page 808, “Chart Node Member” on page 809, “Chart Text Item” on page 810, “Chart Text Item” on page 810, “Colored Region” on page 812, “Colored Region” on page 812, “Crosstab Corner” on page 816, “Crosstab Fact Cells” on page 816, “Crosstab Intersection” on page 816, “Crosstab Member Fact Cells” on page 817, “Crosstab Node Member” on page 817, “Cumulation Line Label” on page 819, “Data Item” on page 821, “Gauge Axis” on page 827, “HTML Item” on page 829, “Image” on page 831, “Line” on page 835, “List Cell” on page 836, “List Column Body” on page 837, “List Column Title” on page 838, “Map Location” on page 841, “Map Location” on page 841, “Map Refinement Location” on page 841, “Map Refinement Location” on page 842, “Marker” on page 842, “Numeric Baseline” on page 847, “Rich Text Item” on page 859, “Scatter Marker” on page 860, “Text Item” on page 865, “Total Column” on page 866, “Win-Loss Measure” on page 869

Rollup Method

Specifies the aggregation method to use to summarize data in the visualization when users select multiple values in an Active Report control, such as a check box control.

Applies to

“Extra Value” on page 827, “Value” on page 867

Rollup Processing

Specifies where to compute aggregates. The Extended setting means that aggregates are computed using an extended aggregate operation. The Database setting means that aggregates are computed by the database software. The Local setting means that aggregates are computed by the data retrieval software in the report server, using a running aggregate.

Applies to

“Query” on page 854

Roll Up Table of Contents

Specifies whether to roll up table of content entries for the booklet item into the report booklet.

Applies to

"Report Reference" on page 858

Root Members Only

Specifies whether the set contains the root members or all of the members of the hierarchy.

Applies to

"Area" on page 801, "Bar" on page 802, "Category Baseline" on page 808, "Chart Node Member" on page 809, "Chart Text Item" on page 810, "Chart Text Item" on page 810, "Colored Region" on page 812, "Colored Region" on page 812, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Cumulation Line Label" on page 819, "Gauge Axis" on page 827, "Hierarchy Set" on page 829, "HTML Item" on page 829, "Image" on page 831, "Line" on page 835, "List Cell" on page 836, "List Column Body" on page 837, "List Column Title" on page 838, "Map Location" on page 841, "Map Location" on page 841, "Map Refinement Location" on page 841, "Map Refinement Location" on page 842, "Marker" on page 842, "Numeric Baseline" on page 847, "Rich Text Item" on page 859, "Scatter Marker" on page 860, "Text Item" on page 865, "Total Column" on page 866, "Win-Loss Measure" on page 869

Rotate Values

Controls whether or not the values displayed on the chart are rotated when the **Chart Orientation** property is set to **Horizontal**. May help make values easier to read on horizontal charts. This property applies only to legacy charts.

Applies to

"Combination Chart" on page 813, "Pareto Chart" on page 849, "Progressive Chart" on page 854

Rotation Angle

Specifies the angle in degrees that labels are rotated when rendering labels on an axis.

Applies to

"Category axis" on page 808

Row Coordinate

Uniquely identifies the row of a node member or spacer on an edge of the crosstab. You cannot modify this value.

Applies to

"Crosstab Intersection" on page 816

Rows Per Page

Specifies the maximum number of rows to show at one time. For Value and Select & Search prompts, allows you to extend or reduce the maximum number of rows beyond the default of 5000.

Applies to

"Crosstab" on page 815, "List" on page 835, "Repeater" on page 857, "Select & Search Prompt" on page 861, "Tree Prompt" on page 867, "Value Prompt" on page 868

Saved Parameter Values

Specifies how to handle saved parameter values that come from the booklet item. Parameter values include signon, validation, and prompt information, and they are saved on the IBM® Cognos® server. When Ignore is selected, the values are not used when the report is run. When Merge is selected, parameter values that come from the booklet item are merged with parameter values that come from the report booklet. If the same value exists for both the booklet item and the booklet, the booklet item value is ignored.

Applies to

"Report Reference" on page 858

Scale

Specifies whether the numeric scale is logarithmic or linear.

Applies to

"Angular Axis" on page 801, "Gauge Numerical Axis" on page 829, "Numerical Axis" on page 846, "Numerical Axis" on page 847, "Radial Axis" on page 855, "X Axis" on page 869, "Y1 Axis" on page 870, "Y2 Axis" on page 870, "Y Axis" on page 871, "Z Axis" on page 871, "Z Axis" on page 872

Scale Interval

Specifies the interval between ticks on the numeric scale. If no value is specified, one will be calculated based on the data.

Applies to

"Angular Axis" on page 801, "Cumulation Line Axis" on page 819, "Gauge Numerical Axis" on page 829, "Numerical Axis" on page 846, "Numerical Axis" on page 847, "Radial Axis" on page 855, "X Axis" on page 869, "Y1 Axis" on page 870, "Y2 Axis" on page 870, "Y Axis" on page 871, "Z Axis" on page 871, "Z Axis" on page 872

Scope

Specifies the scope of the filter in terms of the number of levels.

Applies to

"Summary Filter" on page 863

Search Instructions Text

Specifies the instructions that appear above the keyword search box in select & search prompts. The default text is as follows: Type one or more keywords separated by spaces.

Applies to

“Select & Search Prompt” on page 861

Search Text

Specifies the label that appears on the Search button in select & search prompts. The default label text is Search.

Applies to

“Select & Search Prompt” on page 861

Seconds Text

Specifies the title that appears above the seconds box in interval prompts. The default title text is s.

Applies to

“Interval Prompt” on page 831

Select UI

Specifies the user interface to use for the button in the iterator.

Applies to

“Iterator First” on page 832, “Iterator Last” on page 832, “Iterator Next” on page 832, “Iterator Previous” on page 832

Select UI

Specifies the user interface to use for the labels of iterator values.

Applies to

“Iterator Label Area” on page 832

Select UI

Specifies which interface the prompt control renders.

Applies to

“Value Prompt” on page 868

Select UI

Specifies which interface the prompt control renders.

Applies to

“Date Prompt” on page 824

Select UI

Specifies which interface the prompt control renders.

Applies to

“Time Prompt” on page 866

Select UI

Specifies which interface the prompt control renders.

Applies to

“Date & Time Prompt” on page 823

Separator

Specifies the separator to use when showing multiple values.

Applies to

“Context Item Text” on page 814, “Legend” on page 833

Series Color

Specifies whether data marker colors are synchronized between charts when you use the same data series for multiple charts within a combination chart. For example, if you create a line chart and a bar chart using the years data series, and you set this property to Yes, the data marker for 2010 is the same color in both charts. Use this property to eliminate redundant legend entries and help you interpret the data.

Applies to

“3-D Combination Chart” on page 800, “Combination Chart” on page 813, “Combination Chart” on page 813

Series Type

Specifies how the series will be rendered; for example, absolute, stacked, or stacked 100%.

Applies to

“Area” on page 801, “Bar” on page 802, “Line” on page 835

Set Operation

Specifies the set operation to apply to one or more queries, that results in a projection list on which other queries can be based.

Applies to

“Query Operation” on page 855

Set Sorting

Specifies how the set is sorted. By default, the set is not sorted.

Applies to

"Area" on page 801, "Bar" on page 802, "Category Baseline" on page 808, "Chart Node Member" on page 809, "Chart Text Item" on page 810, "Chart Text Item" on page 810, "Colored Region" on page 812, "Colored Region" on page 812, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Cumulation Line Label" on page 819, "Explicit Member Set" on page 826, "Gauge Axis" on page 827, "Hierarchy Set" on page 829, "HTML Item" on page 829, "Image" on page 831, "Level Set" on page 835, "Line" on page 835, "List Cell" on page 836, "List Column Body" on page 837, "List Column Title" on page 838, "Map Location" on page 841, "Map Location" on page 841, "Map Refinement Location" on page 841, "Map Refinement Location" on page 842, "Marker" on page 842, "Member Children Set" on page 844, "Named Set" on page 845, "Numeric Baseline" on page 847, "Rich Text Item" on page 859, "Scatter Marker" on page 860, "Set Expression" on page 861, "Text Item" on page 865, "Total Column" on page 866, "Win-Loss Measure" on page 869

Set Variable Values

Sets the value of variables when the control or an item in the control is selected.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Button" on page 806, "Button Bar" on page 806, "Check Box Group" on page 811, "Combination Chart" on page 813, "Combination Chart" on page 813, "Continuous Values Slider" on page 814, "Crosstab" on page 815, "Data Button Bar" on page 820, "Data Check Box Group" on page 820, "Data Container" on page 820, "Data Deck" on page 821, "Data Discrete Values Slider" on page 821, "Data Drop-Down List" on page 821, "Data Iterator" on page 822, "Data List Box" on page 822, "Data Radio Button Group" on page 822, "Data Tab Control" on page 823, "Data Toggle Button Bar" on page 823, "Deck" on page 824, "Discrete Values Slider" on page 825, "Drop-Down List" on page 826, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Iterator" on page 831, "List" on page 835, "List Box" on page 836, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Radio Button Group" on page 856, "Repeater Table" on page 857, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Static Repeater Table" on page 862, "Tab Control" on page 863, "Toggle Button Bar" on page 866, "Visualization" on page 868

Share Result Set

Specifies whether to share an identical query between data containers that use it. To share a query, data containers must be lists, repeaters, or repeater tables and must use the same grouping structure and list of properties. The data containers cannot be part of a master detail relationship. When set to Yes, the query sends only one request to the database and shares the result. When set to No, the query is not shared.

Applies to

“List” on page 835, “Repeater” on page 857, “Repeater Table” on page 857

Show Caption

Specifies whether, or where, to show the caption.

Applies to

“Field Set” on page 827

Show Data Points

Specifies whether to show value markers and how they are formatted.

Applies to

“Line” on page 835

Show Data Range in Legend

Specifies whether to show the full range of data in the legend. If set to No, only the values from the palette will be shown.

Applies to

“Point Layer” on page 851, “Region Layer” on page 857

Show Features with No Data

Indicates whether to show the features of a map that do not have corresponding data.

Applies to

“Point Layer” on page 851, “Region Layer” on page 857

Show Feelers

Specifies whether feeler lines are rendered for each marker.

Applies to

“3-D Scatter Chart” on page 800

Show Hover

Specifies whether to highlight areas in the data container that are clickable.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Bubble Chart” on page 805, “Bullet Chart” on page 805, “Combination Chart” on page 813, “Combination Chart” on page 813, “Crosstab” on page 815, “Gauge Chart” on page 828, “Gauge Chart” on page 828, “List” on page 835, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Pie Chart” on page 850, “Polar Chart” on page 852,

"Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Repeater Table" on page 857, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Static Repeater Table" on page 862

Show Hover

Specifies whether to highlight areas in the visualization that are clickable.

Applies to

"Data Container" on page 820

Show Icon

When defined, specifies whether to show the icon for each list item in the drop-down list.

Applies to

"Data Drop-Down List" on page 821, "Drop-Down List" on page 826

Show Icon

Specifies whether to show the icon for the current label.

Applies to

"Iterator Label Area" on page 832

Show Labels

Specifies whether labels are rendered for the display layer in a map.

Applies to

"Display Layer" on page 825

Show Legend Values

Specifies whether and how to show legend values.

Applies to

"Legend" on page 833

Show line

Specifies whether a line may be rendered. This allows you to show markers without lines.

Applies to

"Line" on page 835

Show Pointer Cursor

Specifies whether to show the pointer cursor as a hand when hovering over an area that is clickable. You can set the value of this property for multiple objects simultaneously by first control+clicking the items in the report.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Combination Chart" on page 813, "Combination Chart" on page 813, "Crosstab" on page 815, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "List" on page 835, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Repeater Table" on page 857, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Static Repeater Table" on page 862

Show Prompt Pages

When the report is run, specifies whether to render authored prompt pages that come from the booklet item.

Applies to

"Report Reference" on page 858

Show Tooltip

Specifies whether to show tooltips of the slider values when the thumb is clicked or moved.

Applies to

"Continuous Values Slider" on page 814, "Data Discrete Values Slider" on page 821, "Discrete Values Slider" on page 825

Show Values

Specifies which values to show in a chart legend.

Applies to

"Legend" on page 834

Show Values

Specifies whether values and labels are rendered for the region or point layer in a map.

Applies to

"Point Layer" on page 851, "Region Layer" on page 857

Show Values

Specifies the appearance of data labels in area, bar, line, Pareto, and progressive charts.

Applies to

"Area" on page 801, "Bar" on page 802, "Line" on page 835, "Pareto Chart" on page 849, "Progressive Chart" on page 853

Show Values

Specifies whether to show the labels for the data markers on the cumulation line in a Pareto chart.

Applies to

"Cumulation Line" on page 819

Show Values

Specifies the appearance of data labels in a pie chart.

Applies to

"Pie Chart" on page 850

Show Values

Specifies the appearance of data labels in a scatter chart.

Applies to

"Scatter Chart" on page 860

Show Values

Specifies the appearance of data labels in a bubble chart.

Applies to

"Bubble Chart" on page 805

Size

Specifies the height and width of the control.

Applies to

"Button" on page 806, "Data Deck" on page 821, "Data Drop-Down List" on page 821, "Data List Box" on page 822, "Data Tab Control" on page 823, "Deck" on page 824, "Drop-Down List" on page 826, "List Box" on page 836, "Tab Control" on page 863

Size & Overflow

Specifies the height and width of the object, as well as how overflow content should be treated, using scroll bars and clipping.

Applies to

"Block" on page 804, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Crosstab" on page 815, "Crosstab Columns" on page 815, "Crosstab Columns" on page 815, "Crosstab Corner" on page 816, "Crosstab Fact Cells" on page 816, "Crosstab Intersection" on page 816, "Crosstab Member Fact Cells" on page 817, "Crosstab Node Member" on page 817, "Crosstab Rows" on page 817, "Crosstab Rows" on page 818, "Crosstab Space" on page 818, "Crosstab Summary" on page 818, "Field Set" on page 827, "Hyperlink" on page 830, "Hyperlink Button" on page 830, "Image" on page 831, "List" on page 835

page 835, "List Cell" on page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838, "List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "List Summary" on page 840, "Note" on page 846, "Page" on page 847, "Page Body" on page 847, "Page Break Text" on page 848, "Page Footer" on page 848, "Page Header" on page 848, "Prompt Button" on page 854, "Repeater Table" on page 857, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Static Repeater Table" on page 862, "Table" on page 863, "Table Cell" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Text Box Prompt" on page 865, "Text Item" on page 865, "Tree Prompt" on page 867, "Value Prompt" on page 868, "Variable Text Item" on page 868, "Win-Loss Chart" on page 869

Size & Overflow

Specifies the absolute height and width of the object, as well as how overflow content should be treated, using scroll bars and clipping.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Combination Chart" on page 813, "Combination Chart" on page 813, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Scatter Chart" on page 859, "Scatter Chart" on page 860

Size Legend Title

Specifies a title within the legend above the palette for the point size. If this object is not defined, no additional title is drawn. If no legend is drawn, this object is ignored. Styling for this object is inherited from the legend title.

Applies to

"Point Layer" on page 851

Slice Direction

Specifies the direction in which slices appear in a pie chart.

Applies to

"Pie Chart" on page 850

Slide Animation Direction

Specifies the direction from which a new card appears. Select Auto Horizontal or Auto Vertical to automatically set the direction based on the order of cards in the deck. For example, when Auto Horizontal is specified, if you view the first card in a deck and you select to view the fourth card, the fourth card appears from the right. If you then select to view the first card, the first card appears from the left.

Applies to

"Data Deck" on page 821, "Deck" on page 824

Slider Values Definition

Defines the values of the slider.

Applies to

"Discrete Values Slider" on page 825

Solve Order

Specifies the solve order in the crosstab. The item with the lowest solve order value is calculated first, followed by the next lowest value, and so on. For identical values, column items are calculated first, then row items, and then the measure.

Applies to

"Crosstab Summary" on page 818

Solve Order

Specifies the solve order in crosstabs and charts. The item with the lowest solve order value is calculated first, followed by the next lowest value, and so on. For identical values, in crosstabs, column items are calculated first, then row items, and then the measure. In charts, x-axis items are calculated first and then legend items.

Applies to

"Calculated Measure" on page 807, "Calculated Member" on page 807, "Data Item" on page 821, "Dimensional Edge Summary" on page 825, "Edge Summary" on page 826

Sorting

Specifies the desired sort sequence.

Applies to

"Chart Node Member" on page 809, "Crosstab Node Member" on page 817, "Data Button Bar" on page 820, "Data Check Box Group" on page 820, "Data Deck" on page 821, "Data Discrete Values Slider" on page 821, "Data Drop-Down List" on page 821, "Data Iterator" on page 822, "Data List Box" on page 822, "Data Radio Button Group" on page 822, "Data Tab Control" on page 823, "Data Toggle Button Bar" on page 823, "Level" on page 834, "Node" on page 845, "Select & Search Prompt" on page 861, "Tree Prompt" on page 867, "Value Prompt" on page 868

Source Type

Specifies the source type of the text.

Applies to

"Chart Text Item" on page 810, "Chart Text Item" on page 810, "Cumulation Line Label" on page 819, "Hyperlink" on page 830, "Hyperlink Button" on page 830, "Text Item" on page 865

Source Type

Specifies the source type of the HTML text.

Applies to

“HTML Item” on page 829, “Rich Text Item” on page 859

Source Type

Specifies the source type of the URL.

Applies to

“Hyperlink” on page 830, “Hyperlink Button” on page 830, “Image” on page 831

Source Type

Specifies the source type of the bookmark.

Applies to

“Bookmark” on page 804

Spacing & Breaking

Specifies text properties such as line height, letter spacing, and word breaking.

Applies to

“Block” on page 804, “Conditional Block” on page 814, “Conditional Block” on page 814, “Context Item Text” on page 814, “Crosstab Columns” on page 815, “Crosstab Columns” on page 815, “Crosstab Corner” on page 816, “Crosstab Fact Cells” on page 816, “Crosstab Intersection” on page 816, “Crosstab Member Fact Cells” on page 817, “Crosstab Node Member” on page 817, “Crosstab Rows” on page 817, “Crosstab Rows” on page 818, “Crosstab Space” on page 818, “Crosstab Summary” on page 818, “Hyperlink” on page 830, “List Cell” on page 836, “List Column” on page 836, “List Column Body” on page 837, “List Columns” on page 837, “List Columns” on page 837, “List Columns Body Style” on page 838, “List Columns Title Style” on page 838, “List Column Title” on page 838, “List Footer” on page 839, “List Header” on page 839, “List Row” on page 840, “List Row Cells Style” on page 840, “List Summary” on page 840, “Page Break Text” on page 848, “Repeater Table Cell” on page 858, “Repeater Table Cell” on page 858, “Table Cell” on page 863, “Table of Contents” on page 864, “Table of Contents Entry” on page 864, “Text Item” on page 865, “Variable Text Item” on page 868

Spider Effects

Specifies whether the chart is rendered with web-like flat concentric circles. The Radial Axis property must be set to Show for this property to take effect.

Applies to

“Polar Chart” on page 852, “Radar Chart” on page 855

SQL

The text of the typed-in SQL. It is assumed to be appropriate for the type and data source. If it is not the query may fail, or produce unexpected results.

Applies to

“SQL” on page 862

SQL Join Syntax

Controls the syntax to generate for joins. Click Implicit to generate joins in the WHERE clause. Click Explicit to generate INNER JOIN syntax. If unspecified, the value of the corresponding governor in the model is used.

Applies to

“Query” on page 854

SQL Syntax

Specifies the syntax of the SQL in the query. A value of Cognos SQL indicates that IBM® Cognos® extended SQL-92 syntax is used. A value of Native SQL indicates that native database SQL is used. You cannot use IBM Cognos SQL if the Processing property for the query is set to Database Only; it must have a value of Limited Local. A value of Pass-Through indicates that a standalone query text syntax is used. The default value is Native SQL.

Applies to

“SQL” on page 862

Standard Deviations

Specifies a distance from the mean in standard deviations. This value can be positive or negative. A value of zero indicates the mean value.

Applies to

“Baseline” on page 803, “Baseline” on page 803, “Baseline” on page 803, “Baseline” on page 803, “Marker” on page 843

Standard Deviations

Specifies a distance from the mean in standard deviations. This value can be positive or negative. A value of zero indicates the mean value.

Applies to

“Marker” on page 843

Standard Deviations

Specifies a distance from the mean in standard deviations. This value can be positive or negative. A value of zero indicates the mean value.

Applies to

“Marker” on page 843

Start Heading Level

When the booklet item is included in the table of contents, specifies the starting heading level for the booklet item. For example, if you specify 2, all table of content entries for the booklet item will have section numbers that start at 2.

Applies to

“Report Reference” on page 858

Start Position

Specifies the position of one edge of the colored region along the numeric axis. The region extends from the position defined in this property to the position defined in the End Position property. The value that you specify in this property must be less than the value that is specified in the End Position property.

Applies to

“Colored Region” on page 812

Static Choices

Represents a collection of static choices used by the prompt object.

Applies to

“Select & Search Prompt” on page 861, “Value Prompt” on page 868

Step

Specifies at which intervals the thumb can come to a rest.

Applies to

“Continuous Values Slider” on page 814

Style Variable

Specifies a variable based on which the object can be conditionally styled.

Applies to

“Angular Measure” on page 801, “Axis Title” on page 802, “Block” on page 804, “Bubble Measure” on page 805, “Caption” on page 807, “Chart Body” on page 808, “Chart Footer” on page 809, “Chart Subtitle” on page 810, “Chart Text Item” on page 810, “Chart Title” on page 811, “Conditional Block” on page 814, “Conditional Block” on page 814, “Context Item Text” on page 814, “Crosstab” on page 815, “Crosstab Columns” on page 815, “Crosstab Columns” on page 815, “Crosstab Corner” on page 816, “Crosstab Fact Cells” on page 816, “Crosstab Intersection” on page 816, “Crosstab Member Fact Cells” on page 817, “Crosstab Node Member” on page 817, “Crosstab Rows” on page 817, “Crosstab Rows” on page 818, “Crosstab Space” on page 818, “Crosstab Summary” on page 818, “Cumulation Line Axis” on page 819, “Date & Time Prompt” on page 823, “Date Prompt” on page 824, “Default Measure” on page 824, “Display Layer” on page 825, “Field Set” on page 827, “Gauge Labels” on page 829, “Gauge Numerical Axis” on page 829, “Hyperlink” on page 830, “Hyperlink Button” on page 830, “Image” on page 831, “Interval Prompt” on page 831, “Legend” on page 833,

"Legend Title" on page 834, "List" on page 835, "List Cell" on page 836, "List Column" on page 836, "List Column Body" on page 837, "List Columns" on page 837, "List Columns" on page 837, "List Columns Body Style" on page 838, "List Columns Title Style" on page 838, "List Column Title" on page 838, "List Footer" on page 839, "List Header" on page 839, "List Row" on page 840, "List Row Cells Style" on page 840, "List Summary" on page 840, "Note Content" on page 846, "Page" on page 847, "Page Break Text" on page 848, "Pie Labels" on page 851, "Point Layer" on page 851, "Point Measure" on page 852, "Point Size Measure" on page 852, "Prompt Button" on page 854, "Radial Measure" on page 856, "Region Layer" on page 857, "Region Measure" on page 857, "Repeater Table" on page 857, "Repeater Table Cell" on page 858, "Repeater Table Cell" on page 858, "Select & Search Prompt" on page 861, "Static Repeater Table" on page 862, "Table" on page 863, "Table Cell" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Table Row" on page 864, "Target Measure" on page 864, "Text Box Prompt" on page 865, "Text Item" on page 865, "Time Prompt" on page 866, "Tolerance Measure" on page 866, "Tree Prompt" on page 867, "Value Prompt" on page 868, "Win-Loss Chart" on page 869, "X Axis Measure" on page 870, "Y Axis Measure" on page 871, "Z Axis Measure" on page 872

Subtitle

Specifies whether a chart subtitle is rendered. This property applies only to legacy charts.

Applies to

"Win-Loss Chart" on page 869

Subtitle

Specifies whether a chart subtitle is rendered.

Applies to

Summarize Small Items

Specifies whether to summarize small items, such as slices, lines, areas, bars, or columns, in the chart and how they are summarized. You cannot summarize small items in charts that have matrix edges or in charts that have multiple numeric axes.

Applies to

"Combination Chart" on page 813, "Pareto Chart" on page 849

Summarize Small Slices

Specifies whether to summarize small items, such as slices, lines, areas, bars, or columns, in the chart and how they are summarized. You cannot summarize small items in charts that have matrix edges or in charts that have multiple numeric axes.

Applies to

"Pie Chart" on page 850

Summary Text

Specifies summary text for table-like objects. Use to make your reports accessible for people who use screen readers. The summary text is never displayed in visual Web browsers. Summary text is used only for screen readers and speech browsers. Set this property only on tables that are used to display data, and not on tables that are used for layout purposes. To have a table object function as a data table, ensure that one or more of its cells have the Table Header property set to Yes.

Applies to

“Crosstab” on page 815, “List” on page 835, “Repeater Table” on page 857, “Table” on page 863

Suppress

Specifies the type of suppression to apply to the query results. This property overrides the corresponding SAP BW governor in the model. If unspecified, the value of the governor in the model is used.

When using compatible query mode, this property applies to Essbase, SAP BW, and MSAS data sources. When using dynamic query mode, this property applies to all OLAP data sources, including OLAP over relational (DMR).

Applies to

“Query” on page 854

Suppression

Specifies zero suppression options for the object.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Bubble Chart” on page 805, “Bullet Chart” on page 805, “Combination Chart” on page 813, “Combination Chart” on page 813, “Crosstab” on page 815, “Data Button Bar” on page 820, “Data Check Box Group” on page 820, “Data Deck” on page 821, “Data Discrete Values Slider” on page 821, “Data Drop-Down List” on page 821, “Data Iterator” on page 822, “Data List Box” on page 822, “Data Radio Button Group” on page 822, “Data Tab Control” on page 823, “Data Toggle Button Bar” on page 823, “Gauge Chart” on page 828, “Gauge Chart” on page 828, “List” on page 835, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Pie Chart” on page 850, “Polar Chart” on page 852, “Progressive Chart” on page 853, “Progressive Chart” on page 854, “Radar Chart” on page 855, “Repeater” on page 857, “Repeater Table” on page 857, “Scatter Chart” on page 859, “Scatter Chart” on page 860, “Win-Loss Chart” on page 869

Table Header

Specifies whether the cell is a table header. Use to make reports accessible for people who use screen readers. When set to Yes, screen readers and speech browsers programmatically create relationships between the table header and table cells.

Applies to

"List Cell" on page 836, "Table Cell" on page 863

Table of Contents

Specifies the name of the table of contents to which the entry belongs.

Applies to

"Table of Contents Entry" on page 864

Table of Contents Entry

Specifies whether to include the booklet item when a table of contents is added to the report.

Applies to

"Report Reference" on page 858

Table of Contents Name

Specifies the name that uniquely identifies the table of contents.

Applies to

"Table of Contents" on page 864

Table Properties

Specifies the properties for the table object.

Applies to

"Crosstab" on page 815, "List" on page 835, "Repeater Table" on page 857, "Static Repeater Table" on page 862, "Table" on page 863

Tab Orientation

Specifies the orientation of the tabs in the tab control.

Applies to

"Data Tab Control" on page 823, "Tab Control" on page 863

Tabs Definition

Defines the tabs in the tab control.

Applies to

"Tab Control" on page 863

Tab Width

Specifies the width of tabs in the tab control.

Applies to

“Data Tab Control” on page 823, “Tab Control” on page 863

Target Color

Specifies a color for the vertical lines that mark the target ranges for target measure values in a metrics chart.

Applies to

“Metrics Range Chart” on page 845

Target Marker

Specifies whether the status indicators will appear in the legend.

Applies to

“Metrics Range Chart” on page 845

Target Marker Border Color

Specifies a color for the borders around target value markers in a metrics chart.

Applies to

“Metrics Range Chart” on page 845

Target Marker Position

Specifies whether the status indicators will be rendered over the first bar in the cluster or the middle of the cluster. Does not apply to stacked charts.

Applies to

“Metrics Range Chart” on page 845

Target Range (%)

Specifies target ranges centered around target measure values.

Applies to

“Metrics Range Chart” on page 845

Text

Specifies the static text to render.

Applies to

“Chart Text Item” on page 810, “Chart Text Item” on page 810, “Cumulation Line Label” on page 819, “Hyperlink” on page 830, “Hyperlink Button” on page 830, “Text Item” on page 865, “Total Column” on page 866

Text Color

Specifies the color of the text of each label.

Applies to

“Check Box Group” on page 811, “Data Check Box Group” on page 820, “Data Radio Button Group” on page 822, “Radio Button Group” on page 856

Text Color

Specifies the text color of the button label.

Applies to

“Iterator First” on page 832, “Iterator Label Area” on page 832, “Iterator Last” on page 832, “Iterator Next” on page 832, “Iterator Previous” on page 832

Text Orientation

Specifies the orientation of the text on the gauge axis.

Applies to

“Gauge Axis” on page 827

Text Source Variable

Specifies a variable based on which the text source can be chosen.

Applies to

“Chart Text Item” on page 810, “Chart Text Item” on page 810, “Cumulation Line Label” on page 819, “Hyperlink” on page 830, “Hyperlink Button” on page 830, “Text Item” on page 865

Text Truncation

Specifies whether and how legend items are truncated.

Applies to

“Axis Labels” on page 802, “Legend” on page 834

Tick Interval

Specifies the interval, in slider values, between the appearance of ticks. For example, if you enter 3, a tick will appear for every third value in the slider. To apply this property, a value other than None or No Labels must be specified for the Tick Type property.

Applies to

“Data Discrete Values Slider” on page 821, “Discrete Values Slider” on page 825

Tick Interval

Specifies the interval, in slider values, between the appearance of ticks. For example, if you enter 20 in a slider that contains values between 0 and 100, a tick appears at 20, 40, 60, 80, and 100. To apply this property, a value other than None or No Labels must be specified for the Tick Type property.

Applies to

“Continuous Values Slider” on page 814

Tick Label Skip Interval

Specifies the interval, in ticks, between labels. This helps to avoid label collisions in the slider. If there is a collision between two labels, the second label is not shown.

Applies to

“Continuous Values Slider” on page 814, “Data Discrete Values Slider” on page 821, “Discrete Values Slider” on page 825

Tick Type

Specifies the type of label to show for the ticks in the slider.

Applies to

“Continuous Values Slider” on page 814, “Data Discrete Values Slider” on page 821, “Discrete Values Slider” on page 825

Title

Specifies whether a chart title is rendered. This property applies only to legacy charts.

Applies to

“Win-Loss Chart” on page 869

Title

Specifies whether a chart title is rendered.

Applies to

Title

Specifies whether a chart title is rendered.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Bubble Chart” on page 805, “Bullet Chart” on page 805, “Combination Chart” on page 813, “Combination Chart” on page 813, “Gauge Chart” on page 828, “Gauge Chart” on page 828, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Pie Chart” on page 850, “Polar Chart” on page 852, “Progressive Chart” on page 853, “Progressive Chart” on page 854, “Radar Chart” on page 855, “Scatter Chart” on page 859, “Scatter Chart” on page 860

Tolerance Color

Specifies a color for the vertical lines that mark the tolerance ranges for target measure values in a metrics chart.

Applies to

“Metrics Range Chart” on page 845

Tolerance Label

Specifies whether the label for the Target Tolerance will appear in the legend.

Applies to

“Metrics Range Chart” on page 845

Tooltips

Specifies whether tooltips are shown in a chart when you hover over data elements. Tooltips are not supported in PDF documents.

Applies to

“Combination Chart” on page 813, “Pareto Chart” on page 849, “Progressive Chart” on page 853

Tooltips

Specifies whether tooltips are shown in a pie chart when you hover over data elements. Tooltips are not supported in PDF documents.

Applies to

“Pie Chart” on page 850

Tooltips

Specifies whether tooltips are shown in a chart when you hover over data elements. Tooltips are not supported in PDF documents.

Applies to

“Bubble Chart” on page 805, “Bullet Chart” on page 805, “Gauge Chart” on page 828, “Scatter Chart” on page 860

Tooltips

Specifies whether tooltips are shown in a visualization when you hover over data elements. Tooltips are not supported in PDF documents.

Applies to

“Data Container” on page 820

Tooltips

Specifies whether tooltips are shown in the chart when you hover over data elements. Tooltips are not supported in PDF documents. This property applies only to legacy charts.

Applies to

“3-D Combination Chart” on page 800, “3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Combination Chart” on page 813, “Gauge Chart” on page 828, “Map” on page 841, “Marimekko Chart” on page 842, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Pie Chart” on page 850, “Polar Chart” on page 852, “Progressive Chart” on page 854, “Radar Chart” on page 855, “Scatter Chart” on page 859, “Win-Loss Chart” on page 869

Top Position

Specifies the position of the top edge of the colored region.

Applies to

“Colored Region” on page 812

Top Position (px)

Specifies the pixel position of the top edge of the legend measured from the bottom of the chart.

Applies to

“Legend” on page 833

Total Column

Specifies whether a total column is rendered. This property applies only to legacy charts.

Applies to

“Progressive Chart” on page 854

Total Column

Specifies whether a bar that shows the total cumulative value is rendered.

Applies to

“Progressive Chart” on page 853

Total Column Color

Specifies the color, gradient, or pattern of the total column on the progressive chart.

Applies to

“Total Column” on page 866

To Text

Specifies the label that appears beside the end of a range. This property applies to the following prompt types: date, date & time, time, and interval. The default label text is To.

Applies to

"Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Interval Prompt" on page 831, "Text Box Prompt" on page 865, "Time Prompt" on page 866, "Value Prompt" on page 868

Track Length

Specifies the track length of the slider.

Applies to

"Continuous Values Slider" on page 814, "Data Discrete Values Slider" on page 821, "Discrete Values Slider" on page 825

Trendline Label

Specifies whether to show the default label for the trend line. When set to No, you can type your own label text.

Applies to

"Trendline" on page 867

Trendlines

Adds a trend line or curve that indicates the general direction of the data over time.

Applies to

"Bubble Chart" on page 805, "Combination Chart" on page 813, "Scatter Chart" on page 860

Truncation

Specifies whether labels can be truncated.

Applies to

"Category Axis" on page 808, "Gauge Labels" on page 829, "Pie Labels" on page 851, "X Axis" on page 870, "Y Axis" on page 871

Truncation Text

Specifies the text to append when a label is truncated.

Applies to

"Category Axis" on page 808, "Gauge Labels" on page 829, "Legend" on page 833, "Pie Labels" on page 851, "X Axis" on page 870, "Y Axis" on page 871

Type

Specifies the type of variable.

Applies to

"Variable" on page 868

Type

Specifies the type of trend line.

Applies to

“Trendline” on page 867

Type

Specifies the behavior of the prompt button.

Applies to

“Prompt Button” on page 854

Type

The visualization type. This property shows the visualization ID, which also represents the visualization bundle name.

Applies to

“Visualization” on page 868

Type

Specifies the type of object.

Applies to

“Calculated Measure” on page 807, “Calculated Member” on page 807, “Custom Groups” on page 820, “Dimensional Edge Summary” on page 825, “Edge Summary” on page 826, “Explicit Member Set” on page 826, “Hierarchy Set” on page 829, “Intersection (Tuple)” on page 831, “Level Set” on page 835, “List Summary” on page 840, “Measure” on page 843, “Member” on page 844, “Member Children Set” on page 844, “Member Property” on page 844, “Named Set” on page 845, “Percentaged Measure” on page 850, “Set Expression” on page 861

Update Variables Live

Specifies whether to update variables as the thumb is moved. When set to Yes, the report is updated live when the thumb is moved. When set to No, the report is updated only when the thumb is stopped and released.

Applies to

“Continuous Values Slider” on page 814, “Data Discrete Values Slider” on page 821, “Discrete Values Slider” on page 825

Upper Range Skew (%)

Specifies a percentage that affects the positioning of tolerance bar and range with respect to the target value.

Applies to

“Metrics Range Chart” on page 845

URL

Specifies the URL, using static text.

Applies to

“Hyperlink” on page 830, “Hyperlink Button” on page 830

URL

Specifies the URL, using static text.

Applies to

“Image” on page 831

URL Source Variable

Specifies a variable based on which the URL source can be chosen.

Applies to

“Hyperlink” on page 830, “Hyperlink Button” on page 830, “Image” on page 831

Usage

Specifies whether the usage of this object is Optional, Required, or Disabled. When Optional, this condition applies if all parameters referenced by the expression are provided with values. If the expression does not refer to any parameters, then this condition is always applied. When Disabled, this condition is never applied, which is useful for authoring and testing purposes.

Applies to

“Detail Filter” on page 825, “Summary Filter” on page 863

Use 1.x Behavior

Specifies that IBM® Cognos® ReportNet® query semantics are used if they differ from IBM Cognos Business Intelligence query rules.

Applies to

“Query” on page 854

Use Aggregate Cache

For SAP BW data sources, specifies whether to use the aggregation cache. We recommend that you use the default value.

Applies to

“Query” on page 854

Use Decimal

Specifies whether to use IBM® Cognos® Active Report decimal representation or JavaScript numbers to represent the values. Using Active Report decimal representation produces accurate results, but might affect active report

performance. Using JavaScript numbers can produce floating point inaccuracies with certain decimal numbers, but performance is often better.

Applies to

“Extra Value” on page 827, “Value” on page 867

Use Detail Value on Page

Specifies whether to render a detail value or an aggregate value for a text item that uses a data item as its source. Use this property only when you want to render the value that appears in the first or last detail row of a list, repeater or repeater table on the same page as the text item.

Applies to

“Text Item” on page 865

Use Embedded Data

Specifies whether to use data that is defined in the visualization definition instead of data that you insert from the package.

Applies to

“Visualization” on page 868

Use for Parameter Info

Specifies whether the query should be given priority when determining parameter information. Queries with this property set to Yes are checked for parameter information first, followed by queries with this property set to Default. Queries with this property set to No will not be checked for parameter information unless it is referenced in a query that will be checked. Setting this property to Yes on parameterized queries can improve performance in displaying prompt pages.

Applies to

“Query” on page 854

Use Local Cache

Specifies whether a query is a candidate for reusing the query results set. If set to Yes, the query engine can reuse the existing SQL results from the cache. If set to No, the query is executed rather than using cached results. This property applies only to relational and dimensionally-modeled relational (DMR) data sources.

Applies to

“Query” on page 854

User SAP Member Cache

Signals to the SAP BW provider whether the query associated with this property is cached to the IBM® Cognos® Business Intelligence member cache. When set to Yes, the member cache is populated with the dimensions in the query, encrypted, and saved for later use.

Applies to

“Query” on page 854

Use Same Range For All Instances

Specifies that all instances of the chart use the same maximum value. When set to No, the axis maximum value is recalculated for each chart instance. It is only relevant if the chart is involved in a master detail relationship.

Applies to

“Angular Axis” on page 801, “Gauge Numerical Axis” on page 829, “Numerical Axis” on page 846, “Numerical Axis” on page 847, “Radial Axis” on page 855, “X Axis” on page 869, “Y1 Axis” on page 870, “Y2 Axis” on page 870, “Y Axis” on page 871, “Z Axis” on page 871, “Z Axis” on page 872

Use SAP MUN as Business Key

Specifies whether to return the full SAP MUN as the value for the business key. Use this query hint to allow a drill-down on a business key for a non-leaf member of an external hierarchy. When set to Yes, the full MUN appears in the report output.

Applies to

“Query” on page 854

Use Set Aggregation

Specifies which aggregation clause is used to calculate the summary. When set to Yes, the aggregation clause within set is used. When set to No, the aggregation clause within detail is used.

For more information, see the topic Summarizing Values in Crosstabs.

Applies to

“Dimensional Edge Summary” on page 825, “Edge Summary” on page 826

Use SQL Parameters

Specifies whether the generated SQL uses parameter markers or literal values. When set to Marker, specifies that the generated SQL uses markers to denote that the value will be provided later. When set to Literal, uses literal values in the generated SQL. If not specified, the server determines the behavior.

Dynamic SQL applications have the ability to prepare statements which include markers in the text which denote that the value will be provided later. This is most efficient when the same query is used many times with different values. The technique reduces the number of times a database has to hard parse an SQL statement and it increases the re-use of cached statements. However, when queries navigate larger amounts of data with more complex statements, they have a lower chance of matching other queries. In this case, the use of literal values instead of markers may result in improved performance.

Applies to

“Query” on page 854

Use SQL With Clause

Specifies whether to send a request to the database using an SQL WITH clause. When set to Yes, and if the database supports WITH clauses, a WITH clause request is generated. When set to No, or if the database does not support WITH clauses, a request using derived tables is generated.

Applies to

“Query” on page 854

Use Thousands Separator

Specifies whether to delimit digit groups with the thousands separator.

Applies to

“Text Box Prompt” on page 865

Use Value

Specifies the values used by the prompt object.

Applies to

“Tree Prompt” on page 867

Use Value

Specifies the values used by the prompt object. These values can be different than the ones that are rendered to the user.

Applies to

“Select & Search Prompt” on page 861, “Value Prompt” on page 868

Value Location:

Specifies where values and labels are to be rendered in the chart. This property applies only to legacy charts.

Applies to

“Area” on page 801, “Bar” on page 802, “Bubble Chart” on page 804, “Combination Chart” on page 813, “Cumulation Line” on page 819, “Line” on page 835, “Metrics Range Chart” on page 845, “Pareto Chart” on page 849, “Polar Chart” on page 852, “Progressive Chart” on page 854, “Radar Chart” on page 855, “Scatter Chart” on page 859

Value Markers

Specifies whether to show special value markers and how they are formatted.

Applies to

“Line” on page 835

Value Range

Controls how the minimum and maximum values are calculated for the visualization.

Applies to

“Value” on page 867

Value Representation

Specifies whether values are rendered as percentages.

Applies to

“Pie Chart” on page 850

Values

Specifies what values to show in the chart and whether to show the corresponding measure, series, or category label.

Applies to

“3-D Scatter Chart” on page 800, “Bubble Chart” on page 804, “Polar Chart” on page 852, “Scatter Chart” on page 859

Values

Specifies whether values are rendered in the chart.

Applies to

“3-D Area” on page 799, “3-D Bar” on page 799, “3-D Line” on page 800, “Area” on page 801, “Bar” on page 802, “Cumulation Line” on page 819, “Line” on page 835, “Pareto Chart” on page 849, “Progressive Chart” on page 854, “Radar Chart” on page 855

Values

Specifies whether values are rendered.

Applies to

“Pie Chart” on page 850

Values

Specifies whether values are rendered in the chart.

Applies to

“Marimekko Chart” on page 842

Value Type

Specifies whether absolute values are rendered rather than cumulative values.

Applies to

“Area” on page 801, “Bar” on page 802, “Line” on page 835

Variable

Specifies the variable associated to the slider.

Applies to

“Continuous Values Slider” on page 814

Variable for Maximum

Specifies the variable to use for the maximum value when the slider range type is Range.

Applies to

“Continuous Values Slider” on page 814

Variable for Minimum

Specifies the variable to use for the minimum value when the slider range type is Range.

Applies to

“Continuous Values Slider” on page 814

Vertical Alignment

Specifies how objects contained in this object are vertically aligned.

Applies to

“Crosstab Columns” on page 815, “Crosstab Columns” on page 815, “Crosstab Corner” on page 816, “Crosstab Fact Cells” on page 816, “Crosstab Intersection” on page 816, “Crosstab Member Fact Cells” on page 817, “Crosstab Node Member” on page 817, “Crosstab Rows” on page 817, “Crosstab Rows” on page 818, “Crosstab Space” on page 818, “Crosstab Summary” on page 818, “List Cell” on page 836, “List Column” on page 836, “List Column Body” on page 837, “List Columns” on page 837, “List Columns” on page 837, “List Columns Body Style” on page 838, “List Columns Title Style” on page 838, “List Column Title” on page 838, “List Footer” on page 839, “List Header” on page 839, “List Row” on page 840, “List Row Cells Style” on page 840, “Repeater Table Cell” on page 858, “Repeater Table Cell” on page 858, “Table Cell” on page 863, “Table Row” on page 864

Visible

Specifies whether a column or row is visible when the active report is executed. You can set the value of this property for multiple objects simultaneously by first control+clicking the items in the report.

Applies to

"Crosstab Node Member" on page 817, "Crosstab Space" on page 818, "Crosstab Summary" on page 818

Visible

Specifies whether to display the object. When set to No, the object is hidden but a fixed space is reserved in the report.

Applies to

"3-D Combination Chart" on page 800, "3-D Scatter Chart" on page 800, "Block" on page 804, "Bubble Chart" on page 804, "Bubble Chart" on page 805, "Bullet Chart" on page 805, "Combination Chart" on page 813, "Combination Chart" on page 813, "Conditional Block" on page 814, "Conditional Block" on page 814, "Context Item Text" on page 814, "Crosstab" on page 815, "Cumulation Line Axis" on page 819, "Date & Time Prompt" on page 823, "Date Prompt" on page 824, "Field Set" on page 827, "Gauge Chart" on page 828, "Gauge Chart" on page 828, "Gauge Labels" on page 829, "Gauge Numerical Axis" on page 829, "Hyperlink" on page 830, "Image" on page 831, "Interval Prompt" on page 831, "Legend" on page 833, "List" on page 835, "List Summary" on page 840, "Map" on page 841, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Page Break Text" on page 848, "Pareto Chart" on page 849, "Pareto Chart" on page 849, "Pie Chart" on page 850, "Pie Chart" on page 850, "Pie Labels" on page 851, "Polar Chart" on page 852, "Progressive Chart" on page 853, "Progressive Chart" on page 854, "Radar Chart" on page 855, "Repeater Table" on page 857, "Scatter Chart" on page 859, "Scatter Chart" on page 860, "Select & Search Prompt" on page 861, "Static Repeater Table" on page 862, "Table" on page 863, "Table of Contents" on page 864, "Table of Contents Entry" on page 864, "Text Box Prompt" on page 865, "Text Item" on page 865, "Time Prompt" on page 866, "Tree Prompt" on page 867, "Value Prompt" on page 868, "Variable Text Item" on page 868, "Win-Loss Chart" on page 869

Visual Angle

Specifies the angle, in degrees, in which the chart objects will be displayed when the chart has 3-D effects. This property applies only to legacy charts.

Applies to

"Combination Chart" on page 813, "Marimekko Chart" on page 842, "Metrics Range Chart" on page 845, "Pareto Chart" on page 849, "Progressive Chart" on page 854

White Space

Specifies how to handle the white space inside the object and whether text in the object is wrapped or appears all on one line. The term white space refers to the spaces between words, where text can be wrapped.

When set to **Normal**, the default, text will wrap when necessary, such as when space is limited.

When set to **No Wrap**, the text will never wrap to the next line in all report outputs, even if space is limited.

Applies to

“Block” on page 804, “Conditional Block” on page 814, “Conditional Block” on page 814, “Crosstab Columns” on page 815, “Crosstab Columns” on page 815, “Crosstab Corner” on page 816, “Crosstab Fact Cells” on page 816, “Crosstab Intersection” on page 816, “Crosstab Member Fact Cells” on page 817, “Crosstab Node Member” on page 817, “Crosstab Rows” on page 817, “Crosstab Rows” on page 818, “Crosstab Space” on page 818, “Crosstab Summary” on page 818, “List Cell” on page 836, “List Column” on page 836, “List Column Body” on page 837, “List Columns” on page 837, “List Columns” on page 837, “List Columns Body Style” on page 838, “List Columns Title Style” on page 838, “List Column Title” on page 838, “List Footer” on page 839, “List Header” on page 839, “List Row” on page 840, “List Row Cells Style” on page 840, “Repeater Table Cell” on page 858, “Repeater Table Cell” on page 858, “Table Cell” on page 863, “Table of Contents” on page 864, “Table of Contents Entry” on page 864

Width (px)

Specifies the width of the note, in pixels.

Applies to

“Note” on page 846

Win Color

Specifies a color, color gradient, or pattern to apply to the win values.

Applies to

“Win-Loss Chart” on page 869

Win-Loss Threshold

Specifies the win-loss value in a win-loss chart. It represents values that are ties, which are mapped on the zero line.

Applies to

“Win-Loss Chart” on page 869

X Axis

Specifies whether the axis is rendered.

Applies to

“3-D Combination Chart” on page 800

X Axis

Specifies whether the axis is rendered.

Applies to

“Bubble Chart” on page 804, “Scatter Chart” on page 859

X-Axis Data Item Value

Specifies the scatter marker position on the X-axis.

Applies to

“Scatter Marker” on page 860

Y1 Axis

Specifies whether the axis is rendered.

Applies to

“Combination Chart” on page 813, “Metrics Range Chart” on page 845

Y2 Axis

Specifies whether the axis is rendered.

Applies to

“Combination Chart” on page 813

Y2 Axis Position

Specifies how the second Y axis is rendered. When Y2 Axis Position is set to Dual, the Y2 axis appears across from the Y1 numeric axis. When Y2 Axis Position is set to Bipolar, the Y2 axis appears below the Y1 axis. For example, in a combination chart showing Revenue and Quantity sold by Retailer type, with the Y2 Axis Position set to Dual, the Revenue columns and the Quantity sold line overlap because the Revenue axis (Y1) and the Quantity sold axis (Y2) are across from each other. However, with the Y2 Axis Position set to Bipolar, the Revenue columns appear above the Quantity sold line, and the data does not overlap. This property applies only to legacy charts.

Applies to

“Combination Chart” on page 813

Y Axis

Specifies whether the axis is rendered.

Applies to

“3-D Combination Chart” on page 800

Y Axis

Specifies whether the axis is rendered.

Applies to

“Bubble Chart” on page 804, “Marimekko Chart” on page 842, “Scatter Chart” on page 859

Y-Axis Data Item Value

Specifies the scatter marker position on the Y-axis.

Applies to

“Scatter Marker” on page 860

Data Formatting Properties

The following is a list of properties available in the data formatting dialog.

"Not Applicable" Characters

Specifies the characters to be displayed when the value to be formatted was not applicable. The default value is two dashes (--). Note that the format will be applied only if the data source supports this error condition.

Any Error Characters

Specifies the characters to be displayed when the value to be formatted was not available because of an error. This property is overridden by the more specific formatting error conditions, such as Security Error Characters. The default value is two dashes (--). Note that the format will be applied only if the data source supports this error condition.

Calendar Type

Specifies the type of calendar to be displayed. The date values will be mapped to the selected calendar before being formatted. The default value is inherited from the user's content language. Note that the Japanese Imperial setting is only applicable for Japanese languages.

Clock

Specifies whether to display the time in 12-hour or 24-hour format. The default value is inherited from the user's content language.

Currency

Specifies the currency to be used. The default currency symbol will be displayed unless the values of the Currency Display and Currency Symbol properties are changed. The default value is inherited from the model.

Currency Display

Specifies whether to display the international or local currency symbol. By default, the local currency symbol is displayed.

Currency Symbol

Specifies a character or characters to use as the symbol to identify the local currency. This symbol will precede the number and any sign, even if it is a leading sign. A space between the symbol and the numeric value can be specified by entering it in this property, after the symbol. The default value is inherited from the user's content language.

Currency Symbol Position

Specifies where the currency symbol will appear. If End is selected, any spaces that follow the character or characters in the Currency Symbol or International Currency Symbol properties will be rendered between the number and the symbol. The default value is inherited from the user's content language.

Date Ordering

Specifies the order in which to display the day, month, and year. The default value is inherited from the user's content language.

Date Separator

Specifies the character to be displayed between the year, month, and day. The default value is inherited from the user's content language.

Date Style

Specifies the date style. The results rendered are determined by the language. Generally, Short uses only numbers, Medium uses some abbreviated words, Long uses complete words, and Full includes all available details.

Decimal Separator

Specifies the character that will separate non-decimal numbers from decimals. This property is ignored if no decimals are displayed. The default value is inherited from the user's content language.

Digit Shaping

Specifies the digit shaping option to apply. When National is selected, digit shapes are determined from the user's content language. When Contextual is selected, digit shapes are determined from adjoining characters in the value. For example, if the most recent strongly directional character before the numerical character is left-to-right, the number is displayed as a European number. If the most recent strongly directional character before the numerical character is right-to-left, the number is displayed in Arabic-Indic format. If there are no strongly directional characters before the numerical character, the number is displayed according to the base text direction of the field. When None is selected, no shaping is performed, and the value as it appears in the data source is shown. The default depends on the type of value. When the value is a string, the default is None.

Digit Shaping

Specifies the digit shaping option to apply. When National is selected, digit shapes are determined from the user's content language. When None is selected, no shaping is performed, and the value as it appears in the data source is shown. The default depends on the type of value. When the value is a number, the default is the ICU default for the language.

Display AM / PM Symbols

Specifies whether to display the AM or PM symbols. The default value is inherited from the user's content language.

Display As Exponent

Specifies whether to render values in scientific notation, using exponents. If this property is set to No, scientific notation will not be used. If this property is not

specified, scientific notation will be used only when values exceed the maximum number of digits. The default value is inherited from the user's content language.

Display Days

Specifies whether to display the day. The format of the day can be controlled by selecting one of the specific formats. Selecting Julian means that the 3-digit day of the year will be displayed. The default value is inherited from the user's content language.

Display Eras

Specifies whether to display the era. The default value is inherited from the user's content language.

Display Hours

Specifies whether to display the hours. The default value is inherited from the user's content language.

Display Milliseconds

Specifies whether to display the milliseconds. The format of the milliseconds can be controlled by selecting one of the specific formats. This property is ignored if seconds are not displayed. The default value is inherited from the user's content language.

Display Minutes

Specifies whether to display the minutes. The format of the minutes can be controlled by selecting one of the specific formats. The default value is inherited from the user's content language.

Display Months

Specifies whether to display the month. The format of the month can be controlled by selecting one of the specific formats. The default value is inherited from the user's content language.

Display Months

Specifies whether to display the month. Use this property only when the report is processed entirely in the database, and no local processing is required. The associated database columns must have a YEAR-MONTH interval, and not a DAY-TIME type of interval.

Display Seconds

Specifies whether to display the seconds. The format of the seconds can be controlled by selecting one of the specific formats. The default value is inherited from the user's content language.

Display Time Zone

Specifies whether to display the time zone. The default value is inherited from the user's content language.

Display Weekdays

Specifies whether to display the weekday. The format of the weekday can be controlled by selecting one of the specific formats. The default value is inherited from the user's content language.

Display Years

Specifies whether to display the year. The first two digits of the year, which indicate the century, can be controlled by selecting one of the associated property values. The default value is inherited from the user's content language.

Display Years

Specifies whether to display the year. Use this property only when the report is processed entirely in the database, and no local processing is required. The associated database columns must have a YEAR-MONTH interval, and not a DAY-TIME type of interval.

Divide By Zero Characters

Specifies the characters to be displayed when a numeric value is the result of a division by zero. The default value is /0. Note that the format will be applied only if the data source supports this error condition.

Exponent Symbol

Specifies the character to be displayed to identify exponents if the scientific notation is used. The symbol will be rendered after the number, separated by a space. The default value is inherited from the user's content language.

Group Size (digits)

Specifies the primary grouping size. If a value is specified it represents the number of digits to the left of the decimal point to be grouped together and separated by the thousands separator. The default value is inherited from the user's content language.

International Currency Symbol

Specifies a character or characters to use as a symbol to identify the international currency. This symbol will replace the currency symbol. A space between the symbol and the numeric value can be specified by entering it in this property, after the symbol. The default value is inherited from the user's content language.

Mantissa (digits)

Specifies the number of digits to be displayed following the exponent symbol if the scientific notation is used.

Maximum No. of Digits

Specifies the maximum number of digits that can be displayed. If the maximum number of digits is not sufficient to display the value, a scientific notation will be used. The default value is inherited from the user's content language.

Minimum No. of Digits

Specifies the minimum number of digits that can be displayed. If the minimum number of digits is too high to display a value, the padding character will be used. The default value is inherited from the user's content language.

Missing Value Characters

Specifies the character or characters to be displayed when the value is missing. If no value is entered for this property, an empty string will be displayed.

Negative Pattern

Specifies a presentation format, based on patterns, for negative numbers. Some restrictions exist. The numerical part of the negative pattern is ignored. Only the suffix and the prefix are used. For example, in the pattern ABC###EFG, ABC is the prefix, EFG is the suffix and ### is the numerical part of the pattern.

Negative Sign Position

Specifies where the negative sign will appear. The default value is inherited from the user's content language.

Negative Sign Symbol

Specifies how to display negative numbers. The default value is inherited from the user's content language.

No. of Decimal Places

Specifies the number of digits to be displayed to the right of the decimal point. If this property is not set, the number of decimal places will vary depending on the number rendered.

Numeric Overflow Characters

Specifies the characters to be displayed when a numeric value is the result of a numeric overflow. The default value is two dashes (--). Note that the format will be applied only if the data source supports this error condition.

Padding Character

Specifies the character that will be used to pad values that have fewer digits than the minimum number of digits. The default value is inherited from the user's content language.

Pattern

Specifies a presentation format that is based on patterns. The pattern format overrides formats specified in other properties. For example, to format the date as 2009/12/31 23:59:59 PM, use the pattern yyyy/MM/dd hh:mm:ss aa. For example, to format thousands using the letter K, set the Format Type to Number, set the Scale to -3 (to remove 000), and then use the pattern to ####K.

Percentage Symbol

Specifies whether to display the values per hundred (percent) or per thousand. The symbol will be appended to the number and any trailing sign. A space between the numeric value and the symbol can be specified by entering it in this property, after the symbol. The default value is inherited from the user's content language.

Percent Scale (integer)

Scale to be applied to value after formatting. If omitted, no percent scale will be applied and the value will be formatted according to the normal decimal positioning associated with the percent (or per mille) symbol.

Scale

Specifies how many digits to move the decimal delimiter for formatting purposes. For example, move the decimal three spaces to present values in thousands. The default value is inherited from the database field.

Secondary Group Size (digits)

Specifies the secondary grouping size. If a value is specified it represents the number of digits to the left of the primary group that will be grouped together and separated by the thousands separator. If this property is left blank, the secondary grouping of digits is the same number as the primary group size, as specified by the Group Size (digits) property. The default value is inherited from the user's content language.

Security Error Characters

Specifies the characters to be displayed when the value to be formatted was not available for security reasons. The default value is #!Security. Note that the format will be applied only if the data source supports this error condition.

Thousands Separator

Specifies how to delimit digit groups, such as thousands. This property is only used if the Use Thousands Separator property is set to Yes. The default value is inherited from the user's content language.

Time Separator

Specifies the character to be displayed between the hour, minute, and second. The default value is inherited from the user's content language.

Time Style

Specifies the time style to be displayed. The exact results that will be rendered are determined by the language. Generally, Short means that the minimum details will be displayed, Long adds seconds, and Full means that all details are displayed, including the time zone. The default value is inherited from the user's content language.

Time Unit

Specifies the unit of measure of the value. This property will be ignored if any day or time components are shown. The default value is inherited from the user's content language.

Use Thousands Separator

Specifies whether the grouping delimiter will be applied as defined by the Group Size property. The default value is inherited from the user's content language.

Zero Value Characters

Specifies the character or characters to be displayed when the value is zero (0). If no value is entered for this property, the Maximum No. of Digits property determines how many zero digits are displayed.

Appendix H. Prompt API for IBM Cognos BI

The JavaScript Prompt API provides report authors with a method of customizing prompt interaction in the reports they author.

With the prompt API, JavaScript applications can interact with IBM Cognos Business Intelligence report prompts for the purposes of validation or custom interaction. The prompt API can query and set user selections, validate typed-in values using patterns, set default values using expressions or query data, and more. Examples are provided to show various usage scenarios of the prompt API.

Note: The prompt API does not support tree and search prompt controls. Additionally, date and date & time prompt controls do not support the `setValidator` method.

Related concepts:

“Prompt API samples” on page 547

The following reports are some of the reports found in the `Samples_Prompt_API` folder.

cognos.Prompt object

Defines the class that contains a prompt object from a report.

This object should only be accessed through an instance of `cognos.Report`.

cognos.Prompt.getControlByName method

Returns the control object associated with a name.

Syntax

```
(cognos.Prompt.Control) getControlByName(String sName)
```

Parameters

{String} sName

Specifies the prompt name property set for the control in IBM Cognos Report Studio.

Returns

{cognos.Prompt.Control}

Object associated to the specified `sName` control. Returns `null` if the control does not exist.

Example

The following is an example of the `clearMyPrompt()` function.

```
<script type="text/javascript">  
function clearMyPrompt() {  
    var oCR = cognos.Report.getReport("_THIS_");
```

```
var myPrompt = oCR.prompt.getControlByName("myPrompt");
myPrompt.clearValues();
}
</script>
```

cognos.Prompt.getControls method

Returns an array of all controls associated with the report.

Syntax

```
(cognos.Prompt.Control[]) getControls()
```

Parameters

None.

Returns

```
{cognos.Prompt.Control[]}
```

An array of controls associated with the report.

Example

This example implements a function, `clearAllValues()`, that resets (clears the selection of) all prompt controls for a page.

```
<script type="text/javascript">
function clearAllValues() {
  var oCR = cognos.Report.getReport("_THIS_");
  var aControls = oCR.prompt.getControls();
  for (var i = 0; i < aControls.length; i++) {
    aControls[i].clearValues();
  }
}
</script>
```

cognos.Prompt.Control object

A control is a visual element in the prompt page, such as a text prompt or a value prompt.

cognos.Prompt.Control.addValues method

Add an array of values to a control.

If the control does not support multiple values, only the first one provided is used.

Syntax

```
{void} addValues(aValues)
```

Parameters

```
{cognos.Value[]} aValues
```

The new values to use for this control.

Returns

```
{void}
```


Example

This example adds an array of two values (use and display) to a prompt.

```
var oCR = cognos.Report.getReport("_THIS_");
function setPromptValue( promptName, useValue, displayValue ) {
    var oP = oCR.prompt. getControlByName( promptName );
    var oValue = { 'use': useValue, 'display': displayValue };
    oP.addValue( [oValue] );
}
setPromptValue ( 'country', 'ca', 'Canada');
```

cognos.Prompt.Control.clearValues method

Clear (or deselect) all values for this control.

Syntax

For a text prompt, the text is set to empty. For a value prompt, all the selections are removed.

```
{void} clearValues()
```

Parameters

None.

Returns

```
{void}
```

Example

This example resets all the controls of a page.

```
function clearAllValues() {
    var oCR = cognos.Report.getReport("_THIS_");
    var aControls = oCR.prompt.getControls();
    for (var i = 0; i < aControls.length; i++) {
        aControls[i].clearValues();
    }
}
```

cognos.Prompt.Control.getName method

Returns the name of the control.

The name is set in IBM Cognos Report Studio in the name property set for the control.

Syntax

```
{String} getName()
```

Parameters

None.

Returns

```
{String}
```

The value specified by the name property set for the control.

cognos.Prompt.Control.getValues method

Returns the current value for the control.

This method always returns an array, even if there is only one value selected.

- The following is an example for a text box prompt (single):

```
[ {use: "Smith", display: "Smith"} ]
```

- The following is an example for a select prompt (multiple):

```
[ {use: "CAN", display: "Canada"}, {use: "JPN", display: "Japan"} ]
```

- The following are examples of range prompts:

A range is an array of two elements, with the mandatory names start and end. The value of each element is a regular array as in earlier examples. When the range values are equal, this method returns a normal value instead of a range:

```
[ {use: useValue, display:displayValue} ]
```

When the range values are different, this method returns a range:

```
[ start:{use: useValue, display:displayValue}, end:{use: useValue, display:displayValue} ]
```

Syntax

```
{cognos.Value[]} getValues(boolean v_allOptions)
```

Parameters

{Boolean} v_allOptions

This optional parameter is applicable only to value prompts. The parameter specifies whether to retrieve all values or only selected values.

If the parameter is true, then all options are returned. If the parameter is false or missing, then only the selected options are returned.

The default value of this parameter is false.

Returns

{cognos.Value[]}

An array of values for the control.

Example

This example demonstrates how to adjust your code based on whether the result is a single value or a range.

```
function isRangeOutOfLimits(datePrompt, rangeLimit) {
    var result = false;
    var v = datePrompt.getValues();
    var rangeValue = v[0];
    var rangeDaysDiff = 0;
    if (rangeValue.start) {
        rangeDaysDiff = 0;
        var startDate = rangeValue.start.use;
        var endDate = rangeValue.end.use;
        rangeDaysDiff = dateUtils.substractDate(endDate,startDate);
    }
    if (rangeDaysDiff > 0 && rangeDaysDiff <= rangeLimit) {
        result = true;
    }
    return result;
}
```

This example demonstrates the use of the parameter `v_allOptions`.

```
var allValues = valueControl.getValues(true);  
var selectedValues = valueControl.getValues();
```

cognos.Prompt.Control.setValidator method

Changes the default validation function for a control to one defined by the user.

When the specified function returns `false`, the UI element associated with the control indicates that a validation error occurred. When used in a multi-select control, the **Insert** button is disabled.

Note: Date and date & time prompt controls do not support this method.

Syntax

```
{void} setValidator(oFct)
```

Parameters

{function} oFct

A user-defined function that takes the user input as a parameter and returns a Boolean value.

Returns

```
{void}
```

Example

This example demonstrates how to ensure that a valid postal code is provided in the form A1A 1A1.

```
textBox.setValidator(  
  function (values) {  
    var result = false;  
    if (values && values.length > 0) {  
      var sValue = values[0]['use'];  
      var rePostalCodeFormat = new RegExp( "[a-z][0-9][a-z] ?[0-9][a-z][0-9]", "gi" );  
      if ( rePostalCodeFormat.test(sValue) ) {  
        result=true;  
      }  
    }  
    return result;  
  }  
);
```

cognos.Prompt.Control.setValues method

Resets the control and adds an array of values to a control.

If the control doesn't support multiple values, only the first value provided is used. This is a convenience method that issues consecutive calls to `clearValues()` and `addValues()`.

Syntax

```
{cognos.Value[]} aValues
```

Parameters

{cognos.Value[]} aValues

New values to use for this control.

Returns

{void}

Example

```
function setPromptValue( promptName, value ) {
    var oCR = cognos.Report.getReport("_THIS_");
    var oP = oCR.prompt. getControlByName( promptName );
    oP.setValues( oValues );
}
oValues = [{ 'use': 'ca', 'display': 'Canada' },
           { 'use': 'us', 'display': 'USA' }];
setPromptValue( 'countries', oValues );
```

cognos.Report object

Represents a report object in the content store.

Properties

prompt

References a cognos.Prompt object for this instance.

Example

This example creates a new cognos.Report object from the current instance.

```
var ocr= cognos.Report.getReport("_THIS_");
```

The new ocr object is specific to the cognos.Report namespace and avoids collisions with other objects in your scripts. The keyword `_THIS_` should always be used. The Report Server will replace it with a unique namespace during report execution.

cognos.Report.getReport method

Getter method for a cognos.Report object.

Namespaces are used to support HTML fragments. Always use a proper namespace when using this method to retrieve a cognos.Report object.

Syntax

```
<static> {cognos.Report} cognos.Report.getReport(sNamespace)
```

Parameters

{String} sNamespace *Optional*

Returns

{cognos.Report}

The cognos.Report instance for this namespace.

Example

```
var oCR = cognos.Report.getReport( "_THIS_" );
```

cognos.Report.sendRequest method

Sends a requests with the current parameters and values.

Syntax

```
{void} sendRequest(eAction)
```

Parameters

{cognos.Report.Action} eAction

Specifies one of the cognos.Report.Action enumeration values. No other values are allowed.

Returns

```
{void}
```

Example

```
function customButton( eAction )
{
  var oCR = cognos.Report.getReport("_THIS_");
  oCR.sendRequest( eAction );
}
```

cognos.Report.Action object

Defines constants for report navigation.

cognos.Report.Action.BACK

Go back one prompt page.

Syntax

```
<static> <constant> cognos.Report.Action.BACK
```

cognos.Report.Action.CANCEL

Cancel report execution and navigate to the previous page.

Syntax

```
<static> <constant> cognos.Report.Action.CANCEL
```

cognos.Report.Action.FINISH

Submit parameter values and skip all remaining optional prompts and prompt pages.

Syntax

```
<static> <constant> cognos.Report.Action.FINISH
```

cognos.Report.Action.NEXT

Submit parameter values and go to the next prompt page.

Syntax

<static> <constant> cognos.Report.Action.NEXT

cognos.Report.Action.REPROMPT

If the report contains prompt pages, the first prompt page is displayed. Otherwise, if the report doesn't contain prompt pages, this constant will re-prompt for values.

Syntax

<static> <constant> cognos.Report.Action.REPROMPT

cognos.Value class

JSON structure to represent parameter values.

This object includes the following valid attributes:

- display
- end
- start
- use

Simple values

```
{ 'use': '[a].[b].[c]', 'display': 'Canada' }
```

Range values

```
{  
  'start': { 'use': '2007-01-01', 'display': 'January 1, 2007' },  
  'end': { 'use': '2007-12-31', 'display': 'December 31, 2007' }  
}
```

Multiple values

```
[  
  { 'use': '12', 'display': 'Canada' },  
  { 'use': '41', 'display': 'Germany' },  
  { 'use': '76', 'display': 'Japan' }  
]
```

Notices

This information was developed for products and services offered worldwide.

This material may be available from IBM in other languages. However, you may be required to own a copy of the product or product version in that language in order to access it.

IBM may not offer the products, services, or features discussed in this document in other countries. Consult your local IBM representative for information on the products and services currently available in your area. Any reference to an IBM product, program, or service is not intended to state or imply that only that IBM product, program, or service may be used. Any functionally equivalent product, program, or service that does not infringe any IBM intellectual property right may be used instead. However, it is the user's responsibility to evaluate and verify the operation of any non-IBM product, program, or service. This document may describe products, services, or features that are not included in the Program or license entitlement that you have purchased.

IBM may have patents or pending patent applications covering subject matter described in this document. The furnishing of this document does not grant you any license to these patents. You can send license inquiries, in writing, to:

IBM Director of Licensing
IBM Corporation
North Castle Drive
Armonk, NY 10504-1785
U.S.A.

For license inquiries regarding double-byte (DBCS) information, contact the IBM Intellectual Property Department in your country or send inquiries, in writing, to:

Intellectual Property Licensing
Legal and Intellectual Property Law
IBM Japan Ltd.
19-21, Nihonbashi-Hakozakicho, Chuo-ku
Tokyo 103-8510, Japan

The following paragraph does not apply to the United Kingdom or any other country where such provisions are inconsistent with local law: INTERNATIONAL BUSINESS MACHINES CORPORATION PROVIDES THIS PUBLICATION "AS IS" WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESS OR IMPLIED, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF NON-INFRINGEMENT, MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. Some states do not allow disclaimer of express or implied warranties in certain transactions, therefore, this statement may not apply to you.

This information could include technical inaccuracies or typographical errors. Changes are periodically made to the information herein; these changes will be incorporated in new editions of the publication. IBM may make improvements and/or changes in the product(s) and/or the program(s) described in this publication at any time without notice.

Any references in this information to non-IBM Web sites are provided for convenience only and do not in any manner serve as an endorsement of those Web sites. The materials at those Web sites are not part of the materials for this IBM product and use of those Web sites is at your own risk.

IBM may use or distribute any of the information you supply in any way it believes appropriate without incurring any obligation to you.

Licensees of this program who wish to have information about it for the purpose of enabling: (i) the exchange of information between independently created programs and other programs (including this one) and (ii) the mutual use of the information which has been exchanged, should contact:

IBM Software Group
Attention: Licensing
3755 Riverside Dr.
Ottawa, ON
K1V 1B7
Canada

Such information may be available, subject to appropriate terms and conditions, including in some cases, payment of a fee.

The licensed program described in this document and all licensed material available for it are provided by IBM under terms of the IBM Customer Agreement, IBM International Program License Agreement or any equivalent agreement between us.

Any performance data contained herein was determined in a controlled environment. Therefore, the results obtained in other operating environments may vary significantly. Some measurements may have been made on development-level systems and there is no guarantee that these measurements will be the same on generally available systems. Furthermore, some measurements may have been estimated through extrapolation. Actual results may vary. Users of this document should verify the applicable data for their specific environment.

Information concerning non-IBM products was obtained from the suppliers of those products, their published announcements or other publicly available sources. IBM has not tested those products and cannot confirm the accuracy of performance, compatibility or any other claims related to non-IBM products. Questions on the capabilities of non-IBM products should be addressed to the suppliers of those products.

All statements regarding IBM's future direction or intent are subject to change or withdrawal without notice, and represent goals and objectives only.

This information contains examples of data and reports used in daily business operations. To illustrate them as completely as possible, the examples include the names of individuals, companies, brands, and products. All of these names are fictitious and any similarity to the names and addresses used by an actual business enterprise is entirely coincidental.

COPYRIGHT LICENSE:

This information contains sample application programs in source language, which illustrate programming techniques on various operating platforms. You may copy,

modify, and distribute these sample programs in any form without payment to IBM, for the purposes of developing, using, marketing or distributing application programs conforming to the application programming interface for the operating platform for which the sample programs are written. These examples have not been thoroughly tested under all conditions. IBM, therefore, cannot guarantee or imply reliability, serviceability, or function of these programs. The sample programs are provided "AS IS", without warranty of any kind. IBM shall not be liable for any damages arising out of your use of the sample programs.

If you are viewing this information softcopy, the photographs and color illustrations may not appear.

Depending upon the configurations deployed, this Software Offering may use session and persistent cookies that collect each user's

- name
- user name
- password

for purposes of

- session management
- authentication
- enhanced user usability
- single sign-on configuration
- usage tracking or functional purposes other than session management, authentication, enhanced user usability and single sign-on configuration

These cookies cannot be disabled.

If the configurations deployed for this Software Offering provide you as customer the ability to collect personally identifiable information from end users via cookies and other technologies, you should seek your own legal advice about any laws applicable to such data collection, including any requirements for notice and consent.

For more information about the use of various technologies, including cookies, for these purposes, see IBM's Privacy Policy at <http://www.ibm.com/privacy> and IBM's Online Privacy Statement at <http://www.ibm.com/privacy/details> in the section entitled "Cookies, Web Beacons and Other Technologies" and the "IBM Software Products and Software-as-a-Service Privacy Statement" at <http://www.ibm.com/software/info/product-privacy>.

Trademarks

IBM, the IBM logo and [ibm.com](http://www.ibm.com) are trademarks or registered trademarks of International Business Machines Corp., registered in many jurisdictions worldwide. Other product and service names might be trademarks of IBM or other companies. A current list of IBM trademarks is available on the Web at " Copyright and trademark information " at www.ibm.com/legal/copytrade.shtml.

The following terms are trademarks or registered trademarks of other companies:

- Adobe, the Adobe logo, PostScript, and the PostScript logo are either registered trademarks or trademarks of Adobe Systems Incorporated in the United States, and/or other countries.

- Microsoft, Windows, Windows NT, and the Windows logo are trademarks of Microsoft Corporation in the United States, other countries, or both.
- Linux is a registered trademark of Linus Torvalds in the United States, other countries, or both.
- UNIX is a registered trademark of The Open Group in the United States and other countries.
- Java and all Java-based trademarks and logos are trademarks or registered trademarks of Oracle and/or its affiliates.

Microsoft product screen shot(s) used with permission from Microsoft.

Glossary

This glossary provides terms and definitions for the IBM Cognos Business Intelligence and IBM Cognos Framework Manager software and products.

The following cross-references are used in this glossary:

- *See* refers you from a nonpreferred term to the preferred term or from an abbreviation to the spelled-out form.
- *See also* refers you to a related or contrasting term.

For other terms and definitions, see the IBM Terminology website (opens in new window).

“A” “B” on page 1018 “C” on page 1018 “D” on page 1019 “E” on page 1020 “F” on page 1020 “G” on page 1020 “H” on page 1020 “I” on page 1020 “J” on page 1021 “L” on page 1021 “M” on page 1021 “N” on page 1022 “O” on page 1022 “P” on page 1022 “Q” on page 1023 “R” on page 1023 “S” on page 1024 “T” on page 1024 “U” on page 1025 “V” on page 1025 “W” on page 1025

A

access permission

A privilege that permits the access or use of an object.

accountability scorecard

A scorecard that Metric Studio automatically builds for each user which contains the metrics and projects they own.

active report

A report output type that provides a highly interactive and easy-to-use managed report that users can consume offline. Active reports are built for business users, allowing them to explore their data and derive additional insight.

agent A process that performs an action on behalf of a user or other program without user intervention or on a regular schedule, and reports the results back to the user or program.

alias An alternative name used instead of a primary name.

AnalyticsZone

An IBM online community for business analytics. Users can download products and extensible visualizations, view publications and training materials, learn about upcoming IBM events, and perform other functions.

anonymous access

A type of access that allows users and servers to access a server without first authenticating with it.

application tier component

For installation, the set of processors that access the query databases to gather information and then render the results as PDF and HTML reports and metrics. Application tier components also pass requests to Content Manager and render the results that Content Manager retrieves from the content store.

attribute

1. In relational models, a query item that is not a measure or identifier. When a query item is an attribute, it is not intended to be aggregated, or used for grouping or generating prompt pick lists.
2. In BI Modeling, a characteristic of an entity which is descriptive rather than a unique identifier or an aggregative measure.

authentication (AuthN)

The process of validating the identity of a user or server.

authentication provider

The communication mechanism to an external authentication source. Functionalities, such as user authentication, group membership, and namespace searches, are made available through authentication providers.

AuthN

See authentication.

B

burst To create several report results by running a single report once. For example, the user can create a report that shows sales for each employee, and run it once, sending different results to regional managers by bursting on region.

burst key

The dimension or level of a query in the report specification that is used to create, or burst, a set of report results.

C

CA See certificate authority.

calculated member

A member of a dimension whose measure values are not stored but are calculated at run time using an expression.

canvas

An area within a dashboard or workspace that users interact with to create, view, and manipulate content and data.

capability

A group of functions and features that can be hidden or revealed to simplify the user interface. Capabilities can be enabled or disabled by changing preference settings, or they can be controlled through an administration interface.

cardinality

1. For relational data sources, a numerical indication of the relationship between two query subjects, query items, or other model objects.
2. For OLAP data sources, the number of members in a hierarchy. The cardinality property for a hierarchy is used to assign solve orders to expressions.

cascading prompt

A prompt that uses values from a previous prompt to filter the values in the current prompt or pick list.

certificate

In computer security, a digital document that binds a public key to the identity of the certificate owner, thereby enabling the certificate owner to be authenticated. A certificate is issued by a certificate

authority and is digitally signed by that authority. See also certificate authority.

certificate authority (CA)

A component that issues certificates to each computer on which components are installed.

CGI See Common Gateway Interface.

cipher suite

The combination of authentication, key exchange algorithm, and the Secure Sockets Layer (SSL) cipher specification used for the secure exchange of data.

class style

A combination of formatting characteristics, such as font, font size, and border, that the user names and stores as a set.

CM See Content Manager.

Common Gateway Interface (CGI)

An Internet standard for defining scripts that pass information from a web server to an application program, through an HTTP request, and vice versa.

compatible query mode (CQM)

The query processing mode that is consistent with version 8.4.1 of Cognos Business Intelligence, and that is maintained for upgrade success. See also dynamic query mode.

condition

An expression that can be evaluated as true, false, or unknown. It can be expressed in natural language text, in mathematically formal notation, or in a machine-readable language.

conformed dimension

A dimension with a single definition that can be reused or shared across multiple coordinated data marts.

constraint

1. A restriction on the possible values that users can enter in a field.
2. A security specification that denies one or more users the ability to access a model component or to perform a modeling or authoring task.

contact

A named email address to which reports and agent e-mails can be sent. Contacts are never authenticated.

content locale

A code that is used to set the language or dialect used for browsers and report text, and the regional preferences, such as formats for time, date, money, money expressions, and time of day.

Content Manager (CM)

The service that retrieves information from the content store, and saves information to the content store.

content store

A repository that is used to hold specifications of reports, models, and data sources.

CQM See compatible query mode.

credential

A set of information that grants a user or process certain access rights.

cube A multidimensional representation of data needed for online analytical processing, multidimensional reporting, or multidimensional planning applications.

custom set

In Analysis Studio, a named object which can include filter rules, calculations, and sort rules. Custom sets can define a set of members that is different from any set originally defined in the cube model. See also predefined set, set.

D**dashboard**

A web page that can contain one or more widgets that graphically represent business data.

data source

The source of data itself, such as a database or XML file, and the connection information necessary for accessing the data.

data source connection

The named information that defines the type of data source, its physical location, and any sign-on requirements. A data source can have more than one connection.

data tree

See metadata tree.

deployment

The process of moving an application

(such as a report or model) to a different instance. For example, reports are often created in a test environment and then deployed to production. When an application is deployed, it is exported, transferred, and imported.

deployment archive

A file used for deployment. A deployment archive contains the data from the content store that is being moved.

deployment specification

A definition of what objects to move (deploy) between a source and target environment, the deployment preferences, and the archive name. Deployment specifications are used for import and export.

derived index

A calculated metric that provides a status and a score based on other metrics.

details-based set

A set based on an item and its immediate details. See also set.

dimension

A broad grouping of descriptive data about a major aspect of a business, such as products, dates, or locations. Each dimension includes different levels of members in one or more hierarchies and an optional set of calculated members or special categories.

dimensional data source

A data source containing data modeled using OLAP multidimensional concepts, including dimensions, hierarchies, and measures.

dimensional modeled relational data (DMR)

Metadata that has been modeled to present relational data (tables, columns, joins) as dimensions (members, measures).

DMR See dimensional modeled relational data.

DQM See dynamic query mode.

drill down

In a multidimensional representation of data, to access information by starting with a general category and moving downwards through the hierarchy of information, for example from Years to Quarters to Months.

dynamic cube

An in-memory multidimensional representation of a subset of a data warehouse.

dynamic query mode (DQM)

A Java-based query execution mode that provides native access to data sources. It optimizes queries to address query complexity and large data volumes. It provides advanced query capabilities, such as in-memory caching, that benefits query planning, execution, and results. See also compatible query mode.

E**encryption**

In computer security, the process of transforming data into an unintelligible form in such a way that the original data either cannot be obtained or can be obtained only by using a decryption process.

event A change to a state, such as the completion or failure of an operation, business process, or human task, that can trigger a subsequent action, such as persisting the event data to a data repository or invoking another business process.

event key

A combination of data items that uniquely defines an event instance. Identifying an event instance enables the agent to determine if it is new, ongoing or stopped.

event list

The set of detected event instances evaluated by the task execution rules to determine which agent tasks should be performed.

F

fact See measure.

G**gateway**

An extension of a web server program that transfers information from the web server to another server. Gateways are

often CGI programs, but may follow other standards such as ISAPI and Apache modules.

glyph The actual shape (bit pattern, outline) of a character image. For example, italic A and roman A are two different glyphs representing the same underlying character. Strictly speaking, any two images which differ in shape constitute different glyphs. In this usage, glyph is a synonym for character image, or simply image (The Unicode Standard - Version 1.0).

governor

A set of rules to limit user activities, such as the execution of reports, that either take too long or consume too many resources.

group A collection of users who can share access authorities for protected resources.

grouping

In reporting, the process of organizing identical values of query items together and only displaying the value once.

H**hierarchy**

The organization of a set of entities into a tree structure, with each entity (except the root) having one or more parent entities and an arbitrary number of child entities.

I**information card**

A display of high-level information about dashboard, workspace, or report content, such as owner, contact information, date modified, and an optional thumbnail view of the dashboard, workspace, or report.

information pane

In Analysis Studio, a pane that helps the user to confirm their selection in the data tree by displaying related information, such as the level and attributes.

initiative

A task developed to achieve objectives or close the gap between performance and targets. Initiatives are associated with individual objectives and often known as projects, actions, or activities.

item See member.

J

job A group of runnable objects, such as reports, agents, and other jobs that the user runs and schedules as a batch.

job step
The smallest part of a job that can be run separately. A job step can be a report or it can be another job.

L

layout The arrangement of displayed matter on a screen or page, such as including margins, line spacing, type specification, header and footer information, and indents.

lease key
A timed encryption mechanism that governs authenticated access to stored content on a mobile device.

level A set of entities or members that form one section of a hierarchy in a dimension and represent the same type of object. For example, a geographical dimension might contain levels for region, state, and city.

locale A setting that identifies language or geography and determines formatting conventions such as collation, case conversion, character classification, the language of messages, date and time representation, and numeric representation.

local storage
A device accessed directly (without telecommunications) from the user's system, where information can be retained and later retrieved.

M

macro A fragment of code that can be inserted in a number of locations in models and reports, such as calculation and filter expressions and SQL statements. Macros can include references to session parameters, parameter maps, parameter map entries, and use functions to dynamically customize applications. With macros, a single report can address different business scenarios.

MDX See Multidimensional Expression Language.

measure
A performance indicator that is quantifiable and used to determine how well a business is operating. For example, measures can be Revenue, Revenue/Employee, and Profit Margin percent.

member
A unique item within a hierarchy. For example, Camping Equipment and 4 Man tent are members of the Products hierarchy.

metadata tree
Within a studio, a structure that contains objects such as query subjects, query items, dimensions, levels, and members. A metadata tree is used as a palette of the available data that can be inserted into calculations, filters, display areas, and other authoring gestures.

metric A measurement that assesses a key area of a business.

metric extract
A set of mappings between an existing Cognos data source and a Metric Studio object or value. For example, a cube measure named Revenue is mapped to a Metric Studio metric named Revenue Actual Value.

metric package
In Cognos Connection, a representation of a Metric Studio application. A metric package contains connection information, reports, and metric management tasks for that application. See also package.

metric store
A database that contains content for metric packages. A metric store also contains Metric Studio settings, such as user preferences.

metric type
A category of metrics that defines the business rules such as performance pattern, units, and meaning of a group of metrics. For example, Revenue can be a metric type, and European Revenue and North American Revenue would be metrics of this type.

model A physical or business representation of

the structure of the data from one or more data sources. A model describes data objects, structure, and grouping, as well as relationships and security. In Cognos BI, a model is created and maintained in Framework Manager. The model or a subset of the model must be published to the Cognos server as a package for users to create and run reports.

model segment

A part of a Framework Manager project, such as a parameter map, a data source, a namespace, or a folder, that is a shortcut to a second project. Segments are used to simplify model maintenance or to facilitate multi-user modeling.

multidimensional data source

See dimensional data source.

Multidimensional Expression Language (MDX)

A query language for dimensional sources.

N**named set**

See predefined set.

namespace

A part of the model in which the names may be defined and used. Within a namespace, each name has a unique meaning.

news item

A single entry in a Really Simple Syndication (RSS) compatible format. It can include a headline, text, and a link to more information. A news item task in an agent can be used to create news items for display in a Cognos Connection portlet.

normalization

The process of restructuring a data model by reducing its relations to their simplest forms. It is a key step in the task of building a logical relational database design. Normalization helps avoid redundancies and inconsistencies in data. An entity is normalized if it meets a set of constraints for a particular normal form (first normal form, second normal form, and so on).

O

object In Report Studio, an empty information container that can be dragged to a report from the Toolbox tab and then filled with data. Reports are made up of objects, which include crosstabs, text items, calculations, graphics, and tables.

object extract

An extract that defines the metadata for a Metric Studio object, such as a user defined column, a scorecard, or a data source.

P**package**

A subset of a model, which can be the whole model, to be made available to the Cognos server. See also metric package.

page set

In Report Studio, a set of one or more designed pages which repeat in the report output for each instance of a chosen query item. See also set.

passport

Session-based information, stored and encrypted in Content Manager memory, regarding authenticated users. A passport is created the first time a user accesses Cognos 8, and it is retained until a session ends, either when the user logs off or after a specified period of inactivity.

personal identification number (PIN)

In Cryptographic Support, a unique number assigned by an organization to an individual and used as proof of identity. PINs are commonly assigned by financial institutions to their customers.

PIN See personal identification number.

portlet

A reusable component that is part of a web application that provides specific information or services to be presented in the context of a portal.

predefined set

A set of members defined inside an OLAP data source as a list or by an expression. Predefined sets can be used in analysis and report authoring. See also custom set, set.

product locale

The code or setting that specifies which language, regional settings, or both to use for parts of the product interface, such as menu commands.

project

1. In Metric Studio, a task or set of tasks undertaken by a team and monitored on a scorecard. A project tracks dates, resources, and status.
2. In Framework Manager, a set of models, packages, and related information for administration, and for sharing model information.
3. In Metric Designer, a group of extracts. Each extract contains the metadata that is used to populate the Metric Studio data store or to create applications.

prompt

A report element that asks for parameter values before the report is run.

properties pane

Within a studio, a pane that provides an overview of the properties for selected data. The properties pane can also be used to make several changes and apply them at the same time, instead of repeating several different commands.

publish

In Cognos Business Intelligence, to expose information to the Cognos server so that the data can be used to create reports and other content.

Q

query A business question formulated in Cognos Business Intelligence in a studio or modeling tool that retrieves data from a data source.

query item

A named reference in a model or report to a database column, a calculation, or a query item in another query subject.

query subject

A named collection of query items that are functionally related. This is conceptually similar to a query which is defined to a database or view.

R

Rapidly Adaptive Visualization Engine (RAVE)

A system for the general visualization of all forms of data. RAVE is embedded within IBM Cognos Business Intelligence, and provides the ability for innovative and interactive visualizations.

RAVE See Rapidly Adaptive Visualization Engine.

Really Simple Syndication (RSS)

An XML file format for syndicated web content that is based on the Really Simple Syndication specification (RSS 2.0). The RSS XML file formats are used by Internet users to subscribe to websites that have provided RSS feeds. See also Rich Site Summary.

repeater

In Report Studio, a cell container that repeats values within itself with no predefined internal structure.

repeater table

In Report Studio, a table-like container that repeats cells across and down the page or row in the associated query.

report A set of data deliberately laid out to communicate business information. See also report specification.

report output

The output produced as a result of executing a report specification against a data set.

report specification

An executable definition of a report, including query and layout rules, which can be combined with data to produce a report output. See also report.

report view

A reference to another report that has its own properties, such as prompt values, schedules, and results. Report views can be used to share a report specification instead of making copies of it.

response file

A file that can be customized with the setup and configuration data that automates an installation. During an interactive installation, the setup and configuration data must be entered, but

with a response file, the installation can proceed without any intervention.

reverse proxy

An IP-forwarding topology where the proxy is on behalf of the back-end HTTP server. It is an application proxy for servers using HTTP.

Rich Site Summary (RSS)

An XML-based format for syndicated web content that is based on the RSS 0.91 specification. The RSS XML file formats are used by Internet users to subscribe to websites that have provided RSS feeds. See also Really Simple Syndication.

RSS

1. See Rich Site Summary.
2. See Really Simple Syndication.

S

score A number or ranking that expresses applicability in relation to a standard.

scorecard

A collection of metrics representing the performance of one unit or aspect of an organization.

scorecard structure

The hierarchy of scorecards that reflects how an enterprise organizes its metrics.

Secure Sockets Layer (SSL)

A security protocol that provides communication privacy. With SSL, client/server applications can communicate in a way that is designed to prevent eavesdropping, tampering, and message forgery. See also certificate authority.

security provider

See authentication provider.

selection-based set

A collection of individual items that the user has explicitly selected. The items or members may be selected from one or more levels of the same hierarchy. See also set.

session

The time during which an authenticated user is logged on.

set

A collection of related items or members. Members in a set may be specifically

chosen, or selected by one or more filter rules. In relational query processing, a set is produced by several operations, such as UNION, INTERSECT, and EXCEPT. See also custom set, details-based set, page set, predefined set, selection-based set, stacked set.

SSL See Secure Sockets Layer.

stacked set

Two or more sets arranged one above another in rows or side-by-side in columns. See also set.

strategy

The overall plan of action (such as for a brand unit, business unit, channel, or company) to achieve a stated goal. Strategies normally cover a period of more than one year.

strategy map

In Metric Studio, a visual representation of the strategy and the objectives of that strategy for an organization. For example, a strategy map may show employees how their jobs are aligned to the overall objectives of the organization.

summary

In reporting and analysis, an aggregate value that is calculated for all the values of a particular level or dimension. Examples of summaries include total, minimum, maximum, average, and count.

T

task An action performed by an agent if the event status meets the task execution rules. For example, an agent can send an email, publish a news item, or run a report.

task execution rule

A user-specified option within an agent that determines which statuses and values cause a task to be run. It determines which tasks to execute for each event instance.

template

In report authoring, a reusable report layout or style that can be used to set the presentation of a query or report.

thumbnail

An icon-sized rendering of a larger graphic image that permits a user to

preview the image without opening a view or graphical editor.

TLS See Transport Layer Security.

Transport Layer Security (TLS)

A set of encryption rules that uses verified certificates and encryption keys to secure communications over the Internet. TLS is an update to the SSL protocol.

tuple An ordered collection of two or more members from different dimensions. For example, the tuple (2007, Camping Equipment, Japan) returns the value for the intersection of the three members: 2007, Camping Equipment, and Japan. Tuples can be used to filter and sort data, and to create calculations.

U

union set

See stacked set.

user Any individual, organization, process, device, program, protocol, or system that uses the services of a computing system.

user-defined column

In metric management, a column used to represent a value other than the actual or target. It may be an industry benchmark or any other useful additional numerical information for a period, including a calculation based on the other values of the metric. User-defined columns may be different for each metric type.

user interface profile

A profile that defines the default behavior, set of features, and the functionality that is available to a user in the Report Studio and Cognos Workspace Advanced user interfaces.

V

virtual private network (VPN)

An extension of a company intranet over the existing framework of either a public or private network. A VPN ensures that the data that is sent between the two endpoints of its connection remains secure.

visualization bundle

A compressed file that contains

information required for report authors to add an extensible visualization to reports.

visualization library

A collection of extensible visualizations that are imported into IBM Cognos Administration for use in Report Studio and Cognos Workspace Advanced.

VPN See virtual private network.

W

watch list

A list of metrics that each user has chosen to monitor closely. If notification is enabled in Metric Studio, the user will receive email notification of changes to these metrics. Users can also choose to display their watch list as a portlet within Cognos Connection.

watch rule

A user-defined condition that determines whether a report is delivered to the user. When the rule is run, the output is evaluated and, if it satisfies the condition or rule, the report is delivered by email or news item. Watch rules limit report delivery to those reports containing data of significance to the user.

Web Services for Remote Portlets

A standard for creating presentation-oriented web services so that they can be easily integrated within other applications, such as web portals.

widget

A portable, reusable application or piece of dynamic content that can be placed into a web page, receive input, and communicate with an application or with another widget.

work area

The area within a studio that contains the report, analysis, query, or agent currently being used.

workspace

See dashboard.

Index

Special characters

- characters
 - errors when filtering 553
 - marking special cells 403
 - troubleshooting in reports 499
- ! characters 551
- * characters 403
- % calculations
 - in dimensional reporting 317
 - in relational reporting 264

Numerics

- 100% stacked charts 105
- 3-D charts 106

A

- absolute charts 104
- access code
 - setting for active report 195
- accessibility features 485
 - keyboard shortcuts 485
- accessible reports 486
 - adding alternate text 488
 - adding summary text 489
 - associating labels to prompt controls 490
 - conditional blocks 491
 - emphasizing text 489
 - headings 489
 - report output options 487
 - specifying cell headers in tables 489
- active report output 1
- active report preview 1
- active report slider orientation 2
- active report templates 1
- active reports 193
 - adding controls 197
 - adding interactivity 196
 - choosing where to render visualizations 173
 - controls 193
 - converting existing reports 194
 - converting to templates 469
 - creating and managing active report variables 196
 - defining connections between controls 204
 - drill-through links do not work 524
 - example 213, 217
 - formatting in preview view 210
 - in workspaces in IBM Cognos Workspace 8
 - integrating with IBM Cognos Workspace 196
 - preview view 210
 - running 212
 - saving in MHT format 212
 - setting access code 195
 - setting properties 195
 - specifying maximum number of rows that can appear 195
 - specifying reaction behavior of controls 206
 - specifying selection behavior of controls 206
 - summarizing data 211
 - unable to add to Cognos Workspace 516

- active reports (*continued*)
 - unable to view in Firefox 516
 - unable to view in Firefox 8 or later 516
 - using master detail relationships when authoring decks 210
 - variables 194
- adding
 - data 46
- aggregating
 - limitations with measures 552
 - mapping functions from data sources 242
 - member sets 286
 - samples and time dimensions 527
 - specifying aggregation properties in models 236
 - troubleshooting running totals 514
 - using a simple summary in dimensional reporting 282
 - using simple summaries in relational reporting 235
 - values in crosstabs and charts 283
- aliases in maps 187
- aligning objects 353
- alternate text
 - accessibility 488
- Analysis Studio
 - creating templates in Report Studio 469
- annotations
 - chart baselines 132
 - notes in charts 130
- area charts 92
- arithmetic overflow errors 515
- Auto Group & Summarize 236
- automating IBM Cognos BI using the IBM Cognos Software Development Kit 42
- averages
 - moving and rolling 286
- axes 18
 - in charts 84
 - titles in maps 185
- axis scales 126

B

- backgrounds
 - adding background effects to charts 348
 - adding colors to objects 368
 - changing in current default charts 119
 - changing in legacy charts 119
 - colors not appearing in templates 496
 - inserting background images 348
 - troubleshooting in charts 497
- bar charts 91
- base text direction 60
- baselines
 - adding to charts 132
- bevels
 - adding to legacy charts 120
- bidirectional support 60
 - digit shaping 405
 - enabling 50
 - reports 8
- binary round-off errors 504

- BlackBerry devices
 - creating mobile reports for 65
- block objects 35
- blocks
 - inserting 350
 - resizing 363
- booklet items
 - See report booklets
- bookmarks
 - adding 459
 - creating for drill-through access 434
- borders
 - adding to charts 348
 - adding to legacy charts 120
 - adding to objects 346
- bottom filtering 276
- broadcasting same report to different users
 - See burst reports
- bubble charts 95
 - specifying bubble size in current default charts 151
- bubble size 18
- Build Prompt Page tool 328
- bullet charts 16, 97
 - customizing current default charts 156
- burst reports 395
 - creating against cubes 400
 - creating against dimensional data sources 400
 - creating calculated fields to define recipients 395
 - defining groups 397
 - defining recipients 395
 - denial of service errors in dimensional reporting 517
 - denial of service errors in relational reporting 259
 - enabling in IBM Cognos Connection 399
 - Microsoft Excel format 571
 - setting options 398
 - troubleshooting 513
- business keys
 - using for drill-through 437
- button bars 199

C

- calculated fields in burst reports 395
- Calculation Intersection 560
- calculations
 - adding in dimensional reporting 316
 - adding in relational reporting 262
 - building in dimensional reporting 318
 - building query calculations in relational reporting 265
 - creating simple in dimensional reporting 317
 - creating simple in relational reporting 264
 - function quality of service indicators in dimensional reporting 555
 - function quality of service indicators in relational reporting 265
 - intersecting in crosstabs and charts 557
 - limitations in dimensional reporting 556
 - limitations in relational reporting 263
 - limitations with units of measure in dimensional reporting 556
 - limitations with units of measure in relational reporting 262
 - null values 560
 - resolving in dimensional data sources 560
 - solve order in dimensional reporting 555
 - solve order in relational reporting 262
 - unexplained number discrepancies 504

- calculations (*continued*)
 - using quotation marks in dimensional reporting 556
 - using quotation marks in relational reporting 265
- calculations do not appear in target report
- troubleshooting drilling through 523
- CAMID,
 - See IBM Cognos Access Manager ID
- cascading prompts
 - adding 339
- cascading style sheets 365
- cast_Date functions
 - troubleshooting 511
- changed features
 - in version 10.1.0 22
 - version 10.1.1 14
 - version 10.2.0 10
- chart configurations
 - 100% stacked 105
 - 3-D 106
 - stacked 104
 - standard 104
- chart properties
 - specifying 85
- chart types 87
 - area charts 92
 - bar charts 91
 - bubble charts 95
 - bullet charts 97
 - column charts 88
 - combination charts 94
 - gauge charts 98
 - line charts 89
 - Marimekko charts 101
 - metrics range charts 103
 - microcharts 100
 - Pareto charts 99
 - pie charts 90
 - point charts 93
 - polar charts 102
 - progressive column charts 100
 - quadrant charts 96
 - radar charts 102
 - scatter charts 94
 - win-loss charts 100
- charts 16, 83
 - accessible reports 491
 - adding alternate text 488
 - aggregating values 283
 - axes 18
 - background effects 348
 - background effects in legacy charts 120
 - backgrounds in current default charts 119
 - backgrounds in legacy charts 119
 - bands of color in the background 126
 - baselines 132
 - borders 348
 - bubble size 18
 - bullet 16
 - changing backgrounds in current default charts 119
 - changing backgrounds in legacy charts 119
 - changing colors 112
 - changing lines 123
 - changing scales 123
 - color by value 18
 - colored regions in current default charts 122
 - configurations 87
 - converting current default charts to a matrix 147

- charts (*continued*)
 - converting types 107
 - creating 83
 - cumulation line in current default Pareto charts 154
 - cumulation line in legacy Pareto charts 155
 - current default 83
 - current default in Report Studio 16
 - customizing current default combination charts 145
 - customizing labels 123
 - customizing legend items in current default charts 129
 - customizing legend items in legacy charts 129
 - customizing palettes 112
 - defining colors by values in current default charts 150
 - defining query contexts 142
 - displaying every second label 497
 - drilling through 158
 - drilling up and down 157
 - drop shadows 348
 - elements 84
 - enhanced styles 17
 - fills 348
 - gridlines 126
 - inserting microcharts into crosstabs 155
 - legacy 83
 - legacy and current default 480
 - legacy in Report Studio 16
 - legend titles not supported in Excel 571
 - limitations 519
 - many items on axis produces empty chart in Excel 2002 571
 - markers 135
 - matrices 16
 - metrics range 160
 - notes 18, 130
 - pie 17
 - positioning legends in current default charts 128
 - properties not supported in Microsoft Excel 571
 - regression lines in current default charts 139
 - regression lines in legacy charts 140
 - resizing 363
 - resizing current default 112
 - resizing legacy 112
 - resolving multiple calculations 557
 - series colors in current default combination charts 145
 - setting properties 108
 - showing data labels 140
 - showing data labels in current default pie and donut charts 141
 - showing data points 143
 - showing value markers 143
 - specifying bubble size in current default bubble charts 151
 - specifying default measures 78
 - summarizing small slices or items in current default charts 142
 - tooltips 108
 - troubleshooting axis labels 496
 - troubleshooting differences in appearance when run in different formats or on different operating systems 517
 - troubleshooting gray gradient backgrounds 497
 - types 87
 - types not supported in Microsoft Excel 572
- checkbox groups 200
- classes
 - changing the default for a report 365
- clipboards
 - copying reports 471
- clipboards (*continued*)
 - opening reports 472
- Cognos Business Insight
 - changed name 11
- Cognos Business Insight Advanced
 - changed name 11
- Cognos Report Studio
 - support for Cognos Theme Designer 3
- Cognos SQL
 - in dimensional reporting 309
 - in relational reporting 260
- Cognos Statistics
 - object missing from a report 520
 - removal in version 10.2.1 7
- Cognos Theme Designer
 - supported by Cognos Report Studio and Cognos Workspace Advanced 3
- Cognos Workspace
 - creating reports for workspaces 62
 - filters in workspaces 64
- Cognos Workspace Advanced
 - support for Cognos Theme Designer 3
- color by value 18
- colored regions
 - adding to current default charts 122
- colors
 - adding to current default charts 150
 - adding to objects 368
 - changing in charts 112
 - not appearing in templates 496
- column charts 88
- columns 46
 - adding multiple items in a single column 356
 - calculated in dimensional reporting 316
 - calculated in relational reporting 262
 - grouping in relational reporting 228
 - hiding or showing in list controls 209
 - setting the group span 230
 - sorting in dimensional reporting 297
 - sorting in relational reporting 249
 - swapping with rows 78
 - width limitations in Microsoft Excel 569
- combination charts 94
- concatenating strings 557
- Condition Explorer 30
- conditional block lists
 - inserting 351
- conditional blocks
 - accessible reports 491
- conditional palettes
 - creating 115
- conditional rendering 386
 - adding multiple layouts 391
 - adding variables 386, 387
 - example 389
 - hiding and showing objects 388
- conditional styles
 - creating 381
 - using variables 385
- container direction 60
- context filters
 - creating 293
 - prompting with 295
- continuous values sliders 201
- control data items
 - referencing 204

- controls
 - active reports 193
 - adding data 202
 - adding to an active report 197
 - button bars 199
 - buttons 201
 - checkbox groups 200
 - continuous values sliders 201
 - data button bars 199
 - data checkbox groups 200
 - data decks 198
 - data discrete values sliders 201
 - data drop down lists 200
 - data iterators 201
 - data list boxes 200
 - data radio button groups 200
 - data repeater tables 198
 - data tab controls 199
 - data toggle button bars 199
 - decks 198
 - defining connections 204
 - discrete values sliders 201
 - drop down lists 200
 - iterators 201
 - list boxes 200
 - radio button groups 200
 - referencing data items defined in static controls 204
 - repeater tables 198
 - row numbers 198
 - specifying reaction behavior 206
 - specifying selection behavior 206
 - tab 199
 - toggle button bars 199
 - variable text items 198
 - converting
 - lists to crosstabs 79
 - lists to repeaters 69
 - reports to templates 469
 - to MDX in dimensional reporting 311
 - to SQL in dimensional reporting 311
 - to SQL in relational reporting 261
 - visualizations 177
 - copying
 - reports to the clipboard 471
 - copying reports 472
 - Count
 - changes between IBM Cognos ReportNet and IBM Cognos BI 483
 - Count Distinct 483
 - crosstab node members 71
 - crosstab nodes 71
 - crosstabs 71
 - aggregating values 283
 - allow sorting 210
 - applying table styles 354
 - creating single-edge 74
 - crosstab node members 71
 - crosstab nodes 71
 - default measures 78
 - defining independent drill-through definitions 443
 - discontinuous 80
 - formatting 73
 - indenting data 78
 - inherited table styles 9
 - intersections 73
 - nesting data 75
 - order of styles 73
 - crosstabs (*continued*)
 - overflow errors 511
 - resolving multiple calculations 557
 - showing values as percentages 76
 - CRX-API-0018 errors 555
 - CSV format
 - importing your own files 372
 - producing reports in 53
 - cubes
 - troubleshooting drilling through to relational data 522
 - cumulation lines
 - in current default charts 154
 - in legacy charts 155
 - currencies
 - data format limitations in Microsoft Excel output 570
 - formatting 403
 - formatting disappearing in SSAS 2005 513
 - current default charts 83, 480
 - custom groups
 - creating 229, 279
- ## D
- dashboards
 - creating 325
 - using bullet charts 97
 - using gauge charts 98
 - using global filters 327
 - data
 - adding 46
 - data button bars 199
 - data checkbox groups 200
 - data containers
 - inserting from the Toolbox tab 45
 - data decks 198
 - data discrete values sliders 201
 - data does not appear in target report
 - troubleshooting drilling through 514
 - data drop down lists 200
 - data formats 403
 - date and time symbols 411
 - decimal format symbols 417
 - locale-sensitive 406
 - Microsoft Excel limitations 570
 - specifying default 403
 - specifying for objects 404
 - using patterns 409
 - data is not filtered in target report
 - troubleshooting drilling through 524
 - data items tab 30
 - data iterators 201
 - data list boxes 200
 - data packages
 - refreshing 44
 - specifying 43
 - data points
 - showing in charts 143
 - data radio button groups 200
 - data repeater tables 198
 - data series in charts 84
 - data sources 267
 - data stores
 - conformed dimensions 436
 - data tab controls 199
 - data toggle button bars 199
 - data trees
 - customizing 269

- date & time prompts 330
 - date prompts 330
 - dates
 - filtering 248
 - using for drill-through access 439
 - decimals
 - rounding 404
 - decks 198
 - using master detail relationships 210
 - default chart technology improvements 3
 - denial of service errors
 - in dimensional reporting 517
 - in relational reporting 259
 - depth
 - charts 108
 - derived columns 248
 - detail filters 244
 - diagrams
 - Metric Studio 162
 - dial charts 98
 - dictionary properties in maps 187
 - digit shaping 60
 - in charts and maps 405
 - dimensional 279
 - dimensional coercion rules 562
 - dimensional data sources
 - creating burst reports 400
 - creating master detail relationships 309
 - report limitations 549
 - resolving calculations 560
 - running reports against 549
 - using with queries 298
 - dimensional reporting 267
 - adding data 267
 - best practices 26
 - drilling up and down 321
 - filtering data 292
 - sorting data 295
 - summarizing data 280
 - using calculations 316
 - working with queries 297
 - dimensionally-modeled relational data sources
 - adding dimensional data 267
 - limitations when aggregating measures 552
 - dimensions 46, 267
 - conformed 299
 - conformed for drill-through access 436
 - non-conformed 299
 - overlapping named set levels 497
 - searching 270
 - discontinuous crosstabs
 - creating 80
 - discrete values sliders 201
 - distributing reports,
 - See* burst reports
 - dividing by zero
 - troubleshooting 495
 - Don't Print class 367
 - double counting 483
 - drilling down 321
 - creating drill-up/drill-down reports 322
 - in charts 157
 - using member sets 321
 - drilling through 431
 - business keys 437
 - calculations do not appear in target report 523
 - charts 158
 - drilling through (*continued*)
 - concepts 432
 - creating drill-through reports 439
 - cubes to relational data 522
 - data does not appear in target report 514
 - data is not filtered in target report 524
 - defining different drill-through definitions for crosstabs 443
 - IBM Cognos Visualizer reports 450
 - in maps 189
 - links not active in Safari Web browsers 514
 - members and values 435
 - Microsoft Excel limitations 570
 - model-based access 432
 - multiple values 441
 - nested crosstab only filters on some items 523
 - packages 434
 - paths 432
 - PowerCubes and packages 439
 - PowerPlay reports 450
 - problems with active reports 524
 - relational data to cubes 522
 - report formats 433
 - report-based access 432
 - selection contexts 433
 - specifying drill-through text 444
 - troubleshooting PowerCubes 521
 - using bookmarks 434
 - using dates 439
 - using member unique names 435
 - using scope in model-based reporting 438
 - using URLs 434
 - with conformed dimensions 436
 - wrong data appears in target report 514
 - drilling up 321
 - creating drill-up/drill-down reports 322
 - in charts 157
 - using member sets 321
 - drop down lists 200
 - defining no list value item 209
 - drop shadows
 - adding to legacy chart elements 120
 - drop shadows in charts 348
 - Dynamic Query Migration validation option 48
- ## E
- emailing reports,
 - See* burst reports
 - empty cells
 - specifying what appears for empty data containers 409
 - suppressing 407
 - error messages
 - CRX-API-0018 555
 - denial of service in dimensional reporting 517
 - denial of service in relational reporting 259
 - HRESULT 506
 - missing items 512
 - MSR-PD-0001 376
 - MSR-PD-0012 501
 - MSR-PD-0013 501
 - OP-ERR-0199 228, 496
 - OP-ERR-0201 497
 - OP-ERR-0209 553
 - OP-ERR-0210 553
 - OP-ERR-0212 553
 - OP-ERR-0213 553

- error messages (*continued*)
 - ORA-00907 512
 - overflow errors in crosstabs 511
 - PCA-ERR-0057 514
 - PCA-ERR-0087 517
 - QE-DEF-0288 511
 - QE-DEF-0478 562
 - ReferenceError: HTMLIsIndexElement is not defined 516
 - RQP-DEF-0177 515
 - RSV-SRV-0025 506
 - RSV-SRV-0040 495
 - TypeError: _JS1 is undefined 516
 - UDA-SQL-0114 506, 515
 - UDA-SQL-0206 506
 - UDA-SQL-0564 515
- errors
 - application errors upgrading a report 495
 - filtering results in error characters 553
 - null values in count summaries 498
 - out of memory 324, 518
 - parse errors with upgraded reports 511
 - recursive evaluation 514
 - troubleshooting error cells in reports 552
- escape characters
 - in calculations in dimensional reporting 556
 - in calculations in relational reporting 265
- examples for relational metadata
 - prompts 424
- Excel 2000 format
 - deprecation notices 25
- Excel 2002
 - empty chart produced when too many items on axis 571
- Excel 2007 worksheet tabs 2
- Explorer Bar 30
- expression editor
 - Aster Data 618
 - Aster Data Data Type Formatting 620
 - Aster Data Math 620
 - Aster Data String 618
 - Aster Data Trigonometry 621
 - Block Functions 617
 - browsing data 247
 - Business Date/Time Functions 608
 - Common Functions 741
 - Constants 605
 - Constructs 607
 - creating filters in dimensional reporting 292
 - creating filters in relational reporting 243
 - creating parameters to create prompts 333
 - Date Functions 692
 - DB2 623
 - DB2 Math 623
 - DB2 Trigonometry 623
 - dimensional coercion rules 562
 - Dimensional Functions 753
 - Greenplum 641
 - Greenplum Data type formatting 642
 - Greenplum Math 643
 - Greenplum String 641
 - Greenplum Trigonometry 643
 - Informix 646
 - Informix Math 646
 - Informix Trigonometry 646
 - Macro Functions 725
 - Member Summaries 602
 - MS Access 652
 - MS Access Cast 652
- expression editor (*continued*)
 - MS Access Math 653
 - MS Access Trigonometry 653
 - MySQL 659
 - MySQL Math 660
 - MySQL String 659
 - MySQL Trigonometry 661
 - Netezza 663
 - Netezza Fuzzy 664
 - Netezza Math 663
 - Netezza Phonetic 665
 - Netezza Trigonometry 663
 - Operators 575
 - Oracle 669
 - Oracle Math 669
 - Oracle Trigonometry 669
 - Paraccel 679
 - Paraccel Data type formatting 679
 - Paraccel Math 680
 - Paraccel String 679
 - Postgres 681
 - Postgres Data type formatting 682
 - Postgres Math 683
 - Postgres String 681
 - Postgres Trigonometry 683
 - Red Brick 686
 - Report Functions 779
 - Salesforce.com 692
 - SAP BW 691
 - SAP BW Math 692
 - SAP BW Trigonometry 691
 - searching for values 500
 - SQL Server 696
 - SQL Server Math 696
 - SQL Server Trigonometry 697
 - Statistical functions 583
 - Summaries 583
 - Sybase 704
 - Sybase Math 704
 - Sybase Trigonometry 704
 - Teradata 712
 - Teradata Trigonometry 712
 - Trigonometric functions 751
 - Vectorwise 717
 - Vectorwise Math 718
 - Vectorwise String 717
 - Vectorwise Trigonometry 718
 - Vertica 720
 - Vertica Data type formatting 721
 - Vertica Math 722
 - Vertica String 720
 - Vertica Trigonometry 722
- expressions
 - length 555
 - using summary functions in relational reporting 238
- extended data items 278
 - enabling for new reports 364
 - report option 38
- extensible visualizations 165
 - converting 3
 - optional category fields 3
 - properties 3
- external data
 - importing your own files 372
 - MSR-PD-0012 error when importing 501
 - MSR-PD-0013 error when importing 501
 - reporting 371

external data (*continued*)
supported data sources 14

F

facts 46
field sets
inserting 350
fills
adding to charts 348
adding to legacy charts 120
filtering
-- error characters 553
creating detail filters 244
creating global prompts in dashboards 327
creating summary filters 244
data from SAP BW data sources 554
data in dimensional reporting 292
data in relational reporting 243
date columns 248
drilling through from IBM Cognos Series 7 to IBM Cognos BI 451
limitations when specifying the scope 553
limitations with dimensional data sources 552
members in a set 277
multiple-fact queries 299
removing or editing 247
removing or editing detail filters 247
removing or editing summary filters 247
suppressing null values 408
to top or bottom values 276
troubleshooting `_make_timestamp` columns 506
using context filters 293
using slicers 293
workspaces in Cognos Workspace 64
filters
in_range 340
first-rows optimization
in dimensional reporting 312
in relational reporting 262
floating objects 363
fonts
setting in maps 185
specifying colors 368
specifying for reports 347
footers
adding to maps 185
adding to reports and lists 345
for clauses 238
FOR clauses
incorrect results for OLAP 503
limitations when using in summary functions 551
foregrounds
adding colors to objects 368
formatting
disappearing in SSAS 2005 513
functions
quality of service indicators in dimensional reporting 555
quality of service indicators in relational reporting 265

G

gauge charts 98
generated prompts 330
global filters in dashboards 327

glossaries
accessing the IBM WebSphere Business Glossary 60
glossary 1017
gridlines
adding to charts 126
in charts 84
major and minor 123
grouping
data in relational reporting 228
setting group spans 230
troubleshooting incorrect running totals 514
troubleshooting nested list reports 496
troubleshooting subtotals in grouped lists 496
groups
custom 229, 279

H

headers
adding to reports and lists 345
creating for sets 76
heatmap visualizations 168
heights
specifying for objects 363
hiding columns
list reports 68
hiding objects 388
hierarchies 46
inserting 272
highlighting
adding colors to objects 368
using conditional styles 381
horizontal pagination 467
hotspots 156
HRESULT errors 506
HTML format
producing reports in 50
viewing report pages as tabs 364, 468
HTML items
inserting 351
hyperlinks
buttons are not supported for Microsoft Excel 571
inserting 351

I

IBM Cognos for Microsoft Office
creating reports for 64
IBM Cognos Software Development Kit 42
IBM Cognos Visualizer reports
setting up drill-through access to IBM Cognos BI 450
IBM WebSphere Business Glossary 60
icons 46
images
adding alternate text 488
adding to chart backgrounds 348
inserting in backgrounds 348
inserting in reports 347
Microsoft Excel limitations 567
in_range filters 340
indenting
data in crosstabs 78
objects 355
inline objects 35
Insertable Objects pane 30, 31

- intersections of members
 - in dimensional reporting 320
- interval prompts 330
- iPhone devices
 - creating mobile reports for 65
- iterators 201

J

- Japanese
 - Microsoft Excel limitations 570
- join relationships
 - creating in relational reporting 256
- justification
 - setting for objects 361

L

- labels
 - customizing in charts 123
 - gauge charts
 - customizing 148
 - specifying in current default gauge charts 148
 - specifying in legacy gauge charts 149
- layout
 - using tables 354
- layout component caches 360
- layout component references
 - inserting 352
- layouts 33
 - adding 391
 - choosing 44
 - pages 33
 - relating to queries in dimensional reporting 298
 - relating to queries in relational reporting 251
 - report objects 34
 - report recommendations 343
 - using the page structure view 343
- legacy charts 83, 480
- legends 17
 - adding titles in maps 188
 - hiding or showing in maps 184
 - in charts 84
 - in maps 188
 - positioning in current default charts 128
- level hierarchies 267
- levels 46, 267
 - member unique names 435
- limitations
 - aggregating measures in dimensionally-modeled relational or relational data sources 552
- line breaks 362
- line charts 89
- line spacing 362
- lineage information 58
- linear scales
 - showing 123
- lines
 - adding regression lines to charts 139
 - adding regression lines to legacy charts 140
 - changing in charts 123
- linking data items for drilling 322
- list boxes 200
- list reports
 - hiding columns 68
- lists 67

- lists (*continued*)
 - adding headers and footers 345
 - allow sorting 210
 - applying table styles 354
 - converting to crosstabs 79
 - converting to repeaters 69
 - formatting 68
 - grouping data 228
 - hiding or showing columns 209
 - inherited table styles 9
 - limitations 550
 - single-edge crosstabs 74
 - subtotals in grouped lists 496
- literal strings
 - in calculations in dimensional reporting 556
 - in calculations in relational reporting 265
- locales
 - locale-sensitive properties 406
- location-aware reports
 - creating 66
- locking objects 35
- logarithmic scales 126
 - showing 123

M

- macros
 - adding to expressions 8
- mailing labels
 - creating 69
- Manage External Data tool
 - overview 371
- maps 181
 - aliases 187
 - creating 183
 - customizing 185
 - dictionary property 187
 - drilling through 189
 - ignoring data with no features 185
 - legends 188
 - matching data values 187
 - Microsoft Excel limitations 570
 - notes 189
 - parts of a map report 182
 - point layers 187
 - region layers 186
 - resizing 363
 - showing or hiding properties 185
 - updated 7, 12, 182
 - using from previous versions 13, 182
- margins
 - setting for objects 356
- Marimekko charts 101
- markers
 - adding to charts 135
- master detail relationships
 - creating in dimensional reporting 307
 - creating in relational reporting 258
 - creating when authoring active reports 210
 - denial of service errors in dimensional reporting 517
 - denial of service errors in relational reporting 259
 - linking members from two dimensional data sources 309
 - using to join page sets 456
- matrices 16
- matrix
 - charts 147
- matrix reports 71

- MDX
 - adding your own in dimensional reporting 310
 - converting to in dimensional reporting 311
 - working with in dimensional reporting 309
- measures 46
 - specifying defaults 78
- member properties 267
 - inserting 272
- member sets
 - aggregating 286
 - creating 272, 321
- member unique names 565
 - relational metadata 435
 - troubleshooting running reports with 566
- members 46
 - drill-through access 435
 - excluding 275
 - expanding and collapsing 277
 - folder 267
 - inserting properties 272
 - intersections in dimensional reporting 320
 - moving 275
- Metric Studio diagrams 162
- metrics range charts 103
 - examples 160
- MHT
 - saving active reports 212
- microcharts 100
 - inserting 155
- Microsoft Excel
 - chart legend titles not supported 571
 - grouping and ungrouping repeating cells 54
 - limitations of nested report objects 570
 - producing reports in 54
 - report limitations 567
- missing items
 - troubleshooting 512
- missing values 560
 - suppressing 407
- mobile devices
 - creating reports for 65
 - inline prompts 10
- models 46
 - aggregation properties 236
 - sample models and packages 528
 - using design filters 50
- moving averages 286
- MSR-PD-0001 errors 376
- MSR-PD-0012 errors 501
- MSR-PD-0013 errors 501
- multilingual reports 392
- MUNs,
 - See* member unique names
- My Data Sets
 - overview 372
- My Data Sets tool
 - overview 371

N

- named sets
 - limitations when summarizing 282
 - nested or parallel sets overlapping 497
- names
 - updating references 477
- native SQL
 - in dimensional reporting 309

- native SQL (*continued*)
 - in relational reporting 260
- nested crosstab only filters on some items
 - troubleshooting drilling through 523
- nested list reports
 - not running after upgrading 496
- nested report objects
 - Microsoft Excel limitations 570
- nested sets
 - unexpected summary values 501
- nesting
 - data in crosstabs 75
- new features
 - version 10.1.0 15
 - version 10.1.1 11
 - version 10.2.0 7
 - version 10.2.1 5
 - version 10.2.1.1 4
 - version 10.2.2 1
- no data
 - specify not to render pages 52
 - specifying what appears 409
- No Data Contents 409
- notes 18
 - adding to charts 130
 - adding to maps 189
- null values 560
 - calculations with SAP BW data sources 502
 - suppressing 407
 - suppressing with filters 408
 - troubleshooting in count summaries 498
- number data formats
 - Microsoft Excel limitations 570
- numeric shaping
 - See* digit shaping

O

- objects 35
 - adding 34
 - aligning 353
 - as containers 35
 - finding in reports 36
 - hiding and showing 388
 - hierarchies 36
 - indenting 355
 - inheriting formatting from parents 36
 - inline or block 35
 - inserting formatting objects 352
 - locking and unlocking 35
 - reusing for layouts 358
 - specifying data format 404
 - updating reused 360
- OLAP data sources
 - inserting data 267
 - limitations with relational functions 551
- OP-ERR-0199 errors 228, 496
- OP-ERR-0201 errors 497
- OP-ERR-0209 errors 553
- OP-ERR-0210 errors 553
- OP-ERR-0212 errors 553
- OP-ERR-0213 errors 553
- opening reports
 - from other studios 472
- ORA-00907 errors 512
- Oracle data sources
 - troubleshooting 512

- Oracle Essbase
 - changes 497
- out of memory errors 324
- overflow errors in crosstabs 511

P

- packages 46, 267
 - changing 477
 - drilling through 434
 - referencing items in child queries 257
 - refreshing 44
 - selecting for your report 43
- packed bubble visualizations 170
- padding
 - applying to objects 355
- page breaks 467
 - controlling 364
 - creating 453
 - creating with page layers 457
- Page Explorer 30
- page layers 457
- page numbers
 - adding 464
 - modifying with options 467
- page sets
 - creating 453
 - joining nested page sets 456
- pages 33
 - adding 453
 - associating queries with 453
 - not rendering when there is no data 52
 - viewing as tabs in HTML output 364, 468
- pagination
 - horizontal in PDF output 467
 - specifying for HTML output 364
- palettes 17
 - conditional 115
 - customizing in charts 112
- parameter values
 - clearing 50
- parameters
 - for prompts 333
 - using in master detail relationships in dimensional reporting 307
 - using in master detail relationships in relational reporting 258
- Pareto charts 99
 - cumulation lines in current default charts 154
 - cumulation lines in legacy charts 155
- PCA-ERR-0057 errors 514
- PCA-ERR-0087 517
- PDF format
 - producing reports 50
 - setting page options 58
- PDF problems
 - charts 519
- percent calculations
 - in dimensional reporting 317
 - in relational reporting 264
- pie charts 17, 90
 - converting to current default donut charts 152
 - exploding slices in current default charts 153
 - limitations for Microsoft Excel outputs 568
 - setting the first slice angle in current default charts 152
- point charts 93
- point layers 187

- polar charts 102
- PowerCubes
 - incorrect results 503
 - troubleshooting drilling through 521
- PowerPlay reports
 - setting up drill-through access to IBM Cognos BI 450
- Preview view
 - active reports 210
- printing
 - not printing objects 367
- progressive column charts 100
- prompt pages
 - creating your own 329
- prompt texts
 - customizing 337
- prompts 327
 - adding prompt buttons 339
 - associating labels to create accessible prompts 490
 - associating text items 490
 - changing prompt control interfaces 335
 - creating cascading 339
 - creating in a report page 335
 - creating using query macros 422
 - date 330
 - date & time 330
 - examples 424
 - generated 330
 - in_range 340
 - inline 10
 - interval 330
 - modifying 335
 - pages 328
 - parameters 333
 - requiring user input 336
 - select & search 329
 - selecting multiple values 336
 - showing and hiding 337
 - showing values in generated SQL or MDX 340
 - specifying default selections 337
 - specifying default values 338
 - text box 329
 - time 330
 - tree 340
 - upgrading SAP BW variables 480
 - using context filters 295
 - using slicer filters 295
 - using the Build Prompt Page tool 328
 - using the expression editor 333
 - value 329
 - workspaces in Cognos Workspace 63
- Properties 251
- Properties pane 30
- public variables
 - defining in active reports 8, 196

Q

- QE-DEF-0288 errors 511
- QE-DEF-0478 errors 562
- quadrant charts 96
- quadrants
 - adding to current default charts 122
- queries 35
 - associating with pages 453
 - connecting between data sources in dimensional reporting 299

- queries (*continued*)
 - connecting between data sources in relational reporting 251
 - in dimensional reporting 297
 - in relational reporting 250
 - multiple-fact 299
 - referencing data items in relational reporting 251, 298
 - referencing package items in child queries 257
 - relating to layouts in dimensional reporting 298
 - relating to layouts in relational reporting 251
 - result set of multi-fact query contains blanks 519
 - using with dimensional data sources 298
 - working with MDX in dimensional reporting 309
 - working with SQL in dimensional reporting 309
 - working with SQL in relational reporting 259
- query calculations
 - creating in dimensional reporting 318
 - creating in relational reporting 265
 - null values in count summaries 498
- query context
 - defining in charts 142
- Query Explorer 30
 - using in dimensional reporting 297
 - using in relational reporting 250
- query macros 419
 - adding 421
 - using to create prompts 422
- Query Studio
 - creating templates in Report Studio 469
- quotation marks
 - in calculations in dimensional reporting 556
 - in calculations in relational reporting 265

R

- radar charts 102
- radio button groups 200
- ragged hierarchies 278
- rebranding
 - Cognos Report Studio 3
 - Cognos Workspace Advanced 3
- referenced objects
 - changing 359
 - updating 360
- referenced report styles 366
- refreshing packages 44
- region layers 186
- regression lines 123
 - in current default charts 139
 - in legacy charts 140
- relational functions
 - limitations when used with OLAP data sources 551
- relational reporting 227
 - adding data 227
 - best practices 26
 - filtering data 243
 - grouping data 228
 - sorting data 249
 - summarizing data 233
 - troubleshooting drilling through to cubes 522
 - using calculations 262
 - working with queries 250
- Render Page when Empty 52
- repeater tables 198
 - adding interactive behavior 8
- repeaters
 - converting from lists 69

- repeaters (*continued*)
 - formatting 354
- repeating cells
 - grouping and ungrouping in Excel 2007 output 54
- report booklets 467
- report formats
 - CSV 53
 - Excel 54
 - HTML 50
 - PDF 50
 - specifying 50
 - XML 57
- report outputs
 - accessibility options 487
 - Microsoft Excel 2007 13
- report properties 364
- report samples 525
- report specifications 42
- Report Studio
 - bubble charts 18
 - bullet charts 16
 - chart axes 18
 - chart enhancements 16
 - chart formatting 17
 - chart legends 17
 - color by value 18
 - matrix charts 16, 17
 - new chart technology 16
 - notes 18
 - pie charts 17
 - setting options 37
- report styles 2
 - reusing 366
- ReportNet reports
 - formatting changes when upgrading 513
- reports
 - active 193
 - adding interactivity 196
 - changing the maximum number of tuples allowed 517
 - converting to active reports 194
 - creating booklets 467
 - multilingual 392
 - out of memory errors in interactive HTML output 518
 - supporting bidirectional languages 60
 - tabbed 468
 - validating 48
 - validation options 48
- resizing
 - current default charts 112
 - legacy charts 112
 - objects 363
- reusable report styles 2
- reusing
 - styles 344
- rich text items
 - inserting 351
 - supported elements 352
- rolling averages 286
- rollup calculations
 - in dimensional reporting 317
 - in relational reporting 264
- round-off errors 504
- rounding numbers 404
- row numbers 198
 - inserting 352
- rows
 - swapping with columns 78

- rows per page
 - controlling for multiple containers in HTML and PDF 52
 - setting 50
- RQP-DEF-0177 errors 482, 515
- RSV-SRV-0025 errors 506
- RSV-SRV-0040 errors 495
- run options
 - accessibility options 487
- running and moving summaries
 - limitations with dimensional functions 556
- running reports 50
 - against dimensional data sources 549
 - against SAP BW 549
 - cannot find database errors 511
 - format restrictions 3
 - ORA-00907 errors 512
 - Report Studio is slow 506
- running totals
 - dimensional functions 316
 - troubleshooting 514

S

- Safari Web browsers
 - drill-through links not active 514
- Sample Outdoors Company 525
 - databases, models, and packages 528
 - samples 525
- Sample Outdoors Company samples 525
- samples 525
 - cubes 529
 - database, models, and packages 528
 - employees 527
 - GO data warehouse 528
 - GO Data Warehouse (analysis) package 532
 - GO Data Warehouse (query) package 540
 - GO Sales (analysis) package 541
 - GO Sales (query) package 542
 - GO Sales transactional database 529
 - interactive 545
 - packages 530
 - Prompt API folder 547
 - Sales and Marketing (Cube) package 530
 - sales and marketing data 527
 - Sample Outdoors Sales (cube) package 530
 - The Sample Outdoors Company 525
 - visualizations 544
- SAP BW data sources
 - creating burst reports 400
 - creating expression 556
 - large queries 516
 - limitations when calculating data 262
 - limitations when sorting data 295
 - null results 502
 - query calculations 498
 - running reports against 549
 - sectioning reports 498
 - units of measure notation 549
- SAP variable properties
 - unsupported 549
- scales
 - changing for chart axes 126
 - changing intervals 123
 - linear 123
 - logarithmic 123
- scatter charts 94

- scope
 - filtering 244
 - using in drill-through access 438
- screen resolution requirements 29
- scrollbars
 - adding to block objects 363
- search tab 30
- searching
 - dimensions 270
- section headings 233
- sections
 - creating for dimensional data 457
 - creating on reports with SAP BW data sources 498
 - removing 233
- Secure Socket Layer
 - Microsoft Excel limitations 570
- select & search prompts 329
- set definitions 275
- set expressions
 - building in dimensional reporting 318
 - limitations in list reports 550
- sets
 - editing 275
 - filtering 277
 - reusing 273, 274
 - sharing 6, 273, 274
- sets of members
 - creating 272
 - nested or parallel sets overlapping 497
- shared sets
 - copying 274
 - creating 273
 - managing 274
- sharing
 - sets 273, 274
- showing objects 388
- single-edge crosstabs 74
- singletons 48
- sizes
 - specifying for objects 363
- slicer filters
 - prompting with 295
- slicers
 - creating 293
- slider orientation in active report 2
- solve order 557
 - combined with calculated rollup aggregate function 559
 - dimensional data sources 560
- sorting
 - crosstabs 210
 - data in dimensional reporting 295
 - data in relational reporting 249
 - limitations with SAP BW data sources 295
 - lists 210
 - multiple columns in dimensional reporting 297
 - multiple columns in relational reporting 249
 - visualizations 178
- source tab 30
- source trees
 - customizing 269
- spaces
 - adding around objects 355
- Specifying chart properties 85
- spider charts 102
- SQL
 - adding your own in dimensional reporting 310
 - adding your own in relational reporting 260

- SQL (*continued*)
 - Cognos in dimensional reporting 309
 - Cognos in relational reporting 260
 - converting to in dimensional reporting 311
 - converting to in relational reporting 261
 - first-rows optimization in dimensional reporting 312
 - first-rows optimization in relational reporting 262
 - native in dimensional reporting 309
 - native in relational reporting 260
 - working with in dimensional reporting 309
 - working with in relational reporting 259
- SSAS 2005 cubes
 - troubleshooting 499
- SSAS 2005 data sources
 - creating expression 557
 - disappearing data formats 513
- SSAS cubes
 - problems when very large 324
- stacked charts 104
- standard charts 104
- star charts 102
- strings
 - concatenating 557
- studios
 - Oracle Essbase changes 497
- styles
 - conditional 381
 - reusing 344, 366
- subtotals
 - troubleshooting in grouped lists 496
- summaries
 - adding simple in dimensional reporting 282
 - adding simple in relational reporting 235
 - adding to active reports 211
 - adding to visualizations 176
 - aggregate in dimensional reporting 287
 - aggregate in relational reporting 239
 - automatic in dimensional reporting 287
 - automatic in relational reporting 239
 - average in dimensional reporting 288
 - average in relational reporting 239
 - calculated 559
 - calculated in dimensional reporting 288
 - calculated in relational reporting 239
 - count distinct in dimensional reporting 289
 - count distinct in relational reporting 240
 - count in dimensional reporting 288
 - count in relational reporting 239
 - custom in dimensional reporting 289
 - custom in relational reporting 240
 - FOR clauses 503
 - maximum in dimensional reporting 289
 - maximum in relational reporting 240
 - median in dimensional reporting 290
 - median in relational reporting 240
 - minimum in dimensional reporting 290
 - minimum in relational reporting 240
 - none in dimensional reporting 290
 - none in relational reporting 240
 - not applicable in dimensional reporting 290
 - not applicable in relational reporting 240
 - null values 560
 - rolling and moving averages 286
 - standard deviation in dimensional reporting 290
 - standard deviation in relational reporting 241
 - summarize in dimensional reporting 290
 - summarize in relational reporting 241

- summaries (*continued*)
 - total in dimensional reporting 291
 - total in relational reporting 241
 - troubleshooting 508
 - variance in dimensional reporting 291
 - variance in relational reporting 241
- summarizing data
 - in dimensional reporting 280
 - in relational reporting 233
- summary filters 244
- summary functions
 - in dimensional reporting 287
 - in relational reporting 239
 - limitations when using FOR clauses 551
 - using in expressions in relational reporting 238
- summary text
 - adding to tables 489
- summary values
 - unexpected when using nested sets 501
- supporting bidirectional languages 8
- suppressing
 - data 407
- Symbian devices
 - creating mobile reports for 65

T

- tab controls 199
- tabbed reports 468
- tabbed reports in HTML output 2
- table styles
 - inherited 9
- tables
 - adding summary text 489
 - applying styles 354
 - inserting 354
 - Microsoft Excel width limitations 569
 - specifying cell headers 489
 - using for layout 354
- tables of contents
 - creating 461
- tabular data
 - viewing 50
- target reports
 - creating for drilling through from IBM Cognos Series 7 451
- templates
 - background colors not appearing 496
 - converting from reports 469
 - creating 469
- text
 - adding to reports 347
 - creating labels for prompts 490
 - specifying flow in objects 361
- text box prompts 329
- textures
 - adding to legacy charts 120
- time periods
 - showing data only for specific 287
- time prompts 330
- TM1 data sources
 - order of metadata tree 501
 - report differences 500
- toggle button bars 199
- toolbox tab 30
- tooltips
 - adding to charts 108

- tooltips (*continued*)
 - hiding or showing in maps 185
- top filtering 276
- totals
 - troubleshooting running totals 514
- tree prompts
 - adding 330
 - controlling the data that appears 340
- treemap visualizations 167
- trend lines 123
 - in current default charts 139
 - in legacy charts 140
- troubleshooting
 - differences in the appearance of charts run in different formats or on different operating systems 517
 - maps are missing when report is run 520
 - out of memory errors with reports run in interactive HTML 518
 - result set of multi-fact query contains blanks 519
 - unable to open saved Active Report output in Firefox 8 or later 516
- tuples
 - changing the maximum allowed in reports 517
 - in dimensional reporting 320
- TXT data
 - importing your own files 372

U

- UDA-SQL-0043 errors 515
- UDA-SQL-0114 errors 506, 515
- UDA-SQL-0206 errors 506
- UDA-SQL-0458 errors 482
- UDA-SQL-0564 errors 515
- unbalanced hierarchies 278
- unexplained number calculations 504
- union query
 - creating 253
- units of measure 403
 - notation for SAP BW data sources 549
- unlocking objects 35
- upgrading
 - SAP BW prompt variables 480
- upgrading reports
 - applications errors 495
 - errors 482
 - formatting not retained 513
 - members not suppressed for SAP BW 481
 - overview 479
 - reports will not open 511
 - thousands separators missing 481
- user interface 29

V

- validating reports 48
- value markers
 - showing in charts 143
- value prompts 329
- values
 - showing crosstab values as percentages 76
 - specifying defaults in prompts 338
- variable text items 198
- variables
 - active reports 8, 194, 196

- variables (*continued*)
 - adding 386, 387
 - conditional styles 385
- viewing reports
 - troubleshooting 513
- views
 - page design view 33
 - page preview 33
 - page structure view 33
- visual aids 31
- visualizations
 - adding 165
 - changing the nesting order 173
 - choosing where to render 173
 - converting 177
 - example 223
 - extensible 165
 - resizing 173
 - sample reports 544
 - sorting 178
 - specifying the categorical data to display 174
 - specifying the range of values to display 174
 - summarizing data 176
 - updating 177
 - using embedded data 176
 - working with visualization properties 172

W

- waterfall charts 100
- Web browser settings 41
- white spaces
 - adding padding to objects 355
 - margins 356
- widths
 - Microsoft Excel limitations 569
 - specifying for objects 363
- win-loss charts 100
- Windows Mobile devices
 - creating mobile reports for 65
- word breaks 362
- worksheet tabs in Excel 2007 output 2
- workspaces
 - Cognos Workspace 62
 - prompts in Cognos Workspace 63
- wrong data appears in target report
 - troubleshooting drilling through 514

X

- XLS format
 - importing your own files 372
 - limitations 567
- XML
 - importing your own files 372
 - producing a report 57
 - report specifications 42
- XQE-CON-0007 errors 516

Z

- zeros
 - suppressing 407